CRAIG PAEPRER Chairman

ANTHONY GIANNICO Vice Chairman

BOARD MEMBERS
KIM KUGLER
RAYMOND COTE
ROBERT FRENKEL
MARK PORCELLI
VICTORIA CAUSA

TOWN OF CARMEL PLANNING BOARD



60 McAlpin Avenue Mahopac, New York 10541 Tel. (845) 628-1500 – Ext.190 www.ci.carmel.ny.us MICHAEL CARNAZZA

Director of Code

Enforcement

RICHARD FRANZETTI, P.E. Town Engineer

> PATRICK CLEARY, AICP,CEP, PP, LEED AP Town Planner

PLANNING BOARD AGENDA OCTOBER 21, 2020 – 7:00 P.M.

TAX MAP # PUB. HEARING MAP DATE COMMENTS

<u>Pl</u>	JBLIC HEARING				
1.	Carmel Fire Department – 94 Gleneida Ave (Lot Line Adjustment)	44.14-1-24	10/21/20	9/8/20	Public Hearing/Resolution
2.	Carmel Fire Department – 94 Gleneida Ave (Site Plan)	44.14-1-24	10/21/20	9/8/20	Open Public Hearing
3.	Melchner, Charles & Stephanie – 417 Seminary Hill Road, Carmel	662-37	10/21/20	7/28/20	Public Hearing/Resolution
SI	TE PLAN				
4.	Mahoven LLC (Kaneti) – 737 South Lake Blvd	75.42-1-13		9/3/20	Special Site Plan
5.	14 Nicole Way LLC (Zakon) – 14 Nicole Way	65.6-1-22		9/29/20	Site Plan
SI	JBDIVISION				
6.	Old Forge Estates – Baldwin Place Road	75.15-1-19-40		8/20/20	Cluster Subdivision
7.	Itzla Subdivision – 9 Mechanic Street	55.14-1-6		12/5/19	2 Lot Subdivision
M	SCELLANEOUS				
8.	70 Old Route 6, LLC – 70 Old Route 6, Carmel (formerly Tompkins Recycling Facility)	55.11-1-15		12/8/16	Extension of Final Site Plan Approval
9.	Centennial Golf Club of New York, LLC	442-2,3,4			Resolution

10. Minutes - 08/19/20



October 9, 2020

Town of Carmel Planning Board 60 McAlpin Avenue Mahopac, New York 10541

RE: Carmel Fire Department 94 Gleneida Avenue Town of Carmel TM# 44.14-1-24

Dear Chairman Paeprer and Members of the Board:

Please find enclosed five (5) copies of the following documents in support of an amended site plan application for the above referenced project:

- Site Plans prepared by Insite Engineering, Surveying, and Landscape Architecture P.C. dated May 20, 2020 revised October 8, 2020.
- Letter by Michael Liguori of Hogan & Rossi dated October 9, 2020.

Since the last submission, a traffic study was completed for MSB United Hudson Bank analyzing the use of the eastern driveway between the Bank Parcel and the Carmel Fire Department Parcel. Based on those findings MSB United Hudson Bank is stating that two-way traffic will need to provided, as it currently existing, from the Bank Parcel connecting to Garrett Place / Vink Drive. Drawing SP-2 has been updated to include additional directional pavement markings, signage, and a note stating that "A member of the Carmel Fire Department will be present when a fire apparatus returns and enters the apparatus bay in order to direct non-fire department traffic generated by the Bank Parcel." It should be noted that a variance was granted by the Zoning Board of Appeals for two-way traffic at the 20' wide driveway.

We respectfully request this project be placed on the October 21, 2020 Planning Board meeting for the discussion of the attached material and continuation of a Public Hearing. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

Ву:

John M. Watson, PE Principal Engineer

JMW/kms Enclosures

Cc: Michael Hengel / Carmel Fire Department Michael T. Liguori / Hogan & Rossi, Esqs.

Eric Neiler, H2M Architects

HOGAN & ROSSI

Attorneys At Law 3 Starr Ridge Road - Suite 200 Brewster, New York 10509

John J. Hogan
Donald M. Rossi
Michael T. Liguori*
Jamie Spillane**
Courtney J. Day**

* Also Admitted in CT
** Also Admitted in NJ

Telephone: (845) 279-2986 Facsimile: (845) 279-6425

(845) 278-6135

Of Counsel
Nancy Tagliafierro*
Mary Jane MacCrae
Scott J. Steiner
Bonnie N. Fienzig

October 9, 2020

Hon. Craig Paeprer, Chairman and Members of the Town of Carmel Planning Board 67 McAlpin Avenue Mahopac, New York 10541

Re: Carmel Fire Department, Inc.

Two Way Traffic on Access Drive

Dear Chairman and Members:

The purpose of this letter is to supplement the current submittal by Insite Engineering, Surveying and Landscape Architecture, P.C. for the Carmel Fire Department, Inc. about two-way traffic on the access drive.


Following the recent traffic study prepared by Creighton Manning, we were able to obtain consent from TD that traffic could be limited to one way only based on the limited percentage of usage, however, this posed a new problem. TD would give its consent, but only if the easement was limited to all party's usage of the access drive was one way only instead of just TD's traffic. While the Fire Department traffic's circulation is intended to be an ingress into the fire house with an exit direction of Vink, it does not want to give up its right to be able to exit the new driveway should the need ever arise. Further, one way only on the entirety of the easement could potentially affect the Volunteer Ambulance Corp.'s usage and that simply does not work.

Our proposal, therefore, in addition to the installation of traffic signage, is to implement standard operating procedures for the Fire Department for the use of the driveway to provide that when an apparatus is using the driveway that it give the right of way to vehicular traffic and that volunteers exit the apparatus and physically direct traffic while the driveway is in use. The Fire Department is already experienced with situations like this as it regularly directs traffic as a significant part of its operations. Moreover, driver training and apparatus usage are also an integral part of its operations and all of the drivers and members can be trained about usage of the driveway and these requirements can be consistently applied.

We thank the Board in advance for consideration of the foregoing and ask it note that we have used our best efforts to achieve a solution for the Board's concern and while we were hopeful that we could accommodate the Board's request, we simply were unable to. We believe, however, that the current proposal is safe and can be consistently applied.

Sincerely,

Michael T. Liguori



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION

OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF

SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.


SHEET DRAWING NO. 19135.100 J.M. W. NUMBER MANAGER 5-20-20 C.B.Z. CHECKED BY 1 inch = 20 ft. 1" = 20'K.M.G. SCALE

(IN FEET)

		<u>PLANT LIST</u>		
QUANTITY	KEY	BOTANICAL/COMMON NAME	SIZE	ROOT/SPACING
23	то	Thuja occidentalis 'Emerald Green'' / Emerald Green Arborvitae	6'-7'	B&B
11	IN	llex 'Nellie R. Stevens' / Nellie R. Stevens' Holly	5'-6'	#25

APPARATUS BAY ENTRANCE NOTES:

A member of the Carmel Fire Department will be present when a fire apparatus returns and enters the apparatus bay in order to direct non-fire department traffic generated by the Bank Parcel.



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION

OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF

SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.

	<u>LEGEND</u>
	EXISTING PROPERTY LINE
	- EXISTING EASEMENT
-000000	EXISTING STONE WALL
x	- EXISTING CHAIN LINK FENCE
	- EXISTING STOCKADE FENCE
	EXISTING CONCRETE CURB
	EXISTING DROP IN CONCRETE CURB
	EXISTING SIGN
	EXISTING HEDGE ROW
	EXISTING TREELINE
\$	EXISTING POST MOUNTED LIGHT
0	EXISTING RECESSED LIGHT
P	EXISTING UTILITY POLE
(9)	PROPOSED # OF STALLS TO BE STRIPED
	PROPOSED CONCRETE CURB
ði	PROPOSED PAINTED HANDICAP PARKING SYMBOL
	PROPOSED STRIPED ISLAND
 (1)	PROPOSED SINGLE POLE SIGN
■■■	PROPOSED POLE MOUNTED LIGHT
	PROPOSED BUILDING MOUNTED LIGHT

	<u>SIGN</u>	DATA	TABLE	
LOCATION NO.	TEXT	M.U.T.C.D. NUMBER	SIZE OF SIGN (s.f.)	DESCRIPTION
1	RESERVED PARKING	NY R7-8*	12" × 18"	Green on White Blue Symbol
	VAN	R7-8P	12" x 6"	Green on White
2	NO PARKING ANY TIME	R7–1	12" x 18"	Red on White
3	DO NOT ENTER	R5–1C	30" x 30"	White on Red

<u>Proposed:</u>

C ZONE REQUIREMENTS: Required/Permitted: <u>Existing:</u>

40,000 SF	94,830 SF	94,830 SF
200'	261'±	261'±
200'	450'±	450'±
100'	574.7'±	574.7'±
40'	42'±	41'±
25'	8.9'±*	8.9'±*
30'	185'±	78'±
35'	Less Than 35'	Less Than 35'
5,000 SF	>5,000 SF±	26,900 SF±
30%	14%±**	22%±**
	200' 200' 100' 40' 25' 30' 35' 5,000 SF	200' 261'± 200' 450'± 100' 574.7'± 40' 42'± 25' 8.9'±* 30' 185'± 35' Less Than 35' 5,000 SF >5,000 SF±

* Pre-existing nonconforming condition ** Includes a 775 sf allocation for structures within the cellular tower facility. *** The applicant was granted a variance for a driveway less than 24' (§ 145–42 D)
by the Town of Carmel Zoning Board of Appeals on August 27, 2020. The variance was granted for a 20' driveway.

PARKING SUMMARY REQUIRED:

FIRE DEPARTMENT SPACES (CALCULATED AS WHOLESALE, WAREHOUSE, STORAGE, HEAVY COMMERCIAL ESTABLISHMENTS)
12,524 S.F. @ 1 SPACE/1,000 S.F. = 13 REQUIRED
6,976 S.F. OF OFFICE SPACE @ 1 SPACE/200 S.F. = 35 REQUIRED * 7,400 S.F. OF APPARATUS BAYS ARE NOTE INCLUDED PARKING CALCULATIONS

TOTAL PARKING SPACE REQUIRED = 48 REQUIRED

= 48 PROVIDED TOTAL PARKING SPACE PROVIDED

OUTDOOR TRAINING NOTES:

Outdoor training will occur offsite at the county fire training center. If outdoor training does occur on site, it will occur nights and weekends when possible, and training area will be coned off to preserve necessary vehicular circulation.

GENERAL PLANTING NOTES:

- All proposed planting beds to receive a 12" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
- Any new soils added will be amended as required by results of soil testing and placed using a method that will not cause compaction.
- 3. All plant material to be nursery grown. 4. Plants shall conform with ANSI Z60.1 American Standard for Nursery Stock in all
- ways including dimensions.
- 5. Plant material shall be taken from healthy nursery stock.
- 6. All plants shall be grown under climate conditions similar to those in the locality of the project.
- Plants shall be planted in all locations designed on the plan or as staked in the field by the Landscape Architect.
- 8. The location and layout of landscape plants shown on the site plan shall take precedence in any discrepancies between the quantities of plants shown on the
- plans and the quantity of plants in the Plant List. 9. Provide a 3" layer of shredded pine bark mulch (or as specified) over entire watering saucer at all tree pits or over entire planting bed. Do not place mulch
- within 3" of tree or shrub trunks. 10. All landscape plantings shall be maintained in a healthy condition at all times.
- Any dead or diseased plants shall immediately be replaced "in kind" by the contractor (during warranty period) or project owner.
- 11. All Plantings shall be installed per § 142 of the Town of Carmel Town Code. In addition, plantings shall be verified by the Town of Carmel Wetland Inspector.

3 10-8-20	PLANNING BOARD SUBMISSION	E
2 8-7-20	PLANNING BOARD SUBMISSION	K
1 7-17-20	PLANNING BOARD SUBMISSION	E
NO. DATE	REVISION	E



CARMEL FIRE **DEPARTMENT** 94 GLENEIDA AVENUE, CARMEL, PUTNAM COUNTY, NEW YORK

<u>LAYOUT AND</u> LANDSCAPE PLAN

DRAWING NO. J.M. W.

PROJECT NUMBER 19135.100 1" = 20'


C.B.Z. CHECKED BY

(IN FEET) 1 inch = 20 ft.


GRAPHIC SCALE

K.M.G.

www.insite-eng.com



Z:\E\19135100 Carmel FD\03 SP-2.dwg, 10/8/2020 8:48:12 AM, eappelgren, 1:1



Erosion and Sediment Control Notes, and Erosion and

i. An inspection schedule: Inspections are to be performed

daily by a NYSDEC Trained Contractor as cited in the

this SWPPP requirement.

Erosion and Sediment Control Notes.

Sediment Control Maintenance Schedule serve to satisfy

temporary sanitary facilities (portable toilets) shall be

provided onsite during the entire length of construction.

and inspected weekly for evidence of leaking holding

and areas of disturbance shall be limited to the shortest

e. Description of erosion and sediment control practices:

This plan, and details / notes shown hereon serve to

period of time as practicable.

satisfy this SWPPP requirement.

relocation of utilities and site amenities. The existing

b. Site map / construction drawing: These plans serve to

satisfy this SWPPP requirement.

building will be repurposed to include office, meeting and

<u>LEGEND</u> EXISTING PROPERTY LINE EXISTING EASEMENT EXISTING STONE WALL - EXISTING CHAIN LINK FENCE - EXISTING STOCKADE FENCE EXISTING CONCRETE CURB EXISTING DROP IN CONCRETE CURB EXISTING TRAFFIC SIGNAL BOX EXISTING SIGN - EXISTING UNDERGROUND DRAINAGE PIPE EXISTING CATCH BASIN EXISTING MANHOLE (type unidentified) EXISTING POST MOUNTED LIGHT EXISTING RECESSED LIGHT EXISTING WATER VALVE EXISTING CLEAN OUT EXISTING UTILITY POLE - EXISTING 10' CONTOUR EXISTING 2' CONTOUR EXISTING SPOT GRADE - PROPOSED 10' CONTOUR PROPOSED 2' CONTOUR PROPOSED SPOT ELEVATION TC 101.0 PROPOSED TOP OF CURB & BOTTOM OF BC 100.5 CURB ELEVATIONS PROPOSED DRAIN INLET (DI) OR CATCH BASIN (CB) WITH INLET PROTECTION - PROPOSED CONSTRUCTION FENCE PROPOSED TEMPORARY SOIL STOCKPILE PROPOSED STABILIZED CONSTRUCTION ENTRANCE

EROSION & SEDIMENT CONTROL NOTES:

- 1. The owner's field representative (O.F.R.) will be responsible for the implementation and maintenance of erosion and sediment control measures on this site prior to and during construction.
- 2. All construction activities involving the removal or disposition of soil are to be provided with appropriate protective measures to minimize erosion and contain sediment disposition within. Minimum soil erosion and sediment control measures shall be implemented as shown on the plans and shall be installed in accordance with "New York Standards and Specifications For Erosion and Sediment Control," latest edition.
- 3. Wherever feasible, natural vegetation should be retained and protected. Disturbance shall be minimized in the areas required to perform construction. No more than 5 acres of unprotected soil shall be exposed at any one time.
- 4. When land is exposed during development, the exposure shall be kept to the shortest practical period of time. In the areas where soil disturbance activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within seven (7) days from the date the current soil disturbance activity ceased. Disturbance shall be minimized to the areas required to perform construction.
- 5. Silt fence shall be installed as shown on the plans prior to beginning any clearing, grubbing or earthwork. 6. All topsoil to be stripped from the area being developed shall be stockpiled and
- immediately seeded for temporary stabilization. Ryegrass (annual or perennial) at a rate of 30 lbs. per acre shall be used for temporary seeding in spring, summer or early fall. 'Aristook' Winter Rye (cereal rye) shall be used for temporary seeding in late fall and winter.
- 7. Any disturbed areas not subject to further disturbance or construction traffic. permanent or temporary, shall have soil stabilization measures initiated for permanent vegetation cover in combination with a suitable mulch within 1 business day of final grading. All seeded areas to receive a minimum 4" topsoil (from stockpile area) and be seeded and mulched as follows:
- Seed mixture to be planted between March 21 and May 20, or between August 15 and October 15 or as directed by project representative at a rate of 100 pounds per acre in the following proportions: Kentucky Bluegrass 20% Creeping Red Fescue 40% Perennial Ryegrass 20%
- Annual Ryegrass 20% • Mulch: Salt hay or small grain straw applied at a rate of 90 lbs./1000 S.F. or 2 tons/acre, to be applied and anchored according to "New York Standards and Specification For Erosion and Sediment Control," latest
- 8. Grass seed mix may be applied by either mechanical or hydroseeding methods. Seeding shall be performed in accordance with the current edition of the "NYSDOT Standard Specification, Construction and Materials, Section 610-3.02, Method No. 1". Hydroseeding shall be performed using materials and methods as approved by
- 9. Cut or fill slopes steeper than 3:1 shall be stabilized immediately after grading with Curlex I Single Net Erosion Control Blanket, or approved equal. 10. Paved roadways shall be kept clean at all times.
- 11. The site shall at all times be graded and maintained such that all stormwater
- runoff is diverted to soil erosion and sediment control facilities. 12. All storm drainage outlets shall be stabilized, as required, before the discharge
- 13. Stormwater from disturbed areas must be passed through erosion control barriers before discharge beyond disturbed areas or discharged into other drainage
- 14. Erosion and sediment control measures shall be inspected and maintained on a daily basis by the O.F.R. to insure that channels, temporary and permanent ditches and pipes are clear of debris, that embankments and berms have not
- erosion and sediment control measures shall be immediately repaired by the contractor and inspected for approval by the O.F.R. and/or site engineer. 15. Dust shall be controlled by sprinkling or other approved methods as necessary, or as directed by the O.F.R.
- property of others. 17. All fills shall be placed and compacted in 6" lifts to provide stability of material
- 18. The O.F.R. shall inspect downstream conditions for evidence of sedimentation on a weekly basis and after rainstorms.
- 19. As warranted by field conditions, special additional erosion and sediment control measures, as specified by the site engineer and/or the Town Engineer shall be installed by the contractor.
- 20. Erosion and sediment control measures shall remain in place until all disturbed areas are suitably stabilized.

	111	INSITE 3 Garrett Place Carmel, NY 10512	
NO.	DATE	REVISION	BY
1	7-17-20	PLANNING BOARD SUBMISSION	ERA
2	8-7-20	PLANNING BOARD SUBMISSION	KMG
3	10-8-20	PLANNING BOARD SUBMISSION	ERA

LANDSCAPE ARCHITECTURE, P.C.

GRAPHIC SCALE

(IN FEET)

1 inch = 20 ft.

/ ENGINEERING, SURVEYING & (845) 225-9717 fax www.insite-eng.com

CARMEL FIRE **DEPARTMENT**

94 GLENEIDA AVENUE, CARMEL, PUTNAM COUNTY, NEW YORK EROSION AND SEDIMENT CONTROL


<u>PLAN</u>




19135.100 J.M. W. C.B.Z. 5-20-20 CHECKED 1" = 20'K.M.G.

NUMBER








CHECKED BY

K.M.G.

1" = 30'

1 inch = 30 ft.



NOTE: The passenger car used for vehicle maneuvering is a standard vehicle with an overall length of 19'-0" and width of 7'-0". These standard dimensions show that a passenger car of this size, or similar, will be able to maneuver through the property.

<u>LEGEND</u> - EXISTING PROPERTY LINE — — — — — EXISTING EASEMENT EXISTING STONE WALL EXISTING CHAIN LINK FENCE EXISTING STOCKADE FENCE EXISTING CONCRETE CURB EXISTING DROP IN CONCRETE CURB EXISTING SIGN EXISTING POST MOUNTED LIGHT EXISTING RECESSED LIGHT EXISTING UTILITY POLE PROPOSED # OF STALLS TO BE STRIPED = PROPOSED CONCRETE CURB PROPOSED PAINTED HANDICAP PARKING SYMBOL PROPOSED STRIPED ISLAND PROPOSED SINGLE POLE SIGN PROPOSED POLE MOUNTED LIGHT PROPOSED BUILDING MOUNTED LIGHT

2 10-8-20 1 8-7-20 PLANNING BOARD SUBMISSION NO. DATE 3 Garrett Place Carmel, NY 10512 (845) 225–9690 (845) 225–9717 fax www.insite–eng.com


<u>CARMEL FIRE</u> <u>DEPARTMENT</u> 94 GLENEIDA AVENUE, CARMEL, PUTNAM COUNTY, NEW YORK

<u>VEHICLE MANEUVERING PLAN</u>

DRAWING NO. J.M.W. 7-17-20 DRAWN BY J.F.R. SP-5 1" = 30' CHECKED BY

GRAPHIC SCALE (IN FEET)

1 inch = 30 ft.



UNIVERSE®

LUMIN	AIRE	SCHEDULE			
Symbol	Qty	Catalog Number	Description	Lamp	Mounting Height
A ⊶	2	UCM2-ANG-36L-260 -3K7-4W-HS	ARCHITECTURAL AREA LIGHTING, UNIVERSE COLLECTION, MEDIUM 2.0, HOUSE—SIDE SHIELD	LED	18' - 0"
B •■ C ■•■	8	UCM2-ANG-36L-260 -3K7-4W	ARCHITECTURAL AREA LIGHTING, UNIVERSE COLLECTION, MEDIUM 2.0	LED	AS NOTED
D -	10	UCM2-ANG-36L-260 -3K7-4W	ARCHITECTURAL AREA LIGHTING, UNIVERSE COLLECTION, MEDIUM 2.0	LED	18' - 4 1/2"
0	10	N/A	EXISTING RECESSED BUILDING MOUNTED LIGHTING. MODELED FOR REFERENCE ONLY.	LED	N/A
ф	3	N/A	EXISTING FIXTURES LOCATED ON NEIGHBORING PARCEL. MODELED FOR REFERENCE ONLY.	LED	N/A

DESCRIPTION	SYMBOL	AVG	MAX	MIN	AVG/MAX	AVG/MIN
Project Area	+	0.5 fc	5.4 fc	0.0 fc	N/A	N/A
LIGHT CONTOU	R LEGEND]				
	R LEGEND 10 Foot Candles					
0.1 0 0.5 0.						



FEATURES

 Reliable, uniform, glare free Illumination Types II, III, IV, V and custom distributions 3000K, 4000K, 5000K CCT 0-10V dimming ready

 Integral surge suppression 15 standard powder coat finishes Upgrade Kits







EXISTING CHAIN LINK FENCE EXISTING STOCKADE FENCE EXISTING CONCRETE CURB EXISTING DROP IN CONCRETE CURB EXISTING SIGN EXISTING HEDGE ROW EXISTING TREELINE EXISTING POST MOUNTED LIGHT EXISTING RECESSED LIGHT EXISTING UTILITY POLE PROPOSED # OF STALLS TO BE STRIPED PROPOSED CONCRETE CURB PROPOSED PAINTED HANDICAP PARKING SYMBOL PROPOSED STRIPED ISLAND PROPOSED SINGLE POLE SIGN PROPOSED POLE MOUNTED LIGHT PROPOSED BUILDING MOUNTED LIGHT

<u>LEGEND</u>

EXISTING STONE WALL

EXISTING PROPERTY LINE

LIGHTING NOTES:

pattern differs.

- 1. All lighting shall be as noted on the plan or approved equal.
- 2. Style and finish of all luminaires to be selected by owner.
- 3. Calculation values shown in this plan are taken on a horizontal plane at ground level using a 0.90 light loss factor for LEDs. Topographical information and landscaping have not been accounted for in these calculations.
- 4. Photometric modeling based on similar or specified fixtures. 5. Lighting plan assumes that certain light fixtures will utilize existing foundations. Contractor verify prior to ordering fixtures and shall notify Project Landscape Architect if bolt
- Light levels generated from lighting on adjacent properties are approximate and shown for informational purposes only.

2 10-8-20 PLANNING BOARD SUBMISSION PLANNING BOARD SUBMISSION 1 8-7-20 NO. DATE Carmel, NY 10512 (845) 225-9690 ENGINEERING, SURVEYING & (845) 225-9717 fax LANDSCAPE ARCHITECTURE, P.C. www.insite-eng.com CARMEL FIRE <u>DEPARTMENT</u> 94 GLENEIDA AVENUE, CARMEL, PUTNAM COUNTY, NEW YORK DRAWING: <u>LIGHTING PLAN</u> DRAWING NO. J.M. W. NUMBER

J.F.R.

K.M.G.

7-17-20

1" = 20'


CHECKED BY

GRAPHIC SCALE


(IN FEET)

1 inch = 20 ft.

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.



Z:\E\19135100 Carmel FD\08 PR-1.dwg, 10/8/2020 8:49:52 AM, eappelgren, 1:1



RIB-BAK U-CHANNEL, -

BREAKAWAY POST AS"

APPROVED EQUAL

GALVANIZED STEEL, 3#/FT.,

MANUFACTURED BY NUCOR STEEL MARION INC., OR

COMPACTED SUBGRADE

FINISHED GRADE —


CONCRETE CURB DETAIL (N. T. S.)

- SIGN (SEE TRAFFIC SIGN TABLE)

- GALVANIZED BOLTS WITH NUTS 5/16" DIA.


FACE OF CURB

----- PAVEMENT



ASPHALT PAVEMENT DETAIL

NOTE: DRIVEWAYS SHALL MEET CONSTRUCTION REQUIREMENTS AS OUTLINED IN THE TOWN OF CARMEL CODE §128 STREETS AND SIDEWALKS.



PAINTED NYS ACCESSIBLE PARKING DETAIL

(N.T.S.)

-PROPOSED SUPPORT POSTS

AT 8' ON CENTER

—PROPOSED CONSTRUCTION

CONSTRUCTION EQUIPMENT.

TREE PROTECTION DETAIL


1. INSTALL BARRIER AS SHOWN TO PREVENT

2. OPTIONAL: 2" X 6" WOOD FRAMING BUILT

AS SQUARE AROUND TREE, AS ALTERNATIVE.

COMPACTION OF SOIL AROUND ROOTS BY

LOCATE CONSTRUCTION -FENCE AT DRIP LINE



WITH CELLULAR COMPRESSION MATERIALS AS SPECIFIED, RECESSED 1/4" IN FROM FRONT FACE AND TOP OF CURB. MOUNTABLE CONCRETE CURB DETAIL

STOCKADE FENCE DETAIL (N.T.S.)


(N. T. S.)

STOCKADE

-8" % CONCRETE

FOOTING (TYP.)

FENCE



<u>ELE VA TION</u> NOTE: CHECK WITH REFUSE HAULER PRIOR TO INSTALLATION OF REFUSE ENCLOSURE FOR DIMENSIONS.

DUMPSTER ENCLOSURE DETAIL

(N. T. S.)

—CONCRETE TO BE CROWNED 1/2" *~*−4" DIAMETER STANDARD WEIGHT SCHEDULE 40 GALVANIZED STEEL PIPE (CONCRETE FILLED) -FINISHED GRADE -AIR ENTRAINED CONCRETE (3000 psi) EARTH (TYP.) ¹ DIAMETER ¹ WHEN BOLLARDS ARE TO BE USED FOR PROTECTION OF COMBUSTIBLE OBJECTS, POSTS SHALL BE OFFSET A MINIMUM OF THREE (3) FEET FROM THE OBJECT BEING PROTECTED.

FEET ON CENTER WHEN PROTECTING COMBUSTIBLE OBJECTS.

. BOLLARDS (WHEN MORE THAN ONE IS REQUIRED) SHALL BE SPACED NOT MORE THAN FOUR (4)

— 36" MIN. FENCE POSTS,

DRIVEN MIN. 16" INTO

" MIN. EMBEDMENT

/--- UNDISTURBED GROUND

POSTS: STEEL EITHER T OR U TYPE

OR APPROVED EQUAL

MIRAFI 100X, STABILINKA T140N,

ENVIROFENCE, OR APPROVED


OR 2" HARDWOOD

PREFABRICATED UNIT: GEOFAB,

FILTER CLOTH: FILTER X,


HEIGHT OF FILTER ABOVE 16" MIN. GROUND

STEEL BOLLARD DETAIL (N.T.S.)



REPLACEMENT ASPHALT PAVEMENT DETAIL

(N. T. S.)




TEMPORARY----TYPAR "3401" GEOTEXTILE SEDIMENT POOL OR APPROVED EQUAL CLEAN STONE-__8" х 8" х 16" OR GRAVEL BLOCK (TYPICAL) FILTER FRAME & GRATE


SECTION 'A-A' **CONSTRUCTION NOTES:** 1. LAY ONE LAYER OF BLOCKS ON EACH SIDE OF THE STRUCTURE ON THEIR SIDES FOR DEWATERING. EDGES OF BLOCK SHALL BE 2 INCHES MINIMUM BELOW THE GRATE. BLOCKS SHALL BE PLACED AGAINST THE INLET FOR SUPPORT. PLACE A SECOND LAYER OF BLOCKS ON TOP OF THE FIRST LAYER WITH HOLE FACE UP.


2. GEOTEXTILE SHALL BE PLACED OVER BLOCK OPENINGS TO SUPPORT STONE. 3. USE CLEAN STONE OR GRAVEL 1/2 TO 3/4 INCH IN DIAMETER PLACED ON A


2H: 1V SLOPE OR FLATTER, TO WITHIN 2 INCHES OF THE TOP OF THE BLOCKS. CATCH BASIN IN EXISTING PAVEMENT STONE AND BLOCK DROP INLET PROTECTION DETAIL



CHAIN LINK FENCE DETAIL








PROVIDE STAKING AND GUYING FOR TREES PLANTED ON SLOPES GREATER THAN 3H:1V, IN EXPOSED, WINDY AREAS AND AS SPECIFIED BY LANDSCAPE ARCHITECT. GUY WIRES AND STAKES SHALL BE REMOVED WITHIN TWELVE MONTHS OF PLANTING.


EVERGREEN TREE PLANTING DETAIL (N. T. S.)



<u>INSTALLATION NOTES</u> 1. STONE SIZE - USE 3" STONE

- 2. LENGTH AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.)
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES. 4. WIDTH - 12 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCUR.
- 5. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENCE LOT.
- 6. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED. 7. MAINTENANCE — THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT OF WAY THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS
 CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT OF WAY MUST BE REMOVED IMMEDIATELY.
- 8. WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE OF AN AREA STABILLS DEVICE. APPROVED SEDIMENT TRAPPING DEVICE. 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE DETAIL (N.T.S.)



- 1. AREA CHOSEN FOR STOCKPILE LOCATION SHALL BE DRY AND STABLE.
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 2:1.
- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE IMMEDIATELY SEEDED WITH K31 PERENNIAL TALL FESCUE.

PERSPECTIVE VIEW

CONSTRUCTION NOTES FOR FABRICATED SILT FENCE

SILT FENCE DETAIL

(N. T. S.)

FILTER CLOTH TO BE

EMBED FILTER CLOTH -

MIN. 8" INTO GROUND

POSTS AT TOP AND MID SECTION.

SIX INCHES AND FOLDED.

DEVELOP IN THE SILT FENCE.

1. FILTER CLOTH TO BE FASTENED SECURELY TO

2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN

AND MATERIAL REMOVED WHEN "BULGES"


EACH OTHER THEY SHALL BE OVERLAPPED BY


3. MAINTENANCE SHALL BE PERFORMED AS NEEDED

INSTALLED TO FACE

THE DIRECTION OF

4. ALL STOCKPILES SHALL BE PROTECTED WITH SILT FENCING INSTALLED ON THE DOWNGRADIENT SIDE. TEMPORARY SOIL STOCKPILE DETAIL (N. T. S.)





NOTE: FOR HANDICAP PARKING SIGNAGE, SIGNS SHALL BE INSTALLED


BE OBSCURED BY A VEHICLE PARKED IN THE SPACE.

13W SOLAR PANEL----

AT A CLEAR HEIGHT OF BETWEEN 5'-0" AND 7'-0" ABOVE

GRADE OF PARKING SPACE AND SUCH THAT SIGNS SHALL NOT


FLASHING YIELD SIGN DETAIL



2. GRADE APPROACH TO THE INLET UNIFORMLY AROUND THE BASIN 3. WEEP HOLES SHALL BE PROTECTED BY GRAVEL 4. UPON STABILIZATION OF CONTRIBUTING DRAINAGE AREA, SEAL WEEP HOLES, FILL EXCAVATION WITH STABLE SOIL TO FINAL GRADE, COMPACT IT PROPERLY, AND STABILIZE WITH PERMANENT SEEDING 5. MAXIMUM DRAINAGE AREA = 1 ACRE

EXCAVATED DROP INLET PROTECTION DETAIL

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.





October 7, 2020

Chairman Craig Paeprer and Members of the Planning Board Town of Carmel 60 McAlpin Ave Mahopac, NY 10541

RE: Site Plan for The Mahoven LLC (Lubomir Kaneti) 737 South Lake Boulevard TM #: 75.42-1-13

Dear Mr. Paeprer and Members of the Board,

The following is my response to the Building Inspector's memo dated September 4, 2020.

- 1. We have filed with NYS DOT for the driveway permit.
- 2. The bathhouse has been reduced in size and there is now a 4 FT. aisle from Rt. 6 N to Lake Mahopac.
- 3. The Zoning Chart has been revised.

The following is my response to the Town Planner's memo dated September 16, 2020.


- 1. The proposed extension of the dock will not extend more than 25 FT into the lake.
- 2. The portion of the dock to be removed also includes the supports.
- 3. We have applied for a Driveway Permit from the NYS DOT.

The following is my response to the Town Engineer's memo dated September 4, 2020

- 1. Once the proposed Site Plan layout is agreed to, all the details will be forthcoming.
- 2. The Zoning Chart already indicates that the lake front requirement in 15 FT. and 15 FT. is provided and a 35 FT. variance is required.


If you have any questions, please do not hesitate to contact me.


Very truly yours,






			and the second s		
ALIENSA STORM	PROPERTIES	YIT	HIM	5001	
75.11-2-12	75.11-2-12	75.11-2-19	75.42-1-11	75.42-1-12	
Daniel J Fitzpatrick	Heliodoro R Santacolomo	Sarah Kaplan	Charles Melchner	Bert M Melchner	75.42-1-68
564 West 52nd St Apt 4F	12 Cherry Ln	11 Dorset Dr	722 South Lake Blvd	31 Highridge	Real Holding Corp.
New York, NY 10019	Putnam Valley, NY 10579	Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	740 South Lake Blvd
	**************************************	Assessing Contract about a	******	ivianopae, ivi 10541	Mahopac, NY 10541
75.42-1-61	75.11-2-7	75.11-2-3	75.42-1-68	75 12 1 12	Total Co.
James R OHalloran	Richard Doyle	Johnna Sanzi	Real Management Corp. of NY	75.42-1-13	75.42-1-14
15 Colonial Ter	15 Pine Cone Rd	17 Pine Cone Rd	610 Broadway	Charles J Melchner	Christopher Steckle
Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	Newburgh, NY 12550	417 Seminary Hill Rd	12 Bianca Ct
•				Carmel, NY 10512	Carmel, NY 10512
75.11-2-3	75.11-1-30	75.11-2-2	75.42-1-14	75 42 1 67	100000
Peter Lesley	Stanley Gurewitsch	Ved Parkash	Peter Lesley	75.42-1-67	75.42-1-15
PO BOX 1000	18 Clara Ln	911 1/2 State St	PO BOX 1000	Vincent Cappelletti 740 South Lake Blvd	Daniel Andron
Baldwin Place, NY 10505	Mahopac, NY 10541	Santa Barbara, CA 93101	Baldwin Place, NY 10505		Apt 26E
	•		10000	Mahopac, NY 10541	27110 Grand Central Pkwy Floral Park, NY 110051226
75.11-2-1	75.11-2-17	75.11-2-16	75.42-1-16	75.42-1-17	75.42-1-66
Joseph McKay	Long & Tony Guo	Robert Schiera	Daniel Andron	Daniel Andron	
PO BOX 458	3 Dorset Drive	452 Baldwin Place Rd	Apt 26E	Apt 26E	Christopher Sobieski 746 South Lake Blvd
Mahopac Falls, NY 10542	Mahopac, NY 10541	Mahopac, NY 10541	27110 Grand Central Pkwy	27110 Grand Central Pkwy	
	120 C 120 P (M) 5 T	400	Floral Park, NY 110051226	Floral Park, NY 110051226	Mahopac, NY 10541
75.11-2-18	75.11-1-7	75.11-1-31	75.42-1-18	75.42-1-18	75.42-1-18
Harry Hess	Manuel Inga	Richard S Dudyshyn	RJK Contracting Corp.	RJK Contracting Corp.	75.42-1-18 Ronald J Topal
7 Dorset Dr	15 Trolley Rd	703 Rt 6N	25 Hill St	751 South Lake Blvd	Apt 11A/G
Mahopac, NY 10541	Cortlandt Manor, NY 10567	Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	New York, NY 10024
75.11-1-34	75.11-2-15	75.42-1-1	75.42-1-19	75.42-1-19	75.42-1-19
Cathleen B Fullan	Oscar Chavez	Mahopac Gardens Inc	RJK Contracting Corp.	RJK Contracting Corp.	Ronald Topal
20 Cypress Ln	710 South Lake Blvd	Attn: Karen Piccin, President		751 South Lake Blvd	Apt 11A/G
Yorktown Heights, NY 10598	Mahopac, NY 10541	11 Canopus Rd Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	New York, NY 10024
75.42-1-2	75.11-2-13	75.11-2-13	75.42-1-20	75.42-1-20	75.42-1-20
Robert Beck	Ahmad Hussein	June Fredriksen	RJK Contracting Corp.	RJK Contracting Corp.	Ronald J Topal
c/o Annemarie Catania	716 South Lake Blvd	716 South Lake Blvd	25 Hill St	751 South Lake Blvd	Apt 11A/G
21 Deer Run Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	New York, NY 10024
75.42-1-3	75.42-1-4	75.42-1-5	75.42-1-21	75.42-1-22	75.42-1-23
Gerald D Weis	Robert Stevens	Claudia Stevens	Robert Knapp	Ronald J Topal	Ronald J Topal
277 Cook Ave	245 Lakeshore Dr	245 Lakeshore Dr	60 Dahlia Dr	Apt 11A/G	Apt 11A/G
Yonkers, NY 10701	Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	New York, NY 10024	New York, NY 10024
75.11-2-4	75.42-1-6	75.42-1-7	75.42-1-24		
Charles G Melchner	Robert Stevens	73.42-1-7 725 Lake Property LLC	Ronald J Topal	75.42-1-25	75.42-1-25
722 South Lake Blvd	245 Lakeshore Dr	24 Lake Rd	Apt 11A/G	Real Holding Corp.	Real Management Corp. of NY
Mahopac, NY 10541	Mahopac, NY 10541	Mahopac, NY 10541	New York, NY 10024	740 South Lake Blvd Mahopac, NY 10541	610 Broadway Newburgh, NY 12550
				200000000000000000000000000000000000000	******** = 0-1-1
75.42-1-7	75.42-1-9	75.42-1-10	75.42-1-26	75.42-1-27	75.42-1-28
Benedetto Savino	Claudia Stevens	Jack Nathan	Vincent Cappelletti	Cesar Budiuck	John Buttacavoli
PO BOX 490	245 Lakeshore Dr	PO BOX 500	740 South Lake Blvd	PO BOX 4686	13 Cook Dr
Jefferson Valley, NY 10535	Mahopac, NY 10541	Cooper Station, NY 10276	Mahopae, NY 10541	Sunnyside, NY 11104	Mahopac, NY 10541
75.11-2-6	64.20-1-9	75.11-2-14		LAK	EMAHOPAC
Susan Hayes	State Of New York	Robert Schiera		A (KANE	71
9 Pine Cone Rd	40 Gleneida Ave	452 Baldwin Place Rd		4 4	10/20/19
Mahopac, NY 10541	Carmel, NY 10512	Mahopac, NY 10541		10997	2/19
				16/1/18 18/18	1 1 2 10-
75.11-1-37	75.11-1-35	75.11-1-35		/ 121 g 13 14 15	
Kenneth Rose	Jane (aka Ethel) Benjamin	Millicker Family Trust		67.36	
60 East 96th St Unit 9B	24 Mediterranean Ct	PO BOX 130		,	1 11
New York, NY 10128	Barnegat, NJ 08005	Mahopac Falls, NY 10542		35.33/ 15 20.0 10 10	20.0 10 " 102.75
	me 11.1 co	75 11 1 22		TO BALDWILL	our place to
75.11-1-36	75.11-1-33	75.11-1-32 Delzio's Playa Para Los Ninos			AKE BLVD RIEG
William Boyar	Christopher Steckle 403 Baldwin Place Rd	Deizio's Playa Para Los Niños 11 Otha Dr		ROUT	E GN
PO BOX 444 Mahanas Falls, NV 10542	Mahopac, NY 10541	Katonah, NY 10536		LOCATION	. NA A-O
Mahopac Falls, NY 10542	Interiopae, 14 t 10541	12monut, 141 10550		LOCATION	WAL NID











TWO MUSCOOT ROAD NORTH
MAHOPAC, NY 10541
P 845-628-6613
F 845-628-2807
www.arch-visions.com

PERGOLA & BATHHOUSE FOR MAHOVEN, LLC

LUBOMIR KANETI

737 SOUTH LAKE BLVD. MAHOPAC, NY 10541

TAX MAP NO. 75.42-1-13

PROJECT NO. 05-20-050

DATE: 10/7/2020

<u>DWG S-102</u>





TWO MUSCOOT ROAD NORTH MAHOPAC, NY 10541 P 845-628-6613 F 845-628-2807 www.arch-visions.com

PERGOLA & BATHHOUSE FOR MAHOVEN, LLC

LUBOMIR KANETI

737 SOUTH LAKE BLVD. MAHOPAC, NY 10541

TAX MAP NO. 75.42-1-13

PROJECT NO. 05-20-050

DATE: 10/7/2020

<u>DWG S-103</u>

ALFRED A. CAPPELLI, JR. ARCHITECT 1136 ROUTE 9 WAPPINGERS FALLS, NY 12590

Telephone: 845-632-6500 Fax: 845-632-6499 Email: acappe2102@aol.com

Oct. 8, 2020

Town of Carmel Planning Board 60 McAlpin Ave. Mahopac, NY

Re:

Re-submittal to Planning Board

Zakon Project, Corner NYS Rt. 6 & Nicole Way

TM #65.6-1-22

Dear Chairman Paeprer & Planning Board Members,

Attached please find five sets of revised site plans along with a revised narrative explaining the changes to the plans.

We would very much like to be placed on the next available Planning Board Agenda to continue discussion with the Board on this matter.

If there is anything else that is needed, please do not hesitate to let us know.

Thank you,

Alfred A. Cappelli, Jr.

Architect

AAC/dc Enc.

REVISED

APPLICATION, PROJECT NARRATIVE & EAF

FOR COMMERCIAL DEVELOPMENT

FOR

JOE ZAKON, DBA

14 NICOLE WAY, LLC

CORNER OF NYS ROUTE 6 & NICOLE WAY

TOWN OF CARMEL

PUTNAM COUNTY

NEW YORK

PREPARED BY:

ALFRED CAPPELLI, JR.
ARCHITECT
1136 ROUTE 9
WAPPINGERS FALLS, NY

PHONE: 845-632-6500 EMAIL: acappe2102@aol.com

DECEMBER 18, 2018 REVISED JANUARY 23, 2020 REVISED AUGUST 31, 2020 REVISED OCTOBER 8, 2020

PROJECT OBJECTIVE:

It is the intent of the applicant to construct one building on property known as 14 Nicole Way for the storage of commercial vehicles.

2. APPLICANT:

The applicant is Joe Zakon, 14 Nicole Way, LLC, and owner of local business, Optimum Oil & Propane whose current business location is in the T/O Carmel. Mr. Zakon also resides in the T/O Carmel.

3. PROJECT LOCATION:

The project location is on the southeast corner of the intersection of NYS Rt. 6 and Nicole Way aka 14 Nicole Way, in the T/O Carmel, Putnam County, NY and is also identified as TM 65.01-1-22.

4. SITE DESCRIPTION:

The site is a corner vacant lot, approx. 201" x 207", approx. 1.417 acres. The lot is lightly wooded and gradually slopes up from Rt. 6 up to Nicole Way in the rear.

5. ZONING:

The zoning of the property is Commercial (C) and allows the use proposed.

PROJECT DESCRIPTION/APPLICANT'S PROPOSAL:

It is the applicant/owner's intent to construct only one building on the site for his use. The building would be a $63 \times 90'$, 5,520 sf structure.

Within the building, the owner's own operation, Optimum Oil & Propane would occupy this space for the storage of four – five fuel oil delivery trucks.

When in storage at night, the trucks would be empty of fuel oil as required by code and insurance regulations.

Trucks will leave in the morning and go to the terminals to fill up before delivering fuel oil local to local residences and businesses.

A small section of the garage will be used for storage of parts and equipment incidental to the fuel oil business for service repairs.

There will be a small section "carved" out of the garage bay area for the owner's use.

There will be a service counter area for those who may stop by to pay bills in person or the occasional pick up of a small part for their heating system.

This is not intended to be a retail establishment.

There will be 4-5 employees driving the trucks, depending on the season, with the maximum number in the winter and less drivers in the summer, in addition to Mr. Zakon and one secretary. The drivers will be on the road all day, so in reality, there will be only two full time occupants.

There will be no oil trucks parked outside the garage, particularly in the evening.

Business hours will be 8:00 a.m. to 4:30 p.m., Monday through Friday and 8:00 a.m. to 12:00 noon on Saturday. There will be no business hours on Sunday or in the evenings.

The owner, however, reserves the right, depending on emergency situations, to occasionally have a fuel oil or service vehicle exit or enter the site beyond the hours noted above, but this should be on rare occasions.

Please note, that although fuel oil is a necessity in many cases 52 weeks per year, there will fewer deliveries in the off season with the maximum of staff and vehicles in operation between October and April.

There will be no noise generated from idling trucks warming up in the morning as they are being parked in a heated environment, eliminating the need for long warm-ups.

There will also be no on-site repair of trucks either outside or inside the building. Mr. Zakon has his vehicles serviced elsewhere.

There will also be a small office component for possible office rental, and this has been calculated for the proper parking quantity.

7. BUILDING DESIGN:

The nature of the building's uses suggests a durable material to take the abuse of day to day activities, hence masonry in the form of poured concrete and concrete block will be utilized for part of the exterior construction material for the buildings.

The roof will be a gable roof utilizing asphalt shingles as the finished roofing material.

The building has been situated and designed to have all activities, the garage doors, etc. facing Rt. 6.

Also, the fact that the building, by virtue of the topography, will be built into the hillside and create a much lower profile and be less imposing to the residential neighborhood.

The building's material and Architecture has been designed to complement the surrounding residential nature by way of shape, features and materials.

8. SITE UTILITIES:

Potable water for the building's use will be by way of an on-site drilled well.

The sanitary system will be composed of an on-site sewage disposal system to handle the minimal water use of this type of building and the nature of its use.

Both of the above will require Putnam Count Health Dept. approval.

Stormwater will be collected in catch basins discharging into an on-site infiltration system which will collect and dissipate the stormwater that is created by the newly created impervious areas.

Individual underground electric service will service the building.

9. OTHER SITE IMPROVEMENTS AND SITE AMENITIES:

Other site improvements and amenities will include, but not necessarily be limited to:

- Asphalt paved driveway and parking area
- Concrete and asphalt curbing
- Concrete sidewalks
- Landscaping
- Site lighting
- Fencing to protect, secure and visually obscure an outside storage area for Optimum Oil & Propane's storage for propane canisters and small tanks for residential use. This area will be inaccessible to the public.

Short Environmental Assessment Form Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.


Part 1 - Project and Sponsor Information								
Name of Action or Project: PROPOSED NEW STORAGE BUILDING FOR JOE	ZAKON							
Project Location (describe, and attach a locati 14 NICOLE WAY, CORNER WITH NYS ROUTE 6	on map):							
Brief Description of Proposed Action: CONSTRUCTION OF A NEW 5,520 SF BUILDING T	O BE USED FOR S	TORAC	GE OF OWNE	RS FUEL OIL DE	ELIVERY TR	ucks		
Name of Applicant or Sponsor:		-		Telephone: 84	45 632-6500			
ALFRED CAPPELLI, JR. ARCHITECT				E-Mail: ACAF	PPE2102@A	OL.COM		
Address: 1136 ROUTE 9								
City/PO: WAPPINGERS FALLS				State: NY		Zip Co 12590	de:	
Does the proposed action only involve the administrative rule, or regulation? If Yes, attach a narrative description of the immay be affected in the municipality and process. Does the proposed action require a permit If Yes, list agency(s) name and permit or approximately.	tent of the propose ed to Part 2. If no t, approval or func royal PLANNING B	ed action, conting from	on and the e inue to ques om any othe FOR SITE PL	nvironmental retion 2.	esources the Agency? T. FOR BLDG		NO NO	YES YES
a. Total acreage of the site of the propose b. Total acreage to be physically disturbe c. Total acreage (project site and any con or controlled by the applicant or proj	ed action? ed? tiguous properties			1.41 acres .99 acres 1.41 acres				
4. Check all land uses that occur on, are adjusted. 5. Urban Rural (non-agriculture) Forest Agriculture Parkland	oining or near the p Industrial Aquatic	Towns I	ced action: Commercia Other(Spec		ntial (subur	ban)		

Page I of 3

5.	Is the proposed action,	YES	N/A
	a. A permitted use under the zoning regulations?		
	b. Consistent with the adopted comprehensive plan?	~	
6	Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES
6.	is the proposed action consistent with the predominant character of the existing built of natural landscape.		V
7.	Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?	NO	YES
If Y	Yes, identify:	V	
		NO	YES
8.	a. Will the proposed action result in a substantial increase in traffic above present levels?	V	
	b. Are public transportation services available at or near the site of the proposed action?	V	
	c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?	V	
9.	Does the proposed action meet or exceed the state energy code requirements?	NO	YES
Ift	he proposed action will exceed requirements, describe design features and technologies:		
		V	
10	Will the proposed action connect to an existing public/private water supply?	NO	YES
	If No, describe method for providing potable water:	V	
11	. Will the proposed action connect to existing wastewater utilities?	NO	YES
	If No, describe method for providing wastewater treatment:		
12	a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district	NO	YES
Co	nich is listed on the National or State Register of Historic Places, or that has been determined by the ommissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the late Register of Historic Places?	~	
ar	b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for chaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	V	
13	a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO	YES
	b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?	V	ĪĒ
If	Yes, identify the wetland or waterbody and extent of alterations in square feet or acres:	-	
		-	
-			


14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply:		
☐ Shoreline ☐ Forest ☐ Agricultural/grasslands ☐ Early mid-successional		
□Wetland □ Urban ☑ Suburban		
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or	NO	YES
Federal government as threatened or endangered?		V
16. Is the project site located in the 100-year flood plan?	NO	YES
	V	
17. Will the proposed action create storm water discharge, either from point or non-point sources?	NO	YES
If Yes,	Ш	0
a. Will storm water discharges flow to adjacent properties?	V	
b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? If Yes, briefly describe:	V	
18. Does the proposed action include construction or other activities that would result in the impoundment of water or other liquids (e.g., retention pond, waste lagoon, dam)?	NO	YES
If Yes, explain the purpose and size of the impoundment:		
	6	Ш
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility?	NO	YES
If Yes, describe:		
	~	
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste?	NO	YES
If Yes, describe:		
	~	
I CERTIFY THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BI	EST OF	
MY KNOWLEDGE	.or or	
Applicant/sponsor/name: ALFRED CAPPELLI, JR., PROJECT ARCHITECT Date: 10/8/20 (REVIS	ED)	
Signature:		

AREA MAP





JOE ZAKON - COMMERCIAL DEVELOPMENT 14 NICOLE WAY & NYS ROUTE 6

LOCATION MAP



JOE ZAKON - COMMERCIAL DEVELOPMENT 14 NICOLE WAY & NYS ROUTE 6






JOE 6 & NI

DATE 10/8/18 SCALE 1" = 20' 18 010

S 2



REVISIONS BY

N.Y. 12590

ECT
TE 9 WAPPINGERS FALL

ARCHITECT 1136 ROUTE 9 WA

JOE ZAKON dba 14 NICOLE WAY CORNER OF ROUTE 6 & NICOLE WAY TOWN OF CARM

ANDSCAPING PLAN, DETAILS & NOTES

DATESEPT. 29, 2020


SCALE 1" = 20'

DRAWN AC

JOB 18-010

SHEET

\$-3




ROUTE (845) 632 1136 Phone:

COLE ママッ ZAKON
OF ROUTE A JOE

SEPT. 29, 2020 JAN. 6, 2020

DATE 10/8/18 SCALE AS NOTED AC

18-010



PRE-CONSTRUCTION SEQUENCE:

- SUBMIT NOTICE OF INTENT (N.O.I) TO NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION (NYS DEC) BUREAU OF WATER PERMITS, ALBANY NY.
- 2. RECEIVE ACKNOWLEDGMENT OF N.O.I . FROM NYS DEC.
- 3. HOLD A PRE-CONSTRUCTION MEETING WITH THE OWNER/OPERATOR, SITE ENGINEER, TOWN ENGINEER, TRAINED CONTRACTOR, QUALIFIED EROSION CONTROL INSPECTOR AND THE BUILDING INSPECTOR. PLACE A COPY OF THE SWPPP REPORT IN SITE MAILBOX ALONG WITH A COPY OF THE INSPECTOR'S LOG BOOK CONTAINING COPIES OF THE WEEKLY INSPECTIONS (APPLICANT'S EROSION & SEDIMENT CONTROL INSPECTION AGENT SHALL CONDUCT AN INSPECTION ON A WEEKLY BASIS)

CONSTRUCTION SEQUENCE:

- PRIOR TO CONSTRUCTION, THE ANTI-TRACKING PAD SHALL BE INSTALLED.
- 2. INSTALL SEDIMENT AND EROSION CONTROL MEASURE AS SHOWN ON THE SEDIMENT & EROSION CONTROL PLAN.
- 3. COMMENCE INITIAL CLEARING AND GRUB OF THE SITE.
- 4. BEGIN SITE GRADING AND EXCAVATION, ROUGH CUT PARKING AREAS TO SUB-GRADE
- 5. AREAS WHERE INFILTRATION MEASURES (E.G. SEPTIC AND POROUS PAVEMENT) ARE PROPOSED SHALL BE CORDONED OFF AFTER COMPLETION OF ROUGH GRADING WITH CONSTRUCTION FENCE TO MINIMIZE COMPACTION DURING THE REMAINDER OF CONSTRUCTION TO EVERY EXTENT POSSIBLE
- 6. INSTALL RETAINING WALLS AND GRADE REMAINDER OF THE SITE.
- 7. INSTALL SITE UTILITIES AND/OR INFRASTRUCTURE
- 8. PLACE CONCRETE FOOTINGS AND FOUNDATIONS FOR THE PROPOSED BUILDING AND OTHER STRUCTURES.
- ONCE ALL MAJOR SITE WORK HAS BEEN COMPLETED, INSTALL THE POROUS PAVEMENT STONE BASE AND SEPTIC SYSTEMS.
- 10. INSTALL BINDER COURSE, SIDEWALKS AND CURBING ONCE ALL MAJOR SITE WORK IS COMPLETE.
- 11. TOPSOIL, SEED AND MULCH ALL DISTURBED AREAS THAT HAVE OBTAINED FINISHED GRADE ELEVATIONS.
- 12. SEED AND MULCH ALL DISTURBED AREAS THAT WILL NOT BE RE-DISTURBED FOR AT LEAST 14 DAYS.
- 13. FINALIZE BUILDING CONSTRUCTION.
- 14. INSPECT INFILTRATION SYSTEM FOR ANY SEDIMENT ACCUMULATION AND/OR DAMAGE.
- 15. PAVE PARKING AREA AND DRIVES WITH FINAL TOP-COAT OF ASPHALT.
- 16. ONCE ALL MAJOR SITE DISTURBANCE ACTIVITIES HAVE CEASED AND THE SITE HAS ACHIEVED FINAL STABILIZATION, COORDINATE WITH THE LOCAL MS4 STORM WATER OFFICER TO FACILITATE TERMINATION OF EROSION CONTROL INSPECTIONS.
- 17. ONCE THE SITE IS STABILIZED (I.E. THE GRASS HAS BEEN STABILIZED), THE EROSION CONTROL MEASURES CAN BE REMOVED.
- 18. FILE A NOTICE OF TERMINATION WITH THE NYS DEC.

SITE NOTES

- 1. PROPERTY BOUNDARY, TOPOGRAPHY AND EXISTING UTILITY SHOWN HEREON ARE BASED ON A SURVEY ENTITLED "TOPOGRAPHIC SURVEY PREPARED FOR 14 NICOLE WAY, INC." DATED MAY 4, 2018.
- 2. ESTIMATED AMOUNT OF MATERIAL EXPORTED 2,800YD³ ESTIMATED TRUCK TRIPS 187

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW FOR ANY PERSONS TO ALTER THESE PLANS, SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR.

		Mark A. Day, PE
	09-29-2020	
	08-05-2020	
	07-23-2020	
	04-08-2020	
100	03-16-2020	089840 /07/
	03-03-2020	N ESSIONAL!
Revisions	02-19-2020	
Project No.	2018:419	License No. 069646

DAY STOKOSA Engineering P.C.

3 Van Wyck Lane


Wappingers Falls, New York 12590 (845) 223-3202


14 Nicole Way

Town of Caramel Putnam County, New York

Grading Plan

1" = 20'	BJW	C-1
DATE	CHECKED BY	O-1
01-25-20	MAD	1 of 9





LUMINAIRE SCHEDULE									
CALLOUT	SYMBOL	LAMP	DESCRIPTION	LUMENS / LAMP	BALLAST	${\it MOUNTING}$	MODEL	VOLTS	QUANTITY
Pole Mount	○ —□	(1) 3,000K LED	Howard Lighting Products L400 Series Street and Area Light	2427	ELECTRONIC	POLE	L401L-25W-40K-T4	120V 1P 2W	7
Wall Mount	Ю	(1) 5,000K LED	Howard Lighting Products Medium Wall Pack (MWP)	2360	ELECTRONIC	WALL	MWP-5028R-LED-MV	120V 1P 2W	8

GENERAL

SCHEDULE

AVERAGE FOOT-CANDLES

FOOT-CANDLES

FOOT-CANDLES

MAXIMUM

MINIMUM

FC RATIO

FC RATIO

FC RATIO

FC RATIO

PHOTOMETRIC

MINIMUM TO MAXIMUM 0.00

AVERAGE TO MAXIMUM 0.09

MAXIMUM TO MINIMUM 4.09 / 0.00

AVERAGE TO MINIMUM | 0.37 / 0.00

0.37

4.1

0.0

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW FOR ANY PERSONS TO ALTER THESE PLANS, SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR

PROFESSIONAL ENGINE	ER OR LAND SURVEYO
	Mark A. Day, PE
09-29-2020	
08-05-2020	
07-23-2020	
04-08-2020	
03-16-2020	11 1 0898 10 15°
03-03-2020	TO STONAL!
Revisions 02-19-2020	
Project No. 2018:419	License No. 069646

DAY STOKOSA ENGINEERING P.C.

3 Van Wyck Lane

Town of Caramel

Suite 2 Wappingers Falls, New York 12590 (845) 223-3202

14 Nicole Way

Putnam County, New York


Lighting Plan

1" = 20'
BJW

TE CHECKED BY
01-25-20 MAD

CHAWN BY
BJW

CHECKED BY
3 of 9



IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW FOR ANY PERSONS TO ALTER THESE PLANS, SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR.



ENGINEERING P.C.


3 Van Wyck Lane


Suite 2 Wappingers Falls, New York 12590 (845) 223-3202

14 Nicole Way
Tax Map 65.01-1-22

Town of Caramel Vehicle Movement Plan

1" = 30' 01-25-20 4 of 9





CONSTRUCTION NOTES:

1. THE TOP OF THE PIPES TO BE SET AT EQUAL ELEVATIONS WHEN INLET PIPE IS SMALLER THAN OUTLET PIPE. 2. POLYPROPYLENE STEEL REINFORCED PLASTIC STEPS AS SUPPLIED BY M.A. INDUSTRIES, OR EQUAL, TO BE SET EVERY 12" TO BOTTOM

OF CATCH BASIN. 3. FRAME AND GRATE TO MEET OR EXCEED H-20 LOADING.

4. ALL PIPES SHALL BE INSTALLED FLUSH WITH THE INSIDE WALL OF THE CATCH BASIN AND GROUTED IN PLACE ON BOTH THE INSIDE AND OUTSIDE FACE OF THE BASIN

5. BRICK FRAME AND GRATE TO GRADE MATCH BOTH CROWN OF ROAD AND SLOPE OF ROAD. A MAXIMUM OF TWO TIERS OF CONCRETE BRICKS OR ONE 6" SOLID CONCRETE BLOCK SHALL BE PERMITTED. RISERS SHALL BE PARGED BOTH INSIDE AND OUTSIDE.

6. BASE AND RISER SECTIONS SHALL BE INTEGRALLY CAST 7. INSIDE DIMENSIONS SHALL REMAIN CONSTANT FROM TOP TO BOTTOM AND SHALL MATCH THE FRAME OPENING OF THE GRATE.

8. THE BASINS SHALL CONFORM TO ASTM C-478 SPECIFICATIONS AND SHALL HAVE A MIN. 28-DAY COMPRESSIVE STRENGTH OF 4,000

9. PROVIDE PROPER ANCHORING IN CASES OF HIGH GROUNDWATER

TO PREVENT FLOATATION. 10. ALL BASINS WITH A TOTAL DEPTH OF GREATER THAN 8'-0" SHALL HAVE A MIN. WALL THICKNESS OF 8".


11. LADDER RUNGS TO BE PROVIDED FOR CATCH BASINS IN EXCESS OF 4'-0" TOTAL DEPTH (TOP TO BOTTOM OF SUMP).

12. DRAINS TO CONNECT TO STORM SEWER SYSTEM WHENEVER POSSIBLE UNLESS OTHERWISE STATED IN THE APPROVED PLANS.

13. SHOP DRAWINGS TO REFLECT KNOCKOUTS OR OPENING SIZES INDICATIVE OF OUTSIDE PIPE DIAMETER FOR VARIOUS PIPE SIZES AND LOCATIONS WHERE PIPE(S) DO NOT MEET BASIN AT RIGHT ANGLES.

PRE CAST CONCRETE DROP INLET

NOT TO SCALE



1. FILL OR BACKFILL MATERIAL SHALL BE DEPOSITED IN 12" LIFTS. EACH LIFT SHALL BE


COMPACTED TO 95% STANDARD PROCTOR PRIOR TO THE PLACEMENT OF THE NEXT LIFT. 2. BACKFILLING AROUND PIPES SHALL BE DONE UNIFORMLY ON EACH SIDE OF THE PIPE.BACKFILL MATERIAL SHALL BE 1-1/2" MINUS GRADATION.

3. ALL SITE UTILITIES ARE TO BE INSTALLED BY A QUALIFIED CONTRACTOR & INSPECTED BY THE DESIGN ENGINEER PRIOR TO BACKFILLING. 4. IN THE EVENT THAT THE CONDUIT IS BEING INSTALLED IN WET CONDITIONS, THE CONTRACTOR

SHALL LINE THE TRENCH WITH FILTER FABRIC & BED THE PIPE IN 3/4" CRUSHED STONE INSIDE

5. BACKFILL MATERIAL SHALL BE FREE FROM ORGANICS, BOULDERS, FROZEN SOILS OR OTHER **DELETERIOUS MATERIAL.**

TRENCHING DETAIL NOT TO SCALE



SUBGRADE MUST HAVE ADEQUATE BEARING CAPACITY AND BE SUITABLE FOR INFILTRATION, DO NOT COMPACT.

2. IF THE NATIVE SOIL HAS BEEN EXPOSED TO RAINFALL DURING EXCAVATING TO THE BOTTOM OF THE FACILITY, HAND RAKE THE SURFACE TO A DEPTH OF 3" TO RESTORE INFILTRATION CAPACITY. 3. AGGREGATE BASE COURSE SHALL BE DELIVERED CLEAN (2% WASH LOSS) AND WASHED ON-SITE TO

REDUCE WASH LOSS TO 0.5%. THIS MAY BE DONE BY HOSING THE ROCK OFF WHILE STILL IN THE DELIVERY TRUCK OR AFTER STOCKPILING. HOSE OFF AS NEEDED AS THE PILE DIMINISHES SINCE FINES WILL MIGRATE TO LOWER LEVELS OF THE PILE.

4. AGGREGATES MUST BE PROPERTY COMPACTED TO PROVIDE A STABLE SURFACE SUCH THAT THE BASE ROCK WILL NOT ROLL AND CAUSE A WAVY APPEARANCE IN FINISHED PAVED SURFACE. 5. CHOKER COURSE IS OPTIONAL AND HELPS TO "LOCK IN" THE LARGER BASE COURSE AND STABILIZE THE SURFACE FOR ROLLING. THIS COURSE MAY BE FIELD DETERMINED IF REQUIRED AND IS

TYPICALLY 1-2 INCHES IN DEPTH. 6. No. 2 STONE MAY BE REPLACED WITH No.3 OR No.4 STONE FOR THE SUBBASE.

7. POROUS ASPHALT PAVEMENT SHALL BE A BITUMINOUS MIX, 1/2 INCH NOMINAL MAXIMUM AGGREGATE SIZE, 16-20% AIR VOIDS AND DRAINDOWN LESS THAN 0.3%.

POROUS ASPHALT (LOCATION AS PER SITE PLAN) NOT TO SCALE

VARIES

4'-0" MAX

9" MIN.

NOT TO SCALE

41" "REDI-ROCK"

MIDDLE BLOCK

FINISHED GRADE

WITH 1.625'

SETBACK

THE CONTRACTOR SHALL VERIFY WALLS BASED ON ACTUAL FIELD CONDITIONS AND GRADING. CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF ACTUAL

5'-6"

QUANTITIES OF MATERIALS REQUIRED FOR INSTALLATION. 2. UNSUITABLE SOILS IN THE FOUNDATION SHALL BE REMOVED AND REPLACED WITH \(\frac{3}{4} \)" CRUSHED STONE. THIS INCLUDES ANY FROZEN SOILS PRESENT AT THE

TIME OF INSTALLATION. 3. THE REDI-ROCK WALL UNITS SHALL HAVE A MIN. 28-DAY COMPRESSIVE

STRENGTH OF 4,000 PSI. 4. THE BASE STONE SHALL BE A 12" THICK BED OF $\frac{3}{4}$ " CRUSHED STONE. THE BASE STONE SHALL BE COMPACTED TO 95% OF STANDARD PROCTOR DENSITY (ASTM

THE FIRST COURSE OF BOTTOM BLOCK SHALL BE PLACED ON THE STONE BASE AND CHECKED FOR LEVEL AND ALIGNMENT PRIOR TO INSTALLING SUBSEQUENT _AYERS OF BLOCK. 6. SWEEP ALL EXCESS MATERIAL FROM THE TOP OF THE BLOCK PRIOR TO

NSTALLING THE NEXT LAYER OF BLOCK. THE RETAINED BACKFILL SHALL BE AS FOLLOWS:

0-100

0-35

PLACE SOLID PVC DRAIN PIPE ---THROUGH NOTCHED HOLE

AND GROUT INTO PLACE

SIEVE SIZE % PASSING 3/4" 100-75

No. 4

No. 200

2'-10"

Non-woven geo extile fabric between

 $rac{1}{2}$ Fill all void spac is in and between blocks

Non-woven ged extile fabric at back of XL

blocks and behind drainstone (if specified

by Engineer balled on site soil conditions)

adjacent blocks at face (required)

with drainstone ASTM No. 57 or

Redi-Rock XL F ock (typical)

3'-0"

30 mil PVC or EPDM geomembrane

(Textured on both sides)

(AASHTO M288 Survivability Class 2)

between geomembrane and soil

Non-woven geotextile fabric

Non-woven geotextile fabric

Drain (As specified by Engineer)

RETAINING WALLS OVER 4FT IN HEIGHT ARE REQUIRED TO BE

DESIGNED BY A NYS LICENSED PROFESSIONAL ENGINEER. FINAL DESIGNS BASED UPON THE APPROVED SITE PLAN ARE TO BE SEALED

AND SIGNED AND SUBMITTED TO THE AUTHORITY ISSUING THE

BUILDING PERMIT PRIOR TO CONSTRUCTION FOR APPROPRIATE

CONNECT TO

PERFORATED

WALL DRAIN

Middle block (Typical)

REVIEW AND APPROVAL.

Solid bottom block

8. ENSURE THAT EACH COURSE IS COMPLETELY INSTALLED, BACKFILLED AND COMPACTED PRIOR TO INSTALLING SUBSEQUENT LAYERS OF BLOCK.

BACKFILL SHALL BE PLACED WITH A MAXIMUM DEPTH OF 8" LIFTS AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (ASTM D698).

10. ONLY HAND-OPERATED COMPACTION EQUIPMENT SHALL BE ALLOWED WITH 3'

FIELD INSTALLED PIPE

OF THE BACK SURFACE OF THE CONCRETE BLOCK. 11. ACTUAL BLOCKS USED AND REQUIRED INCLUDING SPECIALITY BLOCKS (HALF BLOCK, PLANTER, GARDEN, ETC.) VARY TO ACCOMMODATE ACTUAL WALL AND


GRADING AND PROVIDE TOP OF WALL FINISH. 12. MAXIMUM WALL EXPOSURE SHALL BE 4 FEET IN HEIGHT. THIS MAY BE ACCOMPLISHED THROUGH VARYING THE DEPTH OF THE BOTTOM COURSE OF REDI-ROCK OR APPROPRIATE GRADING OF THE SURROUNDING AREA. A COURSE MAY BE FULLY BURIED IF CONDITIONS WARRANT TO ACCOMMODATE THE HEIGHT OF THE INDIVIDUAL BLOCKS.

> IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW FOR ANY PERSONS TO ALTER THESE PLANS. SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED

OUTLET PIPING TO EXIT WALL

EVERY 50' FOR THE LENGTH

OF THE WALL



License No. 069646 2018:419

ENGINEERNG P.C. 3 Van Wyck Lane

Suite 2 Wappingers Falls, New York 12590 (845) 223-3202

Town of Caramel

14 Nicole Way

Site Details

Putnam County, New York

N.T.S. 01-25-20 6 of 9

GRAVITY RETAINING WALL (HEIGHT LESS THAN 4 FT)

TIERED GRAVITY RETAINAING WALL (TOTAL HEIGHT 10FT)

FINISHED GRADE

28" "REDI-ROCK" TOP BLOCK

RETAINED SOIL

GEOTEXTILE FABRIC

PERFORATED PIPE

BOTTOM BLOCK WIT 1

41" "REDI-ROCK"

1.625" SETBACK


NON-WOVEN

CRUSHED STONE


- 4" PVC


—— 18" OF ⅔"

WITH 1.625" SETBACK



TYPICAL LIFT STATION OWTS NOT TO SCALE





- 1. A 10' MINIMUM SEPARATION DISTANCE SHALL BE MAINTAINED BETWEEN THE SEWER LATERAL AND THE WATER SERVICE LINE.
- 2. THE SEWER LATERAL PIPING SHALL BE SDR-35 PVC AT 2% MIN. SLOPE, ALL JOINTS TO
- BE "BELL & SPIGOT" TYPE 3. THE MATERIAL IMMEDIATELY SURROUNDING THE PIPE TO BE READILY COMPACTABLE SOIL (SAND, LOAMY SAND OR LOAMY CLAY), FREE OF FROZEN LUMPS, DEBRIS, OR STONES LARGER THAN 3/4". THE PIPE SHALL BE BACK-FILLED IN 6" MAXIMUM LIFTS TO A FINAL COMPACTION OF 85%.
- 4. A METAL DETECTION TAPE SHALL BE INSTALLED OVER THE SEWER LATERAL TO
- FACILITATE FUTURE LOCATION. 5. ALL SITE SANITARY SEWER UTILITIES ARE TO BE INSTALLED BY A TOWN LICENSED

PLUMBER OR QUALIFIED CONTRACTOR, IN ACCORDANCE WITH THE TOWN PLUMBING

- CODE & INSPECTED BY THE SEWER DEPARTMENT PRIOR TO BACKFILLING. 6. CLEAN-OUTS TO BE INSTALLED AT A MAXIMUM DISTANCE OF 50', AND AT ANGLE FITTINGS AND BENDS.
- 7. EMBEDMENT OF LATERALS SHALL BE THE SAME AS THE MAINS.

TYPICAL BUILDING SANITARY SEWER LATERAL DETAIL NOT TO SCALE

- 1. THE CONTRACTOR SHALL SEAL PENETRATIONS IN THE TANK SO THAT THE TANK IS WATERTIGHT
- 2. THE TANK SHALL BE CONSTRUCTED FROM CONCRETE WHICH SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT A STANDARD 28 DAY COMPRESSIVE TEST.
- 3. #4 & #5 REBAR SHALL BE USED AS REINFORCEMENT FOR THE
- 4. TWO-PIECE TANKS SHALL BE SEALED WITH A BUTYL GASKET OR AS PER THE MANUFACTURER'S RECOMMENDATIONS.
- 5. THE CONTRACTOR SHALL SEAL THE JOINT BETWEEN THE TOP OF THE TANK & THE CAST IRON FRAME WITH A BUTYL SEALANT.
- 6. THE CONTRACTOR SHALL SEAL THE CONCRETE MANHOLES WITH A COAT OF BITUMASTIC SEALANT APPLIED TO THE SEAT OF THE MANHOLE.
- 7. THE FINISHED GRADE AROUND THE MANHOLE OPENINGS SHALL ENSURE THAT WATER WILL FLOW AWAY FROM THE LID.
- 8. IF TANK IS SEGMENTED, CONTRACTOR SHALL PERFORM A HYDROSTATIC TEST ON THE TANK UPON INSTALLATION AND PRIOR TO BACKFILLING, BY OF FILLING THE TANK TO THE BOTTOM OF THE CONCRETE LID WITH WATER AND VERIFYING THAT NO APPRECIABLE LOSS OCCURS DURING A 24 HOUR PERIOD. A NYS LICENSED PROFESSIONAL ENGINEER SHALL VERIFY IN WRITING TO THE DUTCHESS COUNTY DEPARTMENT OF HEALTH THE RESULTS OF THE HYDROSTATIC TEST.
- 9. THE FRAME & GRATE SHALL BE LOCKING, VANDAL PROOF WATERTIGHT LID.
- 10. TANK SHALL BE HS20-44 + 30% / ASTM C857 (H20 TRAFFIC LOADING RATED)






Quick4 Equalizer 36 Chamber **Typical Trench View** INFILTRATOR® 1-800-221-4436 Quick4.

EFFECTIVE LENGTH

MultiPort EndCap



SIDE VIEW INFILTRATOR WATER TECHNOLOGIES, LLC ("INFILTRATOR") Infiltrator Water Technologies, LLC STANDARD LIMITED Drainfield WARRANTY (a) The structural integrity of each chamber, endosp, EZflow expanded polystyrene and/or other sccessory manufactured by Infiltrator ("Units"), when installed and operated in a leachfield of an onsite septic system in accordance with Infiltrator's instructions, is warranted to the original purchaser ("Holder") against defective materials and workmanship for one year from the date the the septic permit is issued for the septic system containing the Units; provided, however, that if a septic permit is not required by applicable law, the warranty period will begin upon the date that installation of the septic system commences. To exercise its warranty rights, Holder must notify Infiltrator in writing at its Corporate Headquarters in Old Saybrook, Connecticut within fifteer (15) days of the alleged defect, Infiltrator will supply replacement Units for Units determined by Infiltrator to be covered by this Limited Warranty, Infiltrator's liability specifically excludes the cost of removal and/or installation of the Units. (b) THE LIMITED WARRANTY AND REMEDIES IN SUBPARAGRAPH (a) ARE EXCLUSIVE. THERE

uick4® Equalizer 36 Chamber Specifications 22"W x 53"L x 12"H (559 mm x 1346 mm x 305 mm) 48" (1219 mm) 10" (254 mm) 32 gal (121 L) Storage Capacity 6" (152 mm) **Invert Height**

4 Business Perk Road

P.O. Box 768

water technologies www.infiltratorwater.com

FRONT VIEW

- NATIVE BACKFIL

Old Saybrook, CT 08475 860-577-7000 • Fax 860-577-7001

(c) This Limited Warranty shall be void if any part of the chamber system is manufactured by anyone other than Infiltrator. The Limited Warranty does not extend to incidental, consequential, special or indirect damages, Infiltrator shall not be liable for penalties or liquidated damages, including oss of production and profits, labor and materials, overhead costs, or other losses or expenses incurred by the Holder or any third party. Specifically excluded from Limited Warranty coverage are damage to the Units due to ordinary wear and tear, alteration, accident, misuse, abuse or neglect of the Units; the Units being subjected to vehicle traffic or other conditions which are no permitted by the installation instructions; failure to maintain the minimum ground covers set forth in the installation instructions; the placement of improper materials into the system containing the Units; failure of the Units or the septic system due to improper siting or improper sizing, excessive water usage, improper grease disposal, or improper operation; or any other event not caused by Infiltrator. This Limited Warranty shall be void if the Holder fails to comply with all of the terms set forth in this Limited Warranty. Further, in no event shall infiltrator be responsible for any loss or damage to the Holder, the Units, or any third party resulting from installation or shipment, or from any product liability claims of Holder or any third party. For this Limited Warranty to apply, the Units must be installed in accordance with all site conditions required by state and local codes; all other applicable laws; and Infiltrator's installation instructions.

ARE NO OTHER WARRANTIES WITH RESPECT TO THE UNITS, INCLUDING NO IMPLIED

WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE

(d) No representative of infiltrator has the authority to change or extend this Limited Warranty, N warranty applies to any party other than the original Holder. The above represents the Standard Limited Warranty offered by Infiltrator. A limited number of states and counties have different wa ranty requirements. Any purchaser of Units should contact Infiltrator's Corporate Headquarters in Old Saybrook, Connecticut, prior to such purchase, to obtain a copy of the applicable warranty, and should carefully read that warranty prior to the purchase of Units.

MECHANICALLY COMPACTED TO THE

ENGINEER. IF ANY UNSUITABLE SOIL

(HAVING A BEARING CAPACITY LESS

THE SOIL SHALL BE REPLACED WITH A

THAN 3,000 PSF) IS ENCOUNTERED,

SUITABLE SAND & GRAVEL TO THE


ELEVATION OF THE SUBBASE.

SATISFACTION OF THE SITE


S. Patents: 4,759.661; 5,017,041; 5,156,488; 5,336,017; 5,401,116; 5,401,458; 5,511,903; 5,716,163; 5,588,776; 5,639,844 Canadian Patents: 1,329,959; 2,004,564 Other patents pending. Infiltrator, Equalizer, Quick4, and SideWinder are registered trademarks of Infiltrator Water Technologies. Infiltrator is a registered fractments in France. Infiltrator Water Technologies is a registered trademark in Mexico. Contour, MicroLeaching, PolyTuff, ChamberSpacer, MultiPort, PosiLock, QuickCut, QuickPlay, SnapLock and StraightLock are trademarks of Infiltrator Water Technologies.

PolyLok is a trademark of PolyLok. Inc. Tuf-TITE is a registered trademark of Tuf-TITE, InC. Ultra-Rib is a trademark of IPEX Inc.






TRAFFIC DUTY SEPTIC TANK **NOT TO SCALE**



- 1. A MINIMUM OF 4' OF 4"Ø SOLID PIPE SHALL BE PROVIDED PRIOR TO THE START OF THE TRENCHES.
- 2. ALL OUTLETS SHALL BE AT THE SAME ELEVATION. ALL UNUSED OUTLETS MUST BE PLUGGED.
- 3. A PVC 90 TEE SHALL BE PROVIDED ON THE INLET PIPE TO ACT AS A BAFFLE (TYP., NOT PICTURED).
- 4. A BED OF 12" OF PEA GRAVEL SHALL BE PROVIDED UNDER THE D-BOX.
- 5. THE INVERT ON THE INLET PIPE SHALL BE A MINIMUM OF 2" HIGHER THAN THE INVERT OF ANY OF THE OUTLETS.





WELL DETAIL



CONSTRUCTION NOTES

- 1. THE PUMP STATION SHALL BE A 6'Ø WET WELL MANUFACTURED
- BY "FORT MILLER" OR EQUAL THE PUMPS SHALL BE SIZED TO PUMP APPROXIMATELY -- GPM AT A TOTAL DYNAMIC HEAD OF -- FEET.
- THE WET WELL SHALL BE INSTALLED IN A DRY CONDITION ON TOP OF A 12" DEEP BED OF 3/4" CRUSHED STONE. THE STONE SHALL BE INSTALLED OVER UNDISTURBED EARTH HAVING A MINIMUM BEARING CAPACITY OF 3,000 PSI.
- WET WELL SHALL BE CONSTRUCTED OF CONCRETE HAVING A 28 DAY COMPRESSIVE STRENGTH OF 5,000 PSI. ANY REINFORCING STEEL SHALL HAVE A MINIMUM TENSILE STRENGTH OF 40,000 PSI. 5. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO

PERFORM START-UP TESTING OF THE COMPLETED PUMP

- STATION INSTALLATION TO THE ENGINEER'S SATISFACTION. THE INSTALLATION SHALL BE TESTED UNDER EMERGENCY POWER. SITE CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR FOR CONNECTION TO GENERATOR. 6. THE PUMP STATION WET WELL CONSTRUCTION MUST
- CONFORM TO ASTM C-478 STANDARDS. THE CONTRACTOR SHALL FURNISH AND INSTALL AN AUDIO & VISUAL ALARM. 8. PUMP STATION ELECTRICAL WORK IS TO BE ON
- CONFORMANCE WITH TEN STATE STANDARDS AND THE NATIONAL ELECTRIC CODE. 9. THE PUMPS SHALL BE SET UP TO OPERATE WITH A
- LEAD-LAG-ALTERNATE SEQUENCE. 10. THE PUMP STATION HAS BEEN SIZED FOR --- GPD AND -- GPM. ANY INCREASE IN FLOW TO THE PUMP STATION SHALL REQUIRE THE PUMP STATION TO BE RE-ENGINEERED. 11. WET WELL TO BE BACKFILLED WITH SELECT SAND & GRAVEL IN 8" MAXIMUM LIFTS. EACH LIFT TO BE MECHANICALLY

COMPACTED TO 95% STANDARD PROCTOR OR UNTIL SUITABLE


TO SITE ENGINEER PRIOR TO THE INSTALLATION OF THE NEXT 12. THE SITE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH THE SIDEWALLS OF THE WET WELL USING "LINK SEAL". IT SHALL BE THE RESPONSIBILITY OF THE SITE CONTRACTOR TO PROVIDE A WATERPROOF WET WELL. AN EXFILTRATION TEST OF THE WET WELL SHALL BE CONDUCTED

FLOOR OF THE WET WELL.

MINIMUM OF 24 HOURS 13. PUMP STATION AND FORCE MAIN SHALL BE PRIVATELY OWNED, OPERATED AND MAINTAINED.

BY THE SITE CONTRACTOR. THE TEST SHALL RUN FOR A

PUMP STATION DETAIL NOT TO SCALE



SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR. Mark A. Day, PE 09-29-2020 08-05-2020 07-23-2020

04-08-2020 03-16-2020 03-03-2020

02-19-2020 2018:419 License No. 069646

IT IS A VIOLATION OF NEW YORK STATE EDUCATION

LAW FOR ANY PERSONS TO ALTER THESE PLANS,

ENGINEERING P.C


3 Van Wyck Lane Suite 2 Wappingers Falls, New York 12590


(845) 223-3202

14 Nicole Way Town of Caramel Putnam County, New York

Utility Details

01-25-20 7 of 9







MWP

Page 1 of 2

Rev: 8/24/2018





lighting facts

Beam Width

4.2 ft 3.3 ft

8.5 ft 6.5 ft

12.7 ft 9.8 ft

17.0 ft 13.0 ft

21.2 ft 16.3 ft

25.5 ft 19.5 ft

Specifications subject to change without

Visit www.lightingfacts.com for the Label Reference Guide.

nacie; Number: NOT-601881480-2015,pppaded on 19860 Type: Number of Anni Roseivan

Howard Lighting Products | 580 Eastview Drive | Laurel, MS 39443 (toll free) 800.956.3456 (direct) 601.422.0033 (fax) 601.422.1652 www.HawardLightingProducts.com

Rev: 8/24/2018

Page 2 of 2



HOWARD IN SOME

Medium Wall Pack - LED

removable die-cast aluminum door

High output LEDs provide 80+ CRI in 5000 K CCT

28R-LED-MV

2,360 Lumens, 22W

40R-LED-MV

55R-LED-MV

5,490 Lumens, 51W

Cross Reference Chart

Accessories (sold separately)

²Please use LED compatible electronic components to maintain warranty.

Description

Howard Lighting Products | 580 Eastvic v Drive | Laurel, MS 39443

(tall free) 800.956.3456 | (direct) 601.42 1.0033 | (fax) 601.422.1652

www.HowardLightingPr ducts.com

185 MWP-5055R-LED-MV 51

129 MWP-5040R-LED-MV 41

91 MWP-5028R-LED-MV 22

tronic photocontrol²

o Housing has a textured bronze finish

o Borosilicate molded glass lens

maintenance (L70) at 60,000 hours

Note: Order with (-M) for title 24 compliance in CA

120-277V, 50/60Hz

5 Year warranty

MWP- 50: 5000K

70W

Catalog #

120V on Quad Tap Ballast

Specifications subject to change without

Lumen Multiplier

1.00


1.00

1.00

0.99


Features

Construction



- PROVIDE 24" CONCRETE FOUNDATION REVEAL FOR ALL FIXTURES WITHIN PARKING AREAS. ALL OTHER AREAS SHALL BE INSTALLED FLUSH.
- 2. CONCRETE SHALL HAVE A 28 DAY COMPRESSIVE STRENGTH OF
- 3,500 PSI, WITH AIR-ENTAINMENT OF 5-7% COLOR OF LUMINAIRE SHALL MATCH COLOR OF POLE

LIGHT POLE BASE DETAIL NOT TO SCALE



Suite 2 Wappingers Falls, New York 12590 (845) 223-3202

3 Van Wyck Lane

Putnam County, New York Town of Caramel

Lighting Details

01-25-20 8 of 9

PDES GENERAL PERMIT GP-0-15-002 COMPLIANCE NOTES: HE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH THE FOLLOWING

- . THE CONTRACTOR AND HIS/HER SUBCONTRACTORS SHALL READ AND UNDERSTAND THE CONDITIONS OF THE "NYSDEC SPDES GENERAL PERMIT FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES", GP-0-15-002 FOR THIS PROJECT.
- 2. THE CONTRACTOR AND HIS/HER SUBCONTRACTORS SHALL SIGN A COPY OF THE GENERAL PERMIT, GP-0-15-002, CERTIFICATION STATEMENT AS IDENTIFIED IN THE APPENDICES OF THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP).
- 3. THE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS NECESSARY FOR THE WORK OUTLINED HEREIN.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF ALL STORMWATER POLLUTION PREVENTION MEASURES OUTLINED IN THE SWPPP AND PROJECT PLANS.
- 5. THE CONTRACTOR SHALL HOLD A PRECONSTRUCTION CONFERENCE WITH THE OWNER'S REPRESENTATIVES AT LEAST ONE WEEK PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 6. THE CONTRACTOR/OWNER SHALL HAVE A QUALIFIED PROFESSIONAL, AS DEFINED WITHIN THE NYSDEC SPDES GENERAL PERMIT GP-0-15-002, CONDUCT AN INITIAL SITE ASSESSMENT PRIOR TO CONSTRUCTION FOLLOWING THE COMMENCEMENT OF CONSTRUCTION AT LEAST EVERY 7 CALENDAR DAYS. REFER TO SWPPP FOR INSPECTION GUIDELINES.
- 7. PRIOR TO COMMENCEMENT OF CONSTRUCTION, A QUALIFIED PROFESSIONAL (HIRED BY CONTRACTOR OR OWNER) SHALL CONDUCT AN ASSESSMENT OF THE SITE AND CERTIFY THAT THE APPROPRIATE EROSION AND SEDIMENT CONTROL STRUCTURES AS DEPICTED ON THE PLANS HAVE BEEN ADEQUATELY INSTALLED AND IMPLEMENTED. CONTRACTOR SHALL CONTACT THE PROJECT ENGINEER ONCE THE EROSION AND SEDIMENT CONTROL STRUCTURES HAVE BEEN INSTALLED. REFER TO SWPPP FOR INSPECTION GUIDELINES.
- I. THE OWNER/OPERATOR SHALL MAINTAIN A RECORD OF ALL EROSION AND SEDIMENT CONTROL INSPECTION REPORTS AT THE SITE IN A LOG BOOK. THE SITE LOG BOOK SHALL BE MAINTAINED ON-SITE AND BE MADE AVAILABLE TO THE PERMITTING AUTHORITY. THE OWNER/CONTRACTOR SHALL POST AT THE SITE, IN A PUBLICLY ACCESSIBLE LOCATION, A SUMMARY OF THE SITE INSPECTION ACTIVITIES ON A MONTHLY BASIS
- 9. THE OWNER/OPERATOR SHALL FILE A NOTICE OF INTENT (NOI) WITH THE NYSDEC AND LOCAL GOVERNING AUTHORITY PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES AND A NOTICE OF TERMINATION (NOT) WITH NYSDEC FOLLOWING CONSTRUCTION

SPDES GENERAL PERMIT COMPLANCE NOTES NOT TO SCALE

. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE IN STRICT COMPLIANCE WITH "NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL", NOVEMBER 2016

- 2. DAMAGE TO SURFACE WATERS RESULTING FROM EROSION AND SEDIMENTATION SHALL BE MINIMIZED BY STABILIZING DISTURBED AREAS AND BY REMOVING SEDIMENT FROM CONSTRUCTION SITE DISCHARGES.
- 3. AS MUCH AS IS PRACTICAL, EXISTING VEGETATION SHALL BE PRESERVED. FOLLOWING THE COMPLETION OF CONSTRUCTION ACTIVITIES IN ANY PORTION OF THE SITE, PERMANENT VEGETATION SHALL BE ESTABLISHED ON ALL
- 4. SITE PREPARATION ACTIVITIES SHALL BE PLANNED TO MINIMIZE THE SCOPE AND DURATION OF SOIL DISRUPTION.
- 5. PERMANENT TRAFFIC CORRIDORS SHALL BE ESTABLISHED AND "ROUTES OF CONVENIENCE" SHALL BE AVOIDED. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT ALL POINTS OF ENTRY ONTO THE PROJECT SITE.
- 6. SEEDED AREAS TO BE MULCHED WITH STRAW OR HAY MULCH IN ACCORDANCE WITH VEGETATIVE COVER SPECIFICATIONS
- 7. THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL
- MEASURES THROUGHOUT THE COURSE OF CONSTRUCTION. 8. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH
- WATER AS REQUIRED. THE CONTRACTOR IS TO SUPPLY ALL EQUIPMENT AND WATER.

9. WHEN ALL DISTURBED AREAS ARE STABLE, ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE


MAINTENANCE OF EROSION AND SEDIMENT CONTROL MEASURES: NSPECT ALL AREAS THAT HAVE RECEIVED VEGETATION EVERY SEVEN DAYS. ALL AREAS DAMAGED BY EROSION OR WHERE SEED HAS NOT ESTABLISHED SHALL BE REPAIRED AND RESTABILIZED IMMEDIATELY.

STABILIZED CONSTRUCTION ENTRANCE:
INSPECT THE ENTRANCE PAD EVERY SEVEN DAYS. CHECK FOR MUD, SEDIMENT BUILD-UP AND PAD INTEGRITY. MAKE DAILY INSPECTIONS DURING WET WEATHER. RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL. WASH AND REPLACE STONE AS NEEDED. THE STONE IN THE ENTRANCE SHOULD BE WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFF-SITE BY VEHICLES. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. REMOVE TEMPORARY CONSTRUCTION ENTRANCE AS SOON AS THEY ARE NO LONGER NEEDED TO PROVIDE ACCESS TO THE SITE.

- NSPECT FOR DAMAGE EVERY SEVEN DAYS. MAKE ALL REPAIRS IMMEDIATELY. REMOVE SEDIMENT FROM THE UP-SLOPE FACE OF THE FENCE BEFORE IT ACCUMULATES TO A HEIGHT EQUAL TO 1/3 THE HEIGHT OF THE FENCE. IF FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED SECTION OF FENCE IMMEDIATELY.
- SOIL STOCKPILE:
 INSPECT SEDIMENT CONTROL BARRIERS (SILT FENCE OR HAY BALE) AND VEGETATION FOR DAMAGE EVERY SEVEN DAYS. MAKE ALL REPAIRS IMMEDIATELY. REMOVE SEDIMENT FROM THE UP-SLOPE FACE OF THE SEDIMENT CONTROL BARRIER BEFORE IT ACCUMULATES TO A HEIGHT EQUAL TO 1/3 THE HEIGHT OF THE SEDIMENT CONTROL BARRIER. IF SEDIMENT CONTROL BARRIER TEARS, BEGINS TO DECOMPOSE, OR IN ANYWAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED SECTION OF SEDIMENT CONTROL BARRIER IMMEDIATELY. REVEGETATE DISTURBED AREA TO STABILIZE SOIL STOCK PILE
- INLET PROTECTION:
 INSPECT INLET PROTECTION FOR DAMAGE EVERY SEVEN DAYS. MAKE ALL REPAIRS IMMEDIATELY. REMOVE SEDIMENT AS NECESSARY TO PROVIDE FOR ADEQUATE STORAGE VOLUME FOR SUBSEQUENT RAINS.
- <u>DUST CONTROL:</u>
 SCHEDULE CONSTRUCTION OPERATIONS TO MINIMIZE THE AMOUNT OF DISTURBED AREAS AT ANY ONE TIME DURING THE
- COURSE OF WORK, APPLY TEMPORARY SOIL STABILIZATION PRACTICES SUCH AS MULCHING, SEEDING, AND SPRAYING (WATER). STRUCTURAL MEASURES (MULCH, SEEDING) SHALL BE INSTALLED IN DISTURBED AREAS BEFORE SIGNIFICANT BLOWING PROBLEMS DEVELOP. WATER SHALL BE SPRAYED AS
- NEEDED. REPEAT AS NEEDED, BUT AVOID EXCESSIVE SPRAYING, WHICH COULD CREATE RUNOFF AND EROSION PROBLEMS.

EROSION & SEDIMENT CONTROL NOTES NOT TO SCALE

REMOVE THE SEDIMENT CONTROL BARRIER WHEN THE SOIL STOCKPILE HAS BEEN REMOVED.



DURING PERIODS OF RELATIVELY LOW MODERATE SUBSOIL MOISTURE, THE DISTURBED SUBSOILS ARE RETURNED TO ROUGH GRADE AND THE FOLLOWING SOIL RESTORATION STEPS APPLIED:

- APPLY 3 INCHES OF COMPOST OVER SUBSOIL 2. TILL COMPOST INTO SUBSOIL TO A DEPTH OF AT LEAST 12 INCHES USING A CAT-MOUNTED RIPPER, TRACTOR-MOUNTED DISC, OR TILLER, MIXING, AND CIRCULATING AIR AND COMPOST
- INTO SUBSOILS. 3. ROCK-PICK UNTIL UPLIFTED STONE/ROCK MATERIALS OF FOUR INCHES AND LARGER SIZE
- ARE CLEANED OF THE SITE. APPLY TOPSOIL TO A DEPTH OF 6 INCHES.
- 5. VEGETATE AS REQUIRED BY APPROVED PLANS.

CONSTRUCTION WASTE MANAGEMENT PLAN

REDUCE THE POTENTIAL FOR SIGNIFICANT MATERIALS TO COME INTO CONTACT WITH STORMWATER. A MAINTENANCE SCHEDULE SHALL

CONSTRUCTION WASTE MANAGEMENT PRACTICES ARE DESIGNED TO MAINTAIN A CLEAN AND ORDERLY WORK ENVIRONMENT. THIS WILL BE DEVELOPED FOR THESE AREAS. THE GENERAL CONTRACTOR SHALL IMPLEMENT THE FOLLOWING PRACTICES:

1. MATERIAL RESULTING FROM THE CLEARING AND GRUBBING OPERATION WILL BE STOCKPILED UP SLOPE FROM ADEQUATE

SEDIMENTATION CONTROLS. 2. EQUIPMENT CLEANING, MAINTENANCE, AND REPAIR AREAS SHALL BE DESIGNATED AND PROTECTED BY A TEMPORARY PERIMETER

A SPILL PREVENTION AND RESPONSE PLAN SHALL BE DEVELOPED FOR THE SITE BY THE GENERAL CONTRACTOR. THE PLAN SHALL DETAIL THE STEPS NEEDED TO BE FOLLOWED IN THE EVENT OF AN ACCIDENTAL SPILL AND SHALL IDENTIFY CONTACT NAMES AND

3. THE USE OF DETERGENTS FOR LARGE SCALE WASHING IS PROHIBITED (I.E., VEHICLES, BUILDINGS, PAVEMENT SURFACES, ETC.).

THE PLAN SHALL INCLUDE MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS TO BE STORED ON-SITE. ALL WORKERS ON-SITE WILL BE REQUIRED TO BE TRAINED ON SAFE HANDLING AND SPILL PREVENTION PROCEDURES FOR ALL MATERIALS USED DURING CONSTRUCTION. REGULAR TAILGATE SAFETY MEETINGS SHALL BE HELD AND ALL WORKERS THAT ARE EXPECTED ON THE SITE DURING THE WEEK SHALL BE REQUIRED TO ATTEND.

CONSTRUCTION MATERIALS SHALL BE STORED IN A DEDICATED STAGING AREA. THE STAGING AREA SHALL BE LOCATED IN AN AREA THAT MINIMIZES THE IMPACTS OF THE CONSTRUCTION MATERIALS EFFECTING STORMWATER QUALITY.

CHEMICALS, PAINTS, SOLVENTS, FERTILIZERS, AND OTHER TOXIC MATERIAL MUST BE STORED IN WATERPROOF CONTAINERS. EXCEPT DURING APPLICATION, THE CONTENTS MUST BE KEPT IN TRUCKS OR WITHIN STORAGE FACILITIES. RUNOFF CONTAINING SUCH MATERIAL MUST BE COLLECTED, REMOVED FROM THE SITE, TREATED AND DISPOSED AT AN APPROVED SOLID WASTE OR

6. TEMPORARY CONCRETE WASHOUT FACILITY

CHEMICAL DISPOSAL FACILITY.

PHONE NUMBERS OF PEOPLE AND AGENCIES THAT MUST BE NOTIFIED.

TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE LOCATED A MINIMUM OF 50 FT FROM STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, AND WATERCOURSES. EACH FACILITY SHOULD BE LOCATED AWAY FROM CONSTRUCTION TRAFFIC OR ACCESS AREAS TO PREVENT DISTURBANCE OR TRACKING. A SIGN SHOULD BE INSTALLED ADJACENT TO EACH WASHOUT FACILITY TO INFORM CONCRETE EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES.

WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHALL BE REMOVED AND DISPOSED OF. MATERIALS USED TO CONSTRUCT THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE REMOVED FROM THE SITE AND DISPOSED OF. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCE CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE BACKFILLED AND/OR REPAIRED AND SEEDED AND MULCHED FOR FINAL STABILIZATION.

NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, ARE ALLOWED TO BE DISCHARGED FROM THE SITE WITH STORMWATER. ALL SOLID WASTE, INCLUDING DISPOSABLE MATERIALS INCIDENTAL TO THE MAJOR CONSTRUCTION ACTIVITIES, MUST BE COLLECTED AND PLACED IN CONTAINERS. THE CONTAINERS WILL BE EMPTIED PERIODICALLY BY A CONTRACT TRASH DISPOSAL SERVICE AND HAULED

SUBSTANCES THAT HAVE THE POTENTIAL FOR POLLUTING SURFACE AND/OR GROUNDWATER MUST BE CONTROLLED BY WHATEVER MEANS NECESSARY IN ORDER TO ENSURE THAT THEY DO NOT DISCHARGE FROM THE SITE. AS AN EXAMPLE, SPECIAL CARE MUST BE EXERCISED DURING EQUIPMENT FUELING AND SERVICING OPERATIONS. IF A SPILL OCCURS, IT MUST BE CONTAINED AND DISPOSED SO THAT IT WILL NOT FLOW FROM THE SITE OR ENTER GROUNDWATER, EVEN IF THIS REQUIRES REMOVAL, TREATMENT, AND DISPOSAL OF SOIL. IN THIS REGARD, POTENTIALLY POLLUTING SUBSTANCES SHOULD BE HANDLED IN A MANNER CONSISTENT WITH THE IMPACT THEY REPRESENT.

DEPARTMENT. WATER USED FOR CONSTRUCTION THAT DOES NOT ORIGINATE FROM AN APPROVED PUBLIC SUPPLY MUST NOT

NON-STORMWATER COMPONENTS OF SITE DISCHARGE MUST BE CLEAN WATER. WATER USED FOR CONSTRUCTION. WHICH DISCHARGES FROM THE SITE, MUST ORIGINATE FROM A PUBLIC WATER SUPPLY OR PRIVATE WELL APPROVED BY THE HEALTH

DISCHARGE FROM THE SITE. IT CAN BE RETAINED IN THE PONDS UNTIL IT INFILTRATES AND EVAPORATES.

CONSTRUCTION WASTE MANAGEMENT PLAN NOT TO SCALE

1) NON-DISTURBANCE AREAS SHALL BE MARKED WITH 4-FT ORANGE SNOW FENCING TO TOWN ENGINEER'S SATISFACTION PRIOR TO SITE DISTURBANCE, AND SHALL BE MAINTAINED UNTIL ISSUANCE OF A C.O.


2) HOLD A PRE-CONSTRUCTION MEETING WITH THE OWNER/OPERATOR, SITE ENGINEER, TOWN ENGINEER, TRAINED CONTRACTOR, QUALIFIED EROSION CONTROL INSPECTOR AND BUILDING INSPECTOR. PLACE A COPY OF THE SWPPP REPORT ON SITE ALONG WITH A COPY OF THE INSPECTOR'S LOG BOOK CONTAINING COPIES OF THE WEEKLY INSPECTIONS. (APPLICANT'S EROSION & SEDIMENT CONTROL INSPECTION AGENT SHALL CONDUCT AN INSPECTION ON A WEEKLY BASIS)

CONSTRUCTION SEQUENCE:

1. INSTALL AND STABILIZE TEMPORARY EROSION & SEDIMENT CONTROL MEASURES AS SHOWN ON THE SWPPP PLAN.

- 2. BEGIN DEMOLITION OF EXISTING STRUCTURES
- 3. INSTALL TEMPORARY DIVERSION SWALES AS NECESSARY TO DIVERT RUNOF CONSTRUCTION AND CONSTRUCT THE TEMPORARY SEDIMENT BASIN. 4. BEGIN REMAINING SITE GRADING, DRIVEWAY GRADE CONSTRUCTION AND FOUNDATION
- **EXCAVATION** 5. ROUGH CUT DRIVEWAY AND PARKING AREA TO SUB-GRADE
- 6. POUR CONCRETE FOOTINGS AND FOUNDATIONS FOR PROPOSED BUILDINGS. 7. INSTALL REMAINING SITE UTILITIES AND/OR INFRASTRUCTURE.
- 8. INSTALL CURBING ONCE ALL MAJOR WORK ON SITE IS COMPLETE, AS REQUIRED. 9. INSTALL INFILTRATION CHAMBERS AS SHOWN ON THE UTILITY PLAN AND AS PER MANUFACTURER'S
- 10. TOPSOIL, SEED AND MULCH ALL DISTURBED AREAS THAT HAVE OBTAINED FINISHED GRADE ELEVATIONS
- 11. SEED AND MULCH ALL DISTURBED AREAS THAT WILL NOT BE RE-DISTURBED FOR AT LEAST 14
- 12. FINALIZE BUILDING CONSTRUCTION.
- 13. ONCE ALL MAJOR SITE DISTURBANCE ACTIVITIES HAVE CEASED AND THE SITE HAS ACHIEVED FINAL STABILIZATION, FILE AN N.O.T. (NOTICE OF TERMINATION) WITH NYSDEC.
- 14. TERMINATE EROSION CONTROL INSPECTIONS.

CONSTRUCTION SEQUENCE




1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.

- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1V: 2H.
- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH SILT FENCING, THEN STABILIZED WITH VEGETATION OR COVERED.
- 4. SEE SPECIFICATIONS FOR INSTALLATION OF SILT FENCE
- 5. HAYBALES TO BE USED WHERE STOCKPILES ARE LOCATED ON PAVED AREAS.

TEMPORARY SOIL STOCKPILE DETAIL

NOT TO SCALE

MAXIMUN DRAINAGE AREA 1 ACRE



- 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD.
- 2. FILTER CLOTH TO BE TO BE FASTENED SECURELY TO WOVEN WIRE
- FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION FENCE SHALL BE WOVEN WIRE, 12 1/2 GAUGE, 6" MAXIMUM MESH OPENING.
- 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA T140N, OR APPROVED EQUIVALENT.
- 4. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT. 5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.

SILT FENCE DETAIL

NOT TO SCALE

ALL SEDIMENT & EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THESE PLANS & DETAILS. CHANGES, OMISSIONS AND/OR OTHER ALTERATIONS CAN NOT BE IN ADE TO THESE PLANS WITHOUT THE CONSENT OF THE DESIGN ENGINEER.

SILT FENCE SHALL BE INSTALLED AS SHOWN ON THIS DRAWING PRIOR TO BEGINNING ANY

CLEARING, GRUBBING AND EARTHWORK. EXPOSED SLOPES AND ALL GRADED AREAS SHALL BE SEEDED WITH THE FOLLOWING GRASS SEED MIX IMMEDIATELY UPON COMPLETION OF ITS CONSTRUCTION, OR IF PLANNED TO BE LE FI UNDISTURBED FOR MORE THAN 21 DAYS. GRASS SEED MIX TO BE APPLIED AT A RATE OF 50 POUNDS PER ACRE IN THE FOLLOWING PROPORTIONS:

KENTUCKY BLUEGRASS CREEPING RED FESCUE 40% RYE GRASS

4. GRASS SEED MIX MAY BE APPLIED BY EITHER MECHANICAL OR HYDROSEEDING METHODS. HYDROSEEDING SHALL BE PERFORMED IN ACCORDANCE WITH THE CURRENT EDITION OF THE NYSDOT STANDARD SPECIFICATIONS, CONSTRUCTION AND MATERIALS, SECTION 610-3.02,


- 5. SEEDED AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 2 TONS PER ACRE, OR 90 LBS 6. SEDIMENTATION AND EROSION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED IN A DAILY BASIS BY THE OWNER'S FIELD REPRESENTATIVE. 7. DUST SHALL BE CONTROLLED BY SPRINKLING OF WATER OR OTHER APPROVED METHODS AS NECESSARY AS DIRECTED BY THE OWNER'S FIELD REPRESENTATIVE.
- ONTO ADJOINING PROPERTIES. 9. ALL FILLS SHALL BE COMPACTED TO PROVIDE STABILITY OF MATERIALS AND TO PREVENT SETTLEMENT.

8. CUTS AND FILLS SHALL NOT ENDANGER ADJOINING PROPERTY, NOR DIVERT SURFACE WATER

- 10. EXCAVATIONS AND FILLS TO BE ROLLED, SEALED AND STABILIZED AT COMPLETION OF EACH DAY's WORK 11. THE OWNER'S FIELD REPRESENTATIVE SHALL INSPECT THE DOWNSTREAM CONDITIONS FOR
- EVIDENCE OF SEDIMENTATION ON A WEEKLY BASIS AND AFTER RAINSTORMS. AS WARRANTED BY FIELD CONDITIONS, SPECIAL ADDITIONAL SEDIMENTATION AND EROSION CONTROL MEASURES MAY BE ADDED TO THIS PLAN BY THE SITE ENGINEER, TOWN ENGINEER AND HIGHWAY SUPERINTENDENT. ANY REVISIONS TO THIS PLAN MUST BE SUBMITTED TO THE SITE ENGINEER. ANY CHANGES DEEMED NECESSARY TO THIS PLAN SHALL BE DICTATED BY TIE SITE ENGINEER AS NECESSARY TO CARRY-OUT THE INTENT OF THIS PLAN.


SEEDING & MULCHING NOTES

NOT TO SCALE




CONSTRUCTION SPECIFICATIONS

- 1. FILTER FABRIC SHALL HAVE AN EOS OF 40-85. BURLAP MAY BE USED FOR SHORT TERM APPLICATIONS.
- CUT FABRIC FROM A CONTINUOUS ROLL TO ELIMINATE JOINTS. IF JOINTS ARE NEEDED THEY WILL BE OVERLAPPED TO THE NEXT STAKE. 3. STAKE MATERIALS WILL BE STANDARD 2" x 4" WOOD OR EQUIVALENT. METAL WITH A MINIMUM LENGTH OF 3 FEET.
- 5. FABRIC SHALL BE EMBEDDED 1 FOOT MINIMUM BELOW GROUND AND BACKFILLED, IT SHALL BE SECURELY FASTENED TO THE STAKES AND FRAME. 6. A 2" \times 4" WOOD FRAME SHALL BE COMPLETED AROUND THE CREST OF THE FABRIC FOR OVER FLOW STABILITY.
- FILTER FABRIC DROP INLET PROTECTION




- 1. STONE SIZE USE 1-4 INCH STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT 2. LENGTH - NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM
- LENGTH WOULD APPLY). 3. THICKNESS - NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.
- 5. GEOTEXTILE WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. 6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ACCESS SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- 7. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- 8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

ANTI-TRACKING PAD DETAIL



CONCRETE WASHOUT SIGN TO BE INSTALLED WITHIN 30 FEET OF THE TEMPORARY CONCRETE WASHOUT FACILITY.

- 2. REMOVE HARDEN CONCRETE WHEN WITHIN 4" FROM TOP OF STRUCTURE
- 3. CONSTRUCT NEW FACILITIES ONCE CURRENT FACILITIES ARE TWO-THIRDS FULL.
- 4. LINERS, HAYBALES, ET.C SHALL BE INSPECTED FOR DAMAGE. ANY DAMAGE SHALL BE REPAIR PROMPTLY. TEMPORARY CONCRETE WASHOUT DETAIL



NOTES:

1) CONTRACTOR TO INSTALL NORTH AMERICAN GREEN PERMANENT TURF REINFORCEMENT (OR EQUAL) PARALLEL TO THE SLOPE.

2) THERE SHALL BE A 4" OVERLAP OVER CONTIGUOUS STRIPS OF MATTING.

3) INSTALL 3/4" x 3/4" WOODEN STAKES © 6' INTERVALS. LEAVE A 1" REVEAL.

4) HYDROSEED SHOULD BE APPLIED TO AREA AS SOON AS PRACTICABLE.

5) WATER TO BE APPLIED AS REQUIRED TO GERMINATE GRASS SEED.

6) THE CONTRACTOR TO PERIODICALLY INSPECT MATTING AND MAKE REPAIRS
AS NECESSARY. THE MATTING SHALL BE INSPECTED IMMEDIATELY AFTER A STORM EVENT.

7) INSTALL EROSION CONTROL MEASURES AS NECESSARY UPSLOPE OF THE STABILIZED AREA
TO ENSURE MINIMAL EROSION THROUGH STABILIZED AREA.

8) CONTRACTOR TO USE 20% OF RYE GRASS IN THE GRASS SEED MIX TO PROMOTE A STABILIZED GRASS MIXTURE.

EROSION CONTROL MATTING (ECM) DETAIL NOT TO SCALE

IT IS A VIOLATION OF NEW YORK STATE EDUCATION LAW FOR ANY PERSONS TO ALTER THESE PLANS, SPECIFICATIONS, OR REPORTS IN ANY WAY, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR

Mark A. Day, PE 09-29-2020 08-05-2020 07-23-2020 04-08-2020 03-16-2020 03-03-2020 02-19-2020 License No. 069646 2018:419

ENGINEERING P.C

3 Van Wyck Lane Wappingers Falls, New York 12590

(845) 223-3202 14 Nicole Way

Town of Caramel Erosion & Sediment **Control Details**

D-4 01-25-20 MAD 9 of 9

SOIL RESTORATION DETAIL NOT TO SCALE

NOT TO SCALE



September 28, 2020

Mr. Craig Paeprer, Chairman Town of Carmel Planning Board Carmel Town Hall 60 McAlpin Avenue Mahopac, NY 10541

Re:

Old Forge Estates Baldwin Place Road

Mahopac, NY TM: 75.15-1-19

Dear Chairman Paeprer and Members of the Board:

In response to comments received dated March 9, 2020, we have prepared the following responses:

Town Engineer:

Preliminary Detailed Comments:

- 1. Graphical representation of vehicle movements have been provided.
- 2. This has been discussed with the Town of Carmel Highway Superintendent and Engineering Department and found acceptable as it had been in the past.
- 3. Driveway slopes have been provided. All driveways meet Town of Camel code requirements.
- 4. N.Y.C.D.E.P. has contacted the Town Engineer and expressed that treatment would be accomplished through the use of filter strips.

At this time I believe that we are in a position to move forward in having a public hearing as well as being considered for preliminary approval for the project.


I ask that we be placed on the next agenda in order to move forward.

Sincerely yours,

PUTNAM ENGINEERING

Paul M. Lynch, P.E.

PML/rrm



403 Baldwin Place Rd Mahopac NY 10541

409 Baldwin Place Rd Mahopac NY 10541

15 Pine Cone Rd Mahopac NY 10541

12 Pine Cone Rd Mahopac NY 10541

7 Dorset Dr Mahopac NY 10541

22 Drago Ln Mahopac NY 10541

10 Drago Ln Mahopac NY 10541

29 Tribbe HI Mahopac NY 10541

101 Highview Dr Carmel NY 10512

29 Tribbe HI Mahopac NY 10541

414 Baldwin Pl Rd Mahopac NY 10541

Il West Stevens Ave Hawthorne NY 10532

406 Baldwin Place Rd Mahopac NY 10541

402 Baldwin Place Rd Mahapac NY 10541

90-100 Myrtle Ave Mahopac NY 10541

398 Baldwin Place Rd Mahopac NY 10541

2 Muscoot Rd N Mahopac NY 10541

P.O. Box 758 Mahopac NY 10541

P.O. Box 758 Mahopac NY 10541

10 Fowler Ave Carmel NY 10512

P.O. Box 388 Mahopac NY 10541

7 Veschi Lane N Mahopac NY 10541

17 Veschi Lane N Mahopac NY 10541

20 N Veschi Ln Mahopac NY 10541

10 Veschi Lane N Mahopac NY 10541

20 Primrose St Katonah NY 10536

1619 Third Avenue - #16A New York NY 10128

8 Veschi Rd Mahopac NY 10541

29 Tribbe HI Mahopac NY 10541

427 Route 6 Mahopac NY 10541

121 Heather Dr Mahopac NY 10541

421 Rt 6 Mahapac NY 10541

430 Rt 6 Mahopac NY 10541

436 Rt 6 Mahopac NY 10541

466 Rt 6 Mahopac NY 10541

P.O. Box 636 Mahopac NY 10541

60 Mcalpin Ave Mahopac NY 1054

155 Buckshollow Rd Mahopac NY 10541

155 Buckshollow Rd Mahopac NY 10541

P.O. Box 704 431 Route 6 Mahopac NY 10541

441 Rt 6 Mahapac NY 10541

3 Hazen Ln Carmel NY 10512

14 Veschi Lane N Mahopac NY 10541

19 Veschi Lane North Mahopac NY 10541

422 Rt 6 Mahopac NY 10541

418 Baldwin Place Rd Mahopac NY 10541

45-302 IT8 East Lake Blvd Mahopac NY 10541

75.65-1-6 Robert J. Mongelli

75.65-1-13 Stephanie Tropea

75.65-1-17 Mary Keegan

75.65-1-18 Mary Keegan

75.65-1-25 Abraham Lebenkoff

75.65-1-28 Bruce Schwartz

75.65-1-32 Lois Marie Maiuzzo

75.65-1-33 Lois Marie Maiuzzo

75.65-1-39 Patrica Keogh

75.65-1-45 Anthony Morando

75.65-1-46 Thomas Dechiaro

75.65-1-51 Josephine Selimoska

75.66-1-2 Stacy A. Grabeklis

75.66-1-5 Anthony Morando

75.66-1-7 Town of Carmel

75.66-1-8 Anthony Morando

75.66-1-9 Anthony Morando

75.66-1-10 JAB Builders, Inc.

75.66-1-15 James Quinn

75.66-1-14 James F. Quinn & Tara M. Quinn

75.66-1-6 Brendan B. Donohue

75.66-1-1 Eric Gorski

75.66-1-3 Eric Gorski

75.66-1-4 Amy Weldon

75.65-1-8 Lisa M. Rucker & Matthew Benneti

75.65-1-10 The College Edu Milestone Fnd

75.65-I-I2 Terence McDonald & Eileen McDonald

75.65-1-14 Eileen W. Mulczyn & Milliam C. Mulczyn

75.65-1-19 Michael Esteves & Donna Esteves

75.65-1-21 John O'Reilly & Patrice O' Reilly

75.65-1-27 Bruce Schwartz & Judy Schwartz

75.65-1-29 Manuel Oliveira & Carminda Oliveira

75.65-1-36 John V. Kaprielian & Maria Kaprielian

75.65-1-37 Thomas E. Barker & Ellen M. Barker

75.65-1-38 Roger Duran & Jorge Duran

75.65-1-40 Anthony Grosso \$ Laura Grosso

75.65-I-44 Joao Reis & Elizabeth Reis

75.65-1-47 Anthony Puccio & Debra Puccio

75.65-1-48 Dianne Chipman & Robert Chipman

75.65-1-49 Dianne Chipman & Robert Chipman

75.65-1-50 Dianne Chipman & Robert Chipman

75.65-1-41 Gregg C. Morrione & Heidi Turner

75.65-1-43 Peter J. Dandreano & Merry J. Dandreano

75.65-1-16 John J. Walter & Danielle R. Planamenta

75.65-1-24 Patrick B. McGarry & Siobhan M McGarry

75.65-1-7 Nuno Reis

27110 Grand Central Pkwy Floral Park NY 11005-1226 75.65-1-11 Lisa M. Rucker & Matthew Bennett


9 Cross Dr Mahopac NY 10541

4 Cross Dr Mahopac NY 10541

8 Cross Dr Mahopac NY 10541

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK



DRAWING SCHEDULE

DRAMING NO.	SHEET NO.	DRAMING TITLE
C-010 C-020	2	COVER SHEET EXISTING CONDITIONS PLAN
C-lOO C-lOI C-lIO C-l2O 6 C-l2I 7 C-l22 8	EN	SUBDIVISION PLAN ENLARGED SUBDIVISION PLAN ENLARGED SITE LAYOUT PLAN ADING and DRAINAGE PLAN LARGED GRADING and DRAINAGE PLAN LARGED GRADING and DRAINAGE PLAN
C-130 C-140 C-141 C-142	9 10 11 12	UTILITIES PLAN SSTS LAYOUT PLAN ENLARGED SSTS PLAN TEST LOCATION FOR STORMWATER PRACTICES
C-150 C-151 C-152 C-153 C-154 C-155 C-156 C-160	3 4 5 6 7 8 9	EROSION AND SEDIMENT CONTROL PLAN - PHASE IA EROSION AND SEDIMENT CONTROL PLAN - PHASE IB EROSION AND SEDIMENT CONTROL PLAN - PHASES 2 EROSION AND SEDIMENT CONTROL PLAN - PHASES 3 EROSION AND SEDIMENT CONTROL PLAN - PHASES 4 EROSION AND SEDIMENT CONTROL PLAN - PHASES 5A AND 5 EROSION AND SEDIMENT CONTROL PLAN - PHASE 6 LANDSCAPE PLAN
C-2 O C-2 C-2 2 C-2 3	2l 22 23 24	ROAD PROFILES DRAINAGE PROFILES SEMER PROFILES WATERMAIN PROFILES
C-3 O C-3 1 C-3 2 C-3 3 C-3 4 C-3 5 C-3 6 C-3 7	25 26 27 28 29 30 31 32	DETAILS DETAILS DETAILS DETAILS DETAILS DETAILS DETAILS DETAILS DETAILS
C-410 C-420	33 34	DRIVEMAY PROFILES WATERMAIN RELOCATION PLAN

OWNER / APPLICANT

ANGELO MASTRANTONI 23 FRANCES DR. KATONAH, NY 10536

CARMEL PLANNING BOARD APPROVAL

APPROVED BY RESOLUTION OF THE PLANNING BOARD OF THE TOWN OF CARMEL, NEW YORK, ON THE _____ DAY OF _____ 20____, SUBJECT TO ALL REQUIREMENTS AND CONDITIONS OF SAID RESOLUTION. ANY CHANGE, ERASURE MODIFICATION OR REVISION OF THIS PLAT, AS APPROVED, SHALL VOID THIS APPROVAL

SIGNED THIS _____ DAY OF ____

CHAIRMAN

ENGINEERS - ARCHITECTS

ADJOINERS:

75.11-1-2 Rosa Marinaccio

75.11-2-9 Daniel Andron

75.11-2-27 Michael Locurto

75.11-2-34 Kaisy Contreras

75.11-1-1 Christopher Steckle & Suzan Steckle

75.11-1-4 Mahopac Central School Dist

75.11-2-8 William Levy & Marie Levy

75.11-2-7 Richard Doyle & Kimberly Doyle

75.11-2-18 Harry Hess & Christine Kilkenny

75.11-2-26.1 Robert Ansbro & Nancy L. Ansbro

75.11-2-28 Richard Oubina \$ Isabella Oubina

75.11-2-31 Richard Oubina \$ Isabella Oubina

75.11-2-32 Franz Fruhmann & Erika J Fruhmann

75 II-2-35 Maru T Halden & Henry Halden

75.14-1-36 Mahopac Central School Dist

75.15-1-5 Kathleen F. Delamere

75.15-1-7 JDCCG Holdings, LLC.

75.15-1-9 | Ilse Flink & Adolf Flink

75.15-1-10 Frank Selca & Drita Selca

75.15-1-11 Robert J. Placek & Karen N. Placek

75.15-1-12 Joseph E. Tyndall & Rita Tyndall

75.15-1-13 Anthony M. Rush & Bianca Bunyea

75.15-1-15 John Crecco & Nicky Crecco

Giovanni Crecco

75.16-1-20 Thomas Simone & Gene Simone

75.16-1-21 Thomas Simone \$ Nina Simone

75.15-1-17 Sebastian Ferreira

75.15-1-18 Richard Oubina

75.16-1-18 Achilles Doupis

75.16-1-22 Scott Nygard

75.16-1-23 Scott Nygard

75.16-1-32 Eric Gruber

75.16-1-36 Town of Carmel

75.16-1-24 Jacrye Realty Corp.

75.16-1-31 DF Group Realty, LLC

75.16-1-33 442 Realty Group LLC

75.16-1-35 Hilltop Manor Realty Corp

75.15-1-14 Travis B. Mall & Margaret E. Austin

75.15-1-16 Joseph E. Simone, Jr & Susan Simone

75.15-1-6 Fisher Thomas Inc.

75.11-2-33 Alexander Teran & Veronica Teran

75.11-2-26.2 Rose Campanella, Anthony J. Campanella III,

75.11-2-30 Eugene Phillips, Susan Phillips, Anne M Phillips

75.15-1-1 John J. Goodrow Jr & Christine E. Goodrow

75.15-1-4 Patrick J. Delamere & Kathleen F. Delamere

75.15-1-3 Joel Greenberg & Wendy Greenberg

Nicole Esposito, Michele Corrado

OF AN ENGINEER IS ALTERED, THE ALTERING 4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 SIGNATURE AND THE DATE OF SUCH ALTERATION, (845) 279-6789 FAX (845) 279-6769 ● PUTNAM ENGINEERING PLLC 2018

PROJECT PURSUANT TO NEW YORK STATE EDUCATION LAW, DESCRIPTION DESCRIPTION ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS 09 NOV 18 REV. PER BI, TE, TP COMMENTS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF 02 OCT 19 REV. PER TE COMMENTS LICENSED PROFESSIONAL ENGINEER. TO ALTER AN II MAY 20 REV. PER TE COMMENTS ITEM IN ANY WAY, IF AN ITEM BEARING THE SEAL ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS AND A SPECIFIC DESCRIPTION OF THE

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES BALDWIN PLACE ROAD TOWN of CARMEL

PUTNAM COUNTY, NEW YORK

TAX MAP 75.15-1-19



DATE
12 APR 18
PROJECT MANAGER
 PML
 DRAWN BY
 —_BJK
CHECKED BY


AS NOTED


COVER SHEET

DRAWING

ROJECT NUMBER 8286 DRAWING NUMBER

SHEET ___ | OF __34_






RESIDENTIAL CLUSTER DEVELOPMENT:

CONDITIONS PER CHAPTER 156-45 RESIDENTIAL CLUSTER DEVELOPMENT:

- PERMITTED USES:
- A. DWELLING UNITS IN DETACHED, SEMIDETACHED, ATTACHED AND/OR GROUPS OF ATTACHED.
- DETACHED DWELLING UNITS ARE PROPOSED. B. QUASI-PUBLIC SOCIAL, RECREATIONAL AND CULTURAL FEATURES, SUCH AS NEIGHBORHOOD OR COMMUNITY CENTERS, GAME ROOMS, SWIMMING POOLS AND TENNIS COURTS. NO SUCH USES ARE PROPOSED.
- 2. AREA: A RESIDENTIAL CLUSTER DEVELOPMENT SHALL HAVE A TOTAL SITE AREA OF AT LEAST 20 ACRES IN ONE AGGREGATE OR CONTIGUOUS PARCELS. 45.355 ACRES IS PROVIDED.
- 3. OVERALL RESIDENTIAL DENSITY: (PER CHAPTER 156-8 DEFINITIONS) "A RESIDENTIAL CLUSTER DEVELOPMENT THAT OBTAINS A LOT COUNT THROUGH CONVENTIONAL SUBDIVISION APPROVAL, THEN DEVELOPS THE PARCEL AT THE SAME DENSITY THAT WOULD BE ALLOWED IN THE ZONING DISTRICT IN WHICH THE SITE IS LOCATED, PROVIDED THAT THE REMAINING UNDEVELOPED LAND SHALL BE RESERVED AND IMPROVED FOR PERMANENT OPEN SPACE USE." PROPOSED CLUSTER DEVELOPMENT INCLUDES 14 DETACHED DWELLING UNITS.
- OPEN SPACE: THERE SHALL BE PROVIDED AT LEAST 35 PERCENT OF THE GROSS AREA OF A RESIDENTIAL CLUSTER DEVELOPMENT FOR OPEN SPACE, EXCLUSIVE OF STREETS OR OTHER PAVED SURFACES. 37.88 ACRES OR 83.5 PERCENT OPEN SPACE IS PROPOSED.
- HEIGHTS, BULK COVERAGE, LOCATION AND LAND USES: IT IS REQUIRED THAT ALL STAGES OF A RESIDENTIAL CLUSTER DEVELOPMENT BE DEVELOPED ACCORDING TO A COMPREHENSIVE FINAL PLAN FOR THE OVERALL DEVELOPMENT, AS APPROVED BY THE PLANNING BOARD, WHICH SHALL CONFORM TO THE REQUIREMENTS OF THIS CHAPTER AND, IN ADDITION, SHALL BE COMPATIBLE WITH THE OTHER REQUIREMENTS OF THIS CHAPTER FOR RESIDENTIAL OR OTHER LAND USES CONTEMPLATED OR BY COMMON GOOD PRACTICE. REFER TO BULK SCHEDULE FOR PROPOSED REQUIREMENTS.

PRELIMINARY SUBDIVISION PLAN



RESIDENTIAL CLUSTER DENSITY CALCULATION IN ACCORDANCE WITH 156-45E:

THE ACREAGE OF THE PARCEL BEING DEVELOPED WILL BE REDUCED BY TEN (IO) PERCENT TO ALLOW FOR ROADS AND UTILITIES. THE REMAINING ACREAGE SHALL THEN BE DIVIDED BY THE MINIMUM LOT AREA FOR THE ZONING DISTRICT IN WHICH THE PARCEL IS LOCATED. THEREFORE:

- A. 45.355 ACRE LESS 10% (4.535 ACRES) = 40.820 ACRES
- B. (40.82 ACRES x 43,560 SF/ACRE)/120,000 SF = 14.82 LOTS
- THE PROPOSAL IS FOR 14 LOTS WHICH IS EQUAL TO THE MAXIMUM OF 14 LOTS AS CALCULATED.

	TABLE OF EASEMENTS							
EASEMENT	TYPE	GRANTEE	LOTS ENCUMBERED BY EASEMENT					
Α	WATER	TOWN OF CARMEL	OPEN SPACE PARCEL 'A'					
В	WATER	TOWN OF CARMEL	LOTS 7 & 8					
c	WATER	TOWN OF CARMEL	LOTS 10 \$ 11					
D	WATER	TOWN OF CARMEL	OPEN SPACE PARCEL 'A'					

PROJECT

I. PROJECT SITE TO BE DEVELOPED IN ACCORDANCE WITH CHAPTER 156-45 "RESIDENTIAL CLUSTER DEVELOPMENT" OF THE TOWN OF CARMEL ZONING CODE.

56 SPACES REQUIRED

56 SPACES PROVIDED

PROVIDED (MIN.)

0.36

15,807

100

100

22.5

12.5

< 35

< 35

28 SPACES

4.0 PARKING SPACES x 14 DWELLING UNITS =

RESIDENTIAL CLUSTER DEVELOPMENT

MIN. LOT AREA (AC.)

MIN. LOT WIDTH (FT.)

MIN. LOT DEPTH (FT.)

FRONT (FT.)

SIDE (FT.)

REAR (FT.)

MIN. LOT FRONTAGE (L.F.)

MINIMUM YARDS/SETBACKS

MAX. BLDG. HEIGHT (FT.)

MAX. LOT COVERAGE (%)

SIDE YARD SETBACK (FT.)

REAR YARD SETBACK (FT.)

SIDE YARD SETBACK (FT.)

REAR YARD SETBACK (FT.)

SIDE YARD SETBACK (FT.)

REAR YARD SETBACK (FT.)

POOLS AND SHEDS ARE NOT ALLOWED IN THE FRONT YARD

DETACHED SINGLE FAMILY RESIDENCES:

14 GARAGES x 2 SPACES PER GARAGE =

14 DRIVEWAYS x 2 SPACES PER DRIVEWAY =

RESIDENTIAL CLUSTER DEVELOPMENT BULK SCHEDULE

0.35

50

15,250

PROPOSED

- 2. BOUNDARY INFORMATION FROM SURVEY MAP OF PROPERTY, DATED NOVEMBER 14, 1985 AS PREPARED BY BURGESS & BEHR, L.S.

RESIDENTIAL CLUSTER SUBDIVISION NOTES:

- 3. TOPOGRAPHIC INFORMATION FROM A SURVEY MAP DATED JANUARY 28, 1986 AS PREPARED BY
- BURGESS & BEHR, L.S.
- 4. WETLAND LOCATIONS SURVEY LOCATED BY BAXTER LAND SURVEYING, P.C. ON 12/28/17. WETLANDS FLAGGED BY TIM MILLER ASSOCIATES ON 6/2/17 AND 6/9/17.
- 5. EXISTING WATERLINE LOCATION BASED ON FIELD SURVEY ON MAY 12, 2007 BY BAXTER LAND SURVEYING, P.C.
- 6. OWNER/APPLICANT: ANGELO MASTRANTONI

23 FRANCES DRIVE KATONAH, NY 10536

CONTACT: PAUL MASTRANTONI (914) 755-0445

7. SITE DATA: TOTAL LOT AREA = 1,975,697 S.F. (45.355 AC.)

TAX MAP 75.15, BLOCK 1, LOT 19 8. ZONING DISTRICT: R - RESIDENTIAL

UTILITY COMPANY REQUIREMENTS.

9. PROPOSED USE: RESIDENTIAL CLUSTER DEVELOPMENT - 14 LOTS

IO. ALL UTILITIES SHALL BE INSTALLED UNDERGROUND AND IN CONFORMANCE WITH LOCAL CODES AND

II. SEWER SERVICE SHALL BE PROVIDED BY COMMUNITY SUBSURFACE SEWAGE TREATMENT SYSTEM LOCATED ON-SITE AND MAINTAINED AND SERVICED BY HOMEOWNER'S ASSOCIATION. WATER SERVICE SHALL BE PROVIDED BY CONNECTION TO CARMEL WATER DISTRICT #13.

12. ALL ON-SITE TRAFFIC CIRCULATION IS TWO-WAY UNLESS NOTED OTHERWISE.

13. ALL SIGNAGE SHALL CONFORM TO THE REQUIREMENTS OF CHAPTER 63-11 OF THE ZONING CODE OF THE TOWN OF CARMEL.

14. ALL EXTERIOR LIGHTING TO BE INSTALLED SHALL BE DOWNWARD DIRECTED AND SHALL NOT RESULT

IN LIGHT SPILLING OFF THE SITE.

15. THERE ARE NO AREAS PROPOSED TO BE USED FOR OUTDOOR SELLING, DISPLAY OR STORAGE.

16. ALL ON-SITE DEBRIS AND GARBAGE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF.

17. THE USE OF TOWN WATER FOR IRRIGATION PURPOSES IS PROHIBITED.

18. PARCEL 'A' IS OPEN SPACE AND NO FURTHER DEVELOPMENT IS ALLOWED.

ENGINEERS - ARCHITECTS

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

REVISIONS									
NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION				
-	09 NOV 18	REV. PER BI, TE, TP COMMENTS							
2	02 OCT 19	REV. PER TE COMMENTS							
3	II MAY 20	REV. PER TE COMMENTS							

PROPOSED SUBDIVISION PLAN PREPARED FOR:

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



PROJECT MANAGER SUBDIVISION PLAN

DRAWING

12 APR 18

PML

DRAWN BY

_BJK

CHECKED BY


PML


AS NOTED

SCALE

PROJECT NUMBER 8286 DRAWING NUMBER

SHEET ___3_ OF __34_







GRADING NOTES:

- 1. BOUNDARY INFORMATION FROM SURVEY MAP OF PROPERTY, DATED NOVEMBER 14, 1985 AS PREPARED BY BURGESS & BEHR, L.S.
- 2. TOPOGRAPHIC INFORMATION FROM A SURVEY MAP DATED JANUARY 28, 1986 AS PREPARED BY BURGESS & BEHR, L.S.
- 3. WETLAND LOCATIONS SURVEY LOCATED BY BAXTER LAND SURVEYING, P.C. ON 12/28/17 AND _____. WETLANDS FLAGGED BY TIM MILLER ASSOCIATES ON 6/2/17 AND 6/9/17.
- 4. EXISTING WATERLINE LOCATION BASED ON FIELD SURVEY ON MAY 12, 2007 BY BAXTER LAND SURVEYING, P.C.
- 5. PROVIDE 4 INCHES MINIMUM TOPSOIL, WITH SEED AND MULCH AT ALL DISTURBED AREAS.
- 6. CONTOUR INTERVAL = 2 FOOT. VERTICAL DATUM NATIONAL GEODETIC SURVEY STANDARD VERTICAL DATUM OF 1929.
- 7. IF EXPLOSIVES ARE REQUIRED FOR BLASTING, THEY SHALL BE OF SUCH CHARACTER AND STRENGTH AND IN SUCH AMOUNT AS IS PERMITTED BY THE STATE AND LOCAL LAWS AND ORDINANCES AND ALL RESPECTIVE AGENCIES HAVING JURISDICTION OVER THEM A PERMIT WOULD BE REQUIRED FROM THE TOWN

CONTRACTOR INSTALLATION—SEWER/WATER & DRAINAGE NOTES:

1. THE CONTRACTOR IS TO SET ALL STRUCTURES THAT ARE IN ROAD "A" AT BINDER ELEVATION IN ORDER TO COMPLY WITH THE SWPPP. ALL STRUCTURES— DMH, SMH, VALVE COVERS ARE TO BE RAISED USING RINGS WHEN TIME COMES FOR TOP COAT ASPHALT. CATCH BASIN FRAMES AND GRATES WILL HAVE TO BE MANUALLY RESET AT FINISHED GRADE.

	D R /	AINA	GE	STR	UCTU	JRE	SCH	E D U	LE	
DRAIN NO.	CB #1	DMH #1	CB #2	CB #3	DMH #2	DMH #3	CB #5	CB #4	DMH #4	DMH #5
TYPE	СВ	DMH	СВ	СВ	DMH	DMH	СВ	СВ	DMH	DMH
DOWN STREAM DR. NO.	DMH #1	CB #3	CB #3	DMH #2	DMH #3	CB #4	CB #4	DMH #4	DMH #5	CB #7
LENGTH (LF)	60	40	20	85	91	53	20	62	79	87
T.G. / RIM	771.80						753.20	753.20	747.30	739.67
INV. IN / DR#		/CB #1		/CB #2	/CB #3	/DMH #2		750.00	744.40/CB4	736.75/MH4
INV. IN / DR#				/DMH #1						
INV. OUT / DR#	/DMH #1	/CB #3	/CB #3	/DMH #2	/DMH #3	/CB #4	750.30/CB4	749.75/MH4	744.25/MH5	736.25/CB7
STATION	12+37	11+77.5	11+39	11+39	10+56	9+68	9+17	9+17	8+55	7+78
OFFSET	23' R	21' R	12 ' L	12' R	20' R	21' R	12' L	12 ' R	17 ' R	16.5' R

DRAINAGE STRUCTURE SCHEDULE												
DRAIN NO.	ES #1	CB #7	HW #1	CB #6	DMH #6	CB #9	HW #2	YD #1	CB #8	CB #10	CB #11	HW #3
TYPE		CB	HEADWALL	СВ	DMH	СВ	HEADWALL	YD	СВ	CB	СВ	HEADWALL
DOWN STREAM DR. NO.		DMH 6	CB 6	CB 7	CB 9	CB 11	YD 1	CB 8	CB 9	CB 11	DMH 7	DMH 7
LENGTH (LF)		239	16	20	62	142	40	4	20	20	9	70
T.G. / RIM		730.75		730.75		695.55		695.50				
INV. IN / DR#		/CB 6		/HW 1		692.30/CB 8		/HW 2	/YD 1		/CB 9	
INV. IN / DR#		/DMH 5				689.25					/CB 10	
INV. OUT / DR#		/DMH 6	/CB 6	727.70/CB 7			/YD 1	/CB 8	/CB 9	/CB 11	/DMH 7	/DMH 7
STATION		6+92	6+93	6+92	4+44	3+80	3+93	3+78	3+80	2+28	2+28	3+00
OFFSET		12' R	27' L	12' L	16' R	12' R	55' L	17.5' L	12' L	12' L	12' R	35' R

DRAIN NO.	DMH #7	ES #2	CB #12	FS #1	CB #13	FS #2	DMH #8	ES #3
TYPE	DMH	END SECTION	СВ	FLOW SPLITTER	СВ	FLOW SPLITTER	DMH	END SECTION
DOWN STREAM DR. NO.	ES 2		FS 1	UIS/DMH 8	FS 2	UIS/DMH 8	ES 3	
LENGTH (LF)	22		2	40	2	20	56	
T.G. / RIM								
INV. IN / DR#	/HW 3						/FS 1	
INV. IN / DR#	/CB 11						/FS 2	
INV. OUT / DR#	/ES 2		/FS 1	/UIS /DMH 2	/FS 2	/UIS /DMH 8	/ES 3	
STATION	2+25	2+15	0+83	0+81	0+83	0+83	0+60	0+44
OFFSET	22' R	45' R	12' R	16.5' L	12' L	16.5' R	20' R	76' R

DRAINAGE	STRUCTURE	SCHEDULE
DRAIN NO.	OS #1	ES #4
TYPE		
DOWN STREAM DR. NO.		
LENGTH (LF)		
T.G. / RIM		
INV. IN / DR#		
INV. IN / DR#		
INV. OUT / DR#		
STATION		
OFFSET		

1. CB STATIONING AND ELEVATION IS CENTER OF STRUCTURE AT FACE OF CURB.

② DMH, YD, HW ARE CENTER OF STRUCTURE.

DUTNAM NGINEERING, PLLC	
ENGINEERS - ARCHITECTS	

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

——— W ———

CHECK DAM

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION."

REVISIONS

NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION
1	09 NOV 18	REV. PER BI, TE, TP COMMENTS			
2	02 OCT 19	REV. PER TE COMMENTS			

DRAINAGE STRUCTURE SCHEDULE LEGEND: CB - CATCH BASIN

OS - OUTLET OR OVERFLOW STRUCTURE

WV - WATER QUALITY VAULT

CD - CURTAIN DRAIN DMH — DRAINAGE MANHOLE

ES - END SECTION FD - FOOTING DRAIN HW - HEADWALL

RD - ROOF DRAIN YD - YARD DRAIN

GRAPHIC SCALE


1 INCH = 50 FEET


OLD FORGE ESTATES


PROPOSED SUBDIVISION PLAN PREPARED FOR:

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19

DATE	DRAWING	PROJECT NUMBER
12 APR 18		8286
PROJECT MANAGER		DRAWING NUMBER
PML	GRADING and DRAINAGE PLAN	
DRAWN BY	GRADING UND DRAINAGE PLAN	I
B JK		1
CHECKED BY		
PML		
SCALE		
AS NOTED		SHEET <u>6</u> OF <u>34</u>







ENGINEERS - ARCHITECTS

T-INTERSECTION WITH WATER VALVES

HYDRANT

THRUST BLOCK

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION,

AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

771.05

767.35/SMH I

766.36

762.60/SMH 2 | 753.50/SMH 3

757.25

747.60

743.15/SMH 4

737.50

730.00/SMH 5

- 767.10/SMH 3 | 762.40/SMH 4 | 752.00/SMH 5 | 741.40/SMH 6 | 729.75/SMH 7 | 723.75/SMH 8 | 710.00/SMH 9 | 702.50/SEP. TANK | 699.83/WET WELL | 699.72/V. CHAME

773.75

RIM ELEV.

INV. IN / from SS#

INV. IN / from SS#

INV. OUT / to SS# | 769.35/SMH2

REVISIONS NO. DATE DESCRIPTION

729.90

724.00/SMH 6

718.65

714.90/SMH 7

706.50

702.75/SMH 8


PROJECT

700.08/SMH 9 699.72/SEP. TAN

- 8. A WATER METER SHALL BE INSTALLED FOR EACH BUILDING WITH REMOTE ON EXTERIOR OF THE BUILDING. METERS TO BE PURCHASED FROM THE TOWN OF CARMEL.
- 9. ALL DWELLINGS SHALL BE EQUIPPED WITH A PRESSURE REDUCING VALVE ON THE WATER SERVICE LINE AFTER IT ENTERS THE BUILDING TO LIMIT THE WORKING PRESSURE TO A MAXIMUM OF TO PSI.
- IO. TRACER WIRE (14 GA.) TO BE PLACED IN ALL WATER MAIN TRENCHES AT A DEPTH OF 2'-O" BELOW FINISHED GRADE.
- 18. LOCATION OF EXISTING WATERMAIN TAKEN FROM SURVEY PREPARED BY BAXTER SURVEYING IN 2007. EXACT LOCATIONS TO BE VERIFIED IN FIELD.
- 19. REFER TO DRAWING NO. C-315 FOR ADDITIONAL FIRE HYDRANT AND WATER VALVE NOTES.

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES


> BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19





DRAWING 12 APR 18 ROJECT MANAGER UTILITIES PLAN CHECKED BY

ROJECT NUMBER 8286 RAWING NUMBER

SHEET _ 9 OF _ 31







INFILTRATION TEST DATA

TEST RESULT # (INCH/HOUR)		DATE OF TEST
617-1618	13.75	11/16/2016
619-1620	12.25	11/16/2016
620-1621	5.5	11/16/2016
1624	32.2	11/16/2016
1625	10.25	11/16/2016
1626	18.25	11/16/2016
1627	84	11/16/2016
1628	57	11/16/2016
1629	90.0	11/16/2016
1630	20.0	11/16/2016
1631	20.0	11/16/2016
1632	22.0	11/16/2016

SEWER FORCE MAIN

EXISTING CONTOUR EXISTING DRAINAGE LINE

EXISTING CATCH BASIN EXISTING WATER LINE

PROPOSED HOUSE


DEEP TEST HOLE INFILTRATION TEST HOLE

(845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

TE	DRAWING
12 APR 18	
OJECT MANAGER	T CT 00
PML	TEST LOCA
AWN BY	STORMWATE
_BJK	JION MAIL
ECKED BY	
PML	

8286 RAWING NUMBER CATIONS FOR ER PRACTICES

SHEET 12 OF 31



EXISTING DRAINAGE PIPE

EXISTING CONTOURS

PROPOSED CONTOURS



STABILIZED CONSTRUCTION ENTRANCE



——(4|6)——

TEMPORARY STAGING AREA



EARTH DIKE

LIMITS OF DISTURBANCE




TEMPORARY SOIL STOCKPILE

EROSION CONTROL BLANKET



INLET PROTECTION SILT FENCE



XXX


CONSTRUCTION FENCE ORANGE SAFETY FENCE CHECK DAM

LEVEL SPREADER

TEMPORARY SWALE



EROSION & SEDIMENT CONTROL PLAN - PHASE I



TEMPORARY SEDIMENT TRAP & BASIN VOLUMES

- SEDIMENT BASIN; CONTRIBUTING AREA AT PHASE I- 1.05 AC REQUIRED VOLUME (ALL PHASES) = 30,380 CF VOLUME PROVIDED-46,354 CF SEDIMENT REMOVAL ELEVATION- 679.29
- SEDIMENT TRAP #I; CONTRIBUTING AREA- 0.22 AC REQUIRED VOLUME- 3600 CF PER ACRE X 022 ACRES = 792 CF PROVIDED- 795 CF SEDIMENT REMOVAL ELEVATION- 693.20
- 3. SEDIMENT TRAP #2; CONTRIBUTING AREA- 0.71 AC REQUIRED VOLUME- 3600 CF PER ACRE X 0.71 ACRES = 2556 CF PROVIDED- 1970 CF SEDIMENT REMOVAL ELEVATION- 692.67

TEMPORARY SWALE DIMENSIONAL CHART REFER TO DETAIL #4/C-310							
SWALE # BOTTOM WIDTH DEPTH SIDE SLOPE LENGTH (FT) (%)							
1.0	0.75	2:1	730	11.0			
1.0	0.75	2:1	610	11.8			
1.0	1.0	2:1	360	11.1			
1.0	0.75	2:1	80	2.3			
	REF BOTTOM WIDTH (FT) I.O I.O	REFER TO DETA BOTTOM WIDTH (FT) I.O 0.75 I.O 0.75 I.O 1.O	REFER TO DETAIL #4/C-3IO	REFER TO DETAIL #4/C-3IO BOTTOM WIDTH DEPTH (FT) SIDE SLOPE (FT/FT) LENGTH (FT) I.O 0.75 2:1 730 I.O 0.75 2:1 6IO I.O 1.O 2:1 360			

2:1

1.25

LEVEL SPREADER DIMENSIONS							
REFER TO DETAIL #18/C-310							
LEVEL SPREADER #	Q ø (CFS)	DEPTH (INCH)	WIDTH (FT)	LENGTH (FT)			
Ι	0.37	6	э	0			
2	2.18	6	3	20			

SEQUENCE OF CONSTRUCTION:

CREATING ACCESS ROAD DISTURBANCE AREA = 4.15 AC.

- I. SURVEY AND STAKE OUT THE ROAD WITH OFFSETS AND LOCATION OF THE PROPOSED DETENTION POND. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD.
- 2. INSTALL CONSTRUCTION FENCES ALONG LIMITS OF DISTURBANCE. VEHICLES TO BE INSPECTED AND CLEANED,
- 3. MARK IN GROUND LOCATION OF FUTURE UNDERGROUND INFILTRATION SYSTEMS UIS-I AND UIS-2 AND INFILTRATION BASIN IB-2. INSTALL ORANGE SAFETY FENCE AROUND PERIMETERS OF THESE PRACTICES. NO EQUIPMENT CAN BE DRIVEN OVER THESE AREAS.
- 4. INSTALL STABILIZED CONSTRUCTION ENTRANCE AS SHOWN ON THE PLAN.

IF REQUIRED, PRIOR TO ENTERING BALDWIN PLACE ROAD.

- 5. INSTALL SILT FENCES IMMEDIATELY DOWNGRADE OF AREAS OF PROPOSED DISTURBANCE AS SHOWN ON THE
- 6. INSTALL SAND BEDS FOR PLACEMENT OF DEWATERING BAGS. SEE DETAIL #10/C-310. THE DEWATERING BAGS WOULD BE NEEDED IF THE CONTRACTOR HAS STANDING WATER AFTER RAIN EVENTS.
- 7. CLEAR AREA OF PHASE I FROM STATION 0+00 TO STATION 13+50 AND GRUB TO STA. 10+00. TREE STUMPS FROM STA. 10+00 TO STA 13+50 TO REMAIN. STRIP TOPSOIL FROM STA 0+00 TO STA. 10+00. STORE USABLE ORGANIC MATERIAL AT STOCKPILES. PROVIDE STOCKPILE PROTECTION PER DETAIL #3/C-310.
- 8. BRING IN ALL EQUIPMENT AND MATERIALS NECESSARY TO PERFORM PHASE I OF CONSTRUCTION. ESTABLISH STAGING AREA AS SHOWN ON THE PLAN.
- 9. EXCAVATE DETENTION POND TO ACT AS TEMPORARY SEDIMENT BASIN PER DETAIL #1/C-155.
- IO. EXCAVATE ROAD BED FOR ADDITIONAL FILL NECESSARY TO CREATE POND EMBANKMENTS, FILL MATERIAL SHALL BE FREE FROM ROOTS, VEGETATION AND OVERSIZED STONES. FILL TO BE PLACED IN 12 INCH LIFTS AND COMPACTED TO 95% DRY DENSITY BY MECHANICAL MEANS.
- II. INSTALL OUTLET STRUCTURE #OSI ALONG WITH DISCHARGE PIPE. PLUG OUTLET PIPE FROM THE TEMPORARY OUTLET STRUCTURE.
- 12. EXCAVATE STONE OUTLET SEDIMENT TRAPS #1 \$ #2 WHERE SHOWN ON THE PLAN. REFER TO DIMENSIONAL TABLE ON SHEET #C-155 AND DETAIL #12/C-310.
- 13. THE SEDIMENT BASIN, SEDIMENT TRAPS AND ALL DISTURBED AREAS MUST BE STABILIZED WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STABILIZED.
- 14. ONCE THE TEMPORARY SEDIMENT BASIN IS COMPLETED AND STABILIZED, PROCEED WITH WORK.
- 15. CONNECT SKIMMER DEVICE TO THE POND DRAIN PIPE. REMOVE PLUG FROM THE OUTLET PIPE FROM THE OUTLET STRUCTURE OSI.
- 16. INSTALL EARTH DIKE ALONG NORTHERN PERIMETERS OF THE DISTURBANCE FOR THAT PORTION OF THE ROAD LOCATED BETWEEN STA. 0+50 AND 8+75 TO DIVERT CLEAN STORMWATER FROM UNDISTURBED AREAS
- IT. EXCAVATE TEMPORARY SWALES #I AND #2 BETWEEN STA. 6+00 AND IO+00 AS SHOWN ON THE PLAN.
- 18. ROUGH GRADE THE ROAD BETWEEN STA. 0+00 AND 6+00. EXCAVATE TEMPORARY SWALES #1 AND 2 ALONG THE ROAD SHOULDERS AS EXCAVATION PROGRESSES AS SHOWN ON THE PLAN.
- 19. INSTALL WATER BARS PER DETAIL #15/C-310.
- 20. EXCAVATED SOIL TO BE DEPOSITED ON THAT PORTION OF THE ROAD WHERE FILL IS REQUIRED (BETWEEN STA. 6+00 AND 10+00). THE ADDITIONAL EXCAVATED SOIL SHALL BE STORED AT STOCKPILE WHERE SHOWN ON THE PLAN. THIS SOIL SHALL BE NEEDED TO CREATE BUILDING FILL PADS ON LOTS II THRU 14 (PHASE 3 OF CONSTRUCTION).
- 21. STABILIZE ALL DISTURBED AREAS WITHIN ONE (I) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STABILIZED. PLACE 4 INCHES OF TOPSOIL ON EXPOSED SLOPE AND INSTALL EROSION CONTROL BLANKET AS SHOWN IN DETAIL #5/C-3IO.
- 22. EXCAVATE TRENCHES FOR INSTALLATION OF WATER, STORMWATER AND SEWER PIPES ALONG THE ROAD TO STA. 6+00. INSTALL SEMER MANHOLES SMH8 & SMH9. INSTALL CATCH BASIN CB4, MANHOLES DMH3, DMH4 & DMH6, FLOW SPLITTERS F52, F53, F54, YARD DRAIN YD#I AND END SECTION E52. STRUCTURES TO BE INSTALLED STARTING FROM DOWNHILL STRUCTURE TO UPHILL STRUCTURE. SEE SHEETS #C-120 AND C-140 FOR ALL RIM AND INVERT ELEVATIONS. TRENCHES TO BE BACKFILLED IMMEDIATELY UPON COMPLETION OF INSTALLATION OF PIPES AND MANHOLES. EXPOSED SOIL TO BE STABILIZED IMMEDIATELY AFTER BACKFILL. INSTALLATION OF WATER, SEWER AND STORM PIPES SHALL BE PERFORMED CONCURRENTLY.
- 23. RIMS OF STRUCTURES INSTALLED IN PAVED AREAS SHALL BE SET AT BINDER COURSE ELEVATION PER DETAIL #35/C-317. PROTECT CATCH BASIN PER CONSTRUCTION DETAIL. THE STRUCTURES ARE NOT TO RECEIVE ANY STORMMATER FLOW UNTIL ASPHALT BINDER COURSE IS PLACED.
- 24. INSTALL SLEEVE UNDER THE ROAD NEAR STA. 3+85 FOR FUTURE INSTALLATION OF SEMER FORCE MAIN.
- 25. AFTER THE TRENCH WORK IS COMPLETED, INSTALL CONCRETE CURBING FROM STA. 0+00 TO 6+00. THE PROPOSED ROAD SHALL BE PAVED WITH BINDER COURSE PER DETAIL #1/C-314 TO STA. 6+00.
- 26. STABILIZE ALL DISTURBED AREAS WITHIN ONE (I) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STABILIZED.
- 27. PROCEED WITH GRUBING/STUMPING THE ROAD FROM STA. 10+00 TO THE END (STA. 13+50).
- 28. INSTALL ADDITIONAL SILT FENCES WHERE SHOWN ON THE PLAN.
- 29. EXTEND TEMPORARY SWALES AS SHOWN ON THE PLAN.
- 30. EXCAVATE LEVEL SPREADER #1 AND #2 WHERE SHOWN ON THE PLAN, INSTALL EARTH DIKE ALONG EASTERLY PERIMETERS OF THE DISTURBANCE FOR THAT PORTION OF THE ROAD LOCATED BETWEEN STA. 9+60 AND 13+50 TO DIVERT CLEAN STORMWATER FROM UNDISTURBED AREAS UPGRADE. FLOW FROM THE DIKES SHALL TERMINATE AT THE PROVIDED LEVEL SPREADERS.
- 3I. GRADE THE ROAD FROM STA. 6+00 TO 10+00. FILL TO BE PLACED IN 12 INCH LIFTS AND COMPACTED TO 95 PERCENT DRY DENSITY BY MECHANICAL MEANS.
- 32. ROUGH GRADE ROAD AND CUL-DE-SAC TO STA. 13+50. TRUCK OUT THE EXCAVATED SOIL OFF THE SITE.
- 33. CONTINUE WATER BAR INSTALLATION AS ROAD GRADING PROGRESSES.
- 34. STABILIZE ALL DISTURBED AREAS WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STABILIZED. PLACE 4 INCHES OF TOPSOIL ON EXPOSED SLOPES AND INSTALL EROSION CONTROL BLANKET AS SHOWN IN DETAIL #5/C-3IO.
- 35. EXCAVATE TRENCHES FOR INSTALLATION OF WATER, STORMWATER AND SEWER PIPES ALONG THE ROAD FROM STA. 6+00 TO STA. 13+50. INSTALL SEWER MANHOLES SMHI TO SMHT. INSTALL CATCH BASINS CBI TO CB3, MANHOLES DMHI & DMH2, AND FLOW SPLITTER FSI. STRUCTURES TO BE INSTALLED STARTING FROM DOWNHILL STRUCTURE TO UPHILL STRUCTURE. SEE DRAWINGS #C-130 AND C-140 FOR ALL RIM AND INVERT ELEVATIONS.
- 36. INSTALL SLEEVES UNDER THE ROAD NEAR STATIONS 7+00, 9+62, II+05 AND I2+24 FOR FUTURE INSTALLATION OF UTILITY CABLES.
- 37. INSTALL PORTION OF THE PIPE DMH9-FSI WHICH GOES UNDER THE ROAD. PLUG END OF THE PIPE.
- 38. INSTALL THE 3 WAY TEES ON WATER LINE AT ROAD STA. 10+37 AND 12+63 FOR FUTURE CONNECTION TO THE EXISTING WATERMAIN.
- 39. TRENCHES TO BE BACKFILLED IMMEDIATELY UPON COMPLETION OF INSTALLATION OF PIPES AND MANHOLES. EXPOSED SOIL TO BE STABILIZED IMMEDIATELY AFTER BACKFILL. TEST WATER MAIN. TO LIMIT WORK WITHIN ROAD R.O.W., INSTALLATION OF STORMWATER, WATER AND STORM PIPES SHALL BE PERFORMED
- 40. RIMS OF STRUCTURES INSTALLED IN PAVED AREAS SHALL BE SET AT BINDER COURSE ELEVATION PER DETAIL #5/C-317. PROTECT CATCH BASINS PER CONSTRUCTION DETAIL. THE STRUCTURES ARE NOT TO RECEIVE ANY STORMMATER FLOW UNTIL ASPHALT BINDER COURSE IS PLACED.
- 41. AFTER THE TRENCH WORK IS COMPLETED, INSTALL CONCRETE CURB. THE PROPOSED ROAD SHALL BE PAVED WITH BINDER COURSE PER DETAIL #I/C-314 TO STA. 13+50. TEST SEWER MAINS AND MANHOLES.
- 42. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE ALL DISTURBED AREAS AS DESCRIBED IN PHASE I OF SEQUENCE OF CONSTRUCTION ARE STABILIZED.



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 ■ PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145. SECTION 7209 SUBDIVISION 2. "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

EVISIONS

NO.	DATE	DESCRIPTION	i
			1
			i
			i
			1

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES


BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19




120

	DATE	DRAWING
	12 APR 18	
	PROJECT MANAGER	EROSION and SEDII
_	PML	CONTROL DI AI
	DRAWN BY	CONTROL PLAI
	B JK	PHASE I
	CHECKED BY	
	PML	

ROJECT NUMBER 8286 RAWING NUMBER SHEET ___ |3__ OF ___ 3|



EROSION & SEDIMENT CONTROL PLAN - PHASE 2



TEMPORARY SEDIMENT TRAP VOLUMES

- SEDIMENT TRAP #3 CONTRIBUTING AREA- 1.9 AC REQUIRED VOLUME- 3600 CF PER ACRE X 1.9 ACRES = 6840 CF
- PROVIDED- 6881 CF SEDIMENT REMOVAL ELEVATION- 136.68
- SEDIMENT TRAP #4
- CONTRIBUTING AREA- 2.5 AC REQUIRED VOLUME- 3600 CF PER ACRE X 2.5 ACRES = 9000 CF PROVIDED- 9863 CF SEDIMENT REMOVAL ELEVATION- 754.65
 - ENGINEERS ARCHITECTS

4 OLD ROUTE 6, BREMSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

ROJECT REVISIONS NO. DATE DESCRIPTION

OLD FORGE ESTATES

PROPOSED SUBDIVISION PLAN PREPARED FOR:

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19

VEHICLE & EQUIPMENT FUELING and WET NOZZLE REPORT:

DESCRIPTION AND PURPOSE

SEQUENCE OF CONSTRUCTION:

CONSTRUCTION ENTRANCE. REFER TO DETAIL #I/C-3IO.

ESTABLISH STAGING AREA AS SHOWN ON THE PLAN.

ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG LIMITS

2. INSTALL STABILIZED CONSTRUCTION ENTRANCE NEAR STA. 10+00 OF THE CONSTRUCTED ROAD. INSTALL

3. INSTALL ADDITIONAL SILT FENCE IMMEDIATELY DOWNGRADE OF AREAS OF PROPOSED DISTURBANCE AS

6. CLEAR AND PREPARE AREA FOR THE PROPOSED CONSTRUCTION. STRIP TOPSOIL AND STORE USABLE ORGANIC MATERIAL AT STOCKPILE. PROVIDE STOCKPILE PROTECTION PER DETAIL #3/C-3IO.

7. STAKE OUT CORNERS OF THE FUTURE HOUSES ON LOTS #2, 3 \$11 AS SHOWN ON THE PLAN. EXCAVATE

9. STABILIZE ALL DISTURBED AREAS AS DESCRIBED IN "STABILIZATION NOTES" WITHIN ONE (I) WEEK

FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE

EXCAVATE THE SITE EAST OF THE CONSTRUCTED ROAD. DEPOSIT EXCAVATED SOIL WEST OF THE

12. INSTALL WATERMAIN SEGMENTS FROM ROAD TO THE EXISTING WATERMAIN AS OUTLINED IN "WATERMAIN INSTALLATION SEQUENCE OF CONSTRUCTION" ON SHEET #C-XXXX, PERFORM TESTING AND THEN TIE IN. AS

3. CREATE YARDS AND BUILDING PADS FOR THE FUTURE HOUSE CONSTRUCTION. WHERE FILL IS NEEDED TO

14. STABILIZE ALL AREAS DISTURBED IN PHASE 2 OF CONSTRUCTION AS DESCRIBED IN "STABILIZATION NOTES"

THERE SHALL BE A RECEPTACLE PLACED ON THE SITE TO TEMPORARILY STORE GARBAGE, DEBRIS OR

2. THE RECORD OWNER SHALL BE RESPONSIBLE FOR KEEPING THE SITE FREE OF LITTER AT ALL TIMES, DURING

CONSTRUCTION ACTIVITIES THE OWNER MAY DESIGNATE A CONTRACTOR IN CHARGE AS A RESPONSIBLE

3. THE SITE SHALL BE INSPECTED AT THE END OF EACH WORKDAY AND TRASH, DEBRIS AND GARBAGE SHALL

5. CONSTRUCTION VEHICLES SHALL BE SERVICED OFF-SITE AT A PROPER FACILITY. LEAKING OR ILL REPAIRED VEHICLES SHALL NOT BE LOCATED ON SITE. NO OIL CHANGES ARE PERMITTED ON SITE. FUELING OF VEHICLES ON SITE SHALL BE CAREFULLY PERFORMED WITH AN APPROVED DISPENSER NOZZLE HOSE AND PUMP. SPILLS SHALL PROMPTLY BE REPORTED TO THE NYSDEC AND TOWN. OIL ABSORBENT PADS AND ROLLS SHALL BE

7. THE CONTAINERS SHALL BE OF SUFFICIENT SIZE FOR THE CONSTRUCTION ACTIVITY. CONTAINERS SHALL BE

8. PAINTS CHEMICALS OR OTHER TOXIC SUBSTANCES SHALL NOT BE PLACED IN TRASH CONTAINERS, PAINTS.

EMPTIED BY AN APPROVED CARTER TO A PROPER FACILITY WHEN FULL. CONTAINERS SHALL BE COVERED

CHEMICALS OR TOXIC SUBSTANCES SHALL BE REMOVED FROM SITE BY AN APPROVED LICENSED CARTER.

IO. DEBRIS OR TRASH PILES ARE NOT PERMITTED. DEBRIS SHALL BE PLACED IN CONTAINERS. TEMPORARY PILES

OF BRUSH OR STUMPS SHALL BE PROTECTED BY SILT FENCE SIMILAR TO TOPSOIL STOCKPILES.

4. A PORTABLE TOILET FACILITY SHALL BE PROVIDED FOR CONSTRUCTION WORKERS AND AN ADDITIONAL

BE PICKED UP AND PLACED IN ON-SITE DUMPSTERS OR OTHERWISE REMOVED FROM THE SITE.

6. CHEMICAL SOIL ADDITIVES OR HERBICIDES SHALL NOT BE USED ON SITE DURING CONSTRUCTION.

TO PREVENT INFILTRATION OF RAIN AND TO PREVENT WIND BORNE DEBRIS REMOVAL.

TEMPORARY SWALE DIMENSIONAL CHART

REFER TO DETAIL #4/C-3IO

SIDE SLOPE

(FT/FT)

2:1

2:1

2:1

2:1

2:1

2:1

2:1

2:1

LENGTH

(FT)

730

610

360

80

120

230

320

485

SLOPE

11.0

11.8

11.1

2.3

4.3

8.8

3.5

DEPTH

0.75

0.75

1.0

0.75

1.25

1.25

1.25

1.25

BOTTOM WIDTH

1.0

1.0

2.0

2.0

SWALE #

CONSTRUCTION WASTE MATERIAL. THE CONTAINER SHALL NOT BE USED TO TRANSFER ANY GARBAGE FROM

PLACED IN 12 INCH LIFTS AND COMPACTED TO 95 PERCENT DRY DENSITY BY MECHANICAL MEANS.

ON-SITE POLLUTION CONTROL MEASURES:

CREATE THE PADS IT SHOULD BE FREE FROM ROOTS, VEGETATION AND OVERSIZED STONES. FILL TO BE

WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE

EXCAVATION PROGRESSES, REMOVE ABANDONED SECTION OF WATERMAIN.

PROPOSED ROAD. TRUCKS SHALL NOT CROSS THE ROAD. THE SOIL TRANSPORTATION SHALL BE DONE

SEDIMENT TRAPS #3 & 4. THE TRAPS SHALL NOT BE LOCATED CLOSER THAN 20 FEET FROM THE STAKED

TEMPORARY ACCESS CULVERT FOR FUTURE TEMPORARY SWALE #8 CROSSING THE STABILIZED

4. CLEAR AND GRUB AREA OF PHASE 2 TO THE LIMITS OF DISTURBANCE SHOWN ON THE PLAN.

5. BRING IN ALL EQUIPMENT AND MATERIALS NECESSARY TO PERFORM PHASE 2 OF CONSTRUCTION.

PHASE 2

DISTURBANCE AREA = 4.53 AC.

SHOWN ON THE PLAN.

OUT BUILDING CORNERS.

AREAS ARE STABILIZED.

ANY OTHER OFF-SITE ACTIVITY.

FACILITY FOR EVERY 10 ON-SITE WORKERS.

USED TO TEMPORARILY CONTAIN ANY SPILLS.

9. THERE SHALL BE NO OPEN FIRES OR BARREL FIRES PERMITTED.

8. EXCAVATE TEMPORARY SMALES #6, 7 \$ 8.

IO. CONTRACTOR TO START CUT/FILL OPERATIONS.

OVER LAND NORTH OF THE CUL-DE-SAC.

VEHICLE EQUIPMENT FUELING PROCEDURES AND PRACTICES ARE DESIGNED TO PREVENT FUEL SPILLS AND LEAKS, AND REDUCE OR ELIMINATE CONTAMINATION OF STORMWATER. THIS CAN BE ACCOMPLISHED BY FUELING IN DESIGNATED AREAS ONLY, IMPLEMENTING SPILL CONTROLS, AND TRAINING EMPLOYEES AND SUBCONTRACTORS IN PROPER FUELING PROCEDURES.

SUITABLE APPLICATIONS

THESE PROCEDURES ARE SUITABLE ON ALL CONSTRUCTION SITES WHERE VEHICLE AND EQUIPMENT FUELING TAKES

LIMITATIONS

ONSITE VEHICLE AND EQUIPMENT FUELING SHOULD ONLY BE USED WHERE IT IS IMPRACTICAL TO SEND VEHICLES AND EQUIPMENT OFFSITE FOR FUELING.

DISCOURAGE "TOPPING-OFF" OF FUEL TANKS.

AREA WITH LITTLE LOST TIME

- # ABSORBENT SPILL CLEANUP MATERIALS AND SPILL KITS SHALL BE AVAILABLE IN FUELING AREAS AND ON FUELING TRUCKS, AND SHOULD BE DISPOSED OF PROPERLY AFTER USE.
- # DRIP PANS OR ABSORBENT PADS SHOULD BE USED DURING VEHICLE AND EQUIPMENT FUELING, UNLESS THE FUELING IS PERFORMED OVER AN IMPERMEABLE SURFACE IN A DEDICATED FUELING AREA.
- # USE ABSORBENT MATERIALS ON SMALL SPILLS. DO NOT HOSE DOWN OR BURY THE SPILL. REMOVE THE ADSORBENT MATERIALS PROMPTLY AND DISPOSE OF PROPERLY.
- # AVOID MOBILE FUELING OF MOBILE CONSTRUCTION EQUIPMENT AROUND THE SITE; RATHER, TRANSPORT THE EQUIPMENT TO DESIGNATED FUELING AREAS. WITH THE EXCEPTION OF TRACKED EQUIPMENT SUCH AS BULLDOZERS AND LARGE EXCAVATORS, MOST VEHICLES SHOULD BE ABLE TO TRAVEL TO A DESIGNATED
- # EMPLOYEES AND SUBCONTRACTORS SHALL BE TRAINED IN PROPER FUELING AND CLEANUP PROCEDURES
- # WHEN FUELING MUST TAKE PLACE OUTSIDE, DESIGNATE AN AREA AWAY FROM DRAINAGE COURSES TO
- # DEDICATED FUELING AREAS SHOULD BE PROTECTED FROM STORMWATER RUNON AND RUNOFF, AND SHOULD BE LOCATED AT LEAST 50 FEET AWAY FROM DOWNSTREAM DRAINAGE FACILITIES AND WATERCOURSES. FUELING MUST BE PERFORMED ON LEVEL-GRADE AREAS.
- # PROTECT FUELING AREAS WITH BERMS AND DIKES TO PREVENT RUNON, RUNOFF, AND TO CONTAIN
- # NOZZLE USED IN VEHICLE AND EQUIPMENT FUELING SHOULD BE EQUIPPED WITH AN AUTOMATIC SHUTOFF TO CONTROL DRIPS. FUELING OPERATIONS SHOULD NOT BE LEFT UNATTENDED.
- # FEDERAL, STATE AND LOCAL REQUIREMENTS SHOULD BE OBSERVED FOR ANY STATIONARY ABOVE GROUND STORAGE TANKS.

INSPECTION AND MAINTENANCE

- * VEHICLES AND EQUIPMENT SHOULD BE INSPECTED EACH DAY OF USE FOR LEAKS. LEAKS SHOULD BE REPAIRED IMMEDIATELY OR PROBLEM VEHICLES OR EQUIPMENT SHOULD BE REMOVED FROM THE
- # KEEP AMPLE SUPPLIES OF SPILL CLEANUP MATERIALS ON-SITE.
- # IMMEDIATELY CLEAN UP SPILLS AND PROPERLY DISPOSE OF CONTAMINATED SOIL AND CLEANUP MATERIALS.

GENERAL NOTES

- I. THE SITE SHALL BE DISTURBED ONLY WHERE NECESSARY. ONLY THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED (NO MORE THAN 5 ACRES) AT ANY ONE TIME DURING DEVELOPMENT. WHEN LAND IS EXPOSED, THE EXPOSURE SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME BY IMMEDIATE STABILIZATION PER THE STABILIZATION NOTES, UNLESS SPECIFIED OTHERWISE. ALL DISTURBED AREAS ARE CONSIDERED "STABILIZED" WHEN 80% OF UNIFORM, PERENNIAL VEGETATIVE COVER IS ACHIEVED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS MULCHES, EROSION CONTROL BLANKET, ETC.) HAVE BEEN PROPERLY EMPLOYED. NO WORK SHALL CONTINUE BEFORE PRIOR DISTURBANCE IS STABILIZED.
- WHEREVER FEASIBLE, NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED.
- AREAS UNDERGOING EARTHWORK, WHERE SOIL IS TO BE LEFT EXPOSED FOR MORE THAN FIFTEEN DAYS, SHALL BE STABILIZED WITH EITHER TEMPORARY OR PERMANENT VEGETATIVE COVER. TEMPORARY COVER SHALL BE USED WHEN THE PROJECT SCHEDULE DOES NOT COINCIDE WITH THE OPTIMUM PLANTING SEASON. IN GENERAL, OPTIMUM PLANTING TIMES FOR GRASSES ARE MARCH 15TH TO MAY 31ST AND SEPTEMBER 1ST TO NOVEMBER 15TH. DURING OPTIMUM PLANTING TIMES PERMANENT VEGETATIVE COVER WILL BE INSTALLED. SEE SPECIFICATIONS FOR FURTHER DETAILS
- 4. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL ARRANGE A PRE-CONSTRUCTION MEETING INVITING ALL INVOLVED REVIEW AGENCIES AND ENGINEERS OF RECORD PRIOR TO START OF CONSTRUCTION ACTIVITIES.
- 5. TEMPORARY MEASURES SHALL BE MAINTAINED BY PROJECT OWNER / DEVELOPER OR A DESIGNATED REPRESENTATIVE (SUCH AS THE GENERAL CONTRACTOR) DURING THE ENTIRE CONSTRUCTION PERIOD AND UNTIL RESPONSIBILITIES ARE TRANSFERRED TO THE HOMEOWNERS ASSOCIATION (HOA). THE HOA WILL THEN TAKE CHARGE OF ALL MAINTENANCE ACTIVITIES OF THE PERMANENT STORMWATER MANAGEMENT/TREATMENT COMPONENTS AND STRUCTURES.

DEVELOPER/OWNER: ANGELO MASTRANTON

23 FRANCES DRIVE KATONAH, NY 10536 CONTACT: PAUL MASTRANTONI

(914) 755-0445

- 6. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL RETAIN THE SERVICE OF QUALIFIED PERSONNEL (LICENSED PROFESSIONAL ENGINEER, CERTIFIED PROFESSIONAL IN EROSION & SEDIMENT CONTROL-CPESC OR SOIL SCIENTIST) TO PERFORM SITE INSPECTIONS DURING THE CONSTRUCTION PERIOD AND FINAL SITE INSPECTION AT PROJECT COMPLETION.
- 7. THE CONTRACTOR SHALL MAKE AVAILABLE ON SITE, ALL EQUIPMENT, MATERIALS AND LABOR NECESSARY TO EFFECT EMERGENCY REPAIR AND REPLACEMENT OF THE EROSION CONTROL MEASURES.
- 8. SITE INSPECTIONS DURING CONSTRUCTION PERIOD SHALL BE PERFORMED AT LEAST EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER, DURING WINTER, IF THE SOIL DISTURBANCE IS COMPLETELY SUSPENDED AND THE SITE IS PROPERLY STABILIZED, INSPECTION FREQUENCY MAY REDUCE, BUT SHALL MAINTAIN A MINIMUM OF MONTHLY INSPECTIONS IN ALL SITUATIONS (EVEN WHEN THERE IS TOTAL WINTER SHUTDOWN). DURING PERIODS OF REDUCED INSPECTION FREQUENCY, INSPECTIONS MUST STILL BE DONE AFTER EVERY STORM EVENT OF 0.5 INCHES OR GREATER. TO BE ALLOWED TO REDUCE INSPECTION FREQUENCIES, THE OPERATOR MUST COMPLETE STABILIZATION ACTIVITIES (PERIMETER CONTROLS, TRAPS, BARRIERS, ETC.) BEFORE PROPER INSTALLATION IS PRECLUDED BY SNOW COVER OR FROZEN GROUND, IF VEGETATION IS DESIRED, SEEDING, PLANTING, AND/OR SODDING MUST BE SCHEDULED TO AVOID DIE-OFF FROM FALL FROSTS AND ALLOW FOR PROPER GERMINATION/ESTABLISHMENT
- 9. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED AREAS PERIODICALLY
- IO. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL KEEP INSPECTION REPORTS AND LOGS AT THE SITE. A SUMMARY OF INSPECTION ACTIVITIES SHALL BE POSTED AT A PUBLICLY ACCESSIBLE AREA OF THE SITE ON A MONTHLY BASIS.
- PRIOR TO START OF CONSTRUCTION ACTIVITIES, THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL CERTIFY ON THE INSPECTION LOG THAT A SWPPP WAS PROPERLY PREPARED FOR THE PROJECT AND CONFORMS TO ALL FEDERAL, STATE AND LOCAL EROSION & SEDIMENT CONTROL REQUIREMENTS.
- 12. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL PROVIDE A PHONE NUMBER TO THE DIRECTOR OF CODE ENFORCEMENT FOR USE IN EMERGENCY SITUATIONS.
- 13. THE OWNER/DEVELOPER SHALL MAINTAIN THE CONSTRUCTION SITE FREE OF DEBRIS, LITTER AND CONSTRUCTION CHEMICALS. A DUMPSTER SHALL BE LOCATED ON THE SITE AND PICK UP ARRANGED WHEN IT

STABILIZATION NOTES

- TEMPORARY VEGETATIVE COVER:
- A. SCARIFY COMPACTED SOIL AREAS
- B. LIME AS REQUIRED TO PH 6.5. FERTILIZE WITH 10-10-10 AT RATE 200 LBS/AC.
- D. INCORPORATE AMENDMENTS INTO SOIL WITH DISC HARROW. E. SEED AS FOLLOWS:

SPRING/SUMMER/EARLY FALL PLANTING: ANNUAL RYEGRASS AND CEREAL OATS @ 30 LBS/AC. LATE FALL/EARLY WINTER PLANTING: AROOSTOOK WINTER RYE @ 100 LBS./AC.


- F. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED. G. DURING WINTER CONSTRUCTION OR PERIODS OF WET WEATHER, TEMPORARY SLOPE STABILIZATION SHALL BE PROVIDED BY EITHER A ROLLED EROSION CONTROL PRODUCT OR A HEAVY MULCH
- LAYER SUITABLY ANCHORED. THE CONTRACTOR MUST RESEED THE AREA IN THE SPRING WITH THE APPROPRIATE SEEDING. H. DURING DRY WEATHER CONSTRUCTION, ALL SEEDED AREAS ARE TO BE ADEQUATELY WATERED TO
- ENSURE VEGETATED COVER. 2. PERMANENT VEGETATIVE COVER:
- A. GRADE TO FINISHED SLOPES.
- B. SCARIFY COMPACTED SOIL AREAS
- C. TOPSOIL WITH NOT LESS THAN FOUR (4) INCHES OF SUITABLE TOPSOIL MATERIAL. D. LIME AS REQUIRED TO PH 6.5.
- E. FERTILIZE WITH 10-6-4 AT RATE 200 LBS/AC. F. SEED AS FOLLOWS:
- TYPE I FOR USE ON MOWED AREAS (INCLUDING SWALES):
 - KENTUCKY BLUE GRASS CREEPING RED FESCUE RED TOP OR RYE GRASS
- TYPE II FOR USE ON BASIN SIDE SLOPES AND ON NON-MOMED AREAS: USE "ERNMX-ITS" SEED MIX (ERNST CONSERVATION SEEDS, LLP) OR EQUIVALENT. SEEDS INCLUDED IN THE MIX ARE LISTED BELOW. APPLICATION RATE 15 LBS/ACRE.
- GOLDENROD INDIAN GRASS VIRGINIA WILD RYE BIG BLUESTEM LITTLE BLUESTEM FOX SEDGE BLUE INDIGO PARTRIDGE PEA SILKY DOGWOOD
 - OX EYE SUNFLOWER BLACK EYED SUSAN SOFT RUSH RIVERBANK WILDRYE BLUE VERVAIN DEERTONGUE
- G. WILDFLOWER AREAS TO BE MOWED ONCE PER YEAR IN LATE FALL H. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED. I. FOR DISTURBED AREAS WITH SLOPE GREATER THAN IV:3H OR WHEN SLOPES ARE EQUAL TO IV:3H AND THE HEIGHT OF THE SLOPE EXCEEDS 6', INSTEAD OF MULCHING, EROSION CONTROL BLANKET
- SHALL BE USED. J. FOR SEEDING AND PLANTING WITHIN THE MICROPOOL EXTENDED DETENTION POND, REFER TO DRAWING #C-161 (STORMWATER STRUCTURES LANDSCAPING PLAN).
- K. AFTER ESTABLISHMENT OF DENSE, VIGOROUS VEGETATION, PHOSPHORUS BASED FERTILIZERS SHALL NOT BE USED. ONLY NON-PHOSPHORUS BASED FERTILIZER MAY BE APPLIED TO THE LAWNS AND GRASSED AREAS.

EROSION CONTROL LEGEND:

EXISTING DRAINAGE PIPE EXISTING CONTOURS

PROPOSED CONTOURS STABILIZED CONSTRUCTION ENTRANCE

TEMPORARY STAGING AREA



EARTH DIKE


TEMPORARY SOIL STOCKPILE

INLET PROTECTION SILT FENCE

EROSION CONTROL BLANKET


CONSTRUCTION FENCE ORANGE SAFETY FENCE CHECK DAM

LEVEL SPREADER TEMPORARY SWALE





PROPOSED HOUSE




AS NOTED

EROSION and SEDIMENT CONTROL PLAN PHASE 2


8286 RAWING NUMBER

ROJECT NUMBER

SHEET 14 OF 31



EROSION & SEDIMENT CONTROL PLAN - PHASE 2



TEMPORARY SEDIMENT TRAP VOLUMES

- SEDIMENT TRAP #3 CONTRIBUTING AREA - 1.9 AC REQUIRED VOLUME- 3600 CF PER ACRE X 1.9 ACRES = 6840 CF PROVIDED- 6881 CF
- SEDIMENT REMOVAL ELEVATION— 736.68 2. SEDIMENT TRAP #4 CONTRIBUTING AREA - 2.5 AC REQUIRED VOLUME- 3600 CF PER ACRE X 2.5 ACRES = 9000 CF PROVIDED- 9863 CF SEDIMENT REMOVAL ELEVATION- 754.65

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509

UPSHANT TO MEW YORK STATE ERHOLTION LAW	RE	VISIONS	5				PROJECT
URSUANT TO NEW YORK STATE EDUCATION LAW, RTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS	NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION	
A VIOLATION OF THIS LAW FOR ANY PERSON	1	09 NOV 18	REV. PER BI, TE, TP COMMENTS				
NLESS HE IS ACTING UNDER THE DIRECTION OF A ICENSED PROFESSIONAL ENGINEER, TO ALTER AN	2	02 OCT 19	REV. PER TE COMMENTS				
EM IN ANY WAY. IF AN ITEM BEARING THE SEAL							
OF AN ENGINEER IS ALTERED, THE ALTERING IGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND							
THE NOTATION "ALTERED BY" FOLLOWED BY HIS							
IGNATURE AND THE DATE OF SUCH ALTERATION,							
AND A SPECIFIC DESCRIPTION OF THE ALTERATION."							
ALTENATION.							

SWALE #

SEQUENCE OF CONSTRUCTION:

PHASE 2

DISTURBANCE AREA = 4.58 AC.

- 1. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG LIMITS OF
- INSTALL STABILIZED CONSTRUCTION ENTRANCE NEAR STA. 10+00 OF THE CONSTRUCTED ROAD. INSTALL TEMPORARY ACCESS CULVERT FOR FUTURE TEMPORARY SWALE #8 CROSSING THE STABILIZED CONSTRUCTION ENTRANCE. REFER TO DETAIL #1/C-310.
- 3. INSTALL ADDITIONAL SILT FENCE IMMEDIATELY DOWNGRADE OF AREAS OF PROPOSED DISTURBANCE AS SHOWN ON
- 4. CLEAR AND GRUB AREA OF PHASE 2 TO THE LIMITS OF DISTURBANCE SHOWN ON THE PLAN.
- BRING IN ALL EQUIPMENT AND MATERIALS NECESSARY TO PERFORM PHASE 2 OF CONSTRUCTION. ESTABLISH STAGING AREA AS SHOWN ON THE PLAN. CONTRACTOR WILL CONTINUE TO USE YARD AREA AND FUELING AREA ESTABLISHED IN PHASE 1.
- 6. CLEAR AND PREPARE AREA FOR THE PROPOSED CONSTRUCTION. STRIP TOPSOIL AND STORE USABLE ORGANIC MATERIAL AT STOCKPILE. PROVIDE STOCKPILE PROTECTION PER DETAIL #3/C-310.
- 7. STAKE OUT CORNERS OF THE FUTURE HOUSES ON LOTS #2, 3 &11 AS SHOWN ON THE PLAN. EXCAVATE SEDIMENT TRAPS #3 & 4. THE TRAPS SHALL NOT BE LOCATED CLOSER THAN 20 FEET FROM THE STAKED OUT
- 8. EXCAVATE TEMPORARY SWALES #6, 7 & 8.

BUILDING CORNERS.

- 9. STABILIZE ALL DISTURBED AREAS AS DESCRIBED IN "STABILIZATION NOTES" WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STABILIZED.
- 10. CONTRACTOR TO START CUT/FILL OPERATIONS.
- 11. EXCAVATE THE SITE EAST OF THE CONSTRUCTED ROAD. DEPOSIT EXCAVATED SOIL WEST OF THE PROPOSED ROAD. TRUCKS SHALL NOT CROSS THE ROAD. THE SOIL TRANSPORTATION SHALL BE DONE OVER LAND NORTH OF THE CUL-DE-SAC.
- 12. INSTALL WATERMAIN SEGMENTS FROM ROAD TO THE EXISTING WATERMAIN AS OUTLINED IN "WATERMAIN INSTALLATION SEQUENCE OF CONSTRUCTION". PERFORM TESTING AND THEN TIE IN. AS EXCAVATION PROGRESSES, REMOVE ABANDONED SECTION OF WATERMAIN.
- 13. CREATE YARDS AND BUILDING PADS FOR THE FUTURE HOUSE CONSTRUCTION. WHERE FILL IS NEEDED TO CREATE THE PADS IT SHOULD BE FREE FROM ROOTS, VEGETATION AND OVERSIZED STONES. FILL TO BE PLACED IN 12 INCH LIFTS AND COMPACTED TO 95 PERCENT DRY DENSITY BY MECHANICAL MEANS.
- 14. STABILIZE ALL AREAS DISTURBED IN PHASE 2 OF CONSTRUCTION AS DESCRIBED IN "STABILIZATION NOTES" WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE AREAS ARE STÁBILIZED.

ON-SITE POLLUTION CONTROL MEASURES:

- THERE SHALL BE A RECEPTACLE PLACED ON THE SITE TO TEMPORARILY STORE GARBAGE, DEBRIS OR CONSTRUCTION WASTE MATERIAL. THE CONTAINER SHALL NOT BE USED TO TRANSFER ANY GARBAGE FROM ANY OTHER OFF-SITE ACTIVITY.
- 2. THE RECORD OWNER SHALL BE RESPONSIBLE FOR KEEPING THE SITE FREE OF LITTER AT ALL TIMES. DURING CONSTRUCTION ACTIVITIES THE OWNER MAY DESIGNATE A CONTRACTOR IN CHARGE AS A RESPONSIBLE PARTY.
- THE SITE SHALL BE INSPECTED AT THE END OF EACH WORKDAY AND TRASH, DEBRIS AND GARBAGE SHALL BE PICKED UP AND PLACED IN ON-SITE DUMPSTERS OR OTHERWISE REMOVED FROM THE SITE.
- 4. A PORTABLE TOILET FACILITY SHALL BE PROVIDED FOR CONSTRUCTION WORKERS AND AN ADDITIONAL FACILITY FOR EVERY 10 ON-SITE WORKERS.
- . CONSTRUCTION VEHICLES SHALL BE SERVICED OFF-SITE AT A PROPER FACILITY. LEAKING OR ILL REPAIRED VEHICLES SHALL NOT BE LOCATED ON SITE. NO OIL CHANGES ARE PERMITTED ON SITE. FUELING OF VEHICLES ON SITE SHALL BE CAREFULLY PERFORMED WITH AN APPROVED DISPENSER NOZZLE HOSE AND PUMP. SPILLS SHALL PROMPTLY BE REPORTED TO THE NYSDEC AND TOWN. OIL ABSORBENT PADS AND ROLLS SHALL BE USED TO TEMPORARILY CONTAIN ANY SPILLS
- 6. CHEMICAL SOIL ADDITIVES OR HERBICIDES SHALL NOT BE USED ON SITE DURING CONSTRUCTION.

TEMPORARY SWALE DIMENSIONAL CHART

DEPTH

0.75

0.75

1.0

0.75

1.25

1.25

1.25

1.25

BOTTOM WIDTH

1.0

1.0

1.0

1.0

1.0

2.0

1.0

2.0

REFER TO DETAIL #4/C-310

SIDE SLOPE

(FT/FT)

2:1

2:1

2:1

2:1

2:1

2:1

2:1

2:1

LENGTH

(FT)

730

610

360

80

120

230

320

485

SLOPE

11.0

11.8

11.1

2.3

2.1

4.3

8.8

3.5

- 7. THE CONTAINERS SHALL BE OF SUFFICIENT SIZE FOR THE CONSTRUCTION ACTIVITY. CONTAINERS SHALL BE EMPTIED BY AN APPROVED CARTER TO A PROPER FACILITY WHEN FULL. CONTAINERS SHALL BE COVERED TO PREVENT INFILTRATION OF RAIN AND TO PREVENT WIND BORNE DEBRIS REMOVAL.
- . PAINTS, CHEMICALS OR OTHER TOXIC SUBSTANCES SHALL NOT BE PLACED IN TRASH CONTAINERS. PAINTS, CHEMICALS OR TOXIC SUBSTANCES SHALL BE REMOVED FROM SITE BY AN APPROVED LICENSED CARTER.
- 9. THERE SHALL BE NO OPEN FIRES OR BARREL FIRES PERMITTED.
- 10. DEBRIS OR TRASH PILES ARE NOT PERMITTED. DEBRIS SHALL BE PLACED IN CONTAINERS. TEMPORARY PILES OF BRUSH OR STUMPS SHALL BE PROTECTED BY SILT FENCE SIMILAR TO TOPSOIL STOCKPILES.

<u>VEHICLE & EQUIPMENT FUELING and WET NOZZLE REPORT:</u>

DESCRIPTION AND PURPOSE

VEHICLE EQUIPMENT FUELING PROCEDURES AND PRACTICES ARE DESIGNED TO PREVENT FUEL SPILLS AND LEAKS, AND REDUCE OR ELIMINATE CONTAMINATION OF STORMWATER. THIS CAN BE ACCOMPLISHED BY FUELING IN DESIGNATED AREAS ONLY, IMPLEMENTING SPILL CONTROLS, AND TRAINING EMPLOYEES AND SUBCONTRACTORS IN PROPER FUELING

SUITABLE APPLICATIONS

THESE PROCEDURES ARE SUITABLE ON ALL CONSTRUCTION SITES WHERE VEHICLE AND EQUIPMENT FUELING TAKES

LIMITATIONS

ONSITE VEHICLE AND EQUIPMENT FUELING SHOULD ONLY BE USED WHERE IT IS IMPRACTICAL TO SEND VEHICLES AND EQUIPMENT OFFSITE FOR FUELING.

IMPLEMENTATION

- TOPPING-OFF" OF FUEL TANKS.
- T ABSORBENT SPILL CLEANUP MATERIALS AND SPILL KITS SHALL BE AVAILABLE IN FUELING AREAS AND ON FUELING TRUCKS, AND SHOULD BE DISPOSED OF PROPERLY AFTER USE.
- T DRIP PANS OR ABSORBENT PADS SHOULD BE USED DURING VEHICLE AND EQUIPMENT FUELING, UNLESS THE FUELING IS PERFORMED OVER AN IMPERMEABLE SURFACE IN A DEDICATED FUELING AREA.
- Y USE ABSORBENT MATERIALS ON SMALL SPILLS. DO NOT HOSE DOWN OR BURY THE SPILL. REMOVE THE ADSORBENT MATERIALS PROMPTLY AND DISPOSE OF PROPERLY.
- Y AVOID MOBILE FUELING OF MOBILE CONSTRUCTION EQUIPMENT AROUND THE SITE: RATHER, TRANSPORT THE EQUIPMENT TO DESIGNATED FUELING AREAS. WITH THE EXCEPTION OF TRACKED EQUIPMENT SUCH AS BULLDOZERS AND LARGE EXCAVATORS, MOST VEHICLES SHOULD BE ABLE TO TRAVEL TO A DESIGNATED AREA WITH LITTLE LOST TIME.
- ₹ EMPLOYEES AND SUBCONTRACTORS SHALL BE TRAINED IN PROPER FUELING AND CLEANUP PROCEDURES.
- Y WHEN FUELING MUST TAKE PLACE OUTSIDE, DESIGNATE AN AREA AWAY FROM DRAINAGE COURSES TO BE
- P DEDICATED FUELING AREAS SHOULD BE PROTECTED FROM STORMWATER RUNON AND RUNOFF, AND SHOULD BE LOCATED AT LEAST 50 FEET AWAY FROM DOWNSTREAM DRAINAGE FACILITIES AND WATERCOURSES. FUELING MUST BE PERFORMED ON LEVEL-GRADE AREAS.
- PROTECT FUELING AREAS WITH BERMS AND DIKES TO PREVENT RUNON, RUNOFF, AND TO CONTAIN SPILLS.
- Y NOZZLE USED IN VEHICLE AND EQUIPMENT FUELING SHOULD BE EQUIPPED WITH AN AUTOMATIC SHUTOFF TO CONTROL DRIPS. FUELING OPERATIONS SHOULD NOT BE LEFT UNATTENDED.
- FEDERAL, STATE AND LOCAL REQUIREMENTS SHOULD BE OBSERVED FOR ANY STATIONARY ABOVE GROUND STORAGE TANKS.

INSPECTION AND MAINTENANCE

- Y VEHICLES AND EQUIPMENT SHOULD BE INSPECTED EACH DAY OF USE FOR LEAKS. LEAKS SHOULD BE REPAIRED IMMEDIATELY OR PROBLEM VEHICLES OR EQUIPMENT SHOULD BE REMOVED FROM THE PROJECT
- Y KEEP AMPLE SUPPLIES OF SPILL CLEANUP MATERIALS ON-SITE.
- ▼ IMMEDIATELY CLEAN UP SPILLS AND PROPERLY DISPOSE OF CONTAMINATED SOIL AND CLEANUP MATERIALS.

- 1. THE SITE SHALL BE DISTURBED ONLY WHERE NECESSARY. ONLY THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED (NO MORE THAN 5 ACRES) AT ANY ONE TIME DURING DEVELOPMENT. WHEN LAND IS EXPOSED, THE EXPOSURE SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME BY IMMEDIATE STABILIZATION PER THE STABILIZATION NOTES, UNLESS SPECIFIED OTHERWISE. ALL DISTURBED AREAS ARE CONSIDERED "STABILIZED" WHEN 80% OF UNIFORM, PERENNIAL VEGETATIVE COVER IS ACHIEVED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS MULCHES, EROSION CONTROL BLANKET, ETC.) HAVE BEEN PROPERLY EMPLOYED. NO WORK SHALL CONTINUE BEFORE PRIOR DISTURBANCE IS STABILIZED.
- 2. WHEREVER FEASIBLE, NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED.
- 3. AREAS UNDERGOING EARTHWORK, WHERE SOIL IS TO BE LEFT EXPOSED FOR MORE THAN FIFTEEN DAYS, SHALL BE STABILIZED WITH EITHER TEMPORARY OR PERMANENT VEGETATIVE COVER. TEMPORARY COVER SHALL BE USED WHEN THE PROJECT SCHEDULE DOES NOT COINCIDE WITH THE OPTIMUM PLANTING SEASON. IN GENERAL, OPTIMUM PLANTING TIMES FOR GRASSES ARE MARCH 15TH TO MAY 31ST AND SEPTEMBER 1ST TO NOVEMBER 15TH. DURING OPTIMUM PLANTING TIMES PERMANENT VEGETATIVE COVER WILL BE INSTALLED. SEE SPECIFICATIONS FOR FURTHER
- 4. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL ARRANGE A PRE-CONSTRUCTION MEETING INVITING ALL INVOLVED REVIEW AGENCIES AND ENGINEERS OF RECORD PRIOR TO START OF CONSTRUCTION
- 5. TEMPORARY MEASURES SHALL BE MAINTAINED BY PROJECT OWNER / DEVELOPER OR A DESIGNATED REPRESENTATIVE (SUCH AS THE GENERAL CONTRACTOR) DURING THE ENTIRE CONSTRUCTION PERIOD AND UNTIL RESPONSIBILITIES ARE TRANSFERRED TO THE HOMEOWNERS ASSOCIATION (HOA). THE HOA WILL THEN TAKE CHARGE OF ALL MAINTENANCE ACTIVITIES OF THE PERMANENT STORMWATER MANAGEMENT/TREATMENT COMPONENTS AND

DEVELOPER/OWNER: ANGELO MASTRANTONI 23 FRANCES DRIVE KATONAH, NY 10536 CONTACT: PAUL MASTRANTONI (914) 755-0445

- 6. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL RETAIN THE SERVICE OF QUALIFIED PERSONNEL (LICENSED PROFESSIONAL ENGINEER, CERTIFIED PROFESSIONAL IN EROSION & SEDIMENT CONTROL-CPESC OR SOIL SCIENTIST) TO PERFORM SITE INSPECTIONS DURING THE CONSTRUCTION PERIOD AND FINAL SITE INSPECTION AT PROJECT COMPLETION.
- 7. THE CONTRACTOR SHALL MAKE AVAILABLE ON SITE, ALL EQUIPMENT, MATERIALS AND LABOR NECESSARY TO EFFECT EMERGENCY REPAIR AND REPLACEMENT OF THE EROSION CONTROL MEASURES.
- 8. SITE INSPECTIONS DURING CONSTRUCTION PERIOD SHALL BE PERFORMED AT LEAST EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. DURING WINTER, IF THE SOIL DISTURBANCE IS COMPLETELY SUSPENDED AND THE SITE IS PROPERLY STABILIZED, INSPECTION FREQUENCY MAY REDUCE, BUT SHALL MAINTAIN A MINIMUM OF MONTHLY INSPECTIONS IN ALL SITUATIONS (EVEN WHEN THERE IS TOTAL WINTER SHUTDOWN). DURING PERIODS OF REDUCED INSPECTION FREQUENCY, INSPECTIONS MUST STILL BE DONE AFTER EVERY STORM EVENT OF 0.5 INCHES OR GREATER. TO BE ALLOWED TO REDUCE INSPECTION FREQUENCIES, THE OPERATOR MUST COMPLETE STABILIZATION ACTIVITIES (PERIMETER CONTROLS, TRAPS, BARRIERS, ETC.) BEFORE PROPER INSTALLATION IS PRECLUDED BY SNOW COVER OR FROZEN GROUND. IF VEGETATION IS DESIRED, SEEDING, PLANTING, AND/OR SODDING MUST BE SCHEDULED TO AVOID DIE-OFF FROM FALL FROSTS AND ALLOW FOR PROPER GERMINATION/ESTABLISHMENT.
- 9. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED AREAS PERIODICALLY WITH
- 10. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL KEEP INSPECTION REPORTS AND LOGS AT THE SITE. A SUMMARY OF INSPECTION ACTIVITIES SHALL BE POSTED AT A PUBLICLY ACCESSIBLE AREA OF THE SITE ON A MONTHLY BASIS.
- 11. PRIOR TO START OF CONSTRUCTION ACTIVITIES, THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL CERTIFY ON THE INSPECTION LOG THAT A SWPPP WAS PROPERLY PREPARED FOR THE PROJECT AND CONFORMS TO ALL FEDERAL, STATE AND LOCAL EROSION & SEDIMENT CONTROL REQUIREMENTS.
- 12. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL PROVIDE A PHONE NUMBER TO THE DIRECTOR OF CODE ENFORCEMENT FOR USE IN EMERGENCY SITUATIONS.
- 13. THE OWNER/DEVELOPER SHALL MAINTAIN THE CONSTRUCTION SITE FREE OF DEBRIS, LITTER AND CONSTRUCTION CHEMICALS. A DUMPSTER SHALL BE LOCATED ON THE SITE AND PICK UP ARRANGED WHEN IT IS FULL.

EROSION CONTROL LEGEND:

-----(416)-----

EXISTING DRAINAGE PIPE

EXISTING CONTOURS

PROPOSED CONTOURS

TEMPORARY STAGING AREA

TEMPORARY SOIL STOCKPILE

EROSION CONTROL BLANKET

CONSTRUCTION FENCE

ORANGE SAFETY FENCE

INLET PROTECTION

SILT FENCE

CHECK DAM

LEVEL SPREADER

TEMPORARY SWALE

LIMITS OF DISTURBANCE

EARTH DIKE

STABILIZED CONSTRUCTION ENTRANCE

STABILIZATION NOTES:

- 1. TEMPORARY VEGETATIVE COVER:
- A. SCARIFY COMPACTED SOIL AREAS.
- B. LIME AS REQUIRED TO PH 6.5.
- C. FERTILIZE WITH 10-10-10 AT RATE 200 LBS/AC. INCORPORATE AMENDMENTS INTO SOIL WITH DISC HARROW. E. SEED AS FOLLOWS:
- SPRING/SUMMER/EARLY FALL PLANTING: ANNUAL RYEGRASS AND CEREAL OATS @ 30 LBS./AC.
- LATE FALL/EARLY WINTER PLANTING: AROOSTOOK WINTER RYE @ 100 LBS./AC. F. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED.
- G. DURING WINTER CONSTRUCTION OR PERIODS OF WET WEATHER, TEMPORARY SLOPE STABILIZATION SHALL BE PROVIDED BY EITHER A ROLLED EROSION CONTROL PRODUCT OR A HEAVY MULCH LAYER SUITABLY ANCHORED. THE CONTRACTOR MUST RESEED THE AREA IN THE SPRING WITH THE APPROPRIATE SEEDING.
- H. DURING DRY WEATHER CONSTRUCTION, ALL SEEDED AREAS ARE TO BE ADEQUATELY WATERED TO ENSURE VEGETATED COVER.
- 2. PERMANENT VEGETATIVE COVER:
- A. GRADE TO FINISHED SLOPES.
- B. SCARIFY COMPACTED SOIL AREAS
- C. TOPSOIL WITH NOT LESS THAN FOUR (4) INCHES OF SUITABLE TOPSOIL MATERIAL. D. LIME AS REQUIRED TO PH 6.5.
- E. FERTILIZE WITH 10-6-4 AT RATE 200 LBS/AC. F. SEED AS FOLLOWS:
- TYPE I FOR USE ON MOWED AREAS (INCLUDING SWALES):

KENTUCKY BLUE GRASS CREEPING RED FESCUE RED TOP OR RYE GRASS

TYPE II FOR USE ON BASIN SIDE SLOPES AND ON NON-MOWED AREAS: USE "ERNMX-178" SEED MIX (ERNST CONSERVATION SEEDS, LLP) OR EQUIVALENT. SEEDS INCLUDED IN THE MIX ARE LISTED BELOW. APPLICATION RATE 15 LBS/ACRE.

GOI DENROD BIG BLUESTEM LITTLE BLUESTEM BLUE INDIGO SILKY DOGWOOD

INDIAN GRASS VIRGINIA WILD RYE FOX SFDGF PARTRIDGE PEA

BLACK EYED SUSAN BLUE VERVAIN DEERTONGUE

- G. WILDFLOWER AREAS TO BE MOWED ONCE PER YEAR IN LATE FALL.
- H. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED. I. FOR DISTURBED AREAS WITH SLOPE GREATER THAN 1V: 3H OR WHEN SLOPES ARE EQUAL TO 1V: 3H AND THE HEIGHT OF THE SLOPE EXCEEDS 6', INSTEAD OF MULCHING, EROSION CONTROL BLANKET
- SHALL BE USED. J. FOR SEEDING AND PLANTING WITHIN THE MICROPOOL EXTENDED DETENTION POND, REFER TO DRAWING #C-161 (STORMWATER STRUCTURES LANDSCAPING PLAN).
- K. AFTER ESTABLISHMENT OF DENSE, VIGOROUS VEGETATION, PHOSPHORUS BASED FERTILIZERS SHALL NOT BE USED. ONLY NON-PHOSPHORUS BASED FERTILIZER MAY BE APPLIED TO THE LAWNS AND GRASSED AREAS.

XXX

PROPOSED HOUSE

NGINEERS - ARCHITECTS


(845) 279–6789 FAX (845) 279–6769

• PUTNAM ENGINEERING PLLC 2018

OLD FORGE ESTATES

PROPOSED SUBDIVISION PLAN PREPARED FOR:

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



OX EYE SUNFLOWER


SOFT RUSH

RIVERBANK WILDRYE


12 APR 18 PROJECT MANAGER PMLCHECKED BY PMLSCALE

AS NOTED

PROJECT NUMBER 8286 **EROSION and SEDIMENT** DRAWING NUMBER CONTROL PLAN PHASE 2 SHEET ___15__ OF __34_



EROSION & SEDIMENT CONTROL PLAN - PHASE 4



EROSION CONTROL LEGEND:

EXISTING DRAINAGE PIPE EXISTING CONTOURS

PROPOSED CONTOURS



-----(4|6)-----

STABILIZED CONSTRUCTION ENTRANCE



TEMPORARY STAGING AREA

LIMITS OF DISTURBANCE



TEMPORARY SOIL STOCKPILE



INLET PROTECTION

SILT FENCE


EARTH DIKE




EROSION CONTROL BLANKET

CONSTRUCTION FENCE

ORANGE SAFETY FENCE



CHECK DAM LEVEL SPREADER



PROPOSED HOUSE

TEMPORARY SWALE

TEMPORARY SWALE DIMENSIONAL CHART REFER TO DETAIL #4/C-3IO						
SMALE #	BOTTOM WIDTH (FT)	DEPTH (FT)	SIDE SLOPE (FT/FT)	LENGTH (FT)	SLOPE (%)	
I	1.0	0.15	2:1	130	11.0	
2	1.0	0.75	2:1	610	11.8	
B	1.0	1.0	2:1	360	11.1	
4	1.0	0.75	2:1	80	2.3	
5	1.0	1.25	2:1	120	2.l	
6	2.0	1.25	2:1	230	4.3	
7	1.0	1.25	2:1	320	8.8	
8	2.0	1.25	2:1	485	3.5	
9	1.0	1.0	2:1	520	11.5	

LEVEL SPREADER DIMENSIONS							
	REFER '	TO DETAIL \$	18/८-3 10 €				
LEVEL SPREADER #	Q p (CFS)	DEPTH (INCH)	WIDTH (FT)	LENGTH (FT)			
1	0.37	6	w	0			
2	2.18	6	з	20			
3	5.81	6	3	30			

SEQUENCE OF CONSTRUCTION:

PHASE 4A

DISTURBANCE AREA = 1.67 AC.

- ACTIVITIES DESCRIBED BELOW MAY BE PERFORMED CONCURRENTLY WITH PHASE 3 OF CONSTRUCTION.
- CONTRACTOR TO MAINTAIN PREVIOUSLY ESTABLISHED EROSION CONTROL MEASURES ALONG WITH ALL SILT FENCES INSTALLED. REPAIR IF NECESSARY.
- ?. RELOCATE STABILIZED CONSTRUCTION ENTRANCE TO LOCATION NEAR ROAD STA. 6+50, AS SHOWN ON THE PLAN. VEHICLES SHALL BE INSPECTED AND CLEANED, IF REQUIRED, PRIOR TO ENTERING PAVED ROAD.
- 3. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG LIMITS OF DISTURBANCE.
- 4. INSTALL ADDITIONAL SILT FENCES IMMEDIATELY DOWNGRADE OF AREAS OF PROPOSED DISTURBANCE AS SHOWN ON THE PLAN. SILT FENCE TO BE INSTALLED PARALLEL TO CONTOURS.
- 5. ABANDON EARTH DIKE INSTALLED DURING PHASE #I OF CONSTRUCTION. RESTORE GRADING.
- 6. ABANDON TEMPORARY SMALE #7. RESTORE GRADING AND RELOCATE STAGING AREA TO THIS LOCATION. BRING IN ALL EQUIPMENT AND MATERIALS NECESSARY TO PERFORM PHASE 4 OF CONSTRUCTION.
- 7. CLEAR AND GRUB AREA OF PHASE 4 TO THE LIMITS OF DISTURBANCE SHOWN ON THE PLAN.
- 6. EXCAVATE LEVEL SPREADER #3 AT THE END OF TEMPORARY SMALE #6. SEDIMENT TRAP #3 WILL BE
- 1. INSTALL DMH9 AND REMAINING PORTION OF PIPE FSI-DMH9. INSTALL HEAD WALL HW#I AND PIPE HWI-DMH9. PIPES SHALL NOT RECEIVE ANY WATER UNTIL ALL CONTRIBUTING AREAS ARE STABILIZED.
- 10. CONTRACTOR TO START CUT/FILL OPERATIONS.
- . CREATE YARDS AND BUILDING PADS FOR THE FUTURE HOUSES CONSTRUCTION. WHERE FILL IS NEEDED TO CREATE THE PADS IT SHOULD BE FREE FROM ROOTS, VEGETATION AND OVERSIZED STONES. FILL TO BE PLACED IN 12 INCH LIFTS AND COMPACTED TO 95 PERCENT DRY DENSITY BY MECHANICAL MEANS.
- 12. ROUGH GRADE PORTION OF ACCESS DRIVE TO SEPTIC FIELDS ALONG WITH PERMANENT SMALE #2 AS SHOWN ON THE PLAN.
- IS. STABILIZE ALL AREAS DISTURBED IN PHASE 4 OF CONSTRUCTION AS DESCRIBED IN "STABILIZATION NOTES" WITHIN ONE (1) WEEK FOLLOWING THE EARTHWORK. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE THESE

PHASE 4B

DISTURBANCE AREA = XX AC.

MAINTENANCE PROGRAM:

TEMPORARY MEASURES:

- A. <u>SILT FENCE:</u> SEDIMENTS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN IT BECOMES 0.5 FEET DEEP AT THE FENCE. IT SHOULD ALSO BE INSPECTED WEEKLY AND PRIOR TO AND WITHIN 24 HOURS AFTER ALL FORECASTED STORM EVENTS. REPAIR SHALL BE PERFORMED AS NEEDED.
- B. <u>SWALES:</u> PROPOSED SWALES ARE USED AS DIVERSION SWALES DURING THE CONSTRUCTION PHASE. THESE SWALES ARE TO BE INSPECTED WEEKLY AND PRIOR TO AND WITHIN 24 HOURS. AFTER ALL FORECASTED STORM EVENTS FOR SCOUR AND EROSION. REMOVE DEPOSITS OR SEDIMENT OR OTHER OBSTRUCTIONS.
- CONSTRUCTION ENTRANCE: CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. VISUAL INSPECTION SHALL BE PERFORMED DAILY THROUGHOUT THE PROJECT CONSTRUCTION, TOP DRESSING WITH ADDITIONAL STONE OR ADDITIONAL LENGTH AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, MASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-MAY MUST BE REMOVED IMMEDIATELY.
- D. <u>SEDIMENT BASIN:</u> VISUAL INSPECTION OF THE BASIN EMBANKMENT AND DEWATERING SPILLWAY SHALL BE PERFORMED WEEKLY, PRIOR TO AND WITHIN 24 HOURS AFTER ALL FORECASTED STORMS. REPAIRS SHALL BE MADE AS NEEDED. SEDIMENT SHOULD BE REMOVED EVERY SIX (6) MONTHS OR WHEN SEDIMENT ACCUMULATION REACHES THE DESIGN CLEANOUT LEVEL, IN ORDER TO PRESERVE THE AVAILABLE STORMMATER MANAGEMENT CAPACITY OF THE SEDIMENT BASIN. THE LEVEL OF SEDIMENT AT WHICH CLEANOUT IS REQUIRED SHALL BE MARKED ON A FIXED REFERENCE POINT (SEDIMENT REMOVAL MARKER OR MARK ON A RISER TYPE OUTLET).
- E. <u>CURB INLET PROTECTION:</u> INLET PROTECTION SHALL BE INSPECTED WEEKLY AND PRIOR TO AND WITHIN 24 HOURS AFTER ALL FORECASTED STORM EVENTS. SEDIMENTS AND DEBRIS SHALL BE REMOVED FROM BEHIND THE FENCE IF PRESENT. REPAIR SHALL BE PERFORMED AS NEEDED.
- F. <u>LEVEL SPREADER:</u> LEVEL SPREADER SHALL BE INSPECTED WEEKLY AND AFTER STORM EVENTS FOR CLOGGING, DENSITY OF VEGETATION, DAMAGES AND CHANNELIZATION. SEDIMENT AND DEBRIS SHALL BE REMOVED WHEN BUILDUP OCCURS. REGRADE AND RESEED WHEN NECESSARY.

PERMANENT MEASURES

۸ -	NTENANCE ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
	MBANKMENT AND EMERGENCY SPILLWAY		
•	ANNUAL, PRIOR TO AND WITHIN 24 HOURS AFTER ALL FORECASTER MAJOR STORMS)		
	, VEGETATION AND GROUND COVER ADEQUATE		
	2. EMBANKMENT EROSION		
_	3. ANIMAL BURROWS		
	4. UNAUTHORIZED PLANTING		
5	5. CRACKING, BULGING, OR SLIDING OF DAM		
	A) UPSTREAM FACE B) DOWNSTREAM FACE		
	C) AT OR BEYOND TOE		
	DOWNSTREAM		
	UPSTREAM		
	D) EMERGENCY SPILLWAY		
6	5. POND, TOE & CHIMNEY DRAINS CLEAR AND FUNCTIONING		
	J. SEEPS/LEAKS ON DOWNSTREAM FACE		
	B. SLOPE PROTECTION OR RIPRAP FAILURE		
	1. VERTIGAL/HORIZONTAL ALIGNMENT OF TOP OF DAM "AS-BUILT" O. EMERGENCY SPILLWAY CLEAR OF OBSTRUCTIONS AND DEBRIS		
	I. OTHER (SPECIFY)		
	Name the month and the desired		
	RISER AND PRINCIPAL SPILLMAY (ANNUAL) PE: REINFORCED CONCRETE		
111	CORRUGATED PIPE		
	MASONRY		
١.	. LOW FLOW ORIFICE OBSTRUCTED		
2	2. LOM FLOM TRASH RACK		
	A) DEBRIS REMOVAL NECESSARY		
-	B) CORROSION CONTROL		
3	B. WEIR TRASH RACK MAINTENANCE		
	B) CORROSION CONTROL		
4	4. EXCESSIVE SEDIMENT ACCUMULATION INSIDER RISER		
	5. CONCRETE/MASONRY CONDITION RISER AND BARRELS		
	A) CRACKS OR DISPLACEMENT		
	B) MINOR SPALLING (<1")		
	C) MAJOR SPALLING (REBARS EXPOSED)		
	D) JOINT FAILURES		
	E) WATER TIGHTNESS		
	6. METAL PIPE CONDITION		
7	CONTROL VALVE		
	A) OPERATIONAL/EXERCISED		
2	B) CHAINED AND LOOKED B. POND DRAIN VALVE		
J	A) OPERATIONAL/EXERCISED		
	B) CHAINED AND LOCKED		
9	1. OUTFALL CHANNELS FUNCTIONING		
lo	O. OTHER (SPECIFY)		
, P	PERMANENT POOL (MET PONDS) (MONTHLY)		
	. UNDESIRABLE VEGETATION GROWTH		
2	2. FLOATING OR FLOATABLE DEBRIS REMOVAL REQUIRED		
	3. VISIBLE POLLUTION		
	4. SHORELINE PROBLEM		
	SEDIMENT FOREBAYS		
	. SEDIMENTATION NOTED		
	2. SEDIMENT CLEANOUT WHEN DEPTH >20% DESIGN DEPTH		
E. D	PRY POND AREAS		
	VEGETATION ADEQUATE		
2	2. UNDESIRABLE VEGETATIVE GROWTH		
3	2. UNDESTRABLE VEGETATIVE GROWTH B. UNDESTRABLE MOODY VEGETATION FILOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS		
2 3 4	3. UNDESIRABLE WOODY VEGETATION		
2 3 4 5	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION		
2 3 4 5 6	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY)		
2 3 4 5 6 7 F. C	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS)		
2 3 4 5 6 7 F. C	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES		
2 3 4 5 6 7 F. C l.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION		
2 3 4 5 6 7 F. I. 2 3	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES		
2 3 4 5 6 7 F. C I. 2 3 4	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS		
22 3 4 5 6 7 7 7 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES		
22 3 4 5 6 7 7 1. C 2 3 4 5 5 . C	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 6. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 6. RIPRAP FAILURES 6. SLOPE EROSION 6. STORM DRAIN PIPES 6. OTHER (SPECIFY) 6. OTHER (MONTHLY) 6. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA		
2 3 4 5 6 7 7 1. 2 3 4 5 6 2 3 4 5 6 1 1 2 2 3 4 5 1 1 2 3 1 2 3 1 3 1 2 3 1 2 3 1 3 1 2 3 3 3 3	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS		
23 4 5 6 7 1. 2 3 4 5 5. 0 1. 2	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS		
23 4 5 6 7 1. 2 3 4 5 5. 0 1. 2	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS A) GRASS GROWING REQUIRED		
23 4 5 6 7 1. 2 3 4 5 5. 0 1. 2	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 11. OTHER (SPECIFY) 12. CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 13. STORM PRAIN PIPES 14. ENDWALLS/HEADWALLS 15. OTHER (SPECIFY) 16. OTHER (MONTHLY) 17. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 18. AESTHETICS 19. A) GRASS GROWING REQUIRED 19. B) GRAFFITI REMOVAL NEEDED		
23 44 5 6 7 C 1. 23 4 5 C 1. 23 5 C	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 11. OTHER (SPECIFY) 12. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 13. STORM PRAIN PIPES 14. ENDWALLS/HEADWALLS 15. OTHER (SPECIFY) 16. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 16. COMPLAINTS FROM RESIDENTS 16. ACESTHETICS 16. A) GRASS GROWING REQUIRED 16. B) GRAFFITI REMOVAL NEEDED 16. OTHER (SPECIFY)	1	
23 44 5 6 7 7 8 9 1.0 2 3 4 5 6 7 9 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 6. RIPRAP FAILURES 6. STORM DRAIN PIPES 6. ENDWALLS/HEADWALLS 6. OTHER (SPECIFY) DITHER (MONTHLY) 6. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 6. COMPLAINTS FROM RESIDENTS 6. A SESTHETICS 6. A) GRASS GROWING REQUIRED 6. B) GRAFFITI REMOVAL NEEDED 6. OTHER (SPECIFY) 6. CONDITIONS OF MAINTENANCE ACCESS ROUTES		
23 44 55 66 7 F. C. I. 23 44 55 65 1. 23 3	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 11. OTHER (SPECIFY) 12. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 13. STORM PRAIN PIPES 14. ENDWALLS/HEADWALLS 15. OTHER (SPECIFY) 16. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 16. COMPLAINTS FROM RESIDENTS 16. ACESTHETICS 16. A) GRASS GROWING REQUIRED 16. B) GRAFFITI REMOVAL NEEDED 16. OTHER (SPECIFY)	1	
23 44 55 66 7 C 1. 22 33 44 55 66 65 66 66 66 66 66 66 66 66 66 66	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DITHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4. GRASS GROWING REQUIRED 5. GRASS GROWING REQUIRED 6. OTHER (SPECIFY) 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP	1	
23 44 5 6 7 C 1. 23 4 5 6 9 . C 1. 23 4 6 9 . C 1.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DITHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4. GRASS GROWING REQUIRED B) GRAFFITI REMOVAL NEEDED C) OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 5. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING	1	
23 44 5 6 7 C 1. 23 4 5 6 9 . C 1. 23 4 6 9 . C 1.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 7. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 7. RIPRAP FAILURES 7. SLOPE EROSION 7. STORM DRAIN PIPES 7. ENDWALLS/HEADWALLS 7. OTHER (SPECIFY) 7. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 8. GRAFFITI REMOVAL NEEDED 7. OTHER (SPECIFY) 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 7. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF	1	
23 44 5 6 7 C 1. 23 4 5 6 9 . C 1. 23 4 6 9 . C 1.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 6. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 6. RIPRAP FAILURES 6. STORM DRAIN PIPES 6. OTHER (SPECIFY) 6. OTHER (SPECIFY) 6. OTHER (MONTHLY) 6. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 6. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 7. B) GRAFFITI REMOVAL NEEDED 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 6. ANY PUBLIC HAZARDS (SPECIFY) 6. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF 7. WETLAND PLANTS AFTER THE SECOND GROWING SEASON.	1	
F. C. 1. 23 4 5 6 1 4 5 6 H. N. I.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 6. SEDIMENT AND/OR TRASH ACCUMULATION 6. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 6. RIPRAP FAILURES 6. SLOPE EROSION 7. STORM DRAIN PIPES 7. ENDWALLS/HEADWALLS 7. OTHER (SPECIFY) 7. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 7. B) GRAFFITI REMOVAL NEEDED 7. OTHER (SPECIFY) 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 7. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF 7. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. 7. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED)	1	
F. Cl. 23 4 5 6 H. N. I.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 7. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 7. RIPRAP FAILURES 7. SLOPE EROSION 7. STORM DRAIN PIPES 7. ENDWALLS/HEADWALLS 7. OTHER (SPECIFY) 7. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 7. B) GRAFFITI REMOVAL NEEDED 7. OTHER (SPECIFY) 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 7. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF 7. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. 7. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 7. DOMINANT WETLAND PLANTS:	1	
F. Cl. 23 4 5 6 H. W. I.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DITHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4. A) GRASS GROWING REQUIRED 5. GRAFFITI REMOVAL NEEDED 6. OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 6. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING 1. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF 1. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. 1. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: 5. SURVIVAL OF DESIRED WETLAND PLANT SPECIES	1	
F. C. 1. 23 4 5 6 H. W. I. 2	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 7. OTHER (SPECIFY) 6. ONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 7. RIPRAP FAILURES 7. SLOPE EROSION 7. STORM DRAIN PIPES 7. ENDWALLS/HEADWALLS 7. OTHER (SPECIFY) 7. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 7. B) GRAFFITI REMOVAL NEEDED 7. OTHER (SPECIFY) 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 7. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF 7. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. 7. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 7. DOMINANT WETLAND PLANTS:	1	
F. I. 23 4 5 6 H. W. I. 24 5 6 H. W. I. 25 6 H	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4. A) GRASS GROWING REQUIRED 5. B) GRAFFITI REMOVAL NEEDED 6. OTHER (SPECIFY) 6. CONDITIONS OF MAINTENANCE ACCESS ROUTES 6. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING 1. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: SURVIVAL OF DESIRED WETLAND PLANT SPECIES DISTRIBUTION ACCORDING TO LANDSCAPING PLAN?	1	
F. I. 23 4 5 6 H. W. I. 24 5 6 H. W. I. 25 6 H	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DITHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4. A) GRASS GROWING REQUIRED B) GRAFFITI REMOVAL NEEDED C) OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 5. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING WETLAND PLANTS AFTER THE SECOND GROWING SEASON. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: SURVIVAL OF DESIRED WETLAND PLANT SPECIES DISTRIBUTION ACCORDING TO LANDSCAPING PLAN? 3. EVIDENCE OF INVASIVE SPECIES	1	
23 4 5 6 T C I. 23 4 5 6 W I. 23 4 5 6 W II. 23 4 5 6 W II. 23 4 5 6 W II. 24 5 4 5 6 W II. 25 6 W II. 25 6 W II. 25 6 W III.	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 7. RIPRAP FAILURES 7. SLOPE EROSION 7. STORM DRAIN PIPES 7. ENDWALLS/HEADWALLS 7. OTHER (MONTHLY) 7. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 7. COMPLAINTS FROM RESIDENTS 7. AESTHETICS 7. A) GRASS GROWING REQUIRED 7. B) GRAFFITI REMOVAL NEEDED 7. CONDITIONS OF MAINTENANCE ACCESS ROUTES 7. SIGNS OF HYDROCARBON BUILD-UP 7. ANY PUBLIC HAZARDS (SPECIFY) 7. WETLAND VEGETATION (ANNUAL) 7. VEGETATION HEALTHY AND GROWING 7. WETLAND PLANTS AFTER THE SECOND GROWING SEASON. 7. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 7. DOMINANT WETLAND PLANTS: 7. SURVIVAL OF DESIRED WETLAND PLANT SPECIES 7. DISTRIBUTION ACCORDING TO LANDSCAPING PLAN? 7. MAINTENANCE OF ADEQUATE WATER DEPTHS FOR DESIRED	1	
F. I. 23 45 6 WI. I. 2 34 5 H. II. 2	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4.) GRASS GROWING REQUIRED B) GRAFFITI REMOVAL NEEDED C) OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 6. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF WETLAND PLANTS AFTER THE SECOND GROWING SEASON. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: SURVIVAL OF DESIRED WETLAND PLANT SPECIES DISTRIBUTION ACCORDING TO LANDSCAPING PLAN? 3. EVIDENCE OF INVASIVE SPECIES 6. HANYESTING OF EMERGENT PLANTINGS NEEDED WETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES	1	
F. I. 23 4 5 6 W. I. 2 3 4 5 6 H. II. 2 3 4 5 6	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS A) GRASS GROWING REQUIRED B) GRAFFITI REMOVAL NEEDED C) OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 6. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF WETLAND PLANTS AFTER THE SECOND GROWING SEASON. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: SURVIVAL OF DESIRED WETLAND PLANT SPECIES DISTRIBUTION ACCORDING TO LANDSCAPING PLAN? 3. EVIDENCE OF INVASIVE SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DWETLAND PLANT SPECIES DWE	1	
F. 1. 23 4 5 6 7 6 7 6 7 6 7 7 8 7 8 7 8 7 8 7 8 7 8	3. UNDESIRABLE WOODY VEGETATION 4. LOW FLOW CHANNELS CLEAR OF OBSTRUCTIONS 5. STANDING WATER OR WET SPOTS 6. SEDIMENT AND/OR TRASH ACCUMULATION 1. OTHER (SPECIFY) CONDITION OF OUTFALLS (ANNUAL, AFTER MAJOR STORMS) 1. RIPRAP FAILURES 2. SLOPE EROSION 3. STORM DRAIN PIPES 4. ENDWALLS/HEADWALLS 5. OTHER (SPECIFY) DTHER (MONTHLY) 1. ENCROACHMENT ON POND, WETLAND OR EASEMENT AREA 2. COMPLAINTS FROM RESIDENTS 3. AESTHETICS 4.) GRASS GROWING REQUIRED B) GRAFFITI REMOVAL NEEDED C) OTHER (SPECIFY) 4. CONDITIONS OF MAINTENANCE ACCESS ROUTES 6. SIGNS OF HYDROCARBON BUILD-UP 6. ANY PUBLIC HAZARDS (SPECIFY) WETLAND VEGETATION (ANNUAL) 1. VEGETATION HEALTHY AND GROWING WETLAND MAINTAINING 50% SURFACE AREA COVERAGE OF WETLAND PLANTS AFTER THE SECOND GROWING SEASON. (IF UNSATISFACTORY, REINFORCEMENT PLANTINGS NEEDED) 2. DOMINANT WETLAND PLANTS: SURVIVAL OF DESIRED WETLAND PLANT SPECIES DISTRIBUTION ACCORDING TO LANDSCAPING PLAN? 3. EVIDENCE OF INVASIVE SPECIES 6. HANYESTING OF EMERGENT PLANTINGS NEEDED WETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES 6. HARVESTING OF EMERGENT PLANTINGS NEEDED DETLAND PLANT SPECIES	1	

	NIN GARDEN/STORMWATER PLANTER AINTENANCE/INSPECTION ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
A.	DEBRIS CLEANOUT (MONTHLY, AFTER MAJOR STORMS)		
	CONTRIBUTING AREAS CLEAN OF DEBRIS INLET AND OUTLETS CLEAN OF DEBRIS		
В.	VEGETATION (MONTHLY)		
	VEGETATION HEALTHY AND GROWING		
	EVIDENCE OF INVASIVE SPECIES		
	ADEQUATE LAYER OF MULCH		
	EVIDENCE OF STANDING WATER		

GRASS SMALE	SATISFACTORY /	
MAINTENANCE ITEM	UNSATISFACTORY	COMMENTS
A. DEBRIS CLEANOUT (MONTHLY)		
CONTRIBUTING AREAS TO CLEAN OF DEBRIS		
B. CHECK DAMS OR ENERGY DISSIPATORS (ANNUAL, PRIOR TO AND MITHIN 24 HOURS AFTER ALL FORECASTED MAJOR STORMS)		
NO EVIDENCE OF FLOW GOING AROUND STRUCTURES		
NO EVIDENCE OF EROSION AT DOWNSTREAM TOE		
SOIL PERMEABILITY		
GROUNDWATER/BEDROCK		
C. VEGETATION (MONTHLY)		
MOWING DONE WHEN NEEDED		
3" MINIMUM MOWING DEPTH NOT EXCEEDED		
NO EVIDENCE OF EROSION AT DOWNSTREAM TOE		
FERTILIZED PER SPECIFICATION		
D. DEWATERING (MONTHLY)		
DEWATERS BETWEEN STORMS		
E. SEDIMENT DEPOSITION (ANNUAL)		
REMOVE SEDIMENT WHEN SWALE IS 25% FULL WITH SEDIMENT		
F. OUTLET/OVERFLOW SPILLWAY (ANNUAL)		
GOOD CONDITION, NO NEED FOR REPAIRS		
NO EVIDENCE OF EROSION		
CATCH BASIN / YARD DRAIN / MANHOLE		

CATCH BASIN / YARD DRAIN / MANHOLE MAINTENANCE ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
A. VISUAL INSPECTION (EVERY 3 MONTHS)		
I. SEDIMENT ACCUMULATION AT:		
A) RIM		
B) SUMP		
2. SIGN OF EROSION AROUND STRUCTURE		
3. SIGN OF STORMWATER BYPASS		
B. MAINTENANCE (EVERY 3 MONTHS)		
I. REMOVE SEDIMENT IN SUMP IF GREATER THAN		
12" DEEP		
2. CLEAR RIM OF DEBRIS AND LEAVES		
3. CLEAR DEBRIS IN INLET CHANNEL		
4. REPAIR ERODED PORTION OF INLET CHANNEL		
(IF ANY)		
STORM PIPES		
(TWICE A YEAR AND BEFORE ALL MAJOR FORECASTED STORMS)		
MAINTENANCE ITEM		
A. STRUCTURAL INTEGRITY		
B. SIGN OF CLOGGAGE		
RIP RAP OUTLET PROTECTION		
(ONCE A YEAR AND AFTER MAJOR STORMS)		
MAINTENANCE ITEM		
A. CHECK FOR SCOUR AND INTEGRITY		
B. REPAIR IF NEEDED		
# 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		

SATISFACTORY /

UNSATISFACTORY

8286

SHEET <u>16</u> OF <u>31</u>

RAWING NUMBER

D. OVERALL FUNCTION OF FACILITY (ANNUAL) GOOD CONDITION, NO NEED FOR REPAIR NO EVIDENCE OF EROSION		
ROOF LEADERS DISCONNECTION MAINTENANCE/INSPECTION ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
A. PIPES AND DRAINS (ANNUAL) DOWNSPOUTS PROVIDE STABLE CONVEYANCE TO THE DESIGNATED AREA NO EXISTENCE OF LEAKING GUTTERS		
B. DEWATERING (MONTHLY) NO EXISTENCE OF STANDING WATER		
C. SEDIMENT DEPOSITION (SEMI-ANNUAL) SEDIMENT ACCUMULATION DOESN'T YET REQUIRE CLEANOUT		
D. OVERALL FUNCTION OF FACILITY (ANNUAL) GOOD CONDITION, NO NEED FOR REPAIR		



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION,

AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

REVISIONS			PR
NO.	DATE	DESCRIPTION	
	+		

PROPOSED SUBDIVISION PLAN PREPARED FOR:

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19

PROJECT



AS NOTED

DATE	DRAWING
12 APR 18	
PROJECT MANAGER	I EROSION and SEDIMENT
 PML	CONTROL DI ANI DILACE A
 DRAWN BY	CONTROL PLAN PHASE 4
 BJK	MAINTENANCE PROGRAM
CHECKED BY	
PML	
SCALE	

UNDERGROUND INFILTRATION SYSTEM

. DEBRIS CLEANOUT (MONTHLY)

MAINTENANCE/INSPECTION ITEM


OUTLETS CLEAN OF DEBRIS

DEWATERING (MONTHLY)

NO EVIDENCE OF EROSION

DEWATERS BETWEEN STORMS SEDIMENT DEPOSITION (ANNUAL) NO EVIDENCE OF SEDIMENT DEPOSITION .

SEDIMENT ACCUMULATION DOESN'T YET REQUIRE CLEANOUT ..





SEQUENCE OF CONSTRUCTION:

PHASES 5A and 5B

DISTURBANCE AREA: PHASE 5A = 2.90 AC. PHASE 5B = 3.68 AC.

CONSTRUCTION AS DESCRIBED BELOW MAY START AFTER SEPTIC FIELDS, SEWER PIPES AND SEWER PUMPING SYSTEM IS IN GROUND, TESTED AND IN WORKING CONDITION. REFER TO UTILITY PLAN AND SSTS PLANS FOR SPECIFICATION.

CONTRACTOR MAY START CONSTRUCTION OF BOTH PHASES SIMULTANEOUSLY ASSURING THAT THE TOTAL DISTURBANCE AREA WILL NOT EXCEED 5 ACRES. CONSTRUCTION SHALL FOLLOW STEPS LISTED BELOW.

- CONTRACTOR TO MAINTAIN ALL SILT AND SAFETY FENCES PREVIOUSLY INSTALLED.
- 2. SURVEY AND STAKE OUT PROPOSED HOUSES, DRIVEWAYS AND RAIN GARDENS LOCATIONS. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG PERIMETERS OF THE PROPOSED DISTURBANCE.
- . INSTALL STABILIZED CONSTRUCTION ENTRANCE FOR LIGHT DUTY ROADS AS SHOWN. VEHICLES SHALL BE INSPECTED AND CLEANED, IF REQUIRED, PRIOR TO ENTERING PAVED ROAD.
- 4. INSPECT SAFETY FENCES INSTALLED AROUND INFILTRATION PRACTICES. REPAIR IF NECESSARY.
- DEWATERING BAGS SHALL BE AVAILABLE ON THE SITE IN CASE DEWATERING AFTER RAIN EVENT IS
- 6. BUILD HOUSES. INSTALL ROOF DRAINS. CONNECT HOUSES TO ALL UTILITY LINES. TRENCHES TO BE BACKFILLED IMMEDIATELY UPON COMPLETION OF INSTALLATION OF PIPES AND CABLES. EXPOSED SOIL TO BE STABILIZED AFTER BACKFILL.
- COMPLETE GRADING. RESTORE SOIL AROUND THE HOUSES PER "SOIL RESTORATION NOTES". SEED AND STABILIZE DISTURBED AREAS WITHIN ONE (1) WEEK FOLLOWING CONSTRUCTION.
- 8. INSTALL TOP COURSE PAVEMENT ON INDIVIDUAL DRIVEWAYS. CLEAN ALL DRAINAGE STRUCTURES.
- CLEAN ACCUMULATED SEDIMENT IN THE SWALES. UPGRADE TEMPORARY SWALE #6 TO PERMANENT SWALE #1 (PHASE 5A). RESTORE GRADING AT TEMPORARY SWALES #7 (PHASE #5A) AND #8 (PHASE #5B) LOCATIONS.
- IO. RESTORE GRADING AT SEDIMENT TRAP #4.
- COMPLETE PLANTING AND STABILIZE PERMANENTLY ALL DISTURBED AREAS.
- 12. EXCAVATE FOR AND INSTALL RAIN GARDENS AS SHOWN ON PLAN AND DETAILS. CONSTRUCTION OF THESE FACILITIES IS NOT ALLOWED UNTIL ALL CONTRIBUTING DRAINAGE AREAS HAVE BEEN

EROSION & SEDIMENT CONTROL PLAN - PHASES 5A and 5B I INCH = 50 FEET

PHASE 5B

EROSION CONTROL LEGEND:

EXISTING DRAINAGE PIPE EXISTING CONTOURS

STABILIZED CONSTRUCTION ENTRANCE

PROPOSED CONTOURS

TEMPORARY STAGING AREA LIMITS OF DISTURBANCE

EARTH DIKE

INLET PROTECTION

TEMPORARY SOIL STOCKPILE

SILT FENCE

EROSION CONTROL BLANKET

CONSTRUCTION FENCE ORANGE SAFETY FENCE


CHECK DAM

LEVEL SPREADER TEMPORARY SWALE

SOIL RESTORATION NOTES:

PRIOR TO SOIL RESTORATION, ALL CONSTRUCTION ACTIVITIES INCLUDING CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE, SITE CLEANUP AND TRAFFICKING SHOULD BE FINISHED AND THE SITE CLOSED OFF TO FUTURE DISTURBANCE.

- I. AREAS WHERE TOPSOIL IS STRIPPED ONLY, NO CHANGE IN GRADE:
- APPLY 6 INCHES OF TOPSOIL
- 2. AREAS OF CUT AND FILL: AERATE AND APPLY 6 INCHES OF TOPSOIL
- 3. HEAVY TRAFFIC AREA (ESPECIALLY ZONE DISTANT 5 FEET TO 25 FEET FROM FOUNDATION): THE PROCEDURE CAN BE PERFORMED DURING LOW TO MODERATE SOIL MOISTURE CONDITION. A) USING AGRICULTURAL GRADE DEEP RIPPER, DEEP RIP THE AFFECTED THICKNESS OF EXPOSED SUBSOIL MATERIAL AGGRESSIVELY FRACTURING IT BEFORE THE PROTECTED
 - TOPSOIL IS REAPPLIED ON THE SITE. B) SPREAD TOPSOIL IN FRIABLE STATE.
 - USING WINGED SUB-SOILER OR AN EXCAVATOR EQUIPPED WITH A SUBSOILING GRAPPLE RAKE, DECOMPACT UPPER PART OF THE AFFECTED SOIL, RECOMPACTED DURING THE PREVIOUS PHASES. ADD COMPOST ENHANCEMENT.



PROPOSED HOUSE



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AN THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

REVISIONS

NO.	DATE	DESCRIPTION	

OLD FORGE ESTATES

PROPOSED SUBDIVISION PLAN PREPARED FOR:

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19


PROJECT




	DATE	DRAWING
	12 APR 18	
	PROJECT MANAGER	l EROSION and St
_	PML	CONTROL D
_	DRAWN BY	CONTROL P
_	BJ K	PHASES 5A a
	CHECKED BY	
	₽ MI	

AS NOTED

ROJECT NUMBER 8286 SEDIMENT RAWING NUMBER SHEET <u>17</u> OF <u>31</u>





SEQUENCE OF CONSTRUCTION:

PHASES 5A and 5B

DISTURBANCE AREA: PHASE 5A = 2.90 AC. PHASE 5B = 3.68 AC.


CONSTRUCTION AS DESCRIBED BELOW MAY START AFTER SEPTIC FIELDS, SEWER PIPES AND SEWER PUMPING SYSTEM IS IN GROUND, TESTED AND IN WORKING CONDITION. REFER TO UTILITY PLAN AND SSTS PLANS FOR SPECIFICATION.

CONTRACTOR MAY START CONSTRUCTION OF BOTH PHASES SIMULTANEOUSLY ASSURING THAT THE TOTAL DISTURBANCE AREA WILL NOT EXCEED 5 ACRES. CONSTRUCTION SHALL FOLLOW STEPS LISTED BELOW.

- 1. CONTRACTOR TO MAINTAIN ALL SILT AND SAFETY FENCES PREVIOUSLY INSTALLED.
- 2. SURVEY AND STAKE OUT PROPOSED HOUSES, DRIVEWAYS AND RAIN GARDENS LOCATIONS. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG PERIMETERS OF THE PROPOSED DISTURBANCE.
- 5. INSTALL STABILIZED CONSTRUCTION ENTRANCE FOR LIGHT DUTY ROADS AS SHOWN. VEHICLES SHALL BE INSPECTED AND CLEANED, IF REQUIRED, PRIOR TO ENTERING PAVED ROAD.
- 4. INSPECT SAFETY FENCES INSTALLED AROUND INFILTRATION PRACTICES. REPAIR IF NECESSARY.
- 5. DEWATERING BAGS SHALL BE AVAILABLE ON THE SITE IN CASE DEWATERING AFTER RAIN EVENT IS NECESSARY.
- 6. BUILD HOUSES. INSTALL ROOF DRAINS. CONNECT HOUSES TO ALL UTILITY LINES. TRENCHES TO BE BACKFILLED IMMEDIATELY UPON COMPLETION OF INSTALLATION OF PIPES AND CABLES. EXPOSED SOIL TO BE STABILIZED AFTER BACKFILL.
- 7. COMPLETE GRADING. RESTORE SOIL AROUND THE HOUSES PER "SOIL RESTORATION NOTES". SEED AND STABILIZE DISTURBED AREAS WITHIN ONE (1) WEEK FOLLOWING CONSTRUCTION.
- 8. INSTALL TOP COURSE PAVEMENT ON INDIVIDUAL DRIVEWAYS. CLEAN ALL DRAINAGE STRUCTURES.
- 9. CLEAN ACCUMULATED SEDIMENT IN THE SWALES. UPGRADE TEMPORARY SWALE #6 TO PERMANENT SWALE #1 (PHASE 5A). RESTORE GRADING AT TEMPORARY SWALES #7 (PHASE #5A) AND #8 (PHASE #5B) LOCATIONS.
- 10. RESTORE GRADING AT SEDIMENT TRAP #4.
- 11. COMPLETE PLANTING AND STABILIZE PERMANENTLY ALL DISTURBED AREAS.
- 12. EXCAVATE FOR AND INSTALL RAIN GARDENS AS SHOWN ON PLAN AND DETAILS. CONSTRUCTION OF THESE FACILITIES IS NOT ALLOWED UNTIL ALL CONTRIBUTING DRAINAGE AREAS HAVE BEEN STABILIZED.



EROSION & SEDIMENT CONTROL PLAN — PHASES 5A and 5B



PHASE 5B

SOIL RESTORATION NOTES:

APPLY 6 INCHES OF TOPSOIL

TOPSOIL IS REAPPLIED ON THE SITE.

1. AREAS WHERE TOPSOIL IS STRIPPED ONLY, NO CHANGE IN GRADE:

AERATE AND APPLY 6 INCHES OF TOPSOIL

B) SPREAD TOPSOIL IN FRIABLE STATE.

FUTURE DISTURBANCE.

2. AREAS OF CUT AND FILL:

PRIOR TO SOIL RESTORATION, ALL CONSTRUCTION ACTIVITIES INCLUDING CONSTRUCTION EQUIPMENT AND

3. HEAVY TRAFFIC AREA (ESPECIALLY ZONE DISTANT 5 FEET TO 25 FEET FROM FOUNDATION):

PREVIOUS PHASES. ADD COMPOST ENHANCEMENT.

THE PROCEDURE CAN BE PERFORMED DURING LOW TO MODERATE SOIL MOISTURE CONDITION.

A) USING AGRICULTURAL GRADE DEEP RIPPER, DEEP RIP THE AFFECTED THICKNESS OF

C) USING WINGED SUB-SOILER OR AN EXCAVATOR EQUIPPED WITH A SUBSOILING GRAPPLE

RAKE, DECOMPACT UPPER PART OF THE AFFECTED SOIL, RECOMPACTED DURING THE

EXPOSED SUBSOIL MATERIAL AGGRESSIVELY FRACTURING IT BEFORE THE PROTECTED

MATERIAL STORAGE, SITE CLEANUP AND TRAFFICKING SHOULD BE FINISHED AND THE SITE CLOSED OFF TO

EROSION CONTROL LEGEND:

EXISTING DRAINAGE PIPE EXISTING CONTOURS ----(416)----- PROPOSED CONTOURS

STABILIZED CONSTRUCTION ENTRANCE

TEMPORARY STAGING AREA

LIMITS OF DISTURBANCE



EARTH DIKE




TEMPORARY SOIL STOCKPILE



INLET PROTECTION



SILT FENCE EROSION CONTROL BLANKET



CONSTRUCTION FENCE

XXX

ORANGE SAFETY FENCE CHECK DAM

LEVEL SPREADER TEMPORARY SWALE

PROPOSED HOUSE



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 PUTNÁM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

REVISIONS

NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION
1	09 NOV 18	REV. PER BI, TE, TP COMMENTS			
2	02 OCT 19	REV. PER TE COMMENTS			

PROPOSED SUBDIVISION PLAN PREPARED FOR:

PROJECT

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19




	DATE
	12 APR 18
	PROJECT MANAG
	PML
	DRAWN BY
1	—— B JK
	CHECKED BY
	PML
	SCALE

AS NOTED

EROSION and SEDIMENT JECT MANAGER CONTROL PLAN PHASES 5A and 5B

PROJECT NUMBER 8286 DRAWING NUMBER

SHEET <u>18</u> OF <u>34</u>



SLOPE STABILIZATION NOTES:

TEMPORARY STABILIZATION:

AREAS WHERE TEMPORARY STABILIZATION IS NEEDED, SUCH AS GRADED AREAS TO BE STABILIZED UNTIL START OF NEXT CONSTRUCTION PHASE OR SEASON, ARE TO BE IMMEDIATELY STABILIZED AS FOLLOWS

SPRING/SUMMER/EARLY FALL PLANTING: ANNUAL RYEGRASS & CEREAL OATS (LOLIUM MULTIFLORUM) 30 LBS/AC

LATE FALL/EARLY WINTER: AROOSTOOK WINTER RYE (LOLIUM PERENNE VAR. ARISTATUM) 100 LBS/AC

PERMANENT STABILIZATION:

ALL DISTURBED AREAS, CUT SLOPES AND EMBANKMENT FILL AREAS ARE TO BE IMMEDIATELY STABILIZED AS FOLLOWS, UNLESS OTHERWISE SPECIFIED:

MAINTAINED TURF GRASS:

KENTUCKY BLUE GRASS CREEPING RED FESCUE RED TOP OR RYE GRASS


WILDFLOWER AREAS:

"NATIVE STEEP SLOPE MIX WITH ANNUAL RYEGRASS" SEED MIX ERNMX-181 AS MFR. BY ERNST CONSERVATION SEEDS, WITH AN APPLICATION RATE OF 60 LBS/ACRE.

	PLANT LIST					
SYM.	NAME	SIZE (MIN.)	QTY.			
P5	EVERGREEN TREES PINUS STROBUS / EASTERN WHITE PINE	2.5" CAL.	7			
	DECIDUOUS STREET TREES					
AR	ACER RUBRUM / RED MAPLE	2.5" CAL.	15			
AS	ACER SACCHARUM / SUGAR MAPLE	2.5" CAL.	13			
PC	PYRUS CALLERYANA / CLEVELAND PEAR	2.5" CAL.	23			
QP	QUERCUS PALUSTRIS / PIN OAK	2.5" CAL.	13			
NS	NYSSA SYLVATICA/BLACK GUM	2.5" CAL.	4			

PLANTING NOTES:

- I. ALL PLANTINGS SHALL BE VERIFIED BY THE TOWN OF CARMEL WETLANDS INSPECTOR.
- 2. ALL PLANTINGS SHALL BE INSTALLED PER CHAPTER 142 OF THE TOWN OF CARMEL CODE.
- 3. NO PARKING OR STORAGE OF MATERIALS WILL BE PERMITTED UNDER DRIP LINE OF EXISTING TREES AND SHRUBS TO REMAIN.
- 4. ALL PLANT MATERIALS SHALL BE NURSERY GROWN, FULLY FORMED AND IN A HEALTHY CONDITION FREE OF INSECTS, PESTS, DISEASE OR DAMAGE AT THE TIME OF INSTALLATION.
- 5. ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN.
- 6. ALL LANDSCAPING SHOWN SHALL BE MAINTAINED IN A HEALTHY GROWING CONDITION THROUGHOUT THE DURATION OF THE USE BEING SERVED. PLANTS NOT SO MAINTAINED SHALL BE REPLACED WITH HEALTHY NEW PLANTS OF COMPARABLE SIZE, TYPE AND QUANTITY AT THE BEGINNING OF THE IMMEDIATELY FOLLOWING GROWING SEASON.
- 7. TOPSOIL ALL DISTURBED AREAS WITH NOT LESS THAN FOUR (4) INCHES OF SUITABLE TOPSOIL
- 8. SEED ALL OTHER DISTURBED AREAS IN ACCORDANCE WITH THE "SLOPE STABILIZATION NOTES".
- 9. MULCH ALL AREAS WITH STRAW AT THE RATE OF TWO TONS PER ACRE.
- 10. ALL UTILITIES MAY NOT BE SHOWN. CONTRACTOR SHALL VERIFY LOCATIONS OF UTILITIES BEFORE PROCEEDING WITH WORK.
- II. SEE "EROSION AND SEDIMENT CONTROL PLAN", DRAWING #C-153 FOR MAINTENANCE AND ESTABLISHMENT OF GROWTH.
- 12. AFTER ESTABLISHMENT OF DENSE, VIGOROUS VEGETATION, PHOSPHORUS BASED FERTILIZERS SHALL NOT BE USED. ONLY NON-PHOSPHORUS BASED FERTILIZER MAY BE APPLIED TO THE LAWNS AND GRASSED AREAS.



RAIN GARDEN PLANTS:

PLANTINGS TO SELECT FROM ILEX VERTICILLATA (WINTERBERRY) VIBURNUM DENTATUM (ARROWWOOD) CLETHRA ALNIFOLIA (SMEET PEPPERBUSH) CINNAMON FERN (OSMUNDA CINNAMOMEA) CUTLEAF CONEFLOWER (RUDBECKIA LACINIATA) GREAT BLUE LOBELIA (LOBELIA SIPHATICA) WILD BERGAMOT (MONARDA FISTULOSA) NEW ENGLAND ASTER (ASTER NOVAE-ANGLIAE) WOOLGRASS (SCIRPUS CYPERINUS) BUTTERFLY WEED (ASCLEPIAS TUBEROSA) WOOD LILY (LILIUM PHILADELPHICUM)

I. THERE ARE A TOTAL OF 14 RAIN GARDENS PROPOSED FOR THE DEVELOPMENT. THEY VARY BY SHAPE AND SUN EXPOSURE. TO DIVERSIFY LANDSCAPE APPEARANCE AND TO PROVIDE PLANTS BEST SUITABLE FOR THE SUN EXPOSURE AT THE SITE, ONLY GENERAL PLANTING INSTRUCTIONS ARE PROVIDED. EACH RAIN GARDEN SHALL HAVE NUMBER OF SHRUBS AND PERENNIAL AS LISTED BELOW. THE LANDSCAPER WILL BE RESPONSIBLE FOR THE PLANT SELECTION.

SOLOMON'S SEAL (POLYGNATUM BIFLORUMS)

- 2. PLANTS SHALL BE CONTAINER-GROWN WITH A WELL ESTABLISHED ROOT SYSTEM.
- 3. SHREDDED HARDWOOD MULCH SHOULD BE APPLIED UP TO 2 INCHES TO KEEP SOIL IN PLACE.

RAIN GARDEN I.D.	AREA (S.F.)	NUMBER OF GARDENS	NO. OF SHRUBS PER GARDEN	TOTAL NO. OF SHRUBS	NO. OF PERENNIALS PER GARDEN	TOTAL NO. OF PERENNIALS
RGI	220	14	3	30	40	400
RG2	1		-	-	-	
R63	-	1	-	-	-	-





ENGINEERS - ARCHITECTS

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION."

PROPOSED SUBDIVISION PLAN PREPARED FOR:

(I) FLAME AZELEA

RHODODENRON

CALENDULACEUM-

(4) COREOPSIS-

FULL MOON

ROAD FACE

(6) YELLOWROOT

XANTHORHIZA

SIMPLICISSIMA

RHODODENRON-CALENDULACEUM

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



-MULCH PLANTING BED

RIVER BIRCH CLUMP BETULA NIGRA


(5) SWITCHGRASS

PANICUM VIRGATUM VAR.

-	DRAWING
12 APR 18	
JECT MANAGER	
PML	I ANDGE ADE DI ANI
WN BY	LANDSCAPE PLAN
BJK	
CKED BY	
PML	

8286 RAWING NUMBER

SHEET _____ OF ____ 31___



A ROAD PROFILE

G-210 SCALE: HORIZ. I" = 60', VERT. I" = 10'

UTNAM NGINEERING, PLLC ENGINEERS - ARCHITECTS

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509


(845) 279-6789 FAX (845) 279-6769 ● PUTNAM ENGINEERING PLLC 2018 PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION."

REVISIONS					PROJECT	
NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION	
1	09 NOV 18	REV. PER BI, TE, TP COMMENTS				
2	02 OCT 19	REV. PER TE COMMENTS				
3	II MAY 20	REV. PER TE COMMENTS				

PROPOSED SUBDIVISION PLAN PREPARED FOR:

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN OF CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



ROAD PROFILE


DRAWING


PROJECT NUMBER
8286

DRAWING NUMBER

C-2|0

SHEET 21 OF 34





SANITARY SEWER PROFILE

SCALE: HORIZ. I" = 50', VERT. I" = 10'

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL
OF AN ENGINEER IS ALTERED, THE ALTERING
ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

DESCRIPTION DESCRIPTION 09 NOV 18 REV. PER BI, TE, TP COMMENTS 2 02 OCT 19 REV. PER TE COMMENTS 3 | II MAY 20 | REV. PER TE COMMENTS

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES BALDWIN PLACE ROAD

TOWN of CARMEL

PUTNAM COUNTY, NEW YORK

TAX MAP 75.15-1-19

SCALE

AS NOTED


DRAWING 12 APR 18 PROJECT MANAGER PML SANITARY SEWER PROFILE DRAWN BY CHECKED BY PML

PROJECT NUMBER 8286 DRAWING NUMBER

SHEET <u>23</u> OF <u>34</u>

(845) 279-6789 FAX (845) 279-6769

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 PUTNAM ENGINEERING PLLC 2018




MATERMAIN PROFILE: WATERMAIN ALONG ROAD

FIRE HYDRANT NOTES:

- I. ALL FIRE HYDRANTS SHALL BE THE APPROVED AWMA TYPE FIRE HYDRANTS IN CONFORMANCE WITH THE AMERICAN WATER WORKS ASSOCIATION STANDARD FOR FIRE HYDRANTS FOR ORDINARY WATER WORKS SERVICE, AWMA DESIGNATION C502, AND SHALL HAVE A 5-1/4 INCH VALVE OPENING, A 6 INCH MECHANICAL JOINT INLET COMPLETE WITH AN AUXILIARY GATE VALVE (CLOSE COUPLED), A 6 INCH MECHANICAL SHOE, AND ALL APPURTENANCES.
- 2. FIRE HYDRANTS SHALL BE RATED FOR A WORKING PRESSURE OF 250 PSI. FIRE HYDRANTS SHALL BE SIZED FOR A 4'-6" BURY.

VALVE NOTES:

- GATE VALVES SHALL BE AWWA NON-RISING STEM TYPE, AS MANUFACTURED BY "MUELLER CO.",
 MODEL A-2360-23, OR APPROVED EQUAL, CONFORMING TO THE LATEST AWWA STANDARD FOR
 GATE VALVES 3" THROUGH 48" FOR WATER AND OTHER LIQUIDS, AWWA DESIGNATION C509.
- 2. SIZES UP TO AND INCLUDING 12 INCHES SHALL BE 250 PSI WORKING PRESSURE. THE VALVE BODY AND BONNET SHALL BE DUCTILE IRON. ALL INTERIOR AND EXTERIOR METAL SURFACES SHALL BE COATED WITH A TWO-PART THERMOSETTING EPOXY COMPLYING WITH AWWA C550.
- 3. VALVES SHALL HAVE DUAL "O" RING SEALS, INSIDE SCREM, RESILIENT WEDGE SEATS IN ACCORDANCE WITH AWMA DESIGNATION C550 AND SHALL BE CONSTRUCTED SO AS TO PROVIDE UNOBSTRUCTED FULL PORT CLEARANCE WHEN FULLY OPEN AND IMMEDIATE COMPLETE CLOSURE WHEN CLOSED. THE ENDS OF THE VALVES SHALL BE MECHANICAL JOINT.
- 4. ALL VALVES SHALL BE ARRANGED TO OPEN IN COUNTER CLOCKWISE DIRECTION UNLESS OTHERWISE SPECIFICALLY INDICATED AND OPERATING NUTS SHALL BE 2 INCH SQUARE.
- 5. VALVES SHALL BE TESTED TO A PRESSURE OF NOT LESS THAN TWO TIMES THE WORKING PRESSURE.



WATERMAIN PROFILE: CONNECTION to EXISTING WATERMAIN - EASTERN TIE-IN

SCALE: HORIZ. I" = 50', VERT. I" = 10'



ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

PURSUANT TO NEW YORK STATE EDUCATION LAW,

O. DATE DESCRIPTION NO. DATE DESCRIPTION

I 09 NOV IB REV. PER BI, TE, TP COMMENTS

2 02 OCT I9 REV. PER TE COMMENTS

3 II MAY 20 REV. PER TE COMMENTS

PROPOSED SUBDIVISION PLAN PREPARED FOR:

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



SCALE

AS NOTED

I2 APR 18
PROJECT MANAGER

PML
DRAWN BY

BJK
CHECKED BY
PML

DRAWING

WATERMAIN PROFILES


C-213

8286

ROJECT NUMBER


SHEET <u>24</u> OF <u>34</u>

SCALE: HORIZ. I" = 50', VERT. I" = 10'



- 2. LENGTH NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH MOULD APPLY)
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES FOR LIGHT DUTY ROADS AND SINGLE FAMILY RESIDENCES, NOT LESS THAN TEN (IO) INCHES FOR HEAVY DUTY ROADS. 4. WIDTH - TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS
- OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. "MIRAFI" 600X, OR
- APPROVED EQUAL . SURFACE MATER - ALL SURFACE MATER FLOMING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE
- . MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR
- FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. B. WASHING - WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH
- DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. . PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.






- . PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN. 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" (15cm) DEEP X 6" (15cm) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30cm) APART IN THE BOTTOM OF THE TRENCH.

 BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30cm) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30cm) APART ACROSS THE WIDTH OF THE BLANKET.
- 3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN CUIDE. WHEN USING OPTIONAL DOT SYSTEM ", STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN. 4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" (5cm-12.5cm) OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET. 5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5cm) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30cm) APART ACROSS ENTIRE BLANKET WIDTH.

*IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15cm) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.





DEWATERING

RESTRICT SEDIMENT MOVEMENT

CONSTRUCTION SPECIFICATIONS:


I' MIN. TO 2' MAX. BELOW

TOP OF INLET

- CLEAR THE AREA OF ALL DEBRIS THAT WILL HINDER EXCAVATION.
- GRADE APPROACH TO THE INLET UNIFORMLY AROUND THE BASIN.
- 3. WEEP HOLES SHALL BE PROTECTED BY GRAVEL.
- UPON STABILIZATION OF CONTRIBUTING DRAINAGE AREA, SEAL WEEP HOLES. FILL BASIN WITH STABLE SOIL TO FINAL GRADE, COMPACT IT PROPERLY AND STABILIZE WITH PERMANENT

SEEDING. MAX. DRAINAGE AREA I ACRE

PROTECTION DETAIL **C-310** N.T.S.



2. FILTER FABRIC TO BE EMBEDDED IN SOIL A MIN. OF 6". FILTER CLOTH TO BE FASTENED SECURELY TO

3. INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS

MOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.

- 4. SILT FENCE TO BE REMOVED AT END OF CONSTRUCTION BUT NOT BEFORE ALL DISTURBED AREAS ARE STABILIZED AND VEGETATED.
- 5. FOR SILT FENCE INSTALLATION ON PAVED AREAS, REMOVE PORTION OF ASPHALT NECESSARY TO TOE-IN THE FABRIC AND TO INSTALL THE POSTS. THE PAVEMENT SHALL BE RESTORED BEFORE FINAL

STAPLE PATTERN GUIDE

6.67' (2.03 M) WIDE ROLLS

0.7 STAPLES PER SQ. YD. (0.8 STAPLES PER SQ. M)

EROSION CONTROL BLANKET

STAPLE PATTERNS

2 SILT FENCE DETAILS C-310

NEEDED.

NORTH AMERICAN GREEN

EROSION CONTROL Produc

Guaranteed SOLUTIONS

3' (0.9m)

- 3.3' (1.0m)

_ 3.3' (1.0m)

0 0


1.15 STAPLES PER SQ. YD (1.35 STAPLES PER SQ. M)

0

Q (0.6m)

000

— - 1.6' (0.5m)



INSTALLATION NOTES:

NOTES:

C-310

- AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2.

SPACING MAY VARY AS PER MANUFACTURER'S

INTEGRITY OF THE CONSTRUCTION AREA.

RECOMMENDATIONS. MAXIMUM SPACING IS 8'-0".

2. JOIN CONSTRUCTION FENCE SECTIONS BY OVERLAPPING END

INSPECT AND REPAIR PERIODICALLY TO MAINTAIN THE

- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH SILT FENCING.
- 4. SPRING/SUMMER/FALL SEEDING: SEED WITH PERENNIAL RYE GRASS @ 40 LBS/AC. STABILIZATION FROM NOVEMBER I THROUGH MARCH 31 SHALL BE BY A ROLLED EROSION CONTROL PRODUCT OR MAY BE HYDROSEEDED WITH WINTER RYE WITH A HEAVY MULCH LAYER. RESEED STOCKPILE IN SPRING AS NOTED ABOVE.

~48" HIGH DENSITY ORANGE

POLYETHYLENE SAFETY FENCE.

EROSIONRUNNER.COM SAF8, OR

-STAKES: 72" T-POST DRIVEN 20"

-WIRE OR ZIP TIES TO SECURE


SAFETY FENCE TO POST

MIN. BELOW GRADE

-FINISHED GRADE

5. SEE SILT FENCE DETAIL FOR SILT FENCE INSTALLATION SPECIFICATIONS.

TOPSOIL STOCKPILE DETAIL C-310 N.T.S.



CONSTRUCTION SPECIFICATIONS:

FUNCTIONING OF THE SWALE.

- ALL TEMPORARY SWALES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET.


 2. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
- 3. DIVERTED RUNOFF FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT 4. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS
- NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE. THE SMALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA
- SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW. FILLS SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT. ALL EARTH REMOVED AND NOT NEEDED ON CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE

LINED 4-8" RIP-RAP

- 8. STABILIZATION SHALL BE AS PER THE CHART BELOW: FLOW CHANNEL STABILIZATION -SEE TABLES ON EROSION CONTROL PLANS (SHEETS #C-150 to 3C-154) FOR SLOPES
- A (5 AC OR LESS)
- SEED AND STRAW MULCH 3.1%-5% SEED AND STRAM MULCH SEED WITH JUTE OR EXCELSIOR; SOD 5.1%-8%
- 9. PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED AFTER EACH RAIN EVENT.

8.1%-20%





MATER BAR SPACING:

. ALL WATER BARS SHALL BEGIN AT THE INTERSECTION OF THE ROADBED AND CUT SLOPE AND RUN ACROSS THE ENTIRE WIDTH OF THE ROADBED. 2. ALL WATER BARS SHALL HAVE FREE FLOWING OUTLETS. 3. WHEN STAKES ARE USED, THEY DESIGNATE THE OUTLET LOCATION.

10 TO 20 20 TO 35

#605.1001 UNDERLAYMENT

-LIP OF SPREADER

6" x 6" TREATED

#5 REBAR 2' MIN.

UNDISTURBED

501L 15% OR

FLATTER

GEOTEXTILE

TIMBER @ 8 FT.


LENGTHS

<u>SPACING (FT.</u>

CONSTRUCTION SPECIFICATIONS:

- INSTALL THE WATER BAR AS SOON AS THE RIGHT OF WAY IS CLEARED AND GRADED. 2. DISK OR STRIP THE SOD FROM THE BASE FOR THE CONSTRUCTED RIDGE BEFORE PLACING FILL.
- 3. TRACK THE RIDGE TO COMPACT IT TO THE DESIGN CROSS SECTION. 4. THE OUTLET SHALL BE LOCATED ON AN UNDISTURBED AREA. FIELD SPACING WILL BE ADJUSTED TO USE THE MOST
- STABLE OUTLET AREAS. OUTLET PROTECTION WILL BE PROVIDED WHEN NATURAL AREAS ARE NOT ADEQUATE. 5. VEHICLE CROSSING SHALL BE STABILIZED WITH GRAVEL. EXPOSED AREAS SHALL BE IMMEDIATELY SEEDED AND
- 6. PERIODICALLY INSPECT WATER BARS FOR EROSION DAMAGE AND SEDIMENT. CHECK OUTLET AREAS AND MAKE REPAIRS AS NEEDED TO RESTORE OPERATION.






CONSTRUCTION SPECIFICATIONS:

- . FILTER FABRIC SHALL HAVE AN E.O.S. OF 40-85. BURLAP MAY BE USED FOR SHORT TERM
- APPLICATIONS. 2. CUT FABRIC FROM A CONTINUOUS ROLL TO ELIMINATE JOINTS. IF JOINTS ARE NEEDED THEY WILL BE OVERLAPPED TO THE NEXT STAKE. 3. STAKE MATERIALS WILL BE STANDARD 2"x4" WOOD OR EQUIVALENT METAL WITH A MINIMUM LENGTH
- OF 3 FEET. 4. SPACE STAKES EVENLY AROUND INLET 3 FEET APART AND DRIVE A MINIMUM OF 18 INCHES DEEP. SPANS GREATER THAN 3 FEET MAY BE BRIDGED WITH THE USE OF WIRE MESH BEHIND THE FILTER
- 5. FABRIC WILL BE EMBEDDED I FOOT MINIMUM BELOW GROUND AND BACKFILLED. IT SHALL BE SECURELY FASTENED TO THE STAKES AND FRAME.
- 6. A 2"x4" WOOD FRAME SHALL BE COMPLETED AROUND THE CREST OF THE FABRIC FOR OVER FLOW
- 7. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRED AS NEEDED.








VEGETATION OVER

STAPLED IN PLACE

JUTE BLANKET

MIDTH "W" = 5'-0"



A:I SLOPES

B 3:1 SLOPES

.7 STAPLES PER SQ. YD (2.0 STAPLES PER SQ. M)

| - 10" (0.25m)

+PP_P20" (0.5m)C

φο ο ο οφ

3.75 STAPLES PER SQ. YE (4.5 STAPLES PER SQ. M)

2:1 SLOPES & STEEPER SLOPES

(E) HIGH FLOW CHANNEL & SHORELINE

MEDIUM/HIGH FLOW CHANNEL


OPTION: A ONE FOOT LAYER OF 2" STONE MAY BE PLACED ON THE UPSTREAM SIDE OF THE RIP RAP IN PLACE OF THE EMBEDDED FILTER CLOTH.

CROSS SECTION A-A

CONSTRUCTION SPECIFICATIONS FOR ST-V SILT TRAP:

- . AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED, AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED 2. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS AND OTHER WOODY VEGETATION AS WELL AS OVER SIZED STONES, ROCKS, ORGANIC 3. ALL CUT AND FILL SLOPES SHALL BE IV: 2H OR FLATTER
- 4. THE STONE USED IN THE OUTLET SHALL BE SMALL RIP RAP 4"-8" ALONG WITH A 1" THICKNESS OF 2" AGGREGATE PLACED ON THE UPGRADE SIDE ON THE SMALL
- 5. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP, REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- 6. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED.
- 7. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION IS MINIMIZED
- 8. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.
- 9. REFER TO EROSION CONTROL DRAWINGS FOR SIZES.

STONE OUTLET SEDIMENT TRAP DTL. C-310



CONSTRUCTION SAFETY FENCE DTL.

TOP WIDTH MAY BE WIDER AND SIDE SLOPES BE FLATTER IF DESIRED TO FACILITATE CROSSING BY CONSTRUCTION TRAFFIC . FIELD LOCATION SHOULD BE ADJUSTED AS NEEDED TO UTILIZE A STABILIZED SAFE OUTLET. 5. EARTH DIKES SHALL HAVE AN OUTLET THAT FUNCTIONS WITH A MINIMUM OF EROSION. RUNOFF SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE SUCH AS A SEDIMENT TRAP OR SEDIMENT BASIN WHERE EITHER THE DIKE CHANNEL OR THE DRAINAGE AREA

ABOVE THE DIKE ARE NOT ADEQUATELY STABILIZED. 5. STABILIZATION SHALL BE: (A) IN ACCORDANCE WITH STANDARD SPECIFICATIONS FOR SEED AND STRAW MULCH IF NOT IN SEEDING SEASON, (B) FLOW CHANNEL AS PER THE CHART BELOW: FLOW CHANNEL STABILIZATION:

PROJECT

TYPE OF TYPE OF DIKE B

SEED AND STRAW MULCH SEED AND STRAW MULCH LINED RIP RAP 4-8"


SEED AND STRAW MULCH SEED USING JUTE OR EXCELSIOR; SOD; 2" STONE


LINED RIP RAP 4-8 ENGINEERING DESIGN 8.I-20% A. STONE TO BE 2 INCH STONE OR RECYCLED CONCRETE EQUIVALENT IN A LAYER AT LEAST 3 INCHES IN THICKNESS AND BE PRESSED INTO THE SOIL WITH CONSTRUCTION EQUIPMENT.

SEED WITH JUTE OR SOD; 2" STONE

B. RIP RAP TO BE 4-8 INCHES IN A LAYER AT LEAST ϑ INCHES THICK AND PRESSED INTO THE SOIL . APPROVED EQUIVALENTS CAN BE SUBSTITUTED FOR ANY OF THE ABOVE MATERIALS. . PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED AFTER EACH RAIN EVENT

EARTH DIKE DETAILS C-310





LEVEL SPREADER DETAILS

ENGINEERS - ARCHITECTS


4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED. THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

12 11010110					
10.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION
I	09 NOV 18	REV. PER BI, TE, TP COMMENTS			
2	02 OCT 19	REV. PER TE COMMENTS			
3	II MAY 20	REV. PER TE COMMENTS			

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



AS NOTED


PROJECT MANAGER


DRAWING


8286 DRAWING NUMBER **DETAILS** C-310


SHEET ___25__ OF __34_

ROJECT NUMBER









CONSTRUCTION SPECIFICATIONS:

I. CULVERT SIZE AS SHOWN ON EROSION CONTROL PLAN. MINIMUM PIPE SIZE SHALL BE 12 INCH.

2. THE CULVERT SHALL EXTEND A MINIMUM OF I FOOT BEYOND THE UPSTREAM AND DOWNSTREAM TOE OF THE AGGREGATE PLACED AROUND THE THE CULVERT. IN NO CASE SHALL THE CULVERT EXCEED 40 FEET IN LENGTH. 3. FILTER CLOTH SHALL BE PLACED ON THE STREAMBED AND STREAMBANKS PRIOR TO PLACEMENT OF THE CULVERT AND AGGREGATE. THE FILTER CLOTH SHALL COVER THE STREAMBED AND EXTEND A MINIMUM 6 INCHES AND A

MAXIMUM OF I FOOT BEYOND THE END OF THE CULVERT AND BEDDING MATERIAL. 4. THE INVERT ELEVATION OF THE CULVERT SHALL BE INSTALLED ON THE NATURAL STREAMBED GRADE. 5. THE CULVERT SHALL BE COVERED WITH A MINIMUM OF I FOOT OF AGGREGATE. AT THE MINIMUM, THE BEDDING AND

6. ALL AREAS DISTURBED DURING THE CULVERT INSTALLATION SHALL BE STABILIZED WITHIN 1 DAYS OF THE

FILL MATERIAL SHALL BE NYSDOT COARSE AGGREGATE DESIGNATION NO. 4 (3/4" TO 4") ALSO REFERRED TO AS

MAINTENANCE REQUIREMENTS:

. PERIODIC INSPECTION SHALL BE PERFORMED TO ENSURE THAT THE CULVERTS, STREAMBED AND STREAMBANKS ARE

2. MAINTENANCE SHALL BE PERFORMED, AS NEEDED, IN A TIMELY MANNER TO ENSURE THAT STRUCTURES ARE IN COMPLIANCE WITH THIS STANDARD AND SPECIFICATION. THIS SHALL INCLUDE REMOVAL AND DISPOSAL OF ANY TRAPPED SEDIMENT OR DEBRIS. SEDIMENT SHALL BE DISPOSED OF AND STABILIZED OUTSIDE THE WATERWAY FLOOD

CULVERT REMOVAL AND CLEANUP:

I. WHEN THE CROSSING HAS SERVED ITS PURPOSE, ALL CULVERTS, BEDDING, AND FILTER CLOTH MATERIALS SHALL BE REMOVED WITHIN 14 CALENDAR DAYS. IN ALL CASES, THE CULVERT MATERIALS SHALL BE REMOVED WITHIN I YEAR

2. FINAL CLEAN UP SHALL CONSIST OF REMOVAL OF THE CULVERT FROM THE WATERWAY, REMOVAL OF ALL CONSTRUCTION MATERIALS, RESTORATION OF ORIGINAL STREAM CHANNEL CROSS SECTION AND PROTECTION OF THE

3. REMOVAL OF THE CULVERT AND CLEANING UP OF THE AREA SHALL BE ACCOMPLISHED WITHOUT CONSTRUCTION EQUIPMENT WORKING IN THE WATERWAY CHANNEL.


4. ALL AREAS DISTURBED DURING CULVERT REMOVAL SHALL BE STABILIZED WITHIN 14 CALENDAR DAYS OF THE DISTURBANCE IN ACCORDANCE WITH THE SLOPE STABILIZATION NOTES.

NOTE: CONTINUE TIE RODS TO MAIN OR AT LEAST 20 FEET ALONG HYDRANT LATERAL — 3" DIA. SCH. 40 GALVANIZED STEEL POST WITH CAP (TYP). PAINT GREEN SIGN "AUTHORIZED VEHICLES ONLY - DO NOT ENTER" POND ACCESS ROAD -CHAIN POURED CONCRETE FOOTING -|'-O"_


I. CHAIN GATE SHALL BE SECURED TO THE 3" POST BY USE OF EYELET FASTENERS.

2. A LOCK SHALL BE USED TO SECURE THE CHAIN GATE. INDIVIDUAL KEYS ARE TO BE DISTRIBUTED TO THE APPROPRIATE MUNICIPAL EMERGENCY DEPARTMENTS AS WELL AS THE HOMEOWNER'S ASSOCIATION AND THE LANDSCAPER.






SEDIMENT REMOVAL MARKER DETAIL C-3|2 N.T.5.




CATCH BASIN NOTES:

- MALL THICKNESS: 6" POURED CONCRETE OR PRECAST CONC. SECTIONS, CLASS A CONCRETE. 2. ALL CATCH BASINS SHALL CONFORM AND BE INSTALLED IN ACCORDANCE WITH THE NYSDOT
- 3. POURED OR PRECAST WALLS SHALL BE REINFORCED WITH 6x6/W6xW6 WMM. BOTTOM SHALL BE SIMILAR.
- 4. CATCH BASINS SHALL BE DESIGNED FOR AASHTO H-20 LOADING. 5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO CONSTRUCTION.







TEMPORARY ACCESS CULVERT DETAIL




- MALL THICKNESS: 6" POURED CONCRETE OR PRECAST CONC. SECTIONS,
- CLASS A CONCRETE. 2. THICKNESS OF FLOW SPLITTER INSERT- 3"
- 3. POURED OR PRECAST WALLS SHALL BE REINFORCED WITH 6x6/W6xW6 WWM. BOTTOM SHALL BE SIMILAR.
- 5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO
- 4. CATCH BASINS SHALL BE DESIGNED FOR AASHTO H-20 LOADING.





- I. WALL THICKNESS: 6" POURED CONCRETE OR PRECAST CONC. SECTIONS,
- CLASS A CONCRETE. 2. THICKNESS OF FLOW SPLITTER INSERT- 3"
- 3. POURED OR PRECAST WALLS SHALL BE REINFORCED WITH 6x6/W6xW6 WWM. BOTTOM SHALL BE SIMILAR.
- 4. CATCH BASINS SHALL BE DESIGNED FOR AASHTO H-20 LOADING. 5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO



- DRAINAGE MANHOLE NOTES: ALL DRAINAGE MANHOLES SHALL CONFORM AND BE INSTALLED IN ACCORDANCE WITH THE NYSDOT STANDARD SHEETS. . DRAINAGE MANHOLES SHALL BE DESIGNED FOR AASHTO H-20 LOADING. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO
 - * REFER TO GRADING PLAN FOR

SUBGRADE

24"Φ CAST IRON MANHOLE FRAME AND COVER. "CAMPBELL"

PATTERN NO. 1007C OR

APPROVED EQUAL



6 FLOW SPLITTER FS DETAIL
C-3|2 N.T.S.

INLET FRAME AND GRATE --- FINISHED GRADE "CAMPBELL" PATTERN No. 9349 OR APPROVED EQUAL I'-O" WIDE MOWING STRIP, 3" DEEP OF 3/4" WASHED GRAVEL, FLUSH WITH GRADE WEED BARRIER FABRIC ADJUST TO GRADE WITH CEMENT MORTAR CONCRETE SLAB WITH 24" x 24" OPENING NON-SHRINK CEMENT GROUT 6" MIN. CRUSHED STONE BASE UNDISTURBED OR COMPACTED

FLOW SPLITTER FS DETAIL


I. WALL THICKNESS: 6" POURED CONCRETE OR PRECAST CONC. SECTIONS, CLASS A CONCRETE. 2. ALL CATCH BASINS SHALL CONFORM WITH AND BE INSTALLED IN ACCORDANCE WITH THE NYSDOT STANDARD SHEETS. 3. POURED OR PRECAST WALLS SHALL BE REINFORCED WITH 6x6/W6xW6 WWM. BOTTOM SHALL BE






4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE











PROJECT NUMBER 8286 DRAWING NUMBER DETAILS SHEET <u>27</u> OF <u>34</u>


TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19














PROJECT

REVISIONS




4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBI A VIOLATION OF THIS LAW FOR UNLESS HE IS ACTING UNDER THE LICENSED PROFESSIONAL ENGINEE ITEM IN ANY WAY. IF AN ITEM BE OF AN ENGINEER IS ALTERED, ENGINEER SHALL AFFIX TO THE THE NOTATION "ALTERED BY" SIGNATURE AND THE DATE OF AND A SPECIFIC DESCRIPT ALTERATION."

TE EDUCATION LAW, UBDIVISION 2, "IT IS	NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION
FOR ANY PERSON	1	09 NOV 18	REV. PER BI, TE, TP COMMENTS			
THE DIRECTION OF A NEER, TO ALTER AN	2	02 OCT 19	REV. PER TE COMMENTS			
BEARING THE SEAL	3	II MAY 20	REV. PER TE COMMENTS			
D, THE ALTERING						
ITEM HIS SEAL AND FOLLOWED BY HIS						
SUCH ALTERATION,						
PTION OF THE						

PROPOSED SUBDIVISION PLAN PREPARED FOR: OLD FORGE ESTATES BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK

TAX MAP 75.15-1-19




AS NOTED

	DRAWING
12 APR 18	
JECT MANAGER	
PML	DRIVEWAY PROFILES
WN BY	DRIVENAL PROFILES
BJK	
CKED BY	
PML	


8286 RAWING NUMBER C-410

SHEET 33 OF 34





WATER MAIN RELOCATION PLAN



ENGINEERS - ARCHITECTS

4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 PUTNAM ENGINEERING PLLC 2018

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

REVISIONS						PROJE
NO.	DATE	DESCRIPTION	NO.	DATE	DESCRIPTION	
_	09 NOV 18	REV. PER BI, TE, TP COMMENTS				
2	02 OCT 19	REV. PER TE COMMENTS				
3	II MAY 20	REV. PER TE COMMENTS				
				·		

PROPOSED SUBDIVISION PLAN PREPARED FOR:

PROJECT

OLD FORGE ESTATES

BALDWIN PLACE ROAD TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP 75.15-1-19



PML

AS NOTED

DRAWING 12 APR 18 PROJECT MANAGER WATER MAIN RELOCATION PLAN DRAWN BY

MATER MAIN RELOCATION SEQUENCE:

CONSTRUCTION.

THE TIE IN POINTS.

AND THRUST BLOCKS.

LOCATION OF THE TIE INS.

PORTION THAT CROSSES PARCEL A.

PROPOSED WORK TO ISOLATE THE AREA.

I. THE WATER MAIN IN THE SUBDIVISION ROAD WILL HAVE BEEN INSTALLED AS PART OF THE ROAD

CURRENTLY CROSSING LOTS 7, 8, 9 AND 10. TEST PITS, HAND DUG WILL BE PERFORMED TO EXPOSE

CONTRACTOR WILL ALSO EXCAVATE A 20' WIDE STRIP ALONG LOTS IO AND II AS WELL AS THAT

ACCORDANCE WITH THE RULES AND REGULATIONS OF THE PUTNAM COUNTY HEALTH DEPARTMENT.

DISTRICT HOMEOWNERS WHO WILL BE AFFECTED BY THE SHUT DOWN OF THE WATER SYSTEM BY

8 CUT WATERMAIN AT TIE IN POINTS. CONNECT NEW TO OLD WITH 45° BEND AND ASSOCIATED PIPING

2. THE CONTRACTOR WILL FIELD VERIFY THE EXISTING LOCATION OF THE WATER MAIN THAT IS

3. CONTACTOR WILL EXCAVATE OUT 20' WIDE STRIP ON LAND STRADDLING LOT 7 AND 8. THE

5. THE CONTRACTOR WILL PRESSIRE TEST THE NEW WATER MAIN AND DISSINFECT THE LINE IN

6. AFTER RECEIVING SATISFACTORY TEST RESULTS THE CONTRACTOR WILL NOTIFY THE WATER

7. THE WATER MAIN WILL BE TURNED OFF AT THE NEAREST VALVES ON BOTH SIDES OF THE

9. OPEN VALVE ON THE 'FEED' LINE AND OPEN FLUSHING HYDRANT IN SUBDIVISION ROAD.

POSTING SIGNS THREE DAYS IN ADVANCE OF THE CHOSEN DATE.

4. CONTACTOR WILL INSTALL THE BALANCE OF NEW WATER MAIN FROM THE SUBDIVISION ROAD TO

PROJECT NUMBER 8286 DRAWING NUMBER

SHEET <u>34</u> OF <u>34</u>



October 5, 2020

Mr. Craig Paeprer, Chairman Town of Carmel Planning Board 60 McAlpin Avenue Mahopac, NY 10541

Re:

Itzla 2 Lot Subdivision 9 Mechanic Street TM 55.14-1-6

Dear Chairman Paeprer and Members of the Board,

The above project last appeared before the Board on January 27, 2016, at which time a public hearing was held for the proposed two (2) lot subdivision located at 9 Mechanic Street. The public hearing was opened and closed without there being any public comment. I have attached the meeting minutes to refresh everyone's mind.

After the public hearing, the project went cold as several personal issues arose which the applicants had to address and which in essence placed this project on the back burner.

At this time the Itzlas are ready to move forward and complete what they started. We met with the Mr. Franzetti, Mr. Carnazza and Mr. Cleary to review and discuss the status of the project and the steps left to complete.

In response to the Town Engineer's January 25, 2016 comments, we offer the following:

I. General Comments

- 1. Attached is a copy of the letter we sent to the Carmel Fire Department on May 5, 2014 as requested.
- 2. We acknowledge that the Town Highway Department will need to issue a driveway permit prior to the issuance of a building permit.
- 3. The project entails disturbance of approximately 20,000 square feet in total. This is the total disturbance created on lots 1 and 2. A N.O.I. will be prepared and submitted to the Town Engineer's office along with the MS-4 form in order to file for stormwater coverage under N.Y.S.G.P.-0-20-001.
- 4. The N.Y.C.D.E.P. is not an involved agency as we do not trigger any thresholds that would make this fall under their review.
- 5. Noted
- 6. Noted

L1930

We would like to point out to the Board that the pool located on lot #1 was moved so that it now complies with the setbacks that are required.


Sincerely,

PUTNAM ENGINEERING, PLLC

Paul M. Lynch, P.E.

PML/rrm

Attachments



		DJOINERS	
LITTLE POND MANOR HOMEOWNERS LIBERTY MANAGEMENT OF NEW YORK CARLO CAPUTO LOCONTO REINGOLD CURCURUTO SPANGENBERGER VANDENBERG TYCHOSTUP QUATTRUCCI INGLESIAS WATSON RPK PRECISION HOMES, INC. JOHNSON	552-48 55.10-1-11 55.10-1-18 55.10-1-19 55.10-1-21 55.13-1-21 55.13-1-22 55.13-1-23 55.14-1-1 55.14-1-2 55.14-1-3 55.14-1-4 55.14-1-5.1 55.14-1-7.1	MILETTI PALLADINO KUSHNIR BOEHM & PULLEY FLAMIO RUBIN SPADARO STATE OF NEW YORK THE RETREAT AT CARMEL HOA, INC. ALBANO ZOTTOLA ROSSITER KLEIN & HEFFLER BRANDT GERTSEN CASEY	55.14-1-7.2 55.14-1-7.3 55.14-1-8.1 55.14-1-8.3 55.14-1-8.4 55.14-1-9 55.14-1-10 55.14-1-11.2 55.14-1-26.32 55.14-1-30 55.14-1-31 55.14-1-31 55.14-1-33 55.14-1-33

"<u>JURISDICTIONAL</u>" APPROVAL STATEMENT

Approved subject to the provision of a private (public) water supply and private (public) sewage treatment system for each habitable lot in accordance with the Putnam County Sanitary Code and as shown on the Realty Subdivision Plan as filed with the Putnam County Department of Health. Consent is hereby given for the filing of this map in the Office of the County Clerk in accordance with the provisions of Sections 1116 and 1117 of the Public Health.

BY:______ DATE:_____
Environmental Health Services

Expiration Date: _____

Putnam County Department of Health Realty Subdivision General Notes:

- 1. Unauthorized modifications made to this drawing after the date of Putnam County Health Department approval or any misinformation and/or erroneous data voids said approval.
- 2. Purchasers of lots to be furnished with a true copy of this plan as approved by the Putman County Department of Health together with a copy of the Certificate of Approval.
- 3. The conditions noted on the Putman County Department of Health Certificate of Approval are an integral part of this subdivision approval and compliance is required.
- 4. Approval is herewith granted for at total of 2 lots only, namely lots 1 and 2, and these lots only.
- 5. Proposed lots to be served by community water and sewer.
 Proposed sewer service to be provided by a connection to Carmel Sewer
 District #2 Proposed water service to be provided by a connection to
 Carmel Water District #2

Owner/ Applicant

9 Mechanic Street Carmel, N.Y. 10512

The undersigned owner of the property shown hereon states that they are familiar with this map, its contents and its legends and hereby consent to the filing of this map.


Paul H. Itzla: Owner Date:

9 Mechanic Street
Carmel, New York 10512

Elizebeth M. Pinto-Itzla: Owner Date:

Subdivision Notes:

- 1. Premises shown hereon located in the "R"-Residential Zone in the
- 2. Premises shown hereon known and designated as Map 55.14 Block 1 Lot 6 on the Town of Carmel Tax Maps.
- 3. Additional underground easements, utilities or structures, etc. other than those shown may be encountered.
- 4. Total Acreage: 65,170 Sq. Ft. or 1.496 Acres before taking.
- 5. Unauthorized alteration or addition to a survey map bearing a licensed Land Surveyor's seal is a violation of Section 7209, Subdivision 2 of the New York State Education Law.
- 6. Address of Subdivision: 9 Mechanic Street Carmel, New York 10512
- 7. Topographic information in accordance with "Final Subdivision Plat prepared for RPK Precision Homes" Two foot contour Interval.
- 8. All utilities shall be installed underground and in conformance with utility company and town requirements.
- 9. There are no areas proposed to be reserved for Recreation / Open space
- 10. Lands to be dedicated to the Town of Carmel for future road widening purposes (Realignment of Mechanic Street).
- 11. The location of the underground utilities shown hereon is not guaranteed as to accuracy or completeness and should be verified by the contractor before any excavation.



ZONING SCHEDULE

R-RESIDENTIAL	REQUIRED	LOT NO. 1	LOT NO. 2
MIN. LOT AREA (S.F.) MIN. LOT WIDTH (FT.) MIN. LOT DEPTH (FT.) MIN. SETBACK FRONT (FT.) SIDE (FT.) REAR (FT.) MAX HEIGHT OF BUILDING MAX LOT COVERAGE MINIMUM ROAD FRONTAGE	120,000 S.F. 200 FT. 200 FT. 40 FT. 25 FT. 40 FT. 35 FT. 15%	30,236 S.F.* 127 FT. * 235 FT. 54 FT. 25 FT. 59.8 FT. <35 FT. <15% 137.15'	34,180 S.F. * 113 FT. * 276 FT. 159 FT. 31 FT. 55 FT. <35 FT. <15% 50.31' *

* VARIANCES GRANTED BY THE TOWN OF CARMEL ZONING BOARD OF APPEALS ON OCTOBER 23, 2014

The Town of Carmel Zoning Board of Appeal granted the folowing variances.

Lot 1: Area variance granted of 89,764 square feet.

Lot 1: Minimum lot width variance granted for 73 feet.

Lot 2: Area variance granted of 85,820 square feet.

Lot 2: Minimum lot width variance granted for 87 feet.

Lot 2: Frontage variance granted for 49.73 feet.

Planning Board Approval

Approved by Resolution of the Planning Board of the Town of Carmel, New York on the ______ day of ______, 2016. Subject to all requirements and conditions of said Resoloution. Any change, erappoore, modification or revision of this plat, as approved, shall void this approved.

Signed This Day of	_ 20	Ву:
Chairman:		
Secretary:		

SHEET 1 OF 2 FINAL SUBDIVISION PLAT PREPARED FOR

PAUL H. ITZLA

and ELIZABETH M. PINTO-ITZLA

SITUATE IN THE
TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

SCALE: 1" = 30'



Tax Map 55.14 Block 1 Lot 6

TABLE OF AREAS

 LOT 1
 0.694 Acres

 LOT 2
 0.785 Acres

 R.O.W. TAKING
 0.017 Acres

 TOTAL
 1.496 Acres

We, H. Stanley Johnson and Company, Land Surveyors, P.C., the surveyors who made this map, do hereby certify that the survey upon which this map is based was completed December 11, 2015 and that this map was completed January 11, 2016 REVISED: October 1, 2019

Engineering by:

H. STANLEY JOHNSON AND COMPANY LAND SURVEYORS, P.C. 42 SMITH AVENUE P.O. BOX 93 MT. KISCO, N.Y. 10549 TEL. 914-241-3872

FAX. 914-241-0438


NEW YORK STATE LICENSED LAND SURVEYOR NO. 50037
ROBERT S. JOHNSON, P.L.S.


(AKA HORSEPOUND ROAD)

New York State Licensed Professional Engineer No. 067446
Putnam Engineering, PLLC
Engineers - Architects
4 Old Route 6
Brewster, New York 10509
Tel. 845-279-6789 Fax. 845-279-6769

PREPARED BY: JRJ CHECKED BY: RSJ

JOB NO. V99-011.01





LOCATION MAP

S C A L E: 1 " = 3 0 0 '

ADJOINERS:

TAX MAP # OWNER 552-48 LITTLE POND MANOR HOW		JOHNSON
55.10-1-11 LIBERTY MANAGEMENT OF 55.10-1-18 CARLO	55.14-1-7.2 55.14-1-7.3 55.14-1-8.1	PALLADINO
55.10-1-19 CAPUTO 55.10-1-20 LOCONDO 55.10-1-21 REINGOLD	55.14-1-8.2 55.14-1-8.3 55.14-1-8.4	
55.13–1–21 CURCURUTO 55.13–1–22 SPANGENBERGER		SPADARO STATE OF NEW YORK THE RETREAT AT CARMEL HOA, INC.
55.13-1-23 VANDENBERG	55.14-1-26.3 55.14-1-29	2ALBANO ZOTTOLA
55.14-1-1 TYCHOSTUP 55.14-1-2 QUATTRUCCI 55.14-1-3 INGLESIAS 55.14-1-4 WATSON 55.14-1-5.1 RPK PRECISION HOMES, II	55.14-1-32 55.14-1-33	KLEIN & HEFFLER BRANDT GERTSEN


ZONING	SCHEDU	JLE	
R - RESIDENTIAL	REQUIRED	LOT 1	LOT 2
MIN. LOT DIMENSIONS MIN. AREA (SQ. FT.) MIN. WIDTH (FT.) MIN. DEPTH (FT.)	120,000 200 200	30,236 * 127 * 235	34,180 * 113 * 276
MIN. YARD DIMENSIONS FRONT (FT.) SIDE (FT.) REAR (FT.)	40 25 40	54 26 60	159 31 55
MAX. HEIGHT OF BUILDING (FT.)	35	< 35	< 35
MAX. LOT COVERAGE (%)	15	< 15	< 15
MIN. ROAD FRONTAGE (FT.)	100	137.14	50.27 *

* - VARIANCES GRANTED OCTOBER 23, 2014 BY THE TOWN OF CARMEL ZONING BOARD OF APPEALS FOR THE FOLLOWING:

CODE REQUIRES		WILL EXIST	VARIANCE GRANTE
LOT 1 AREA -	120,000 S.F.	30,236 S.F.	89,674 S.F.
LOT 2 AREA -	120,000 S.F.	34,180 S.F.	85,820 S.F.
LOT 1 WIDTH -	200 FT.	127 FT.	73 FT.
LOT 2 WIDTH -	200 FT.	113 FT.	87 F1
LOT 2 FRONTAGE -	100 FT.	50.27 FT.	49.73 FT.

TABLE OF AREAS:

LOT #1	0.694 A
LOT #2	0.785 A
R.O.W. DEDICATION	0.017 AC
TOTAL SITE AREA	1.496 AC



SUBDIVISION PLAN NOTES:

- 1. BOUNDARY INFORMATION TAKEN FROM A PLAN ENTITLED "SKETCH SUBDIVISION PLAN" PREPARED FOR PAUL AND ELIZABETH ITZLA DATED SEPTEMBER 7, 2000 AS PREPARED BY PUTNAM ENGINEERING.
- 2. TOPOGRAPHIC INFORMATION TAKEN FROM "FINAL SUBDIVISION PLAT PREPARED FOR RPK PRECISION HOMES" PREPARED BY BAXTER LAND SURVEYING AND AS-BUILT DRAWINGS FOR CARMEL SEWER DISTRICT #2. TWO FOOT CONTOUR INTERVAL.
- OWNER/APPLICANT:

4. SITE DATA:

9 MECHANIC STREET CARMEL, NY 10512

PAUL ITZLA

- TAX MAP 55.14, BLOCK 1, LOT 6
- LOT AREA = 1.496 ACRES (65,170 S.F.) NUMBER OF PROPOSED LOTS = 2
- ZONING DISTRICT: R-RESIDENTIAL
- 6. PROPOSED LOT IS TO BE SERVED BY COMMUNITY WATER AND SEWER. PROPOSED SEWER SERVICE TO BE PROVIDED BY A CONNECTION TO CARMEL SEWER DISTRICT #2. PROPOSED WATER SERVICE TO BE PROVIDED BY A CONNECTION TO CARMEL WATER
- 7. ALL PROPOSED UTILITIES SHALL BE INSTALLED UNDERGROUND AND IN CONFORMANCE WITH UTILITY COMPANY AND TOWN REQUIREMENTS.
- 8. THERE ARE NO AREAS PROPOSED TO BE RESERVED FOR RECREATION / OPEN SPACE.
- 9. NO CHANGES ARE PROPOSED FOR THE EXISTING HOUSE AND DRIVEWAY SHOWN ON LOT #1, WITH THE EXCEPTION OF RELOCATING THE EXISTING POOL AND SHED.

OWNER/APPLICANT APPROVAL

THE UNDERSIGNED OWNER OF THE PROPERTY HEREON STATES THAT HE IS FAMILIAR WITH THESE DRAWINGS, THEIR CONTENTS AND THEIR LEGENDS AND HEREBY CONSENTS TO ALL THEIR SAID TERMS AND CONDITIONS AS STATED HEREON. FURTHER, THE OWNER CONSENTS TO THE FILING OF THIS MAP.

SIGNED THIS _____, 20___

PLANNING BOARD APPROVAL

APPROVAL HEREBY GRANTED THIS ____ DAY OF ____, 20__.
IF BUILDING PERMIT IS NOT ISSUED WITHIN 12 MONTHS FROM THE
ABOVE DATE, THE APPROVAL BECOMES NULL AND VOID.

TOWN OF CARMEL PLANNING BOARD

SIGNED THIS ____, DAY OF _____, 20____, BY

FINAL



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769

• PUTNAM ENGINEERING PLLC 2014

PURSUANT TO NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 7209 SUBDIVISION 2, "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE

ALTERATION."

NO. DATE DESCRIPTION DESCRIPTION 03 NOV 14 | ADDED SIGHT DISTANCE & ZBA APPROVAL NOTES 02 MAR 15 | REVISED PER TE & TP COMMENTS 16 JUN 15 REVISED PER TE MEMO 18 JAN 16 REVISED TO FINAL SUBDIVISION 05 DEC 19 REVISED PER TE COMMENTS

RESIDENTIAL SUBDIVISION PREPARED FOR:

ITZLA SUBDIVISION

9 MECHANIC STREET TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP No. 55.14, BLOCK 1, LOT 6



PML

RAWN BY

CHECKED BY


PML

SCALE

29 APR 14 PROJECT MANAGER SUBDIVISION PLAN

DRAWING NUMBER

SHEET ___1__ OF ___5__



MAINTENANCE PROGRAM:

- 1. THE PROJECT CONTRACTOR WILL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES WITHIN THE PROJECT PROPERTY.
- 2. PRIOR TO THE DETERMINATION OF A PROJECT CONTRACTOR THE PROJECT APPLICANT SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL TEMPORARY AND PERMANENT MEASURES.

TEMPORARY MEASURES

- A. <u>SILT FENCE:</u> SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN IT BECOMES 0.5 FEET DEEP AT THE FENCE. IT SHOULD ALSO BE INSPECTED WEEKLY AND PRIOR TO AND WITHIN 24 HOURS AFTER ALL FORECASTED STORM EVENTS. REPAIR SHALL BE PERFORMED AS NEEDED.
- B. CONSTRUCTION ENTRANCE: CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. VISUAL INSPECTION SHALL BE PERFORMED DAILY THROUGHOUT THE PROJECT CONSTRUCTION, TOP DRESSING WITH ADDITIONAL STONE OR ADDITIONAL LENGTH AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST
- C. ALL SEEDED AREAS SHALL BE FERTILIZED, RESEEDED AND MULCHED AS SPECIFIED IN THE "SLOPE STABILIZATION NOTES" TO MAINTAIN VIGOROUS, DENSE VEGETATIVE COVER.
- D. ALL SEDIMENT REMOVED FROM BEHIND SILT FENCING SHALL BE CONSIDERED UNSUITABLE AND SHALL BE DISPOSED OF OFF SITE BY CONTRACTOR.

A. <u>SEEDED AREAS:</u> ANNUALLY CHECK THAT VEGETATION AND GROUND COVER IS ADEQUATE. SEED BARE

STABILIZATION NOTES:

- 1. TEMPORARY VEGETATIVE COVER:
- A. SCARIFY COMPACTED SOIL AREAS.
- B. LIME AS REQUIRED TO pH 6.5.
- C. FERTILIZE WITH 10-10-10 AT THE RATE OF 200 LBS/AC.
- D. INCORPORATE AMENDMENTS INTO SOIL WITH DISC HARROW. E. SEED AS FOLLOWS:
- * SPRING/SUMMER/EARLY FALL PLANTING: ANNUAL RYEGRASS AND CEREAL OATS AT 30 LBS/AC
- * LATE FALL/EARLY WINTER PLANTING: AROOSTOOK WINTER RYE AT 100 LBS/AC
- F. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED. G. DURING WINTER CONSTRUCTION OR PERIODS OF WET WEATHER, TEMPORARY SLOPE STABILIZATION SHALL BE PROVIDED BY EITHER A ROLLED EROSION CONTROL PRODUCT OR A HEAVY MULCH LAYER SUITABLY ANCHORED. THE CONTRACTOR MUST RESEED THE AREA IN THE SPRING WITH THE
- H. DURING DRY WEATHER CONSTRUCTION, ALL SEEDED AREAS ARE TO BE ADEQUATELY WATERED TO ENSURE VEGETATED COVER.
- 2. PERMANENT VEGETATIVE COVER:
- A. GRADE TO FINISHED SLOPES.
- B. SCARIFY COMPACTED SOIL AREAS
- C. TOPSOIL WITH NOT LESS THAN FOUR (4) INCHES OF SUITABLE TOPSOIL MATERIAL. D. LIME AS REQUIRED TO pH 6.5.
- E. FERTILIZE WITH 10-6-4 AT THE RATE OF 200 LBS/AC. F. SEED AS FOLLOWS:
- TYPE I FOR USE ON MOWED AREAS:

<u>SEED</u> KENTUCKY BLUE GRASS CREEPING RED FESCUE RED TOP OR RYE GRASS 5

TYPE II FOR USE IN DETENTION BASINS AND ON NON-MOWED AREAS: USE "NEW ENGLAND EROSION CONSERVATION/WILDLIFE" SEED MIX (NEW ENGLAND WETLAND PLANTS, INC.) OR EQUIVALENT. SEEDS INCLUDED IN THE MIX ARE LISTED BELOW. APPLICATION RATE OF 25 LBS/ACRE.

SWITCHGRASS FRINGED BROMEGRASS NODDING BUR-MARIGOLD BIG BLUESTEM CANADA WILD RYE SHOWY TICK-TREFOIL GRASS LEAVED GOLDENROD FLAT-TOP ASTER LITTLE BLUESTEM PARTRIDGE PEA COMMON MILKWEED SILKY SMOOTH ASTER PENNSYLVANIA SMARTWEED WILD BLUE LUPINE

WILDFLOWER AREAS ARE TO BE MOWED ONCE PER YEAR IN LATE FALL.

G. MULCH SEED WITH 2 TONS OF STRAW PER ACRE. ANCHOR AS NEEDED. H. FOR DISTURBED AREAS WITH SLOPES GREATER THAN 1V: 3H OR WHEN SLOPES ARE EQUAL TO 1V: 3H AND THE HEIGHT OF THE SLOPE EXCEEDS 6 FEET, INSTEAD OF MULCHING, EROSION CONTROL BLANKET

ON-SITE POLLUTION CONTROL MEASURES:

POLLUTION PREVENTION MEASURES TO CONTROL LITTER, CONSTRUCTION CHEMICALS & CONSTRUCTION DEBRIS:

- 1. THE RECORD OWNER SHALL BE RESPONSIBLE FOR KEEPING THE SITE FREE OF LITTER AT ALL TIMES. DURING CONSTRUCTION ACTIVITIES THE OWNER MAY DESIGNATE A CONTRACTOR IN CHARGE AS A RESPONSIBLE PARTY.
- THE SITE SHALL BE INSPECTED AT THE END OF EACH WORKDAY AND TRASH, DEBRIS AND GARBAGE SHALL BE PICKED UP AND PLACED IN ON-SITE DUMPSTERS OR OTHERWISE REMOVED FROM THE SITE.
- 3. THERE SHALL BE RECEPTACLES PLACED ON THE SITE TO TEMPORARILY STORE GARBAGE, DEBRIS OR CONSTRUCTION WASTE MATERIALS. THE CONTAINER SHALL NOT BE USED TO TRANSFER ANY GARBAGE FROM ANY
- 4. THE CONTAINERS SHALL BE OF SUFFICIENT SIZE FOR THE CONSTRUCTION ACTIVITY. CONTAINERS SHALL BE EMPTIED BY AN APPROVED CARTER TO A PROPER FACILITY WHEN FULL. CONTAINERS SHALL BE COVERED TO PREVENT INFILTRATION OF RAIN AND WEATHER AND TO PREVENT WIND BORNE DEBRIS REMOVAL.
- 5. DEBRIS OR TRASH PILES ARE NOT PERMITTED. DEBRIS SHALL BE PLACED IN CONTAINERS. TEMPORARY PILES OF BRUSH OR STUMPS SHALL BE PROTECTED BY SILT FENCE SIMILAR TO TOPSOIL STOCKPILES.
- 6. A PORTABLE TOILET FACILITY SHALL BE PROVIDED FOR CONSTRUCTION WORKERS AND AN ADDITIONAL FACILITY FOR EVERY 10 ON-SITE WORKERS.
- 7. CONSTRUCTION VEHICLES SHALL BE SERVICED OFF-SITE AT A PROPER FACILITY. LEAKING OR ILL REPAIRED VEHICLES SHALL NOT BE LOCATED ON SITE. NO OIL CHANGES ARE PERMITTED ON SITE. FUELING OF VEHICLES ON-SITE SHALL BE CAREFULLY PERFORMED WITH AN APPROVED DISPENSER NOZZLE HOSE AND PUMP. SPILLS SHALL BE PROMPTLY REPORTED TO THE NYSDEC AND TOWN. OIL ABSORBANT PADS AND ROLLS SHALL BE USED TO TEMPORARILY CONTAIN ANY SPILLS.
- 8. CHEMICAL SOIL ADDITIVES OR HERBICIDES SHALL NOT BE USED ON SITE DURING CONSTRUCTION UNLESS APPROVED BY THE TOWN AND ARE IN COMPLIANCE WITH NYSDEC REGULATIONS.
- 9. PAINTS, CHEMICALS OR OTHER TOXIC SUBSTANCES SHALL NOT BE PLACED IN TRASH CONTAINERS. PAINTS, CHEMICALS OR TOXIC SUBSTANCES SHALL BE REMOVED FROM THE SITE BY AN APPROVED LICENSED CARTER.
- 10. THERE SHALL BE NO OPEN FIRES OR BARREL FIRES PERMITTED UNLESS APPROVED BY THE TOWN AND FIRE

ON-SITE STORAGE OF CONSTRUCTION AND WASTE MATERIALS:

- 1. CONSTRUCTION MATERIALS STORED ON-SITE ARE ANTICIPATED TO BE:
 - A. BRUSH OR TREE STUMPS
 - B. SOIL STOCKPILES C. CONSTRUCTION EQUIPMENT AND MACHINERY
- D. DUMPSTERS OR STORAGE CONTAINERS E. BUILDING CONSTRUCTION MATERIALS (MASONRY, WOOD, ETC.)
- 2. POLLUTION CONTROLS SHALL CONSIST OF:
- A. POLLUTION PREVENTION MEASURES DESCRIBED ABOVE B. COVERING OF EXPOSED PRODUCTS WHEN NOT IN USE C. IMPLEMENTATION OF TEMPORARY STOCKPILE PROTECTION MEASURES

EROSION CONTROL GENERAL NOTES:

- 1. TOWN OF CARMEL GENERAL NOTES:
- A. CONSTRUCTION EQUIPMENT SHALL NOT UNNECESSARILY CROSS LIVE STREAMS EXCEPT BY MEANS OF BRIDGES AND CULVERTS OR OTHER APPROVED METHODS.
- B. WHENEVER FEASIBLE, NATURAL VEGETATION SHOULD BE RETAINED AND PROTECTED.
- C. ONLY THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED AT ANY ONE TIME
- D. WHEN LAND IS EXPOSED DURING DEVELOPMENT, THE EXPOSURE SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME.
- E. THE PERMANENT FINAL VEGETATION AND STRUCTURES SHALL BE INSTALLED AS SOON AS PRACTICAL AND AS MAY BE DIRECTED BY THE ENGINEER.
- 2. ALL DISTURBED AREAS ARE CONSIDERED "STABILIZED" WHEN 80% OF UNIFORM, PERENNIAL VEGETATIVE COVER IS ACHIEVED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS MULCHES, EROSION CONTROL BLANKET, ETC.) HAVE BEEN PROPERLY EMPLOYED. NO WORK SHALL CONTINUE
- 3. AREAS UNDERGOING EARTHWORK, WHERE SOIL IS TO BE LEFT EXPOSED FOR MORE THAN FIFTEEN DAYS, SHALL BE STABILIZED WITH EITHER TEMPORARY OR PERMANENT VEGETATIVE COVER. TEMPORARY COVER SHALL BE USED WHEN THE PROJECT SCHEDULE DOES NOT COINCIDE WITH THE OPTIMUM PLANTING SEASON. IN GENERAL, OPTIMUM PLANTING TIMES FOR GRASSES ARE MARCH 15th TO MAY 31st AND SEPTEMBER 1st TO NOVEMBER 15th. DURING OPTIMUM PLANTING TIMES, PERMANENT VEGETATIVE COVER WILL BE INSTALLED. SEE SPECIFICATIONS FOR FURTHER DETAILS.
- 4. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL ARRANGE A PRE-CONSTRUCTION MEETING INVITING ALL INVOLVED REVIEW AGENCIES AND ENGINEERS OF RECORD PRIOR TO START OF CONSTRUCTION ACTIVITIES.
- 5. TEMPORARY MEASURES SHALL BE MAINTAINED BY PROJECT OWNER / DEVELOPER OR A DESIGNATED REPRESENTATIVE (SUCH AS THE GENERAL CONTRACTOR) DURING THE ENTIRE CONSTRUCTION PERIOD AND UNTIL RESPONSIBILITIES ARE TRANSFERRED TO THE INDIVIDUAL HOMEOWNER. LEGALLY BINDING DOCUMENTS SHALL BE INCLUDED WITH THE SALE OF THE PROPERTY.

DEVELOPER/OWNER: PAUL ITZLA 9 MECHANIC STREET CARMEL, NY 10512

BEFORE PRIOR DISTURBANCE IS STABILIZED.

- 6. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL RETAIN THE SERVICE OF QUALIFIED PERSONNEL (LICENSED PROFESSIONAL ENGINEER, CERTIFIED PROFESSIONAL IN EROSION & SEDIMENT CONTROL-CPESC, OR SOIL SCIENTIST) TO PERFORM SITE INSPECTIONS DURING THE CONSTRUCTION PERIOD AND FINAL SITE INSPECTION AT PROJECT COMPLETION.
- 7. THE CONTRACTOR SHALL MAKE AVAILABLE ON SITE, ALL EQUIPMENT, MATERIALS AND LABOR NECESSARY TO EFFECT EMERGENCY REPAIR AND REPLACEMENT OF THE EROSION CONTROL MEASURES.
- 8. SITE INSPECTIONS DURING CONSTRUCTION PERIOD SHALL BE PERFORMED AT LEAST EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. DURING WINTER, IF THE SOIL DISTURBANCE IS COMPLETELY SUSPENDED AND THE SITE IS PROPERLY STABILIZED, INSPECTION FREQUENCY MAY REDUCE, BUT SHALL MAINTAIN A MINIMUM OF MONTHLY INSPECTIONS IN ALL SITUATIONS (EVEN WHEN THERE IS TOTAL WINTER SHUTDOWN) DURING PERIODS OF REDUCED INSPECTION FREQUENCY, INSPECTIONS MUST STILL BE DONE AFTÉR EVERY STORM EVENT OF 0.5 INCHES OR GREATER. TO BE ALLOWED TO REDUCE INSPECTION FREQUENCIES, THE OPERATOR MUST COMPLETE STABILIZATION ACTIVITIES (PERIMETER CONTROLS, TRAPS, BARRIERS, ETC.) BEFORE PROPER INSTALLATION IS PRECLUDED BY SNOW COVER OR FROZEN GROUND. IF VEGETATION IS DESIRED, SEEDING, PLANTING, AND/OR SODDING MUST BE SCHEDULED TO AVOID DIE-OFF FROM FALL FROSTS AND ALLOW FOR PROPER GERMINATION/ESTABLISHMENT.
- 9. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED AREAS PERIODICALLY WITH WATER.
- 10. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL KEEP INSPECTION REPORTS AND LOGS AT THE SITE. A SUMMARY OF INSPECTION ACTIVITIES SHALL BE POSTED AT A PUBLICLY ACCESSIBLE AREA OF THE SITE ON A MONTHLY BASIS.
- 11. PRIOR TO START OF CONSTRUCTION ACTIVITIES, THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL CERTIFY ON THE INSPECTION LOG THAT A SWPPP WAS PROPERLY PREPARED FOR THE PROJECT AND CONFORMS TO ALL FEDERAL, STATE AND LOCAL EROSION & SEDIMENT CONTROL REQUIREMENTS.
- 12. THE PROJECT OWNER / DEVELOPER OR DESIGNATED REPRESENTATIVE SHALL PROVIDE A PHONE NUMBER TO THE DIRECTOR OF CODE ENFORCEMENT FOR USE IN EMERGENCY SITUATIONS.

SEQUENCE of CONSTRUCTION:

TOTAL AREA OF DISTURBANCE = 0.41 AC.

IN ORDER TO EFFECTIVELY CONTROL EROSION AND SEDIMENT. THE CONTRACTOR SHALL ADHERE TO THE LOCATION. MATERIALS, DETAILS AND PROCEDURES SHOWN ON THIS DRAWING, AND THE FOLLOWING SEQUENCE OF

- 1. SURVEY AND STAKE OUT PROPOSED HOUSE AND DRIVEWAY LOCATIONS. ESTABLISH LIMITS OF DISTURBANCE AND MARK IN THE FIELD. INSTALL CONSTRUCTION FENCE ALONG PERIMETER OF THE PROPOSED DISTURBANCE.
- 2. INSTALL SAFETY ORANGE CONSTRUCTION FENCING AROUND FUTURE UNDERGROUND INFILTRATION SYSTEM
- LOCATION WHERE SHOWN ON THE PLAN. 3. INSTALL STABILIZED CONSTRUCTION ENTRANCE WHERE SHOWN ON THE PLAN. VEHICLES SHALL BE INSPECTED
- 4. INSTALL SILT FENCE IMMEDIATELY DOWNGRADE OF AREAS OF PROPOSED DISTURBANCES AND WHERE INDICATED
- ON PLAN. ALL SILT FENCE TO BE INSTALLED PARALLEL TO CONTOURS. 5. CLEAR AND GRUB AREAS OF PROPOSED DISTURBANCE. STRIP TOPSOIL FROM THE PROPOSED DISTURBANCE
- AREAS AND STORE USABLE ORGANIC MATERIAL IN STOCKPILES WHERE SHOWN ON THE PLAN. PROVIDE STOCKPILE PROTECTION PER DETAIL #3/C-210.
- 7. ROUGH GRADE THE PROPOSED DRIVEWAY AND HOUSE LOCATIONS.

AND CLEANED, IF REQUIRED, PRIOR TO ENTERING ONTO MECHANIC STREET.

- 8. SEED AND STABILIZE DISTURBED AREAS PER "STABILIZATION NOTES" AND APPROPRIATE DETAILS WITHIN ONE (1) WEEK AFTER GRADING. NO FURTHER CONSTRUCTION IS ALLOWED BEFORE ALL DISTURBED AREAS ARE
- 9. CONSTRUCT THE HOUSE. INSTALL FOOTING DRAINS AND OUTFALL. CONNECT HOUSE TO ALL UTILITY LINES. TRENCHES TO BE BACKFILLED IMMEDIATELY UPON COMPLETION OF INSTALLATION OF PIPES AND CABLES. EXPOSED SOIL TO BE STABILIZED IMMEDIATELY AFTER BACKFILL
- 10. EXCAVATE FOR AND INSTALL ROOF LEADER DRAINS AND UNDERGROUND INFILTRATION SYSTEM AS SHOWN ON
- 11. PAVE DRIVEWAY.
- 12. COMPLETE FINSHED GRADING. SEED AND STABILIZE DISTURBED AREAS IMMEDIATELY AFTER GRADING.
- 13. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES TO INCLUDE SILT FENCING.
- 14. UPON COMPLETION OF ALL ABOVE ACTIVITIES AND SATISFACTORY ESTABLISHMENT OF VEGETATION ON ALL
- DISTURBED AREAS, CONTRACTOR TO PERFORM FINAL CLEANING OF THE PROJECT SITE.



4 OLD ROUTE 6, BREWSTER, NEW YORK 10509 (845) 279-6789 FAX (845) 279-6769 • PUTNAM ENGINEERING PLLC 2014

A VIOLATION OF THIS LAW FOR ANY PERSON UNLESS HE IS ACTING UNDER THE DIRECTION OF LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE ITEM HIS SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION."

03 NOV 14 ADDED SIGHT DISTANCE & ZBA APPROVAL NOTES 02 MAR 15 | REVISED PER TE & TP COMMENTS 16 JUN 15 REVISED PER TE MEMO 18 JAN 16 | REVISED TO FINAL SUBDIVISION 05 DEC 19 REVISED PER TE COMMENTS

ITZLA SUBDIVISION

9 MECHANIC STREET TOWN of CARMEL PUTNAM COUNTY, NEW YORK TAX MAP No. 55.14, BLOCK 1, LOT 6



PROJECT MANAGER RAWN BY CHECKED BY SCALE

29 APR 14

PML


PML


EROSION CONTROL and CONSTRUCTION PLAN


RAWING NUMBER C - 120

ROJECT NUMBER

SHEET <u>2</u> OF <u>5</u>









August 28, 2020

Mr. Craig Paeprer, Chairman Town of Carmel Planning Board 60 McAlpin Avenue Mahopac, NY 10541

Re:

Tompkins Recycling 60 Old Route 6 Carmel. NY T.M. #55.11-1-15

Dear Chairman Paeprer and Members of the Board:

Re approval of the site plan was granted to 70 Old Route 6, LLC for the Tompkins Recycling Project on July 17, 2019 for a period of one year. That approval has lapsed and we request that the Board consider an extension of the site plan approval.

The project has the following permits:

1. Town of Carmel – Site Plan Approval

- Expires 7/17/20

2. Town of Carmel Wetland Permit

- Expires 6/30/21

3. N.Y.S.D.E.C. – Solid Waste Management Permit – Expires 2/7/24

4. N.Y.S.D.E.C. – Freshwater Wetland Permit

- Expires 12/4/22

5. N.Y.C.D.E.P. – SWPPP Approval

- Expires 3/29/22

6. N.Y.S.D.E.C. - General General Permit G.P.-0-10-001 Permit #NYR10Q049. This permit is valid (open) until an N.O.T. is filed to close out the project.

FEMA has issued a conditional letter of map revision (7/24/14) based on fill which will remove the property from the flood plain once as-built topographic survey is submitted verifying compliance with the design drawings.

Sincerely,

PUTNAM ENGINEERING, PLLC

Paul M. Lynch, P.E.

PML/rrm

L1939