

ROBERT LAGA  
*Chairman*

ANTHONY DUSOVIC  
*Vice-Chair*

ROSE TROMBETTA  
*Secretary*

DAVID KLOTZLE  
*Wetland Inspector*

**TOWN OF CARMEL**  
**ENVIRONMENTAL CONSERVATION BOARD**



60 McAlpin Avenue  
Mahopac, New York 10541  
Tel. (845) 628-1500 - Ext. 190  
[www.ci.carmel.ny.us](http://www.ci.carmel.ny.us)

**BOARD MEMBERS**

Edward Barnett  
Marc Pekowsky  
Vincent Turano  
Nicholas Fannin  
John Starace

**ENVIRONMENTAL CONSERVATION BOARD AGENDA**

**JUNE 18, 2015 – 7:30 P.M.**

**SUBMISSION OF AN APPLICATION OR LETTER OF PERMISSION**

<b><u>APPLICANT</u></b>	<b><u>ADDRESS</u></b>	<b><u>TAX MAP #</u></b>	<b><u>COMMENTS</u></b>
1. Sheppard Estates, Inc. c/o Lou Panny	17 Pleasant Road	53.15-1-24	Construct 1 Family Home
2. Roa, Efraim & Aida	41 Averill Drive	64.16-1-33	Renovation of Existing Residence

**MISCELLANEOUS**

3. Minutes – 04/09/15 & 05/07/15

**JOHN KARELL, JR., P.E.**  
**121 CUSHMAN ROAD**  
**PATTERSON, NEW YORK, 12563**  
845-878-7894 FAX 845 878 4939  
[jack4911@yahoo.com](mailto:jack4911@yahoo.com)

---

**STORMWATER POLLUTION PREVENTION PLAN**  
**EROSION AND SEDIMENT CONTROL**  
**RAIN GARDEN DESIGN**

**LOUIS PANNY**  
**PLEASANT ROAD**  
**CARMEL (T)**

March 24, 2015, revised June 8, 2015



## **I. INTRODUCTION**

### **1.1. Project background**

The project site is vacant land located on Pleasant Road in the Town of Carmel, Putnam County, New York. The property is identified as tax map # 53.15-1-24. The site presently contains a small cottage.

#### **Site Description**

The site is 0.8 acres in size. The proposed house construction will result in an increase in impervious area of 3,300 square feet and 0.7 acres of total disturbance.

### **1.2. SWPPP Overview**

It is proposed to construct a single family house will be 1,350 square feet in size, An existing drilled well and new onsite subsurface sewage treatment system (SSTS) will provide water and sewer service to the proposed house. The purpose of this report is to address Storm Water Pollution Prevention and Management for the proposed improvements.

In accordance with Chapter 103 of the Code of the Town of Carmel entitled Stormwater Management and NYSDEC SPDES General Permit for Storm water Discharges from Construction Activities, General Permit GP-0-1 5-002 ,because the proposed disturbance for the project exceeds 5,000 square feet, coverage under the General Permit is required, a Notice of Intent (NOI) must be filed and a stormwater pollution prevention plan is required for this project. No SWPPP approval is required by the NYCDEP as the proposed project does not exceed the thresholds for requiring preparation of a SWPPP, nor proposes a regulated impervious surface within the limiting distance of a NYCDEP regulated watercourse or wetland.

Construction will begin immediately after receiving approval from the Town of Carmel Building Department of a SWPPP in accordance with the provisions of the Town Code.

## **II. EXISTING SITE CONDITIONS**

### **2.0 General**

The existing property contains a cottage which will be removed from the site. The property consists of lots 18 & 19 on a subdivision entitled, "Mahopac Falls Park, Section 4", approved August 12, 1939. The lot is located on the north side of the Pleasant Road.

Generally the topography on the site flows from north to south. The subject property is located in the Amawalk Reservoir Drainage Basin which is located in the NYC EOH Watershed.

### **2.1 Surface Water**

No lake, pond or other surface water exists on this property, except for a small wetland in the southeast corner of the property near the road and associated 100 foot buffer area.

## **2.2 Soils**

### **2.1.1. Hydrologic Soils/NRCS Web Soils Survey**

Soils on the property are classified by the United States Department of Agriculture Soil Conservation Service as Charlton Chatfield Complex, Hydrologic soil group B from the Web Soil Survey. Soil boundaries are shown on the Site Plan.

The pre developed site consists of woods and lawn in good condition.

### **2.1.2. Site Geotechnical Evaluation**

The deep test holes indicated a rock and groundwater at depths greater than 8 feet. Soil percolation tests indicated a percolation rate of 11-15 minutes per inch.

## **2.3. Groundwater**

Groundwater was not encountered to a depth of 8 feet.

## **2.4. Natural Resources**

Natural resources contained on the site is the woodland area. Some woodland will be removed however the extent of removal will be minimized.

## **2.5. New York State Register of Historic Places Assessment**

There are no Historic places on this property. See letter from SHPO.

## **2.6. Critical Habitat**

There are no critical habitats on this property.

## **2.7. Offsite Drainage**

No changes in drainage patterns are proposed.

## **2.8 Pre-construction Drainage Areas**

Most of the property drains to the area along Pleasant Road. No changes to pre construction runoff patterns will result from the construction of this project.

## **2.9 Potential sources of pollution**

Potential sources of pollution which may be reasonably expected to affect the quality of stormwater discharges.

- Sediment – all disturbed areas will be stabilized

### **III. Stormwater Management, Treatment and Conveyance**

A. Storm water treatment is not required. Management of stormwater from this property will be discharging driveway drainage to adjacent lawn areas and collection of roof drainage for discharge into rain gardens.

B. Stormwater conveyance for this project consists of sheet flow onto adjacent lawn areas and piping to stormwater structures and rain gardens.

### **IV. Stormwater Management**

Treatment of stormwater is not required, however to mitigate disturbance in the 100 foot wetland setback, rain gardens will be provided to treat roof drainage.

### **V. Erosion and Sediment Control**

#### **A. Temporary Erosion and Sediment Control Measures**

1. Temporary erosion and sediment control measures in the design of this project are silt fence. The driveway will be provided with a stabilized construction entrance. The contractor will be responsible for daily sediment cleanup on the driveway, if any. Silt fence are proposed to be installed along the downslope of all areas of disturbance as shown on the site plan, or as determined to be necessary during construction.

2. Runoff will be controlled within the project area. Bare soil areas, disturbed areas, will be seeded and mulched to control possible erosion and slow the velocity of runoff. Such activities shall be initiated by the end of the next business day and completed within 7 days from the date the current soil disturbance activity ceased.

3. Initial grading shall take place to install the sediment control measures. Soil stockpiles shall be stabilized away from any drainage structures or natural drainage paths. Once final grading has been achieved in any area that area shall be seeded and mulched and not redisturbed again.

4. Soil stockpiles must be protected with seeding and/or mulching as soon as possible but no longer than 7 days after ceasing activity. (see item # 2 above)

5. Measures must be in place prior to disturbance of a particular area in order to prevent

sediment from traveling off site. This is accomplished on this site by the proper installation of silt fence.

6. Dust shall be controlled to keep the amount of particles/sediment generation by construction activity to a minimum. This will be accomplished by seeding and mulching of disturbed areas and wetting areas prone to airborne dust.

7. All temporary and permanent sediment and erosion control measures must be checked on a weekly basis for functionality and stability. This includes the silt fencing and the stabilized construction entrance. Any bare spots in areas previously seeded will be reseeded and remulched as soon as necessary. In areas where soil erosion and sedimentation is found to be a problem and measures are not in place, appropriate measures must be installed as required by the supervising engineer.

8. Final grading shall match approximately the cut and fill lines as shown on the plans. This must be accomplished within 7 days of the end of the construction activity unless otherwise specified under the Town or DEC permits. (see item # 2 above)

9. Temporary measures shall not be removed until all disturbed areas protected by such measures are fully and properly stabilized.

10. Permanent non structural measures to remain in place are re-established areas of grass and landscaping within the non impervious areas.

11. Pollution prevention measures that will be utilized to prevent construction debris from becoming a pollutant source include:

...Litter control – refuse containers will be provided on the site for the deposition of any debris. The contractor shall police the site at the end of each day, collect litter and deposit litter in the refuse containers.

...Construction chemicals – all construction chemicals including but not limited to equipment fuels and oils and cleaning solvents shall be stored in appropriate containers and within a locked facility overnight.

Any spills of construction chemicals will be immediately cleaned up in accordance with appropriate procedures.

Any significant spill will be immediately reported to the NYSDEC pursuant to State Regulations, procedures and requirements.

...Construction debris will be collected and placed in roll off containers and disposed off site in at an appropriate disposal facility. (Part III.B.1.j)

## **B. Permanent Erosion Control Measures**

1. Permanent erosion control measures employed in the design of the project include stabilization of all disturbed areas with grass, pvc pipe, settling practices and rain gardens.

## VI. Inspection & Maintenance of Stormwater and Erosion Control Measures

### A. Inspection and Reporting Requirements

All erosion control measures are to be inspected weekly. In the case of a rain event, measures must be checked immediately after. Inspections shall be made by a qualified professional and reports will be kept on site in a dedicated mailbox labeled, "Storm water Documents".

### B. Responsibilities

The project contractor and/or subcontractors shall be responsible to install, construct, repair, replace, inspect and maintain the temporary erosion and sediment control practices included in the SWPPP. The project contractor/subcontractor shall be responsible for constructing the post construction storm water management practices included in the SWPPP. Such measures will be maintained by the project contractor/subcontractor during the entire construction period.

Permanent measures will be maintained by the owner of the property.  
(Part III.A.6) (Part IV)

Developer:

Louis Panny  
P.O. Box 658  
Mahopac, New York, 10541

Owner/ Applicant

Same as developer

The *owner or operator* shall have each of the contractors and subcontractors identify at least one person from their company that will be responsible for implementation of the SWPPP. This person shall be known as the *trained contractor*. The *owner or operator* shall ensure that at least one *trained contractor* is on site on a daily basis when soil disturbance activities are being performed.

The *owner or operator* shall have each of the contractors and subcontractors identified above sign a copy of the following certification statement below before they commence any *construction activity*:

"I hereby certify that I understand and agree to comply with the terms and

conditions of the SWPPP and agree to implement any corrective actions identified by the *qualified inspector* during a site inspection. I also understand that the *owner or operator* must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for storm water discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings. "

In addition to providing the certification statement above, the certification page must also identify the specific elements of the SWPPP that each contractor and subcontractor will be responsible for and include the name and title of the person providing the signature; the name and title of the *trained contractor* responsible for SWPPP implementation; the name, address and telephone number of the contracting firm; the address (or other identifying description) of the site; and the date the certification statement is signed.

The *owner or operator* shall attach the certification statement(s) to the copy of the SWPPP that is maintained at the construction site. If new or additional contractors are hired to implement measures identified in the SWPPP after construction has commenced, they must also sign the certification statement and provide the information listed above.

## **C. Temporary Measures**

### **1. Construction Entrance(s)**

The construction entrances shall be maintained in a condition which will prevent tracking or flowing of sediment onto the public right of way. This will require, sweeping and washing the driveway surfaces, periodic top dressing with addition stone or additional length as conditions demand based on daily inspections and repair and/or clean out of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights of way must be immediately removed.

### **2. Silt Fence**

Silt fence is proposed down gradient from all disturbed areas proposed on the site. Silt fence is used to collect the transported sediment load due to runoff and to slow said runoff, in an effort to prevent erosion. The silt fence is a temporary barrier of geotextile fabric supported by fence posts at a 10 foot maximum interval.



Sediments shall be removed from behind the fence when it becomes 0.5 feet deep at the fence. It should also be inspected regularly, at least once a week and repaired as needed to maintain a barrier.

#### **D. Permanent Measures**

##### **1. Permanent vegetation**

All grassed areas shall be maintained to provide a vegetative cover to hold soils in place.

##### **2. HDPE Pipe**

Maintenance need is fairly low for HDPE pipe. Inspection shall be carried out after major storm events or once every year. If pipe is clogged or damaged, repair must be made immediately.

##### **3. Rain Gardens**

Invasive species shall be removed from the rain gardens as necessary but at least once per year in the early summer.

##### **4. Pretreatment Units**

The pretreatment unit shall be inspected once per year for accumulated solids. Accumulated solids shall be removed when the inspection indicates one half of the tank volume has been reached.

#### **VII. General Requirements for Owners or Operators with Permit Coverage**

A. The *owner or operator* shall maintain a copy of the General Permit (GP-0-15-002), NOI, *NOI Acknowledgment Letter*, SWPPP, MS4 SWPPP Acceptance form and inspection reports at the construction site until all disturbed areas have achieved *final stabilization* and the NOT has been submitted to the Department.

The documents must be maintained in a secure location, such as a job trailer, on-site construction office, or mailbox with lock. The secure location must be accessible during normal business hours to an individual performing a compliance inspection. (Part II.B.C.2)

B. For *construction activities* that are subject to the requirements of a *regulated, traditional land use control MS4*, the *owner or operator* shall notify the *MS4* in writing of any planned amendments or modifications to the post-construction stormwater management practice component of the SWPPP required by Part III.A. 4. and 5. of this permit. Unless otherwise notified by the *MS4*, the *owner or operator* shall have the SWPPP amendments or modifications reviewed and accepted by the *MS4* prior to commencing construction of the post-construction

stormwater management practice. (Part II.C.5)

C. For *construction activities* that are subject to the requirements of a *regulated, traditional land use control MS4* and meet subdivision 2a. or 2b. of this Part, the *owner or operator* shall also have the MS4 sign the “MS4 Acceptance” statement on the NOT. The *owner or operator* shall have the principal executive officer, ranking elected official, or duly authorized representative from the *regulated, traditional land use control MS4*, sign the “MS4 Acceptance” statement. The MS4 official, by signing this statement, has determined that it is acceptable for the *owner or operator* to submit the NOT in accordance with the requirements of this Part. The MS4 can make this determination by performing a final site inspection themselves or by accepting the *qualified inspector’s* final site inspection certification(s) required in Part V.3. (Part V.A.4)

D. In accordance with the requirements of the Town of Carmel Town Code, within 10 days after the installation of all erosion control plan measures, the applicant shall submit to the Building Inspector a letter from the qualified professional who designed the plan for George Sica stating that all erosion control measures have been constructed and installed in compliance with the approved plans.

E. Various certifications are required to be completed as follows:

1. SWPPP Modification Summary Sheet
2. SWPPP Preparer Certification
3. Contractor and Sub-contractor Certification

These documents are appended to this SWPPP.

### **VIII. Conclusions**

In conclusion, the proposed project shall not result in any negative impact to existing hydrologic condition at the vicinity of the property and proposed storm water management practices conforms to NYSDEC Storm water Management Design Manual and GP-0-15-002. In addition, the design of all storm water management practices meets the requirements of the Town of Carmel.

**LOU PANNY STORMWATER POLLUTION PREVENTION PLAN  
SEQUENCE OF CONSTRUCTION**

The following are sequence and methods of construction for the construction of a house on property owned by Lou Panny, Pleasant Road, Carmel (T), Putnam County, New York. Erosion and sediment control measures are incorporated into the construction program. Construction of this project will be in one phase.

Proposed erosion and sediment control methods are found on the Site Plan. The erosion controls are designed in accordance with the State of New York, "Guidelines for Urban Erosion and Sediment Control". The project is expected to start in the Summer of 2015 and continue over a 6 month period.

**A. General Construction Notes**

1. The site shall be disturbed only when and where necessary. Only the smallest practical area of land shall be exposed at any one time during development. When land is exposed, the exposure shall be kept to the shortest practical period of time by immediate stabilization per the stabilization notes, unless specified otherwise. All disturbed areas that are seeded with appropriate seed mixture and procedure are considered stabilized when 80% of the vegetation is achieved.
2. Where ever feasible, natural vegetation shall be retained and protected.
3. The contractor shall inspect all erosion and sediment control devices during all storm events, prior to weekends and prior to all forecasted storm events.
4. The Contractor shall grade and provide stabilization of newly graded and disturbed areas per item 11 of this sequence.

**B. Construction Sequence**

1. Install all erosion control measures.
2. Perform site grading for the house, septic system and driveway.
3. Begin house construction.
4. Install proposed utilities including rain gardens and associated structures, septic system, water lines and underground utilities.
5. Topsoil, seed and mulch all disturbed areas in accordance with the stabilization notes.
6. Remove all temporary erosion control measures. Restore/backfill to final grade and provide stabilization is necessary.
7. Contractor to perform final site clean up and dispose of all debris properly.

**8. STABILIZATION NOTES**

- A. Grade to finished slopes
- B. Soils shall be scarified.
- C. Topsoil with not less than four inches of suitable topsoil material
- D. Seed as follows:

Spring/Fall Planting: Tall fescue	100
Kobe Gespedza	10
Bahi Grass	25
Rye Grass	40

Temporary Summer Planting	
German Millet	40

All above units in lbs/sc

**JOHN KARELL, JR., P.E.**  
**121 CUSHMAN ROAD**  
**PATTERSON, NEW YORK, 12563**  
845-878-7894 FAX 845 878 4939  
jack4911@yahoo.com

---

## **DRAINAGE STUDY**

**June 8, 2015**

**Louis Panny, Pleasant Road, Hamlet of Mahopac, Carmel (T)**

### **DESIGN PARAMETERS**

Proposed Impervious area roof = 1,350 square feet  
Design Storm = 1.2 inches  
Soils CrC Charlton Chatfield

### **WATER QUALITY VOLUME**

$$\begin{aligned} \text{WQV} &= (P)(RV)(A)/12 \\ P &= 1.2 \quad RV = 0.95 \quad A = 1,350 \text{ SF} \\ \text{WQV} &= 1.2(0.95)(1,350)/12 \\ &= 128.25 \text{ cf} \end{aligned}$$

$$\text{Pretreatment Volume} = 25\% (\text{WQV}) = .25 (128) = 32 \text{ CF}$$

Use a concrete structure 4 ft x 3.5 ft x 4.5 ft, 63 cubic feet, gross capacity. Capacity 12 inches below top is 49 CF

## PROPOSED RAIN GARDEN DESIGN

It is proposed to treat the storm water from all impervious surfaces in two (2) rain gardens. The design of the rain gardens are as follows:

Total Impervious area = 1,350 sf. Use 2 rain gardens each designed at 700 sf

Treatment area; 1,350 square feet at 100% impervious

Rain garden section: 12" soil (0.2 porosity), 6" drainage layer (0.4 porosity, 8" ponding depth 6"

Design storm: 1.2" of rainfall

Proposed Rain Garden Area : 98 square feet

RV = 0.95

$WQV = (\text{Rainfall in inches})(0.05 + (0.009)(\% \text{ impervious}))(\text{treatment area})/12$

$WQV = (1.2)(0.95)(700)/12$

$WQV = 66.5 \text{ cf}$

$\text{Soil Volume} = (98 \text{ sq ft})(1 \text{ ft})(0.20) = 19.6 \text{ cf}$

$\text{Drainage Layer Volume} = (98 \text{ sq ft})(0.5 \text{ ft})(0.40) = 19.6 \text{ cf}$


$\text{Ponding volume} = (98 \text{ sq ft})(0.5 \text{ ft}) = 49 \text{ cf}$

Total Treatment Volume =  $19.6 + 19.6 + 49 = 88 \text{ cf} > 66.5 \text{ cf}$

**Two (2) rain gardens at 14 x 7 ft (98 sf) will be provided to treat the roof impervious areas. A settling basin, catch basin, will be provided before the rain gardens. The flow outleting the catch basin will be split in two in a distribution box, half to each rain garden. All underground piping will be 6" pvc.**

# NOTICE OF INTENT

## New York State Department of Environmental Conservation



### Division of Water

625 Broadway, 4th Floor

Albany, New York 12233-3505

NYR

□□□□□□

(for DEC use only)

Stormwater Discharges Associated with Construction Activity Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-10-001  
All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

### -IMPORTANT-

### RETURN THIS FORM TO THE ADDRESS ABOVE

OWNER/OPERATOR MUST SIGN FORM

#### Owner/Operator Information

Owner/Operator (Company Name/Private Owner Name/Municipality Name)

L O U I S P A N N Y

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

P A N N Y

Owner/Operator Contact Person First Name

L O U I S

Owner/Operator Mailing Address

P O B O X 6 5 8

City

M A H O P A C

State

N Y

Zip

1 0 5 4 1 -

Phone (Owner/Operator)

0 1 4 - 4 9 0 - 4 4 1 0

Fax (Owner/Operator)

- - -

Email (Owner/Operator)

FED TAX ID

-

(not required for individuals)

Project Site Information

Project/Site Name

P A N N Y   H O U S E   C O N S T R U C T I O N

Street Address (NOT P.O. BOX)

1 7   P L E A S A N T   R O A D

Side of Street

North    South    East    West

City/Town/Village (THAT ISSUES BUILDING PERMIT)

C A R M E L

State

N Y

Zip

1 0 5 1 2 -

County

P U T N A M

DEC Region

3

Name of Nearest Cross Street

H I L L S I D E   R O A D

Distance to Nearest Cross Street (Feet)

5 0 0

Project In Relation to Cross Street

North    South    East    West

Tax Map Numbers

Section-Block-Parcel

5 3 . 1 5 - 1 - 2 4

Tax Map Numbers

1. Provide the Geographic Coordinates for the project site in NYTM Units. To do this you **must** go to the NYSDEC Stormwater Interactive Map on the DEC website at:

[www.dec.ny.gov/imsmaps/stormwater/viewer.htm](http://www.dec.ny.gov/imsmaps/stormwater/viewer.htm)

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located your project site, go to the tool boxes on the top and choose "i"(identify). Then click on the center of your site and a new window containing the X, Y coordinates in UTM will pop up. Transcribe these coordinates into the boxes below. For problems with the interactive map use the help function.

X Coordinates (Easting)

6 0 4 7 6 7

Y Coordinates (Northing)

4 5 8 4 7 9 2

2. What is the nature of this construction project?

New Construction

Redevelopment with increase in impervious area

Redevelopment with no increase in impervious area







15. Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)?  Yes  No  Unknown

16. What is the name of the municipality/entity that owns the separate storm sewer system?

T O W N O F C A R M E L

17. Does any runoff from the site enter a sewer classified as a Combined Sewer?  Yes  No  Unknown

18. Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law?  Yes  No

19. Is this property owned by a state authority, state agency, federal government or local government?  Yes  No

20. Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.)  Yes  No

21. Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?  Yes  No

22. Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)?  Yes  No  
If No, skip questions 23 and 27-39.

23. Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual?  Yes  No





Post-construction Stormwater Management Practice (SMP) Requirements

**Important:** Completion of Questions 27-39 is not required  
if response to Question 22 is No.

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

- Preservation of Undisturbed Areas
- Preservation of Buffers
- Reduction of Clearing and Grading
- Locating Development in Less Sensitive Areas
- Roadway Reduction
- Sidewalk Reduction
- Driveway Reduction
- Cul-de-sac Reduction
- Building Footprint Reduction
- Parking Reduction

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

- All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
- Compacted areas were considered as impervious cover when calculating the **WQv Required**, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

**Total WQv Required**

.     acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required (#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

**Note:** Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

Table 1 - Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

	<u>Total Contributing Area (acres)</u>		<u>Total Contributing Impervious Area (acres)</u>	
<u>RR Techniques (Area Reduction)</u>				
<input type="checkbox"/> Conservation of Natural Areas (RR-1) ...	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Sheetflow to Riparian Buffers/Filters Strips (RR-2) .....	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Tree Planting/Tree Pit (RR-3) .....	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Disconnection of Rooftop Runoff (RR-4) ..	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<u>RR Techniques (Volume Reduction)</u>				
<input type="checkbox"/> Vegetated Swale (RR-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Rain Garden (RR-6) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Stormwater Planter (RR-7) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Rain Barrel/Cistern (RR-8) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Porous Pavement (RR-9) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Green Roof (RR-10) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs with RRv Capacity</u>				
<input type="checkbox"/> Infiltration Trench (I-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Infiltration Basin (I-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Dry Well (I-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Underground Infiltration System (I-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Bioretention (F-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Dry Swale (O-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs</u>				
<input type="checkbox"/> Micropool Extended Detention (P-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Pond (P-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Extended Detention (P-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Multiple Pond System (P-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pocket Pond (P-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Surface Sand Filter (F-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Underground Sand Filter (F-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Perimeter Sand Filter (F-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Organic Filter (F-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Shallow Wetland (W-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Extended Detention Wetland (W-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pond/Wetland System (W-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pocket Wetland (W-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Swale (O-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>

**Table 2 - Alternative SMPs  
(DO NOT INCLUDE PRACTICES BEING  
USED FOR PRETREATMENT ONLY)**

<u>Alternative SMP</u>	<u>Total Contributing Impervious Area (acres)</u>	
<input type="radio"/> Hydrodynamic .....		
<input type="radio"/> Wet Vault .....		
<input type="radio"/> Media Filter .....		
<input type="radio"/> Other <span style="border: 1px solid black; display: inline-block; width: 150px; height: 1.2em; vertical-align: middle;"></span> .....		

Provide the name and manufacturer of the Alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment.

Name

Manufacturer

**Note:** Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.

30. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and Standard SMPs with RRv capacity identified in question 29.

Total RRv provided

.   acre-feet

31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28).

Yes  No

If Yes, go to question 36.  
If No, go to question 32.

32. Provide the Minimum RRv required based on HSG.  
[Minimum RRv Required = (P)(0.95)(Ai)/12, Ai=(S)(Aic)]

Minimum RRv Required

.   acre-feet

32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)?

Yes  No

If Yes, go to question 33.

**Note:** Use the space provided in question #39 to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). A detailed evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP.

If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.









### Owner/Operator Certification

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

Print First Name

L	O	U	I	S															
---	---	---	---	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

MI

--

Print Last Name

P	A	N	N	Y															
---	---	---	---	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Owner/Operator Signature

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Date

0	6	/	0	8	/	2	0	1	5
---	---	---	---	---	---	---	---	---	---

617.20  
Appendix B  
Short Environmental Assessment Form

**Instructions for Completing**

**Part 1 - Project Information.** The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

<b>Part 1 - Project and Sponsor Information</b>			
Name of Action or Project: Pleasant Road House			
Project Location (describe, and attach a location map): Pleasant Road, Mahopac Hamlet of Carmel New York			
Brief Description of Proposed Action: Demolition of existing single family house and construction of a new single family house, driveway and septic system.			
Name of Applicant or Sponsor: Louis Panny		Telephone: 914 490 4411sdf	
		E-Mail:	
Address: P.O. Box 658			
City/PO: Mahopac		State: New York	Zip Code: 10541
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.			NO <input checked="" type="checkbox"/>
2. Does the proposed action require a permit, approval or funding from any other governmental Agency? If Yes, list agency(s) name and permit or approval:			YES <input type="checkbox"/>
3.a. Total acreage of the site of the proposed action? _____ 0.8 acres			
b. Total acreage to be physically disturbed? _____ 0.6 acres			
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor? _____ 0.8 acres			
4. Check all land uses that occur on, adjoining and near the proposed action. <input type="checkbox"/> Urban <input type="checkbox"/> Rural (non-agriculture) <input type="checkbox"/> Industrial <input type="checkbox"/> Commercial <input checked="" type="checkbox"/> Residential (suburban) <input type="checkbox"/> Forest <input type="checkbox"/> Agriculture <input type="checkbox"/> Aquatic <input type="checkbox"/> Other (specify): _____ <input type="checkbox"/> Parkland			




18. Does the proposed action include construction or other activities that result in the impoundment of water or other liquids (e.g. retention pond, waste lagoon, dam)? If Yes, explain purpose and size: _____	NO	YES
_____	<input checked="" type="checkbox"/>	<input type="checkbox"/>
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility? If Yes, describe: _____	NO	YES
_____	<input checked="" type="checkbox"/>	<input type="checkbox"/>
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste? If Yes, describe: _____	NO	YES
_____	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<b>I AFFIRM THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BEST OF MY KNOWLEDGE</b>		
Applicant/sponsor name: <u>Louis Panny</u>	Date: <u>October 22, 2014</u>	
Signature: _____		

**Part 2 - Impact Assessment. The Lead Agency is responsible for the completion of Part 2.** Answer all of the following questions in Part 2 using the information contained in Part 1 and other materials submitted by the project sponsor or otherwise available to the reviewer. When answering the questions the reviewer should be guided by the concept "Have my responses been reasonable considering the scale and context of the proposed action?"

	No, or small impact may occur	Moderate to large impact may occur
1. Will the proposed action create a material conflict with an adopted land use plan or zoning regulations?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Will the proposed action result in a change in the use or intensity of use of land?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. Will the proposed action impair the character or quality of the existing community?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4. Will the proposed action have an impact on the environmental characteristics that caused the establishment of a Critical Environmental Area (CEA)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. Will the proposed action result in an adverse change in the existing level of traffic or affect existing infrastructure for mass transit, biking or walkway?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6. Will the proposed action cause an increase in the use of energy and it fails to incorporate reasonably available energy conservation or renewable energy opportunities?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7. Will the proposed action impact existing:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
a. public / private water supplies?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. public / private wastewater treatment utilities?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
8. Will the proposed action impair the character or quality of important historic, archaeological, architectural or aesthetic resources?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. Will the proposed action result in an adverse change to natural resources (e.g., wetlands, waterbodies, groundwater, air quality, flora and fauna)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>

	No, or small impact may occur	Moderate to large impact may occur
10. Will the proposed action result in an increase in the potential for erosion, flooding or drainage problems?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
11. Will the proposed action create a hazard to environmental resources or human health?	<input checked="" type="checkbox"/>	<input type="checkbox"/>

**Part 3 - Determination of significance. The Lead Agency is responsible for the completion of Part 3.** For every question in Part 2 that was answered "moderate to large impact may occur", or if there is a need to explain why a particular element of the proposed action may or will not result in a significant adverse environmental impact, please complete Part 3. Part 3 should, in sufficient detail, identify the impact, including any measures or design elements that have been included by the project sponsor to avoid or reduce impacts. Part 3 should also explain how the lead agency determined that the impact may or will not be significant. Each potential impact should be assessed considering its setting, probability of occurring, duration, irreversibility, geographic scope and magnitude. Also consider the potential for short-term, long-term and cumulative impacts.

<input type="checkbox"/>	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action may result in one or more potentially large or significant adverse impacts and an environmental impact statement is required.
<input checked="" type="checkbox"/>	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action will not result in any significant adverse environmental impacts.
_____	October 22, 2014
Name of Lead Agency	Date
_____	_____
Print or Type Name of Responsible Officer in Lead Agency	Title of Responsible Officer
_____	
Signature of Responsible Officer in Lead Agency	Signature of Preparer (if different from Responsible Officer)



**PRINT**

DESIGNED BY: JOHN KAREL, JR., P.E. 121 CUSHMAN ROAD, PATERSON, NEW YORK

DATE: OCTOBER 11, 2014





SCALE: 1" = 20'

SHEET NO. 1 OF 1



**NOTES:**

1. THE PROPOSED DRIVE SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
2. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
3. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
4. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
5. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
6. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
7. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
8. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
9. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.
10. THE DRIVEWAY SHALL BE CONSTRUCTED TO A FINISH GRADE OF 2% SLOPE TO THE ADJACENT DRIVEWAY.



**PROF. OF CAMEL ROAD INTEREST:**

JOHN KAREL, JR., P.E.

121 CUSHMAN ROAD  
PATERSON, NEW YORK

LOUIS PANNY  
PLEASANT ROAD  
TOWN OF CAMEL

INTEGRATED PLOT PLAN

DATE: OCTOBER 11, 2014

SCALE: 1" = 20'

SHEET NO. 1 OF 1



## NATHANIEL J. HOLT, PE

---

June 11, 2015

dan@holtengineering.net

Town of Carmel  
Environmental Conservation Board  
60 McAlpin Avenue  
Mahopac, New York 10541

Attn: Robert Laga, Chairman

RE: Roa Residence  
41 Averill Drive

Dear Chairman Laga and Members of the Environmental Conservation Board:

Subsequent to the last meeting of your Board, the Roa's have reconsidered their plans for the home on Averill Drive which resulted in substantial changes; all of which have reduced the scope of the project while reducing the amount of disturbance within the regulated area. As you will note, the in-ground pool and patio has been eliminated from the plan. Another significant change in the plans had to do with a decrease in the building footprint; specifically the garage width has been reduced by approximately two feet.

From a stormwater mitigation stand point, these changes also reduced the impervious surfaces, which enabled us to replace the proposed infiltration system with a rain garden. Essentially, the only disturbance within the regulated area is the rain garden and the pipes leading to it.

During the meeting the Board also cited several items that it wanted addressed with the next submission.

- Construction access to the rear of the house has now been improved through the reduction in the width of the garage. The plan now reflects the construction access (with a stabilized entrance) along the northerly side of the house. The phasing of the work will be such that the steps leading from the driveway to the back of the home will be completed after the need to access the rear of the residence with heavy equipment has been eliminated.
- Again, due to the referenced changes, the extent of earthwork has also been greatly reduced. Any demolition material associated with the residence will be placed in a roll-off bin located in the front of the house. It is estimated that the bulk excavation (24 cubic yards) associated with the house will be for the construction of footings and foundations. Similarly, the excavation associated with the rain garden is estimated to be 6 cubic yards.

Approximately 12 cubic yards will be backfilled against the foundation, leaving approximately 18 cubic yards of soil to be hauled away. Due to site limitations, under no circumstance is it expected that the excess fill will be kept on site for a

period in excess of one week.

The only place where the stripping of topsoil is anticipated is the area of the rain garden and along the route of the drainage pipes leading to it. This topsoil will be stored on site and re-spread as part of the stabilization of disturbed areas. As the volume of stripped topsoil is expected to be small (5 cubic yards) it is not anticipated that any of this material will be trucked off-site.

A soil stock pile has been indicated on the plans for those times when the material will be stored until hauled away or re-used.

- As-built information for septic systems is generally limited to the location of the absorption fields and septic tank. In situations such as this one, the contractor is required to make investigative excavations (by hand) to locate the limits of the system and take the necessary steps to protect it. The plans have been so noted to explain these requirements to the contractor. It is important to note that while under construction the house will be vacant and therefore the septic system will be dormant.

Attached, please find a copy of the revised Site Plans for your consideration.

Very truly yours

Nathaniel J. Holt, PE  
Holt Engineering & Consulting, PA


encl

cc: Michael Piccirillo



**NOTES**

1. EXISTING CONDITIONS MUST BE PROPERLY INSTALLED, MAINTAINED AND PROTECTED.
2. CONSTRUCTION OPERATIONS MUST BE PROPERLY MAINTAINED SO THAT NO ADJACENT AREAS MUST BE STABILIZED AS SOON AS LAND ALTERATIONS ARE COMPLETED.
3. ALL CONSTRUCTION OPERATIONS MUST BE CONDUCTED IN ACCORDANCE WITH THE CITY OF MAHOPAC ZONING ORDINANCES AND ANY APPLICABLE ORDINANCES.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE CITY OF MAHOPAC.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.
19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE STATE OF NEW YORK.
20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE FEDERAL GOVERNMENT.




**ROA RESIDENCE RENOVATIONS**  
 41 AVERILL ROAD MAHOPAC, N.Y. 10561

**SITE PLAN**

**NATHANIEL J. HOLT, P.E.**  
 592 ROUTE 22  
 PAWLING, NEW YORK 12564  
 (914) 780-1800



**SHEET: 2**  
**6**



- NOTES**
1. EXISTING CONDITIONS AND MATERIALS TO BE PROTECTED, MAINTAINED AND REPAIRS TO BE MADE AS NECESSARY.
  2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RESIDENTIAL CODE BOOK (IRC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 90A AND 90B.
  3. EXISTING FOUNDATIONS SHALL BE REINFORCED AND STABILIZED AS SOON AS LAID OUT.
  4. ANY UNDERGROUND UTILITIES SHALL BE PROTECTED AND MAINTAINED.
  5. ALL MATERIALS TO BE REMOVED SHALL BE PROPERLY DISPOSED OF.
  6. ALL CONSTRUCTION SHALL BE COMPLETED WITHIN THE SPECIFIED TIME FRAME.
  7. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RESIDENTIAL CODE BOOK (IRC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 90A AND 90B.
  8. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RESIDENTIAL CODE BOOK (IRC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 90A AND 90B.
  9. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RESIDENTIAL CODE BOOK (IRC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 90A AND 90B.
  10. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RESIDENTIAL CODE BOOK (IRC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 90A AND 90B.

COMPILED BY: JOHN J. HOLT, P.E.  
 DRAWN BY: JOHN J. HOLT, P.E.  
 CHECKED BY: JOHN J. HOLT, P.E.  
 DATE: MAY 10, 2015



