

CRAIG PAEPRER
Chairman

ANTHONY GIANNICO
Vice Chairman

BOARD MEMBERS
RAYMOND COTE
ROBERT FRENKEL
VICTORIA CAUSA
JOHN NUCULOVIC
NICHOLAS BALZANO

TOWN OF CARMEL
PLANNING BOARD



60 McAlpin Avenue
Mahopac, New York 10541
Tel. (845) 628-1500 – Ext.190
www.ci.carmel.ny.us

MICHAEL CARNAZZA
*Director of Code
Enforcement*

RICHARD FRANZETTI,
P.E., BCEE
Town Engineer

PATRICK CLEARY,
AICP, CEP, PP, LEED AP
Town Planner

PLANNING BOARD AGENDA
APRIL 24, 2024 – 7:00 P.M.

TAX MAP # PUB. HEARING MAP DATE COMMENTS

SITE PLAN

1. The Hamlet at Carmel – Stoneleigh Ave, Carmel	66.-2-58	4/10/24	Amended Site Plan
2. 728 Route 6 LLC – 728 Route 6	76.22-1-54	3/2/23	Amended Site Plan
3. Lamanna Auto Body – 255 Route 6	86.7-1-37	4/15/24	Site Plan
4. 2 Clark Place, LLC. – 2 Clark Place	75.12-1-42	2/12/24	Residential Site Plan

MISCELLANEOUS

5. Western Bluff Subdivision – 350 West Shore Dr	66.14-1-20		Extension of Final Subdivision Approval
6. Minutes – 02/08/24 & 02/28/24			



April 10, 2024

Town of Carmel Planning Board
60 McAlpin Avenue
Mahopac, New York 10541

RE: Amended Site Plan
The Hamlet at Carmel
TM# 66.-2-58

Dear Chairman Paerprer and Members of the Board:

Please find enclosed the following plans and documents in support of an application for an amended site plan approval for the above referenced project:


- Eleven (11) sheet Amended Site Plan Set, dated April 10, 2024. (5 copies)
- Amended SWPPP, dated April 10, 2024. (2 copies)
- Architectural Drawings by Coppola Associates, dated November 2, 2023. (5 copies)
- Narrative in Support of Reaffirmation of 2021 SEQRA Determination, dated April 10, 2024.

The applicant is seeking an amendment to the site plan that was approved in 2022 which consisted of 150 units (75 market rate and 75 mixed income units). The southern portion of the project (75 mixed income units) has been constructed, and the applicant is in the process of seeking Certificates of Occupancy for same. It is proposed to amend the northern 75 units to mixed income units which results in minor building footprint changes. It is also proposed to modify the access to this portion of the site resulting in less clearing and reduced impervious surfaces. The original bedroom and unit count remains unchanged and as such water/sewer demands and traffic volumes will remain unchanged.

Please place the project on the April 24, 2024, Planning Board agenda for a discussion with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By: 
Richard D. Williams, Jr., PE
Senior Principal Engineer

RDW/ad

Enclosures (all via email)


cc: Ken Kearney
Sean Kearney
Mario Salpepi

Insite File No. 14211.100

3 Garrett Place, Carmel, New York 10512 (845) 225-9690 Fax (845) 225-9717
www.insite-eng.com



TOWN OF CARMEL
**SITE PLAN APPLICATION
 INSTRUCTIONS**



The Town of Carmel Planning Board meetings are held twice a month, on the second and fourth Wednesday's, at 7:00 PM at Carmel Town Hall, 60 McAlpin Avenue, Carmel

The submission deadline is 10 days prior to the Planning Board meeting. New site plan applications that have been deemed complete will be placed on the agenda in the order they are received.

No application will be placed on the agenda that is incomplete

Pre-Submission:

Prior to the formal submission of the site plan, a pre-submission conference may be requested by the applicant to be conducted with representatives from the Town, which may include the Town Planner, Town Engineer, Director of Code Enforcement and/or the Planning Board Attorney. This conference will serve to educate the applicant on the process he/she must follow, clarify the information required to submit a complete site plan application, and to highlight any specific areas of concern. You may arrange a pre-submission conference through the Planning Board Secretary at (845) 628-1500 extension 190.

Submission Requirements:

At least 10 days prior to the Planning Board meeting, the site plan application shall be submitted to the Planning Board Secretary as follows:

All site plans shall be signed, sealed and folded with the title box legible. The application package shall include:

- 11 copies of the Site Plan Application Form, signed and notarized.
- 11 copies of the SEQR Environmental Assessment Form (use of short form or long form shall be determined at pre-submission conference).
- 5 full size sets of the Site Plan (including floor plans and elevations)
- 1 CD (in pdf. format) containing an electronic version of the Site Plan
- 2 copies of the Disclosure Statement
- 11 copies of the Site Plan Completeness Certification Form
- All supplemental studies, reports, plans and renderings.
- 2 copies of the current deed.
- 2 copies of all easements, covenants and restrictions.
- The appropriate fee, determined from the attached fee schedule. Make checks payable to the *Town of Carmel*.

Rose Yromlith 4/15/24
 Planning Board Secretary; Date

Richard J. [Signature] 4/12/24
 Town Engineer; Date



TOWN OF CARMEL SITE PLAN APPLICATION



Per Town of Carmel Code – Section 156 - Zoning


SITE IDENTIFICATION INFORMATION		
Application Name: The Hamlet at Carmel Amended Site Plan (Reservoir Place)	Application # 24-0011	Date Submitted: 4-10-24
Site Address: No. _____ Street: Stoneleigh Avenue Hamlet: Carmel		
Property Location: (Identify landmarks, distance from intersections, etc.) Stoneleigh Avenue, Carmel, NY 10512		
Town of Carmel Tax Map Designation: Section 66. Block 2 Lot(s) 58	Zoning Designation of Site: R	
Property Deed Recorded in County Clerk's Office Date Liber 1969 Page 307	Liens, Mortgages or other Encumbrances Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
Existing Easements Relating to the Site No <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Describe and attach copies: Access and Utility Easement though Putnam Hospital Center	Are Easements Proposed? No <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Describe and attach copies:	
Have Property Owners within a 500' Radius of the Site Been Identified? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Attached List to this Application Form		
APPLICANT/OWNER INFORMATION		
Property Owner: The Hamlet at Carmel Associates, LLC	Phone #: 845-306-7705 Fax#: 845-306-7707	Email: KKearney@KearneyRealtyGroup.com
Owners Address: No. 57 Street: Route 6, Suite 207 Town: Baldwin Place State: NY Zip: 10505		
Applicant (If different than owner):	Phone #: Fax#:	Email:
Applicant Address (If different than owner): No. _____ Street: _____ Town: _____ State: _____ Zip: _____		
Individual/ Firm Responsible for Preparing Site Plan: Richard D. Williams, Jr., P.E. Insite Engineering, Surveying & Landscape Architecture, P.C	Phone #: 845-225-9690 Fax#: 845-225-9717	Email: jcontelmo@insite-eng.com
Address: No. 3 Street: Garrett Place Town: Carmel State: NY Zip: 10512		
Other Representatives:	Phone #: Fax#:	Email:
Owners Address: No. _____ Street: _____ Town: _____ State: _____ Zip: _____		
PROJECT DESCRIPTION		
Describe the project, proposed use and operation thereof: The applicant is seeking an amendment to the site plan that was approved in 2022 which consisted of 150 units (75 market rate and 75 mixed income units). The southern portion of the project (75 mixed income units) has been constructed, and the applicant is in the process of seeking Certificates of Occupancy for same. It is proposed to amend the northern 75 units to mixed income units which results in slight building footprint changes. It is also proposed to modify the access to this portion of the site resulting in less clearing and reduced impervious surfaces. The original bedroom and unit count remains unchanged and as such water/sewer demands and traffic volumes will remain unchanged.		

TOWN OF CARMEL SITE PLAN APPLICATION

Is the site listed on the State or Federal Register of Historic Place (or substantially contiguous) Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>			
Is the site located in a designated floodplain? , Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>			
Will the project require coverage under the Current NYSDEC Stormwater Regulations <div style="text-align: right;">Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/></div>			
Will the project require coverage under the Current NYCDEP Stormwater Regulations <div style="text-align: right;">Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/></div>			
Does the site disturb more than 5,000 sq ft		Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>	
Does the site disturb more than 1 acre		Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>	
Does the site contain freshwater wetlands? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>			
Jurisdiction: NYSDEC: <input type="checkbox"/> Town of Carmel: <input type="checkbox"/>			
<i>If present, the wetlands must be delineated in the field by a Wetland Professional, and survey located on the Site Plan.</i>			
Are encroachments in regulated wetlands or wetland buffers proposed?		Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Does this application require a referral to the Environmental Conservation Board?		Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Does the site contain waterbodies, streams or watercourses?		Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>	
Are any encroachments, crossings or alterations proposed?		Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Is the site located adjacent to New York City watershed lands?		Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>	
Is the project funded, partially or in total, by grants or loans from a public source? Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> <small>NYS Homes and Community Renewal, NYS Housing Finance agency</small>			
Will municipal or private solid waste disposal be utilized? Public: <input type="checkbox"/> Private: <input checked="" type="checkbox"/>			
Has this application been referred to the Fire Department?		Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>	
What is the estimated time of construction for the project? 18 Months			
ZONING COMPLIANCE INFORMATION			
Zoning Provision	Required	Existing	Proposed
Lot Area	10 ac	35.28	35.28
Lot Coverage	30%		
Lot Width	200'	1170'	1170'
Lot Depth	200'	1161'	1161'
Front Yard	100'	N/A	668±
Side Yard	100'	N/A	102±
Rear Yard	100'	N/A	115±
Minimum Required Floor Area	N/A	---	---
Floor Area Ratio	N/A	---	---
Height	35'	N/A	<35'
Off-Street Parking	2/unit @ 150 units = 300	0	300
Off-Street Loading	0	0	0

TOWN OF CARMEL SITE PLAN APPLICATION

Will variances be required? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	If yes, identify variances:
PROPOSED BUILDING MATERIALS	
Foundation	Concrete
Structural System	Wood Frame
Roof	Asphalt Shingle
Exterior Walls	Fiber cement
APPLICANTS ACKNOWLEDGEMENT	
I hereby depose and certify that all the above statements and information, and all statements and information contained in the supporting documents and drawings attached hereto are true and correct.	
<u>Ken Korman</u> Applicants Name	<u>[Signature]</u> Applicants Signature
Sworn before me this <u>9th</u> day of <u>April</u> 20 <u>24</u>	
<u>[Signature]</u> Notary Public	





TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



All Site Plans submitted to the Planning Board for review shall include the following information and details, as set forth in Section 156-61 B of the Town of Carmel Zoning Ordinance.

This form shall be included with the site plan submission

	<i>Requirement Data</i>	<i>To Be Completed by the Applicant</i>	<i>Waived by the Town</i>
1	Name and title of person preparing the site plan	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2	Name of the applicant and owner (if different from applicant)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3	Original drawing date, revision dates, scale and north arrow	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4	Tax map, block and lot number(s), zoning district	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5	All existing property lines, name of owner of each property within a 500' radius of the site	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6	Contour lines at two-foot intervals, grades of all roads, driveways, sanitary and storm sewers	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7	The location of all water bodies, streams, watercourses, wetland areas, wooded areas, rights-of-way, streets, roads, highways, railroads, buildings, structures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
8	The location of all existing and proposed easements	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9	The location of all existing and proposed structures, their use, setback dimensions, floor plans, front, side and rear elevations, buildable area.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
10	On site circulation systems, access, egress ways and service roads, emergency service access and traffic mitigation measures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
11	Sidewalks, paths and other means of pedestrian circulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12	On-site parking and loading spaces and travel aisles with dimensions	<input checked="" type="checkbox"/>	<input type="checkbox"/>
13	The location, height and type of exterior lighting fixtures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
14	Proposed signage	<input checked="" type="checkbox"/>	<input type="checkbox"/>
15	For non-residential uses, an estimate of the number of employees who will be using the site, description of the operation, types of products sold, types of machinery and equipment used	<input type="checkbox"/> N/A	<input type="checkbox"/>



TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



	Requirement Data	To Be Completed by the Applicant	Waived by the Town
16	The location of clubhouses, swimming pools, open spaces, parks or other recreational areas, and identification of who is responsible for maintenance	<input checked="" type="checkbox"/>	<input type="checkbox"/>
17	The location and design of buffer areas, screening or other landscaping, including grading and water management. A comprehensive landscaping plan in accordance with the Tree Conservation Law	<input checked="" type="checkbox"/>	<input type="checkbox"/>
18	The location of public and private utilities, maintenance responsibilities, trash and garbage areas	<input checked="" type="checkbox"/>	<input type="checkbox"/>
19	A list, certified by the Town Assessor, of all property owners within 500 feet of the site boundary	<input checked="" type="checkbox"/>	<input type="checkbox"/>
20	Any other information required by the Planning Board which is reasonably necessary to ascertain compliance with this chapter	<input checked="" type="checkbox"/>	<input type="checkbox"/>



Applicants Certification (to be completed by the licensed professional preparing the site plan:

I RICHARD D WILLIAMS, PE hereby certify that the site plan to which I have attached my seal and signature, meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:



[Signature]
Signature - Applicant

4-9-24
Date


Professionals Seal

[Signature]
Signature - Owner

4-9-24
Date



TOWN OF CARMEL
**SITE PLAN COMPLETENESS
CERTIFICATION FORM**



Town Certification (to be completed by the Town)

I _____ hereby confirm that the site plan meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:

Rose Tronchetti
Signature - Planning Board Secretary

4/15/24
Date

Richard [Signature]
Signature - Town Engineer

4/12/24
Date



The Hamlet at Carmel (Reservoir Place) Amended Site Plan

Narrative in Support of Reaffirmation of 2021 SEQRA Determination

**Stoneleigh Avenue, Town of Carmel, New York
Tax Map # 66-2-58**

April 10, 2024

The Hamlet at Carmel project was first presented to the Town of Carmel Planning Board in 2008. At that time, the Planning Board elected to act as lead agency under the New York State Environmental Quality Review Act (SEQRA). In the course of the Board’s review, a full Environmental Impact Statement (EIS) was prepared and approved by the Planning Board, and a Finding Statement, dated December 17, 2008, was adopted.

In 2021 an amendment to the approved site plan (2022 amended site plan) was presented to the Board, and a resolution, dated January 26, 2022, was adopted, reaffirming the 2008 Finding Statement. It was determined that the revisions laid out in the amended site plan did not exceed any thresholds for the development established in the Finding Statement.

The 2022 amended site plan provided for 150 total dwelling units of multifamily housing. At the time, 75 of the units were proposed as mixed-income, and the other 75 units would be provided at market rate. Since the 2022 SEQRA determination and site plan approval, the mixed-income portion of the project has been built out.

Based on the extraordinary demand for rental units at the mixed income rates, and as evidenced by the overwhelming demand for units at the Hamlet at Carmel, the applicant is now presenting an amended site plan to build out the remaining portion of the development as affordable housing.

The material revisions to the plan are minimal but improve upon the 2022 site plan with respect to a reduction in impervious surfaces, and site disturbance. The principal change to the site plan is that a driveway to the eastern side of the second phase will connect to the existing driveway from the south, rather than from the north, as shown in the 2022 plan, which will shorten the connection and create less site disturbance and impervious surface than previously proposed. In addition, the building footprints have slightly decreased in size. The total unit count and bedroom count remain unchanged. As such traffic, water and sewer remain unchanged from the previous approval.

Below is a summary of the potential impacts discussed in the 2008 Finding Statement, and how the currently proposed amended site plan does not cause the project impacts to exceed thresholds established therein. Contained thereafter is a more detailed discussion on each finding.

Finding Section:	Parameter Studied:	Change from previous finding:
3.1	Soils and Topography	No Change
<p>The area of disturbance and proposed impervious surfaces are reduced from the 2022 plan. By accessing the second phase from the south, rather than from the north the driveway is shortened. The buildings are also somewhat smaller than those previously proposed for this phase. This will represent a reduction in impacts to site soils and the potential for erosion.</p>		

3.2	Terrestrial and Aquatic Resources	No Change
	The area of disturbance and proposed impervious surfaces are reduced from the 2022 plan. Less of the existing forested area will be impacted than in the 2022 plan. As with the 2022 plan, the watercourses on the west end of the site will not be impacted.	
3.3	Water Resources	No Change
	The area of disturbance and proposed impervious surfaces are reduced from the 2022 plan. The stormwater management practices have been installed as part of the first phase of work and are temporarily functioning as erosion control practices. At the conclusion construction the basins will be converted to manage stormwater runoff from the finished surfaces to provide storage and stormwater quality as previously approved. The basins were designed based on the 2022 site plan. Based on the reduction in impervious surfaces in the current site plan, the proposed stormwater management practices continue to be appropriately sized for the reduced amount of runoff.	
3.4	Zoning and Surrounding Land Use	No Change
	As noted in the 2008 finding statement the project will be “compatible with the surrounding development, which consists of a variety of residential densities similar to the proposed development, and will not result in significant adverse impacts.” The project remains zoning compliant and the same with regard to use and unit count.	
3.5	Traffic and Transportation	No Change
	The unit count and bedroom count remains the same as approved in 2022. No additional traffic is anticipated as part of this amendment.	
3.6	Community Services and Socioeconomics	No Change
	The unit count and bedroom count remains the same as approved in 2002. No additional need for community services is anticipated as part of this amendment. It should be noted that the proposed amended site plan will provide tax revenue, whereas the 2008 Finding Statement anticipated “no post-development tax revenues.”	
3.7	Visual Resources	No Change
	The amended site plan will site the proposed buildings in the same general location as the approved 2022 plan, but the area of disturbance is reduced. Less of the existing forested area will be impacted than in the 2022 plan. Specifically, along the northern end of the property there was a driveway leading to the eastern row of buildings in the 2022 plan. In the current plan that driveway has been shifted to the south of those buildings, which will allow for a deeper forested buffer between the development and the hospital property to the north.	
3.8	Cultural Resources	No Change
	Per the 2008 Finding Statement, “There are no National Register Listed properties located on or within one mile of the project site.”	



The Hamlet at Carmel
(Formerly The Putnam Community Foundation)
Amended Stormwater Pollution Prevention Plan (ASWPPP)
Town of Carmel, New York
May 11, 2022
Revised: April 10, 2024

1.0 INTRODUCTION

The Hamlet at Carmel (HAC) project is proposed on a 35 ± acre parcel of vacant land designated as Town of Carmel Tax Map Parcel #66.-2-58. Access to the HAC project is provided through the adjoining Putnam Hospital Center property to the north. The hospital parcel is designated as Town of Carmel Tax Map Parcel #66.-2-57. The subject parcels are located in the R (residential) zoning district. The parcels and their surroundings are delineated on the Overall Site Plan.

A SWPPP approval was obtained for the subject project (formerly known as The Putnam Community Foundation) from the NYCDEP on March 23, 2010, and a previous Amended SWPPP was approved on May 16, 2022 for The Hamlet at Carmel project. The original approved SWPPP is titled “Stormwater Pollution Prevention Plan for The Putnam Community Foundation” and dated March 9, 2010. This document is a supplement to the original approved SWPPP. The Putnam Community Foundation project consisted of 120 senior housing units, access driveway, sports court, community building and parking. The current proposed project for the project site consists of the construction of a multifamily residential development of ten (10) buildings totaling 150 units and associated parking, recreation and utility areas. The current project scope is proposed to consist of less impervious cover and less disturbance on the project site than the previously approved project.

The project received coverage under the New York State Department of Environmental Conservation General Permit GP-0-10-001. The identification number is NYR11C513. As noted in Part II.E of GP-0-20-001, “owner operator of a construction activity with coverage under GP-0-15-002, as of the effective date of GP-0-20-001, shall be authorized to discharge in accordance with GP-0-20-001, unless otherwise notified by the Department”. The permit also notes that “the owner or operator may continue to implement the technical/design components of the post-construction stormwater management controls provided that such design was done in conformance with the technical standards in place at the time of initial project authorization”. The current stormwater design will meet the requirements for stormwater treatment in accordance with the General Permit GP-0-10-001.

The following sections of this report have been prepared to address the proposed site changes for The Hamlet at Carmel project from the approved SWPPP for the Putnam Community Foundations as well as assess the stormwater management practices within the framework of the previously approved SWPPP. This Amended SWPPP is supplemental to the approved SWPPP for The Putnam Community Foundation project. For further information refer to the approved SWPPP titled “Stormwater Pollution Prevention Plan for The Putnam Community Foundation”, dated March 9, 2010.

2.0 STORMWATER ASSESSMENT

This section of the SWPPP amendment discusses the proposed modifications from the approved SWPPP to the current proposed project. As previously discussed, the proposed site development has been modified from the approved SWPPP. The overall general layout of the site has not changed but proposed development has changed from 120 senior housing units to the construction of a multifamily residential development including ten (10) buildings totaling 150 units and associated appurtenances. The type and

number of stormwater management practices as approved in the SWPPP prepared for The Putnam Community Foundation (PCF) project have not been altered.

The approved PCF project consisted of 7.7 acres of 1/8 acre lots (65% impervious) and 1.3 acres of impervious surfaces associated with the proposed driveway, parking areas and appurtenances. The Hamlet at Carmel development proposes less total impervious area from the approved SWPPP. The project also proposes to decrease the overall limit of disturbance associated with the development from the approved SWPPP. See table below for a comparison between the overall impervious area and limit of disturbance for the approved PCF project and the Hamlet at Carmel development.

Table 2.1 – Impervious Area and Limit of Disturbance Summary Table

	Approved SWPPP	Amended SWPPP
Overall Proposed Impervious Area (ac.)	6.3	5.8
Overall Proposed Limit of Disturbance (ac.)	23.9	18.6

As the project site is mostly wooded, by reducing the overall limit of disturbance for the subject project, the proposed tree removal for the project will decrease as well. By decreasing the tree removal for the subject project, the stormwater runoff from the site will decrease which will reduce the water quality treatment volumes required for stormwater management. With the same amount of impervious area for the subject project and decrease in tree removal, the water quality and quantity requirements for stormwater treatment will be reduced from the approved SWPPP, thereby decreasing the required size of the proposed stormwater management practices. As the proposed stormwater management practices have not been altered and the stormwater quality and quantity treatment requirements have been reduced, the approved stormwater management practices are adequate to treat the stormwater runoff from the proposed Hamlet at Carmel development in accordance with the NYCDEP and NYSDEC requirements during the time of the original approval. See Section 3.0 and 4.0 below for further information on the stormwater quantity and quality requirements.

A summary of the impervious cover and total tributary area for each subcatchment in the post-development condition is provided in Table 2.2 below for the approved SWPPP and the proposed amended SWPPP.

Table 2.2 – Impervious and Total Tributary Area Comparison

Design Line/Point	Subcatchment	Impervious Area (ac.)		Total Area (ac.)	
		Approved SWPPP	Amended SWPPP	Approved SWPPP	Amended SWPPP
Design Point 2	2.1S	3.25	2.90	7.9	6.8
	2.2S	-	-	0.9	0.9
	2.3S	-	-	2.8	2.8
	Total	3.25	2.90	11.6	10.5
Design Point 3	3.1S	3.05	2.90	8.9	8.1
	3.2S	-	-	0.6	0.6
	3.3S	-	-	2.9	2.9
	Total	3.05	2.90	12.4	11.6
Design Line 4	4.1S	-	-	8.8	8.0
	Total	0.0	0.0	8.8	8.0
Design Line 5	5.1S	-	-	2.1	4.3
	Total	0.0	0.0	2.1	4.3

¹ The impervious areas shown in the table represent 65% of the area input into HydroCAD, where 1/8 acre lots was used for the ground cover.

To assess the stormwater quantity and quality requirements of state and local agencies found in the original SWPPP approval by others, the “HydroCAD” Stormwater Modeling System,” by HydroCAD Software Solutions LLC in Tamworth, New Hampshire, was used to model and assess the peak stormwater flows for the subject project. HydroCAD is a computer aided design program for modeling the hydrology and hydraulics of stormwater runoff. It is based primarily on hydrology techniques developed by the United States Department of Agriculture, Soil Conservation Service (USDA, SCS) TR-20 method combined with standard hydraulic calculations.

The input requirements for the HydroCAD computer program are as follows:

Subcatchments (contributing watershed/sub-watersheds)

- Design storm rainfall in inches
- CN (runoff curve number) values which are based on soil type and land use/ground cover
- Tc (time of concentration) flow path information

Stormwater Basins

- Surface area at appropriate elevations
- Flood elevation
- Outlet structure information

The precipitation values for the 1-Year, 2-Year, 10-Year, 25-Year, and 100-Year 24-hour design storm events and rainfall distribution curves utilized for this report were consistent with the precipitation values utilized in the previously approved SWPPP. The values provided for all design storms analyzed have been listed below.

Design Storm	24-Hour Rainfall
1-Year	3.1"
2-Year	3.5"
10-Year	5.5"
25-Year	6.0"
100-Year	9.7"

The CN (runoff curve number) values utilized in this report were referenced from the USDA, SCS publication *Urban Hydrology for Small Watersheds*. The following is a summary of the various land uses/ground covers and their associated CN values utilized in this report.

Table 2.3 – Project Ground Cover and Associated Curve Numbers (CN)

Land Use/Ground Cover	CN Value
Woods, Good, B Soil	55
Woods, Good, C Soil	70
>75% Grass Cover, Good, B Soil	74
Gravel, C Soil	89
1/8 acre lots, 65% imp., C Soil	90
Paved Parking and Roofs	98

3.0 STORMWATER QUALITY

The pollutant loading coefficient method was utilized to calculate the annual export of Biological Oxygen Demand (BOD), Total Phosphorus (TP), Total Nitrogen (TN), and Total Suspended Solids (TSS). The publication *Fundamentals of Urban Runoff Management: Technical and Institutional Issues* produced by the Terrene Institute was referenced to determine the appropriate loading rates for TP, TN, and TSS. The New York State Department of Environmental Conservation (NYSDEC) publication *Reducing the Impacts of Stormwater Runoff from New Development (Impacts)* was referenced to determine appropriate loading rates for BOD. The appropriate loading rates were then utilized to calculate the annual pollutant runoff values. The following table summarizes the pollutant loading rates utilized for the subject project.

Table 3.1 - Summary of Pollutant Loading Rates (lbs/acre/year)

Land Use/Ground Cover	BOD	TP	TN	TSS
Woods	6.0	0.10	1.8	77
Grass	6.0	0.12	3.7	308
Pavement	111.0	0.98	2.1	446
Multifamily Residential	50.0	0.63	5.0	395

The following pollutant removal efficiencies are referenced from *Impacts*. By meeting the requirements set forth by the NYCDEP, which exceed the requirements in *Impacts* for the Design 2 extended detention basins, the pollutant removal efficiencies for a Design 2 extended detention pond can be applied for the proposed stormwater ponds. Grass Swales will also be used to treat stormwater runoff from the proposed project.

Table 3.2 - Long Term Pollutant Removal Efficiencies

Treatment Method	BOD	TP	TN	TSS
Design 2 Extended Detention Pond (Micropool Extended Detention Pond P-1)	40%-60%	40%-60%	20%-40%	80%-100%
Design 14 Grass Swale	20%-40%	20%-40%	20%-40%	20%-40%

The following tables summarize the estimated pre-development and post-development annual pollutant loads from the approved SWPPP and compares them to the calculated post-development annual pollutant loads (contained in Appendix C of this report) calculated for the subject project. The annual pollutant loading calculation in Appendix C and summarized below have been provided for all four design points/lines separately as well as the overall pollutant loads for the subject project.

Table 3.3 - Annual Pollutant Loading Summary for Overall Project

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	206.4	3.44	61.9	2,649
Approved SWPPP Post-Development Annual Pollutant Loads	261.5 to 151.8	3.69 to 2.34	69.3 to 47.7	1,793 to 1,532
Amended SWPPP Post-Development Annual Pollutant Loads	274.8 to 163.4	3.85 to 2.50	69.1 to 49.7	1,910 to 1,663

Table 3.4 - Annual Pollutant Loading Summary to Design Point 2

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	34.8	0.58	10.4	447
Approved SWPPP Post-Development Annual Pollutant Loads	90.7 to 40.0	1.27 to 0.59	24.2 to 12.9	345.6 to 215.6
Amended SWPPP Post-Development Annual Pollutant Loads	86.0 to 39.6	1.20 to 0.59	22.5 to 12.5	337 to 216

Table 3.5 - Annual Pollutant Loading Summary to Design Point 3

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	36.0	0.60	10.8	462
Approved SWPPP Post-Development Annual Pollutant Loads	105.4 to 46.4	1.32 to 0.64	23.7 to 13.4	400 to 270
Amended SWPPP Post-Development Annual Pollutant Loads	115.1 to 50.1	1.40 to 0.67	22.5 to 13.1	395 to 270

Table 3.6 - Annual Pollutant Loading Summary to Design Line 4

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	90.0	1.50	27.0	1,155
Approved SWPPP Post-Development Annual Pollutant Loads	52.8	0.88	15.8	678
Amended SWPPP Post-Development Annual Pollutant Loads	48.0	0.80	14.4	616

Table 3.7 - Annual Pollutant Loading Summary to Design Line 5

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	45.6	0.76	13.7	585
Approved SWPPP Post-Development Annual Pollutant Loads	12.6	0.23	5.5	370
Amended SWPPP Post-Development Annual Pollutant Loads	25.8	0.45	9.6	562

As seen by the above summaries, the overall post-development pollutant loads are within the range of the pre-development pollutants of concern for the overall project as required by the NYCDEP regulations, which is consistent with the standards at the time of the original SWPPP Approval.

Similar to the approved SWPPP, the pollutant loads to Design Point 2 and 3 are greater in the post-development condition than the pre-development but are less for Design Lines 4 and 5. Design Points 2 and 3 and Design Line 4 discharge to the west while Design Line 5 discharges to the east. The subject property and the causeway for Stoneleigh Avenue separate the eastern and western sides of the Croton Falls Reservoir. As previously stated and shown above, there is a decrease in all the pollutant loads to the east side (Design Line 5) of the reservoir. The table below summarizes the pollutant loads reaching the western side of the reservoir (Design Points 2 and 3 and Design Line 4).

Table 3.8 - Annual Pollutant Loading Summary to West Side

	Annual Loads (lb/yr)			
	BOD	TP	TN	TSS
Pre-Development Annual Pollutant Loads	160.8	2.68	48.2	2,064
Approved SWPPP Post-Development Annual Pollutant Loads	248.9 to 139.2	3.47 to 2.11	63.7 to 42.1	1,423 to 1,164
Amended SWPPP Post-Development Annual Pollutant Loads	249.0 to 137.6	3.40 to 2.05	59.4 to 40.0	1,348 to 1,101

As shown in the table above, the post-development pollutant loads reaching the western side of the reservoir are within the pre-development range, similar to the approved SWPPP.

The water quality volume (WQ_v) is intended to improve water quality by sizing the stormwater management practices to fully capture and treat a specified quantity of water. Chapter 10 of the Design

Manual specifies that the WQ_v in a Phosphorus TMDL watershed shall be the estimated runoff from the 1-year 24-hour design storm. Stormwater ponds 2.1P and 3.1P are proposed as P-1 micropool extended detention basins to meet the NYSDEC WQ_v treatment requirements. A summary of the WQ_v requirement for each stormwater pond based on the stormwater runoff from the contributing area during the 1-year, 24-hour storm event is provided in the table below. The table compares the WQ_v requirement from the approved SWPPP to this amended SWPPP.

Table 3.9 – Required Water Quality Volume Summary (Per Design Manual Chapter 10)

Subcatchment	Stormwater Pond	Approved SWPPP WQ_v (cf)	Amended SWPPP WQ_v (cf)
2.1S	2.1P	45,869	39,465
3.1S	3.1P	47,088	44,910

*Information regarding the 1-year 24-hour Design Storm Volumes (WQ_v) is shown in Appendix B

As there are no proposed changes to the stormwater management ponds from the Approved SWPPP, and the Water Quality Volume requirement from the contributing subcatchment have been reduced from the approved SWPPP, the approved stormwater management practices are adequately sized to treat the stormwater runoff from the proposed Hamlet at Carmel development in accordance with the NYCDEP and NYSDEC requirements during the time of the original approval.

4.0 STORMWATER QUANTITY

To meet the Stream Channel Protection (C_p) requirements of the NYSDEC 24 hours of center of mass detention for the 1-Year, 24-hour design storm has been provided in each of the proposed treatment trains. The following table summarizes the center of mass detention times of each treatment train prior to discharging out of the stormwater management system.

CENTER OF MASS DETENTION TIME (MIN) FOR 1-YEAR, 24 HOUR DESIGN STORM

Treatment Train	Center of Mass Time IN to Treatment Train (Min)	Center of Mass Time OUT of Treatment Train (Min)	Total Center of Mass Detention (Min)	Total Center of Mass Detention (Hr)
2.1P – 2.2P	837.1	3,003.4	2,166.3	36.1
3.1P – 3.2P	848.7	3,772.0	2,923.3	48.7

The data for the table above was taken from Appendix B of this SWPPP. As shown in the table above a minimum of 24 hours or 1,440 minutes has been provided within each treatment train prior to discharge from the site. By providing 24 hours of detention of the center of mass for the 1-Year, 24-hour design storm the NYSDEC requirements for Stream Channel Protection (C_p) have been met.

Consistent with the approved SWPPP, the same two Design Lines and two Design Points were used to quantitatively analyze the stormwater runoff from the proposed development. The NYSDEC and NYCDEP regulations at the time of the original SWPPP approval required the attenuation of peak flows from the 2, 10, 25, and 100-year storms to pre-development levels. The attenuation of the peak flows from the proposed development is accomplished within the proposed stormwater management practices on the site. Table 4.1 thru 4.4 below summarizes the pre and post development peak flows expected for the proposed amended project.

Table 4.1 – Design Point 2 - Pre and Post-Development Peak Flows (cfs)

24-HOUR DESIGN STORM								
DESIGN POINT 2	2-YEAR		10-YEAR (Qp)		25-YEAR		100-YEAR (Qf)	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post
Approved SWPPP	3.93	2.49	10.12	6.26	11.82	7.31	25.27	25.10
Amended SWPPP		2.47		6.24		7.28		20.32

Table 4.2 – Design Point 3 - Pre and Post-Development Peak Flows (cfs)

24-HOUR DESIGN STORM								
DESIGN POINT 3	2-YEAR		10-YEAR (Qp)		25-YEAR		100-YEAR (Qf)	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post
Approved SWPPP	4.02	2.58	10.35	6.58	12.09	7.68	25.84	16.46
Amended SWPPP		2.58		6.57		7.67		16.45

Table 4.3 – Design Line 4 - Pre and Post-Development Peak Flows (cfs)

24-HOUR DESIGN STORM								
DESIGN LINE 4	2-YEAR		10-YEAR (Qp)		25-YEAR		100-YEAR (Qf)	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post
Approved SWPPP	10.27	6.03	27.27	16.00	31.99	21.03	69.66	69.20
Amended SWPPP		5.48		14.55		17.06		55.06

Table 4.4 – Design Line 5 - Pre and Post-Development Peak Flows (cfs)

24-HOUR DESIGN STORM								
DESIGN LINE 5	2-YEAR		10-YEAR (Qp)		25-YEAR		100-YEAR (Qf)	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post
Approved SWPPP	5.24	1.91	13.49	4.70	15.79	5.45	33.77	11.33
Amended SWPPP		3.92		9.63		11.17		23.20

As seen by the above summaries, the post-development peak flows for the 2-, 10-, 25-, and 100-year design storms have been attenuated to be less than the pre-development peak flows, therefore the receiving drainage system will see a reduction in peak flows during the storm events shown above.

5.0 STORMWATER CONVEYANCE SYSTEM

The stormwater conveyance system for the project consists of grass swales, precast concrete drainage structures, HDPE and PVC SDR 35 drainage piping. The proposed conveyance system has been sized utilizing the Rational Method and is a standard method used by engineers to develop flow rates for sizing collection systems. The Rational Method calculates flows based on a one-hour design storm. The collection system has been sized to convey, at a minimum, the 100-year design storm. Pipe sizing calculations will be provided in future reports.

6.0 CONCLUSION

The proposed stormwater management practices sized for the original scope of the approved SWPPP for the Putnam Community Foundation project and are adequately sized for the proposed modifications to the site improvements for The Hamlet of Carmel project. As previously stated, the proposed modifications have no impact on the approved stormwater management practices on the project site and all modifications meet the requirements of the NYCDEP and NYSDEC within the framework of the original approved SWPPP.




APPENDICIES

Appendix A	Pre Development Computer Data
Appendix B	Post Development Computer Data
Appendix C	Pollutant Loading Calculations

Figures

Figure 1	The Hamlet at Carmel - Post Development Drainage Map
Figure 2	The Putnam Community Foundation - Pre Development Drainage Map (Approved)
Figure 3	The Putnam Community Foundation - Post Development Drainage Map (Approved)

APPENDIX A
Pre Development Computer Data



Routing Diagram for The Hamlet at Carmel Pre Development

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

The Hamlet at Carmel Pre Development

Type III 24-hr 1 year Rainfall=3.20"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 2

Summary for Subcatchment 2.0S:

Runoff = 3.13 cfs @ 12.38 hrs, Volume= 0.400 af, Depth= 0.83"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1 year Rainfall=3.20"

Area (ac)	CN	Description
5.800	70	Woods, Good, HSG C
5.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.2	100	0.0600	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
10.6	1,100	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.8	1,200	Total			

Subcatchment 2.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 1 year Rainfall=3.20"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 3

Summary for Subcatchment 3.0S:

Runoff = 3.21 cfs @ 12.39 hrs, Volume= 0.414 af, Depth= 0.83"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.20"

Area (ac)	CN	Description
6.000	70	Woods, Good, HSG C
6.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.4	100	0.0350	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.1	940	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
24.5	1,040	Total			

Subcatchment 3.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 1 year Rainfall=3.20"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment 4.0S:

Runoff = 8.11 cfs @ 12.31 hrs, Volume= 0.974 af, Depth= 0.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.20"

Area (ac)	CN	Description
14.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
15.000	69	Weighted Average
15.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 1 year Rainfall=3.20"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 5

Summary for Subcatchment 5.0S:

Runoff = 4.18 cfs @ 12.36 hrs, Volume= 0.524 af, Depth= 0.83"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.20"

Area (ac)	CN	Description
7.600	70	Woods, Good, HSG C
7.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.5	100	0.0200	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.3	140	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
22.8	240	Total			

Subcatchment 5.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment 2.0S:

Runoff = 3.93 cfs @ 12.37 hrs, Volume= 0.487 af, Depth= 1.01"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
5.800	70	Woods, Good, HSG C
5.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.2	100	0.0600	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
10.6	1,100	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.8	1,200	Total			

Subcatchment 2.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment 3.0S:

Runoff = 4.02 cfs @ 12.38 hrs, Volume= 0.504 af, Depth= 1.01"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
6.000	70	Woods, Good, HSG C
6.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.4	100	0.0350	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.1	940	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
24.5	1,040	Total			

Subcatchment 3.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 8

Summary for Subcatchment 4.0S:

Runoff = 10.27 cfs @ 12.30 hrs, Volume= 1.192 af, Depth= 0.95"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
14.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
15.000	69	Weighted Average
15.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment 5.0S:

Runoff = 5.24 cfs @ 12.35 hrs, Volume= 0.638 af, Depth= 1.01"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
7.600	70	Woods, Good, HSG C
7.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.5	100	0.0200	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.3	140	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
22.8	240	Total			

Subcatchment 5.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 10

Summary for Subcatchment 2.0S:

Runoff = 10.12 cfs @ 12.34 hrs, Volume= 1.167 af, Depth= 2.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
5.800	70	Woods, Good, HSG C
5.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.2	100	0.0600	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
10.6	1,100	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.8	1,200	Total			

Subcatchment 2.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 11

Summary for Subcatchment 3.0S:

Runoff = 10.35 cfs @ 12.35 hrs, Volume= 1.207 af, Depth= 2.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
6.000	70	Woods, Good, HSG C
6.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.4	100	0.0350	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.1	940	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
24.5	1,040	Total			

Subcatchment 3.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 12

Summary for Subcatchment 4.0S:

Runoff = 27.27 cfs @ 12.28 hrs, Volume= 2.910 af, Depth= 2.33"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
14.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
15.000	69	Weighted Average
15.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 13

Summary for Subcatchment 5.0S:

Runoff = 13.49 cfs @ 12.33 hrs, Volume= 1.529 af, Depth= 2.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
7.600	70	Woods, Good, HSG C
7.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.5	100	0.0200	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.3	140	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
22.8	240	Total			

Subcatchment 5.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 14

Summary for Subcatchment 2.0S:

Runoff = 11.82 cfs @ 12.34 hrs, Volume= 1.356 af, Depth= 2.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
5.800	70	Woods, Good, HSG C
5.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.2	100	0.0600	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
10.6	1,100	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.8	1,200	Total			

Subcatchment 2.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 15

Summary for Subcatchment 3.0S:

Runoff = 12.09 cfs @ 12.35 hrs, Volume= 1.403 af, Depth= 2.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
6.000	70	Woods, Good, HSG C
6.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.4	100	0.0350	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.1	940	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
24.5	1,040	Total			

Subcatchment 3.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 16

Summary for Subcatchment 4.0S:

Runoff = 31.99 cfs @ 12.28 hrs, Volume= 3.391 af, Depth= 2.71"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
14.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
15.000	69	Weighted Average
15.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 17

Summary for Subcatchment 5.0S:

Runoff = 15.79 cfs @ 12.32 hrs, Volume= 1.777 af, Depth= 2.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
7.600	70	Woods, Good, HSG C
7.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.5	100	0.0200	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.3	140	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
22.8	240	Total			

Subcatchment 5.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 18

Summary for Subcatchment 2.0S:

Runoff = 25.27 cfs @ 12.33 hrs, Volume= 2.879 af, Depth= 5.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
5.800	70	Woods, Good, HSG C
5.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.2	100	0.0600	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
10.6	1,100	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.8	1,200	Total			

Subcatchment 2.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 19

Summary for Subcatchment 3.0S:

Runoff = 25.84 cfs @ 12.34 hrs, Volume= 2.978 af, Depth= 5.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
6.000	70	Woods, Good, HSG C
6.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.4	100	0.0350	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.1	940	0.1500	1.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
24.5	1,040	Total			

Subcatchment 3.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 20

Summary for Subcatchment 4.0S:

Runoff = 69.66 cfs @ 12.27 hrs, Volume= 7.284 af, Depth= 5.83"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
14.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
15.000	69	Weighted Average
15.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.0S:

Hydrograph



The Hamlet at Carmel Pre Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 1/4/2022

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 21

Summary for Subcatchment 5.0S:

Runoff = 33.77 cfs @ 12.31 hrs, Volume= 3.772 af, Depth= 5.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
7.600	70	Woods, Good, HSG C
7.600		100.00% Pervious Area




Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.5	100	0.0200	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.3	140	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
22.8	240	Total			

Subcatchment 5.0S:

Hydrograph



APPENDIX B
Post Development Computer Data



Routing Diagram for The Hamlet at Carmel Post Development
 Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., Printed 4/10/2024
 HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 2

Summary for Subcatchment 2.1S:

Runoff = 10.15 cfs @ 12.18 hrs, Volume= 0.906 af, Depth= 1.60"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
2.900	98	Paved parking, HSG C
3.850	74	>75% Grass cover, Good, HSG C
* 0.050	89	Gravel, HSG C
6.800	84	Weighted Average
3.900		57.35% Pervious Area
2.900		42.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	100	0.0200	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.50"
1.9	110	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
1.3	190	0.0150	2.49		Shallow Concentrated Flow, Paved Kv= 20.3 fps
12.6	400	Total			

Subcatchment 2.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 3

Summary for Subcatchment 2.2S:

Runoff = 0.97 cfs @ 12.09 hrs, Volume= 0.073 af, Depth= 0.97"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
0.900	74	>75% Grass cover, Good, HSG C
0.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment 2.3S:

Runoff = 1.73 cfs @ 12.21 hrs, Volume= 0.180 af, Depth= 0.77"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
2.800	70	Woods, Good, HSG C
2.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	24	0.5000	0.33		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.0	76	0.1700	0.18		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.2	330	0.2400	2.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
3.1	400	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
13.5	830	Total			

Subcatchment 2.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 5

Summary for Subcatchment 3.1S:

Runoff = 9.44 cfs @ 12.30 hrs, Volume= 1.031 af, Depth= 1.53"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
2.900	98	Paved parking & roofs
4.450	74	>75% Grass cover, Good, HSG C
0.500	70	Woods, Good, HSG C
* 0.250	89	Gravel, HSG C
8.100	83	Weighted Average
5.200		64.20% Pervious Area
2.900		35.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.1	80	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	30	0.0450	1.48		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.9	150	0.0150	0.86		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.1	270	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
0.2	72	0.0100	4.91	3.86	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
0.1	48	0.0100	5.70	7.00	Pipe Channel, 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.012
0.5	610	0.0700	20.64	64.84	Pipe Channel, 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.012
21.4	1,360	Total			

The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 6

Subcatchment 3.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment 3.2S:

Runoff = 0.65 cfs @ 12.09 hrs, Volume= 0.049 af, Depth= 0.97"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
0.600	74	>75% Grass cover, Good, HSG C
0.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 3.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 8

Summary for Subcatchment 3.3S:

Runoff = 1.84 cfs @ 12.20 hrs, Volume= 0.186 af, Depth= 0.77"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
2.700	70	Woods, Good, HSG C
0.200	74	>75% Grass cover, Good, HSG C
2.900	70	Weighted Average
2.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	26	0.4200	0.32		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.6	74	0.1300	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
3.1	388	0.1700	2.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	207	0.0480	13.23	128.96	Trap/Vee/Rect Channel Flow, Bot.W=2.00' D=1.50' Z= 4.0 & 2.0 '/' Top.W=11.00' n= 0.022 Earth, clean & straight
12.4	695	Total			

Subcatchment 3.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment 4.1S:

Runoff = 3.96 cfs @ 12.32 hrs, Volume= 0.483 af, Depth= 0.72"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
7.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
8.000	69	Weighted Average
8.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 10

Summary for Subcatchment 5.1S:

Runoff = 2.94 cfs @ 12.24 hrs, Volume= 0.311 af, Depth= 0.87"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 year Rainfall=3.10"

Area (ac)	CN	Description
1.000	74	>75% Grass cover, Good, HSG C
3.150	70	Woods, Good, HSG C
* 0.150	89	Gravel, HSG C
4.300	72	Weighted Average
4.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.4	120	0.0800	1.41		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.6	220	Total			

Subcatchment 5.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 11


Summary for Reach DL4:

Inflow Area = 8.000 ac, 0.00% Impervious, Inflow Depth = 0.86" for 1 year event
Inflow = 3.96 cfs @ 12.32 hrs, Volume= 0.573 af
Outflow = 3.96 cfs @ 12.32 hrs, Volume= 0.573 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DL4:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 12


Summary for Reach DP 2:

Inflow Area = 10.500 ac, 27.62% Impervious, Inflow Depth = 1.32" for 1 year event
Inflow = 1.83 cfs @ 12.21 hrs, Volume= 1.157 af
Outflow = 1.83 cfs @ 12.21 hrs, Volume= 1.157 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 2:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 13


Summary for Reach DP 3:

Inflow Area = 11.600 ac, 25.00% Impervious, Inflow Depth = 1.21" for 1 year event
Inflow = 1.90 cfs @ 12.20 hrs, Volume= 1.173 af
Outflow = 1.90 cfs @ 12.20 hrs, Volume= 1.173 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 3:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 14

Summary for Pond 2.1P:

Inflow Area = 6.800 ac, 42.65% Impervious, Inflow Depth = 1.60" for 1 year event
 Inflow = 10.15 cfs @ 12.18 hrs, Volume= 0.906 af
 Outflow = 0.85 cfs @ 14.08 hrs, Volume= 0.904 af, Atten= 92%, Lag= 114.1 min
 Primary = 0.85 cfs @ 14.08 hrs, Volume= 0.904 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 439.00' Surf.Area= 13,300 sf Storage= 26,000 cf
 Peak Elev= 440.51' @ 14.08 hrs Surf.Area= 18,275 sf Storage= 49,803 cf (23,803 cf above start)

Plug-Flow detention time= 2,320.1 min calculated for 0.307 af (34% of inflow)
 Center-of-Mass det. time= 1,002.9 min (1,840.1 - 837.1)

Volume	Invert	Avail.Storage	Storage Description
#1	435.00'	106,100 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
435.00	1,500	0	0
437.00	5,600	7,100	7,100
439.00	13,300	18,900	26,000
441.00	19,900	33,200	59,200
443.00	27,000	46,900	106,100

Device	Routing	Invert	Outlet Devices
#1	Primary	434.00'	24.0" Round Culvert L= 70.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 434.00' / 423.00' S= 0.1571 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	439.00'	2.9" Vert. Orifice/Grate C= 0.600
#3	Device 1	440.40'	6.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.85 cfs @ 14.08 hrs HW=440.51' TW=420.78' (Dynamic Tailwater)

- 1=Culvert (Passes 0.85 cfs of 35.50 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.26 cfs @ 5.67 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 0.59 cfs @ 0.92 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 15

Pond 2.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 16

Summary for Pond 2.2P:

Inflow Area = 7.700 ac, 37.66% Impervious, Inflow Depth = 1.52" for 1 year event
 Inflow = 1.11 cfs @ 12.09 hrs, Volume= 0.977 af
 Outflow = 0.17 cfs @ 38.75 hrs, Volume= 0.977 af, Atten= 85%, Lag= 1,599.5 min
 Primary = 0.17 cfs @ 38.75 hrs, Volume= 0.977 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 422.26' @ 38.75 hrs Surf.Area= 10,006 sf Storage= 17,058 cf


Plug-Flow detention time= 1,237.5 min calculated for 0.977 af (100% of inflow)
 Center-of-Mass det. time= 1,236.3 min (3,003.4 - 1,767.1)

Volume	Invert	Avail.Storage	Storage Description
#1	420.00'	113,000 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
420.00	5,100	0	0
422.00	9,400	14,500	14,500
424.00	14,000	23,400	37,900
426.00	18,700	32,700	70,600
428.00	23,700	42,400	113,000

Device	Routing	Invert	Outlet Devices
#1	Primary	419.00'	24.0" Round Culvert L= 85.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 419.00' / 408.00' S= 0.1294 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	419.00'	1.9" Vert. Orifice/Grate C= 0.600
#3	Device 2	420.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Device 1	424.50'	2.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.17 cfs @ 38.75 hrs HW=422.26' TW=0.00' (Dynamic Tailwater)



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 17

Pond 2.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 18

Summary for Pond 3.1P:

Inflow Area = 8.100 ac, 35.80% Impervious, Inflow Depth = 1.53" for 1 year event
 Inflow = 9.44 cfs @ 12.30 hrs, Volume= 1.031 af
 Outflow = 1.17 cfs @ 13.81 hrs, Volume= 1.028 af, Atten= 88%, Lag= 90.1 min
 Primary = 1.17 cfs @ 13.81 hrs, Volume= 1.028 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 448.00' Surf.Area= 15,300 sf Storage= 26,700 cf
 Peak Elev= 449.37' @ 13.81 hrs Surf.Area= 21,807 sf Storage= 52,116 cf (25,416 cf above start)

Plug-Flow detention time= 2,615.4 min calculated for 0.415 af (40% of inflow)
 Center-of-Mass det. time= 1,156.3 min (2,005.1 - 848.7)

Volume	Invert	Avail.Storage	Storage Description
#1	444.00'	124,600 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
444.00	1,200	0	0
446.00	5,100	6,300	6,300
448.00	15,300	20,400	26,700
450.00	24,800	40,100	66,800
452.00	33,000	57,800	124,600


Device	Routing	Invert	Outlet Devices
#1	Primary	444.00'	24.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 444.00' / 436.00' S= 0.0800 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	448.00'	2.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	449.20'	2.5' long x 0.5' breadth Broad-Crested Rectangular Weir X 2.00 Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=1.17 cfs @ 13.81 hrs HW=449.37' TW=425.65' (Dynamic Tailwater)

- 1=Culvert (Passes 1.17 cfs of 31.62 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.18 cfs @ 5.42 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 0.98 cfs @ 1.15 fps)

Pond 3.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 20

Summary for Pond 3.2P:

Inflow Area = 8.700 ac, 33.33% Impervious, Inflow Depth > 1.48" for 1 year event
 Inflow = 1.22 cfs @ 13.77 hrs, Volume= 1.076 af
 Outflow = 0.25 cfs @ 23.07 hrs, Volume= 1.076 af, Atten= 80%, Lag= 557.8 min
 Primary = 0.12 cfs @ 23.07 hrs, Volume= 0.986 af
 Secondary = 0.13 cfs @ 23.07 hrs, Volume= 0.090 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 428.37' @ 23.07 hrs Surf.Area= 6,885 sf Storage= 18,876 cf

Plug-Flow detention time= 1,819.3 min calculated for 1.076 af (100% of inflow)
 Center-of-Mass det. time= 1,818.5 min (3,772.0 - 1,953.5)

Volume	Invert	Avail.Storage	Storage Description
#1	424.00'	52,500 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
424.00	2,000	0	0
426.00	4,000	6,000	6,000
428.00	6,400	10,400	16,400
430.00	9,000	15,400	31,800
432.00	11,700	20,700	52,500

Device	Routing	Invert	Outlet Devices
#1	Primary	423.00'	15.0" Round Culvert L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 423.00' / 420.00' S= 0.0600 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	423.00'	1.4" Vert. Orifice/Grate C= 0.600
#3	Device 2	424.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Secondary	428.30'	2.5' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Primary OutFlow Max=0.12 cfs @ 23.07 hrs HW=428.37' TW=0.00' (Dynamic Tailwater)

- ↑1=Culvert (Passes 0.12 cfs of 12.88 cfs potential flow)
- ↑2=Orifice/Grate (Orifice Controls 0.12 cfs @ 11.10 fps)
- ↑3=Orifice/Grate (Passes 0.12 cfs of 4.38 cfs potential flow)

Secondary OutFlow Max=0.13 cfs @ 23.07 hrs HW=428.37' TW=0.00' (Dynamic Tailwater)

- ↑4=Broad-Crested Rectangular Weir (Weir Controls 0.13 cfs @ 0.73 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 1 year Rainfall=3.10"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 21

Pond 3.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 22

Summary for Subcatchment 2.1S:

Runoff = 12.31 cfs @ 12.18 hrs, Volume= 1.097 af, Depth= 1.94"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
2.900	98	Paved parking, HSG C
3.850	74	>75% Grass cover, Good, HSG C
* 0.050	89	Gravel, HSG C
6.800	84	Weighted Average
3.900		57.35% Pervious Area
2.900		42.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	100	0.0200	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.50"
1.9	110	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
1.3	190	0.0150	2.49		Shallow Concentrated Flow, Paved Kv= 20.3 fps
12.6	400	Total			

Subcatchment 2.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 23

Summary for Subcatchment 2.2S:

Runoff = 1.27 cfs @ 12.09 hrs, Volume= 0.093 af, Depth= 1.24"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
0.900	74	>75% Grass cover, Good, HSG C
0.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 24

Summary for Subcatchment 2.3S:

Runoff = 2.37 cfs @ 12.21 hrs, Volume= 0.235 af, Depth= 1.01"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
2.800	70	Woods, Good, HSG C
2.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	24	0.5000	0.33		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.0	76	0.1700	0.18		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.2	330	0.2400	2.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
3.1	400	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
13.5	830	Total			

Subcatchment 2.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 25

Summary for Subcatchment 3.1S:

Runoff = 11.53 cfs @ 12.30 hrs, Volume= 1.255 af, Depth= 1.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
2.900	98	Paved parking & roofs
4.450	74	>75% Grass cover, Good, HSG C
0.500	70	Woods, Good, HSG C
* 0.250	89	Gravel, HSG C
8.100	83	Weighted Average
5.200		64.20% Pervious Area
2.900		35.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.1	80	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	30	0.0450	1.48		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.9	150	0.0150	0.86		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.1	270	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
0.2	72	0.0100	4.91	3.86	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
0.1	48	0.0100	5.70	7.00	Pipe Channel, 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.012
0.5	610	0.0700	20.64	64.84	Pipe Channel, 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.012
21.4	1,360	Total			

The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 26

Subcatchment 3.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 27

Summary for Subcatchment 3.2S:

Runoff = 0.84 cfs @ 12.09 hrs, Volume= 0.062 af, Depth= 1.24"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
0.600	74	>75% Grass cover, Good, HSG C
0.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 3.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 28

Summary for Subcatchment 3.3S:

Runoff = 2.52 cfs @ 12.19 hrs, Volume= 0.244 af, Depth= 1.01"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
2.700	70	Woods, Good, HSG C
0.200	74	>75% Grass cover, Good, HSG C
2.900	70	Weighted Average
2.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	26	0.4200	0.32		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.6	74	0.1300	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
3.1	388	0.1700	2.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	207	0.0480	13.23	128.96	Trap/Vee/Rect Channel Flow, Bot.W=2.00' D=1.50' Z= 4.0 & 2.0 '/' Top.W=11.00' n= 0.022 Earth, clean & straight
12.4	695	Total			

Subcatchment 3.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 29

Summary for Subcatchment 4.1S:

Runoff = 5.48 cfs @ 12.30 hrs, Volume= 0.636 af, Depth= 0.95"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
7.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
8.000	69	Weighted Average
8.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 30

Summary for Subcatchment 5.1S:

Runoff = 3.92 cfs @ 12.23 hrs, Volume= 0.402 af, Depth= 1.12"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 year Rainfall=3.50"

Area (ac)	CN	Description
1.000	74	>75% Grass cover, Good, HSG C
3.150	70	Woods, Good, HSG C
* 0.150	89	Gravel, HSG C
4.300	72	Weighted Average
4.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.4	120	0.0800	1.41		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.6	220	Total			

Subcatchment 5.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 31


Summary for Reach DL4:

Inflow Area = 8.000 ac, 0.00% Impervious, Inflow Depth = 1.43" for 2 year event
Inflow = 5.48 cfs @ 12.30 hrs, Volume= 0.952 af
Outflow = 5.48 cfs @ 12.30 hrs, Volume= 0.952 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DL4:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 32


Summary for Reach DP 2:

Inflow Area = 10.500 ac, 27.62% Impervious, Inflow Depth = 1.63" for 2 year event
Inflow = 2.47 cfs @ 12.21 hrs, Volume= 1.423 af
Outflow = 2.47 cfs @ 12.21 hrs, Volume= 1.423 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 2:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 33


Summary for Reach DP 3:

Inflow Area = 11.600 ac, 25.00% Impervious, Inflow Depth = 1.28" for 2 year event
Inflow = 2.58 cfs @ 12.19 hrs, Volume= 1.241 af
Outflow = 2.58 cfs @ 12.19 hrs, Volume= 1.241 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 3:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 34

Summary for Pond 2.1P:

Inflow Area = 6.800 ac, 42.65% Impervious, Inflow Depth = 1.94" for 2 year event
 Inflow = 12.31 cfs @ 12.18 hrs, Volume= 1.097 af
 Outflow = 1.76 cfs @ 12.98 hrs, Volume= 1.095 af, Atten= 86%, Lag= 48.3 min
 Primary = 1.76 cfs @ 12.98 hrs, Volume= 1.095 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 439.00' Surf.Area= 13,300 sf Storage= 26,000 cf
 Peak Elev= 440.60' @ 12.98 hrs Surf.Area= 18,576 sf Storage= 51,479 cf (25,479 cf above start)

Plug-Flow detention time= 1,837.8 min calculated for 0.498 af (45% of inflow)
 Center-of-Mass det. time= 853.2 min (1,684.8 - 831.6)

Volume	Invert	Avail.Storage	Storage Description
#1	435.00'	106,100 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
435.00	1,500	0	0
437.00	5,600	7,100	7,100
439.00	13,300	18,900	26,000
441.00	19,900	33,200	59,200
443.00	27,000	46,900	106,100

Device	Routing	Invert	Outlet Devices
#1	Primary	434.00'	24.0" Round Culvert L= 70.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 434.00' / 423.00' S= 0.1571 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	439.00'	2.9" Vert. Orifice/Grate C= 0.600
#3	Device 1	440.40'	6.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=1.75 cfs @ 12.98 hrs HW=440.60' TW=420.79' (Dynamic Tailwater)

- 1=Culvert (Passes 1.75 cfs of 35.79 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.27 cfs @ 5.85 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 1.49 cfs @ 1.25 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 35

Pond 2.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 36

Summary for Pond 2.2P:

Inflow Area = 7.700 ac, 37.66% Impervious, Inflow Depth = 1.85" for 2 year event
 Inflow = 1.91 cfs @ 12.95 hrs, Volume= 1.188 af
 Outflow = 0.19 cfs @ 36.25 hrs, Volume= 1.188 af, Atten= 90%, Lag= 1,398.3 min
 Primary = 0.19 cfs @ 36.25 hrs, Volume= 1.188 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 422.92' @ 36.25 hrs Surf.Area= 11,509 sf Storage= 24,085 cf

Plug-Flow detention time= 1,591.2 min calculated for 1.188 af (100% of inflow)
 Center-of-Mass det. time= 1,590.2 min (3,210.2 - 1,620.0)

Volume	Invert	Avail.Storage	Storage Description
#1	420.00'	113,000 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
420.00	5,100	0	0
422.00	9,400	14,500	14,500
424.00	14,000	23,400	37,900
426.00	18,700	32,700	70,600
428.00	23,700	42,400	113,000

Device	Routing	Invert	Outlet Devices
#1	Primary	419.00'	24.0" Round Culvert L= 85.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 419.00' / 408.00' S= 0.1294 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	419.00'	1.9" Vert. Orifice/Grate C= 0.600
#3	Device 2	420.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Device 1	424.50'	2.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.19 cfs @ 36.25 hrs HW=422.92' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 0.19 cfs of 25.83 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.19 cfs @ 9.43 fps)
- 3=Orifice/Grate (Passes 0.19 cfs of 3.58 cfs potential flow)
- 4=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 37

Pond 2.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 38

Summary for Pond 3.1P:

Inflow Area = 8.100 ac, 35.80% Impervious, Inflow Depth = 1.86" for 2 year event
 Inflow = 11.53 cfs @ 12.30 hrs, Volume= 1.255 af
 Outflow = 2.37 cfs @ 13.05 hrs, Volume= 1.251 af, Atten= 79%, Lag= 45.1 min
 Primary = 2.37 cfs @ 13.05 hrs, Volume= 1.251 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 448.00' Surf.Area= 15,300 sf Storage= 26,700 cf
 Peak Elev= 449.49' @ 13.05 hrs Surf.Area= 22,356 sf Storage= 54,669 cf (27,969 cf above start)

Plug-Flow detention time= 1,963.0 min calculated for 0.638 af (51% of inflow)
 Center-of-Mass det. time= 967.5 min (1,810.5 - 843.1)

Volume	Invert	Avail.Storage	Storage Description
#1	444.00'	124,600 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
444.00	1,200	0	0
446.00	5,100	6,300	6,300
448.00	15,300	20,400	26,700
450.00	24,800	40,100	66,800
452.00	33,000	57,800	124,600

Device	Routing	Invert	Outlet Devices
#1	Primary	444.00'	24.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 444.00' / 436.00' S= 0.0800 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	448.00'	2.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	449.20'	2.5' long x 0.5' breadth Broad-Crested Rectangular Weir X 2.00 Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=2.37 cfs @ 13.05 hrs HW=449.49' TW=425.70' (Dynamic Tailwater)

- 1=Culvert (Passes 2.37 cfs of 32.04 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.19 cfs @ 5.66 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 2.17 cfs @ 1.52 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 39

Pond 3.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 2 year Rainfall=3.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 40

Summary for Pond 3.2P:

Inflow Area = 8.700 ac, 33.33% Impervious, Inflow Depth = 1.81" for 2 year event
 Inflow = 2.46 cfs @ 13.04 hrs, Volume= 1.313 af
 Outflow = 0.77 cfs @ 16.63 hrs, Volume= 1.313 af, Atten= 69%, Lag= 215.7 min
 Primary = 0.12 cfs @ 16.63 hrs, Volume= 0.998 af
 Secondary = 0.65 cfs @ 16.63 hrs, Volume= 0.316 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 428.51' @ 16.63 hrs Surf.Area= 7,064 sf Storage= 19,839 cf

Plug-Flow detention time= 1,536.9 min calculated for 1.313 af (100% of inflow)
 Center-of-Mass det. time= 1,536.5 min (3,302.0 - 1,765.5)

Volume	Invert	Avail.Storage	Storage Description
#1	424.00'	52,500 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
424.00	2,000	0	0
426.00	4,000	6,000	6,000
428.00	6,400	10,400	16,400
430.00	9,000	15,400	31,800
432.00	11,700	20,700	52,500

Device	Routing	Invert	Outlet Devices
#1	Primary	423.00'	15.0" Round Culvert L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 423.00' / 420.00' S= 0.0600 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	423.00'	1.4" Vert. Orifice/Grate C= 0.600
#3	Device 2	424.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Secondary	428.30'	2.5' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Primary OutFlow Max=0.12 cfs @ 16.63 hrs HW=428.51' TW=0.00' (Dynamic Tailwater)


- ↑1=Culvert (Passes 0.12 cfs of 13.06 cfs potential flow)
- ↑2=Orifice/Grate (Orifice Controls 0.12 cfs @ 11.24 fps)
- ↑3=Orifice/Grate (Passes 0.12 cfs of 4.45 cfs potential flow)

Secondary OutFlow Max=0.65 cfs @ 16.63 hrs HW=428.51' TW=0.00' (Dynamic Tailwater)

- ↑4=Broad-Crested Rectangular Weir (Weir Controls 0.65 cfs @ 1.24 fps)

Pond 3.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 42

Summary for Subcatchment 2.1S:

Runoff = 23.66 cfs @ 12.17 hrs, Volume= 2.114 af, Depth= 3.73"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
2.900	98	Paved parking, HSG C
3.850	74	>75% Grass cover, Good, HSG C
* 0.050	89	Gravel, HSG C
6.800	84	Weighted Average
3.900		57.35% Pervious Area
2.900		42.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	100	0.0200	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.50"
1.9	110	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
1.3	190	0.0150	2.49		Shallow Concentrated Flow, Paved Kv= 20.3 fps
12.6	400	Total			

Subcatchment 2.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 43

Summary for Subcatchment 2.2S:

Runoff = 2.92 cfs @ 12.08 hrs, Volume= 0.208 af, Depth= 2.77"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
0.900	74	>75% Grass cover, Good, HSG C
0.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 44

Summary for Subcatchment 2.3S:

Runoff = 6.11 cfs @ 12.20 hrs, Volume= 0.563 af, Depth= 2.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
2.800	70	Woods, Good, HSG C
2.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	24	0.5000	0.33		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.0	76	0.1700	0.18		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.2	330	0.2400	2.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
3.1	400	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
13.5	830	Total			

Subcatchment 2.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 45

Summary for Subcatchment 3.1S:

Runoff = 22.41 cfs @ 12.29 hrs, Volume= 2.450 af, Depth= 3.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
2.900	98	Paved parking & roofs
4.450	74	>75% Grass cover, Good, HSG C
0.500	70	Woods, Good, HSG C
* 0.250	89	Gravel, HSG C
8.100	83	Weighted Average
5.200		64.20% Pervious Area
2.900		35.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.1	80	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	30	0.0450	1.48		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.9	150	0.0150	0.86		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.1	270	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
0.2	72	0.0100	4.91	3.86	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
0.1	48	0.0100	5.70	7.00	Pipe Channel, 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.012
0.5	610	0.0700	20.64	64.84	Pipe Channel, 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.012
21.4	1,360	Total			

The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 46

Subcatchment 3.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 47

Summary for Subcatchment 3.2S:

Runoff = 1.95 cfs @ 12.08 hrs, Volume= 0.138 af, Depth= 2.77"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
0.600	74	>75% Grass cover, Good, HSG C
0.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 3.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 48

Summary for Subcatchment 3.3S:

Runoff = 6.50 cfs @ 12.18 hrs, Volume= 0.583 af, Depth= 2.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
2.700	70	Woods, Good, HSG C
0.200	74	>75% Grass cover, Good, HSG C
2.900	70	Weighted Average
2.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	26	0.4200	0.32		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.6	74	0.1300	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
3.1	388	0.1700	2.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	207	0.0480	13.23	128.96	Trap/Vee/Rect Channel Flow, Bot.W=2.00' D=1.50' Z= 4.0 & 2.0 '/' Top.W=11.00' n= 0.022 Earth, clean & straight
12.4	695	Total			

Subcatchment 3.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 49

Summary for Subcatchment 4.1S:

Runoff = 14.55 cfs @ 12.28 hrs, Volume= 1.552 af, Depth= 2.33"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
7.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
8.000	69	Weighted Average
8.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 50

Summary for Subcatchment 5.1S:

Runoff = 9.63 cfs @ 12.22 hrs, Volume= 0.928 af, Depth= 2.59"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 year Rainfall=5.50"

Area (ac)	CN	Description
1.000	74	>75% Grass cover, Good, HSG C
3.150	70	Woods, Good, HSG C
* 0.150	89	Gravel, HSG C
4.300	72	Weighted Average
4.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.4	120	0.0800	1.41		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.6	220	Total			

Subcatchment 5.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 51


Summary for Reach DL4:

Inflow Area = 8.000 ac, 0.00% Impervious, Inflow Depth = 4.68" for 10 year event
Inflow = 14.55 cfs @ 12.28 hrs, Volume= 3.118 af
Outflow = 14.55 cfs @ 12.28 hrs, Volume= 3.118 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DL4:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 52


Summary for Reach DP 2:

Inflow Area = 10.500 ac, 27.62% Impervious, Inflow Depth = 3.29" for 10 year event
Inflow = 6.24 cfs @ 12.20 hrs, Volume= 2.883 af
Outflow = 6.24 cfs @ 12.20 hrs, Volume= 2.883 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 2:

Hydrograph




Summary for Reach DP 3:

Inflow Area = 11.600 ac, 25.00% Impervious, Inflow Depth = 1.66" for 10 year event
Inflow = 6.57 cfs @ 12.18 hrs, Volume= 1.603 af
Outflow = 6.57 cfs @ 12.18 hrs, Volume= 1.603 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 3:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 54

Summary for Pond 2.1P:

Inflow Area = 6.800 ac, 42.65% Impervious, Inflow Depth = 3.73" for 10 year event
 Inflow = 23.66 cfs @ 12.17 hrs, Volume= 2.114 af
 Outflow = 12.66 cfs @ 12.41 hrs, Volume= 2.112 af, Atten= 46%, Lag= 14.4 min
 Primary = 12.66 cfs @ 12.41 hrs, Volume= 2.112 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 439.00' Surf.Area= 13,300 sf Storage= 26,000 cf
 Peak Elev= 441.14' @ 12.41 hrs Surf.Area= 20,396 sf Storage= 62,018 cf (36,018 cf above start)

Plug-Flow detention time= 781.2 min calculated for 1.515 af (72% of inflow)
 Center-of-Mass det. time= 477.5 min (1,290.4 - 812.9)

Volume	Invert	Avail.Storage	Storage Description
#1	435.00'	106,100 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
435.00	1,500	0	0
437.00	5,600	7,100	7,100
439.00	13,300	18,900	26,000
441.00	19,900	33,200	59,200
443.00	27,000	46,900	106,100


Device	Routing	Invert	Outlet Devices
#1	Primary	434.00'	24.0" Round Culvert L= 70.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 434.00' / 423.00' S= 0.1571 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	439.00'	2.9" Vert. Orifice/Grate C= 0.600
#3	Device 1	440.40'	6.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=12.62 cfs @ 12.41 hrs HW=441.14' TW=421.96' (Dynamic Tailwater)

- 1=Culvert (Passes 12.62 cfs of 37.48 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.31 cfs @ 6.84 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 12.30 cfs @ 2.78 fps)

Pond 2.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 56

Summary for Pond 2.2P:

Inflow Area = 7.700 ac, 37.66% Impervious, Inflow Depth = 3.62" for 10 year event
 Inflow = 13.62 cfs @ 12.40 hrs, Volume= 2.320 af
 Outflow = 1.38 cfs @ 15.75 hrs, Volume= 2.320 af, Atten= 90%, Lag= 201.4 min
 Primary = 1.38 cfs @ 15.75 hrs, Volume= 2.320 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 424.84' @ 15.75 hrs Surf.Area= 15,978 sf Storage= 50,514 cf

Plug-Flow detention time= 1,918.0 min calculated for 2.320 af (100% of inflow)
 Center-of-Mass det. time= 1,917.5 min (3,166.9 - 1,249.4)

Volume	Invert	Avail.Storage	Storage Description
#1	420.00'	113,000 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
420.00	5,100	0	0
422.00	9,400	14,500	14,500
424.00	14,000	23,400	37,900
426.00	18,700	32,700	70,600
428.00	23,700	42,400	113,000


Device	Routing	Invert	Outlet Devices
#1	Primary	419.00'	24.0" Round Culvert L= 85.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 419.00' / 408.00' S= 0.1294 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	419.00'	1.9" Vert. Orifice/Grate C= 0.600
#3	Device 2	420.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Device 1	424.50'	2.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=1.38 cfs @ 15.75 hrs HW=424.84' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 1.38 cfs of 33.28 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.23 cfs @ 11.56 fps)
- 3=Orifice/Grate (Passes 0.23 cfs of 4.61 cfs potential flow)
- 4=Broad-Crested Rectangular Weir (Weir Controls 1.15 cfs @ 1.69 fps)

Pond 2.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 58

Summary for Pond 3.1P:

Inflow Area = 8.100 ac, 35.80% Impervious, Inflow Depth = 3.63" for 10 year event
 Inflow = 22.41 cfs @ 12.29 hrs, Volume= 2.450 af
 Outflow = 12.87 cfs @ 12.59 hrs, Volume= 2.447 af, Atten= 43%, Lag= 18.1 min
 Primary = 12.87 cfs @ 12.59 hrs, Volume= 2.447 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 448.00' Surf.Area= 15,300 sf Storage= 26,700 cf
 Peak Elev= 450.04' @ 12.59 hrs Surf.Area= 24,950 sf Storage= 67,712 cf (41,012 cf above start)

Plug-Flow detention time= 812.5 min calculated for 1.834 af (75% of inflow)
 Center-of-Mass det. time= 528.2 min (1,352.1 - 823.9)

Volume	Invert	Avail.Storage	Storage Description
#1	444.00'	124,600 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
444.00	1,200	0	0
446.00	5,100	6,300	6,300
448.00	15,300	20,400	26,700
450.00	24,800	40,100	66,800
452.00	33,000	57,800	124,600


Device	Routing	Invert	Outlet Devices
#1	Primary	444.00'	24.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 444.00' / 436.00' S= 0.0800 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	448.00'	2.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	449.20'	2.5' long x 0.5' breadth Broad-Crested Rectangular Weir X 2.00 Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=12.85 cfs @ 12.59 hrs HW=450.04' TW=427.96' (Dynamic Tailwater)

- 1=Culvert (Passes 12.85 cfs of 33.95 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.23 cfs @ 6.69 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 12.62 cfs @ 3.02 fps)

Pond 3.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 10 year Rainfall=5.50"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 60

Summary for Pond 3.2P:

Inflow Area = 8.700 ac, 33.33% Impervious, Inflow Depth = 3.57" for 10 year event
 Inflow = 13.17 cfs @ 12.58 hrs, Volume= 2.585 af
 Outflow = 8.07 cfs @ 13.04 hrs, Volume= 2.585 af, Atten= 39%, Lag= 27.2 min
 Primary = 0.13 cfs @ 13.04 hrs, Volume= 1.020 af
 Secondary = 7.95 cfs @ 13.04 hrs, Volume= 1.566 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 429.34' @ 13.04 hrs Surf.Area= 8,141 sf Storage= 26,138 cf

Plug-Flow detention time= 810.9 min calculated for 2.585 af (100% of inflow)
 Center-of-Mass det. time= 810.7 min (2,134.9 - 1,324.2)

Volume	Invert	Avail.Storage	Storage Description
#1	424.00'	52,500 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
424.00	2,000	0	0
426.00	4,000	6,000	6,000
428.00	6,400	10,400	16,400
430.00	9,000	15,400	31,800
432.00	11,700	20,700	52,500

Device	Routing	Invert	Outlet Devices
#1	Primary	423.00'	15.0" Round Culvert L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 423.00' / 420.00' S= 0.0600 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	423.00'	1.4" Vert. Orifice/Grate C= 0.600
#3	Device 2	424.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Secondary	428.30'	2.5' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Primary OutFlow Max=0.13 cfs @ 13.04 hrs HW=429.34' TW=0.00' (Dynamic Tailwater)


- ↑1=Culvert (Passes 0.13 cfs of 14.12 cfs potential flow)
- ↑2=Orifice/Grate (Orifice Controls 0.13 cfs @ 12.07 fps)
- ↑3=Orifice/Grate (Passes 0.13 cfs of 4.84 cfs potential flow)

Secondary OutFlow Max=7.93 cfs @ 13.04 hrs HW=429.34' TW=0.00' (Dynamic Tailwater)

- ↑4=Broad-Crested Rectangular Weir (Weir Controls 7.93 cfs @ 3.06 fps)

Pond 3.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 62

Summary for Subcatchment 2.1S:

Runoff = 26.52 cfs @ 12.17 hrs, Volume= 2.378 af, Depth= 4.20"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
2.900	98	Paved parking, HSG C
3.850	74	>75% Grass cover, Good, HSG C
* 0.050	89	Gravel, HSG C
6.800	84	Weighted Average
3.900		57.35% Pervious Area
2.900		42.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	100	0.0200	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.50"
1.9	110	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
1.3	190	0.0150	2.49		Shallow Concentrated Flow, Paved Kv= 20.3 fps
12.6	400	Total			

Subcatchment 2.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 63

Summary for Subcatchment 2.2S:

Runoff = 3.36 cfs @ 12.08 hrs, Volume= 0.239 af, Depth= 3.18"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
0.900	74	>75% Grass cover, Good, HSG C
0.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 64

Summary for Subcatchment 2.3S:

Runoff = 7.14 cfs @ 12.19 hrs, Volume= 0.655 af, Depth= 2.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
2.800	70	Woods, Good, HSG C
2.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	24	0.5000	0.33		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.0	76	0.1700	0.18		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.2	330	0.2400	2.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
3.1	400	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
13.5	830	Total			

Subcatchment 2.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 65

Summary for Subcatchment 3.1S:

Runoff = 25.19 cfs @ 12.29 hrs, Volume= 2.762 af, Depth= 4.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
2.900	98	Paved parking & roofs
4.450	74	>75% Grass cover, Good, HSG C
0.500	70	Woods, Good, HSG C
* 0.250	89	Gravel, HSG C
8.100	83	Weighted Average
5.200		64.20% Pervious Area
2.900		35.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.1	80	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	30	0.0450	1.48		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.9	150	0.0150	0.86		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.1	270	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
0.2	72	0.0100	4.91	3.86	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
0.1	48	0.0100	5.70	7.00	Pipe Channel, 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.012
0.5	610	0.0700	20.64	64.84	Pipe Channel, 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.012
21.4	1,360	Total			

The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 66

Subcatchment 3.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 67

Summary for Subcatchment 3.2S:

Runoff = 2.24 cfs @ 12.08 hrs, Volume= 0.159 af, Depth= 3.18"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
0.600	74	>75% Grass cover, Good, HSG C
0.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 3.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 68

Summary for Subcatchment 3.3S:

Runoff = 7.59 cfs @ 12.18 hrs, Volume= 0.678 af, Depth= 2.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
2.700	70	Woods, Good, HSG C
0.200	74	>75% Grass cover, Good, HSG C
2.900	70	Weighted Average
2.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	26	0.4200	0.32		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.6	74	0.1300	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
3.1	388	0.1700	2.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	207	0.0480	13.23	128.96	Trap/Vee/Rect Channel Flow, Bot.W=2.00' D=1.50' Z= 4.0 & 2.0 '/' Top.W=11.00' n= 0.022 Earth, clean & straight
12.4	695	Total			

Subcatchment 3.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 69

Summary for Subcatchment 4.1S:

Runoff = 17.06 cfs @ 12.28 hrs, Volume= 1.808 af, Depth= 2.71"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
7.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
8.000	69	Weighted Average
8.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 70

Summary for Subcatchment 5.1S:

Runoff = 11.17 cfs @ 12.22 hrs, Volume= 1.073 af, Depth= 2.99"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 25 year Rainfall=6.00"

Area (ac)	CN	Description
1.000	74	>75% Grass cover, Good, HSG C
3.150	70	Woods, Good, HSG C
* 0.150	89	Gravel, HSG C
4.300	72	Weighted Average
4.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.4	120	0.0800	1.41		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.6	220	Total			

Subcatchment 5.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 71


Summary for Reach DL4:

Inflow Area = 8.000 ac, 0.00% Impervious, Inflow Depth = 5.55" for 25 year event
Inflow = 17.06 cfs @ 12.28 hrs, Volume= 3.703 af
Outflow = 17.06 cfs @ 12.28 hrs, Volume= 3.703 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DL4:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 72


Summary for Reach DP 2:

Inflow Area = 10.500 ac, 27.62% Impervious, Inflow Depth = 3.74" for 25 year event
Inflow = 7.28 cfs @ 12.19 hrs, Volume= 3.269 af
Outflow = 7.28 cfs @ 12.19 hrs, Volume= 3.269 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 2:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 73


Summary for Reach DP 3:

Inflow Area = 11.600 ac, 25.00% Impervious, Inflow Depth = 1.76" for 25 year event
Inflow = 7.67 cfs @ 12.18 hrs, Volume= 1.701 af
Outflow = 7.67 cfs @ 12.18 hrs, Volume= 1.701 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 3:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 74

Summary for Pond 2.1P:

Inflow Area = 6.800 ac, 42.65% Impervious, Inflow Depth = 4.20" for 25 year event
 Inflow = 26.52 cfs @ 12.17 hrs, Volume= 2.378 af
 Outflow = 15.77 cfs @ 12.37 hrs, Volume= 2.376 af, Atten= 41%, Lag= 12.0 min
 Primary = 15.77 cfs @ 12.37 hrs, Volume= 2.376 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 439.00' Surf.Area= 13,300 sf Storage= 26,000 cf
 Peak Elev= 441.25' @ 12.37 hrs Surf.Area= 20,776 sf Storage= 64,220 cf (38,220 cf above start)

Plug-Flow detention time= 682.7 min calculated for 1.779 af (75% of inflow)
 Center-of-Mass det. time= 430.6 min (1,240.2 - 809.6)

Volume	Invert	Avail.Storage	Storage Description
#1	435.00'	106,100 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
435.00	1,500	0	0
437.00	5,600	7,100	7,100
439.00	13,300	18,900	26,000
441.00	19,900	33,200	59,200
443.00	27,000	46,900	106,100

Device	Routing	Invert	Outlet Devices
#1	Primary	434.00'	24.0" Round Culvert L= 70.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 434.00' / 423.00' S= 0.1571 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	439.00'	2.9" Vert. Orifice/Grate C= 0.600
#3	Device 1	440.40'	6.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=15.69 cfs @ 12.37 hrs HW=441.24' TW=422.25' (Dynamic Tailwater)

- 1=Culvert (Passes 15.69 cfs of 37.80 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.32 cfs @ 7.02 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 15.37 cfs @ 3.04 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 75

Pond 2.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 76

Summary for Pond 2.2P:

Inflow Area = 7.700 ac, 37.66% Impervious, Inflow Depth = 4.07" for 25 year event
 Inflow = 16.99 cfs @ 12.36 hrs, Volume= 2.615 af
 Outflow = 2.16 cfs @ 14.55 hrs, Volume= 2.615 af, Atten= 87%, Lag= 131.5 min
 Primary = 2.16 cfs @ 14.55 hrs, Volume= 2.615 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 424.97' @ 14.55 hrs Surf.Area= 16,283 sf Storage= 52,609 cf


Plug-Flow detention time= 1,716.3 min calculated for 2.614 af (100% of inflow)
 Center-of-Mass det. time= 1,715.7 min (2,918.2 - 1,202.6)

Volume	Invert	Avail.Storage	Storage Description
#1	420.00'	113,000 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
420.00	5,100	0	0
422.00	9,400	14,500	14,500
424.00	14,000	23,400	37,900
426.00	18,700	32,700	70,600
428.00	23,700	42,400	113,000


Device	Routing	Invert	Outlet Devices
#1	Primary	419.00'	24.0" Round Culvert L= 85.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 419.00' / 408.00' S= 0.1294 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	419.00'	1.9" Vert. Orifice/Grate C= 0.600
#3	Device 2	420.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Device 1	424.50'	2.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=2.16 cfs @ 14.55 hrs HW=424.97' TW=0.00' (Dynamic Tailwater)



Pond 2.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 78

Summary for Pond 3.1P:

Inflow Area = 8.100 ac, 35.80% Impervious, Inflow Depth = 4.09" for 25 year event
 Inflow = 25.19 cfs @ 12.29 hrs, Volume= 2.762 af
 Outflow = 15.59 cfs @ 12.56 hrs, Volume= 2.758 af, Atten= 38%, Lag= 16.2 min
 Primary = 15.59 cfs @ 12.56 hrs, Volume= 2.758 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 448.00' Surf.Area= 15,300 sf Storage= 26,700 cf
 Peak Elev= 450.15' @ 12.56 hrs Surf.Area= 25,417 sf Storage= 70,579 cf (43,879 cf above start)

Plug-Flow detention time= 710.5 min calculated for 2.145 af (78% of inflow)
 Center-of-Mass det. time= 475.1 min (1,295.6 - 820.5)

Volume	Invert	Avail.Storage	Storage Description
#1	444.00'	124,600 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
444.00	1,200	0	0
446.00	5,100	6,300	6,300
448.00	15,300	20,400	26,700
450.00	24,800	40,100	66,800
452.00	33,000	57,800	124,600

Device	Routing	Invert	Outlet Devices
#1	Primary	444.00'	24.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 444.00' / 436.00' S= 0.0800 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	448.00'	2.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	449.20'	2.5' long x 0.5' breadth Broad-Crested Rectangular Weir X 2.00 Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=15.56 cfs @ 12.56 hrs HW=450.15' TW=428.52' (Dynamic Tailwater)

- 1=Culvert (Passes 15.56 cfs of 34.33 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.23 cfs @ 6.89 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 15.33 cfs @ 3.23 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 79

Pond 3.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 80

Summary for Pond 3.2P:

Inflow Area = 8.700 ac, 33.33% Impervious, Inflow Depth = 4.02" for 25 year event
 Inflow = 15.98 cfs @ 12.55 hrs, Volume= 2.918 af
 Outflow = 11.22 cfs @ 12.91 hrs, Volume= 2.918 af, Atten= 30%, Lag= 21.8 min
 Primary = 0.13 cfs @ 12.91 hrs, Volume= 1.023 af
 Secondary = 11.09 cfs @ 12.91 hrs, Volume= 1.895 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 429.56' @ 12.91 hrs Surf.Area= 8,434 sf Storage= 28,008 cf

Plug-Flow detention time= 722.1 min calculated for 2.917 af (100% of inflow)
 Center-of-Mass det. time= 721.8 min (1,991.8 - 1,270.1)

Volume	Invert	Avail.Storage	Storage Description
#1	424.00'	52,500 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
424.00	2,000	0	0
426.00	4,000	6,000	6,000
428.00	6,400	10,400	16,400
430.00	9,000	15,400	31,800
432.00	11,700	20,700	52,500

Device	Routing	Invert	Outlet Devices
#1	Primary	423.00'	15.0" Round Culvert L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 423.00' / 420.00' S= 0.0600 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	423.00'	1.4" Vert. Orifice/Grate C= 0.600
#3	Device 2	424.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Secondary	428.30'	2.5' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Primary OutFlow Max=0.13 cfs @ 12.91 hrs HW=429.56' TW=0.00' (Dynamic Tailwater)

- ↑1=Culvert (Passes 0.13 cfs of 14.40 cfs potential flow)
- ↑2=Orifice/Grate (Orifice Controls 0.13 cfs @ 12.28 fps)
- ↑3=Orifice/Grate (Passes 0.13 cfs of 4.95 cfs potential flow)

Secondary OutFlow Max=11.06 cfs @ 12.91 hrs HW=429.56' TW=0.00' (Dynamic Tailwater)

- ↑4=Broad-Crested Rectangular Weir (Weir Controls 11.06 cfs @ 3.50 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 25 year Rainfall=6.00"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 81

Pond 3.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 82

Summary for Subcatchment 2.1S:

Runoff = 47.61 cfs @ 12.17 hrs, Volume= 4.385 af, Depth= 7.74"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
2.900	98	Paved parking, HSG C
3.850	74	>75% Grass cover, Good, HSG C
* 0.050	89	Gravel, HSG C
6.800	84	Weighted Average
3.900		57.35% Pervious Area
2.900		42.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	100	0.0200	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.50"
1.9	110	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
1.3	190	0.0150	2.49		Shallow Concentrated Flow, Paved Kv= 20.3 fps
12.6	400	Total			

Subcatchment 2.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 83

Summary for Subcatchment 2.2S:

Runoff = 6.80 cfs @ 12.07 hrs, Volume= 0.485 af, Depth= 6.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
0.900	74	>75% Grass cover, Good, HSG C
0.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 84

Summary for Subcatchment 2.3S:

Runoff = 15.24 cfs @ 12.19 hrs, Volume= 1.390 af, Depth= 5.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
2.800	70	Woods, Good, HSG C
2.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	24	0.5000	0.33		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.0	76	0.1700	0.18		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
2.2	330	0.2400	2.45		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
3.1	400	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
13.5	830	Total			

Subcatchment 2.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 85

Summary for Subcatchment 3.1S:

Runoff = 45.74 cfs @ 12.29 hrs, Volume= 5.138 af, Depth= 7.61"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
2.900	98	Paved parking & roofs
4.450	74	>75% Grass cover, Good, HSG C
0.500	70	Woods, Good, HSG C
* 0.250	89	Gravel, HSG C
8.100	83	Weighted Average
5.200		64.20% Pervious Area
2.900		35.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.1	80	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	30	0.0450	1.48		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.9	150	0.0150	0.86		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
2.1	270	0.0200	2.12		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
0.2	72	0.0100	4.91	3.86	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.012
0.1	48	0.0100	5.70	7.00	Pipe Channel, 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.012
0.5	610	0.0700	20.64	64.84	Pipe Channel, 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.012
21.4	1,360	Total			

The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 86

Subcatchment 3.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 87

Summary for Subcatchment 3.2S:

Runoff = 4.54 cfs @ 12.07 hrs, Volume= 0.324 af, Depth= 6.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
0.600	74	>75% Grass cover, Good, HSG C
0.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 3.2S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 88

Summary for Subcatchment 3.3S:

Runoff = 16.32 cfs @ 12.17 hrs, Volume= 1.439 af, Depth= 5.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
2.700	70	Woods, Good, HSG C
0.200	74	>75% Grass cover, Good, HSG C
2.900	70	Weighted Average
2.900		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	26	0.4200	0.32		Sheet Flow, Grass: Dense n= 0.240 P2= 3.50"
7.6	74	0.1300	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
3.1	388	0.1700	2.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.3	207	0.0480	13.23	128.96	Trap/Vee/Rect Channel Flow, Bot.W=2.00' D=1.50' Z= 4.0 & 2.0 '/' Top.W=11.00' n= 0.022 Earth, clean & straight
12.4	695	Total			

Subcatchment 3.3S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 89

Summary for Subcatchment 4.1S:

Runoff = 37.15 cfs @ 12.27 hrs, Volume= 3.885 af, Depth= 5.83"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
7.300	70	Woods, Good, HSG C
0.700	55	Woods, Good, HSG B
8.000	69	Weighted Average
8.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.3	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
8.2	980	0.1600	2.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	1,080	Total			

Subcatchment 4.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 90

Summary for Subcatchment 5.1S:

Runoff = 23.20 cfs @ 12.21 hrs, Volume= 2.227 af, Depth= 6.21"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 year Rainfall=9.70"

Area (ac)	CN	Description
1.000	74	>75% Grass cover, Good, HSG C
3.150	70	Woods, Good, HSG C
* 0.150	89	Gravel, HSG C
4.300	72	Weighted Average
4.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.2	100	0.0500	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.50"
1.4	120	0.0800	1.41		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.6	220	Total			

Subcatchment 5.1S:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 91


Summary for Reach DL4:

Inflow Area = 8.000 ac, 0.00% Impervious, Inflow Depth = 12.45" for 100 year event
Inflow = 55.06 cfs @ 12.39 hrs, Volume= 8.300 af
Outflow = 55.06 cfs @ 12.39 hrs, Volume= 8.300 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DL4:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 92


Summary for Reach DP 2:

Inflow Area = 10.500 ac, 27.62% Impervious, Inflow Depth = 7.15" for 100 year event
Inflow = 20.32 cfs @ 12.62 hrs, Volume= 6.257 af
Outflow = 20.32 cfs @ 12.62 hrs, Volume= 6.257 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 2:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 93


Summary for Reach DP 3:

Inflow Area = 11.600 ac, 25.00% Impervious, Inflow Depth = 2.57" for 100 year event
Inflow = 16.45 cfs @ 12.17 hrs, Volume= 2.483 af
Outflow = 16.45 cfs @ 12.17 hrs, Volume= 2.483 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs

Reach DP 3:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 94

Summary for Pond 2.1P:

Inflow Area = 6.800 ac, 42.65% Impervious, Inflow Depth = 7.74" for 100 year event
 Inflow = 47.61 cfs @ 12.17 hrs, Volume= 4.385 af
 Outflow = 34.76 cfs @ 12.30 hrs, Volume= 4.383 af, Atten= 27%, Lag= 7.9 min
 Primary = 34.76 cfs @ 12.30 hrs, Volume= 4.383 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 439.00' Surf.Area= 13,300 sf Storage= 26,000 cf
 Peak Elev= 441.84' @ 12.30 hrs Surf.Area= 22,879 sf Storage= 77,150 cf (51,150 cf above start)

Plug-Flow detention time= 371.3 min calculated for 3.786 af (86% of inflow)
 Center-of-Mass det. time= 256.2 min (1,048.9 - 792.7)

Volume	Invert	Avail.Storage	Storage Description
#1	435.00'	106,100 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
435.00	1,500	0	0
437.00	5,600	7,100	7,100
439.00	13,300	18,900	26,000
441.00	19,900	33,200	59,200
443.00	27,000	46,900	106,100

Device	Routing	Invert	Outlet Devices
#1	Primary	434.00'	24.0" Round Culvert L= 70.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 434.00' / 423.00' S= 0.1571 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	439.00'	2.9" Vert. Orifice/Grate C= 0.600
#3	Device 1	440.40'	6.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=34.76 cfs @ 12.30 hrs HW=441.84' TW=424.89' (Dynamic Tailwater)

- 1=Culvert (Passes 34.76 cfs of 39.56 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.36 cfs @ 7.94 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 34.39 cfs @ 3.98 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 95

Pond 2.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 96

Summary for Pond 2.2P:

Inflow Area = 7.700 ac, 37.66% Impervious, Inflow Depth = 7.59" for 100 year event
 Inflow = 37.51 cfs @ 12.29 hrs, Volume= 4.868 af
 Outflow = 16.77 cfs @ 12.75 hrs, Volume= 4.868 af, Atten= 55%, Lag= 27.8 min
 Primary = 16.77 cfs @ 12.75 hrs, Volume= 4.868 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 426.34' @ 12.75 hrs Surf.Area= 19,540 sf Storage= 77,021 cf

Plug-Flow detention time= 952.5 min calculated for 4.868 af (100% of inflow)
 Center-of-Mass det. time= 952.3 min (1,977.2 - 1,024.9)

Volume	Invert	Avail.Storage	Storage Description
#1	420.00'	113,000 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
420.00	5,100	0	0
422.00	9,400	14,500	14,500
424.00	14,000	23,400	37,900
426.00	18,700	32,700	70,600
428.00	23,700	42,400	113,000

Device	Routing	Invert	Outlet Devices
#1	Primary	419.00'	24.0" Round Culvert L= 85.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 419.00' / 408.00' S= 0.1294 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	419.00'	1.9" Vert. Orifice/Grate C= 0.600
#3	Device 2	420.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Device 1	424.50'	2.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=16.77 cfs @ 12.75 hrs HW=426.34' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 16.77 cfs of 38.07 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.26 cfs @ 12.97 fps)
- 3=Orifice/Grate (Passes 0.26 cfs of 5.28 cfs potential flow)
- 4=Broad-Crested Rectangular Weir (Weir Controls 16.51 cfs @ 4.50 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 97

Pond 2.2P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 98

Summary for Pond 3.1P:

Inflow Area = 8.100 ac, 35.80% Impervious, Inflow Depth = 7.61" for 100 year event
 Inflow = 45.74 cfs @ 12.29 hrs, Volume= 5.138 af
 Outflow = 33.72 cfs @ 12.48 hrs, Volume= 5.135 af, Atten= 26%, Lag= 11.6 min
 Primary = 33.72 cfs @ 12.48 hrs, Volume= 5.135 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Starting Elev= 448.00' Surf.Area= 15,300 sf Storage= 26,700 cf
 Peak Elev= 450.80' @ 12.48 hrs Surf.Area= 28,061 sf Storage= 87,821 cf (61,121 cf above start)

Plug-Flow detention time= 382.9 min calculated for 4.521 af (88% of inflow)
 Center-of-Mass det. time= 279.4 min (1,082.7 - 803.3)

Volume	Invert	Avail.Storage	Storage Description
#1	444.00'	124,600 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
444.00	1,200	0	0
446.00	5,100	6,300	6,300
448.00	15,300	20,400	26,700
450.00	24,800	40,100	66,800
452.00	33,000	57,800	124,600

Device	Routing	Invert	Outlet Devices
#1	Primary	444.00'	24.0" Round Culvert L= 100.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 444.00' / 436.00' S= 0.0800 '/' Cc= 0.900 n= 0.012, Flow Area= 3.14 sf
#2	Device 1	448.00'	2.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	449.20'	2.5' long x 0.5' breadth Broad-Crested Rectangular Weir X 2.00 Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=33.63 cfs @ 12.48 hrs HW=450.79' TW=430.58' (Dynamic Tailwater)

- 1=Culvert (Passes 33.63 cfs of 36.41 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.27 cfs @ 7.89 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 33.36 cfs @ 4.19 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 99

Pond 3.1P:

Hydrograph



The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 100

Summary for Pond 3.2P:

Inflow Area = 8.700 ac, 33.33% Impervious, Inflow Depth = 7.53" for 100 year event
 Inflow = 34.82 cfs @ 12.47 hrs, Volume= 5.459 af
 Outflow = 31.62 cfs @ 12.63 hrs, Volume= 5.458 af, Atten= 9%, Lag= 9.7 min
 Primary = 0.14 cfs @ 12.63 hrs, Volume= 1.044 af
 Secondary = 31.47 cfs @ 12.63 hrs, Volume= 4.415 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-300.00 hrs, dt= 0.05 hrs
 Peak Elev= 430.74' @ 12.63 hrs Surf.Area= 9,995 sf Storage= 38,803 cf

Plug-Flow detention time= 397.3 min calculated for 5.458 af (100% of inflow)
 Center-of-Mass det. time= 397.2 min (1,463.5 - 1,066.4)

Volume	Invert	Avail.Storage	Storage Description
#1	424.00'	52,500 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
424.00	2,000	0	0
426.00	4,000	6,000	6,000
428.00	6,400	10,400	16,400
430.00	9,000	15,400	31,800
432.00	11,700	20,700	52,500

Device	Routing	Invert	Outlet Devices
#1	Primary	423.00'	15.0" Round Culvert L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 423.00' / 420.00' S= 0.0600 '/' Cc= 0.900 n= 0.012, Flow Area= 1.23 sf
#2	Device 1	423.00'	1.4" Vert. Orifice/Grate C= 0.600
#3	Device 2	424.00'	0.5" Vert. Orifice/Grate X 320.00 C= 0.600
#4	Secondary	428.30'	2.5' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32

Primary OutFlow Max=0.14 cfs @ 12.63 hrs HW=430.73' TW=0.00' (Dynamic Tailwater)

- ↑ 1=Culvert (Passes 0.14 cfs of 15.75 cfs potential flow)
- ↑ 2=Orifice/Grate (Orifice Controls 0.14 cfs @ 13.34 fps)
- ↑ 3=Orifice/Grate (Passes 0.14 cfs of 5.44 cfs potential flow)

Secondary OutFlow Max=31.41 cfs @ 12.63 hrs HW=430.73' TW=0.00' (Dynamic Tailwater)

- ↑ 4=Broad-Crested Rectangular Weir (Weir Controls 31.41 cfs @ 5.16 fps)

The Hamlet at Carmel Post Development

Type III 24-hr 100 year Rainfall=9.70"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.


Printed 4/10/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 101

Pond 3.2P:

Hydrograph



APPENDIX C
Pollutant Loading Calculations

**THE HAMLET AT CARMEL, MULTI-FAMILY HOUSING DEVELOPMENT
PRE-DEVELOPMENT ANNUAL POLLUTANT LOADS**

SUBCATCHMENT 2.0S

Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	5.80	6.0	0.10	1.8	77	34.8	0.58	10.4	447
SUBCATCHMENT 2.0S SUBTOTAL						34.8	0.58	10.4	447

SUBCATCHMENT 3.0S

Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	6.00	6.0	0.10	1.8	77	36.0	0.60	10.8	462
SUBCATCHMENT 3.0S SUBTOTAL						36.0	0.60	10.8	462

SUBCATCHMENT 4.0S

Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	15.00	6.0	0.10	1.8	77	90.0	1.50	27.0	1155
SUBCATCHMENT 4.0S SUBTOTAL						90.0	1.50	27.0	1155

SUBCATCHMENT 5.0S

Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	7.60	6.0	0.10	1.8	77	45.6	0.76	13.7	585
SUBCATCHMENT 5.0S SUBTOTAL						45.6	0.76	13.7	585

PRE-DEVELOPMENT TOTALS						206.4	3.44	61.9	2649
-------------------------------	--	--	--	--	--	--------------	-------------	-------------	-------------

**THE HAMLET AT CARMEL, MULTI-FAMILY HOUSING DEVELOPMENT
POST-DEVELOPMENT ANNUAL POLLUTANT LOADS**

SUBCATCHMENT 2.1SA

Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Multifamily Residential	0.70	50.0	0.63	5.0	395.0	35.0	0.44	3.5	277
Grass	0.50	6.0	0.12	3.7	308	3.0	0.06	1.9	154
TOTAL						38.0	0.50	5.4	431
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
SUBTOTAL						40%	40%	40%	40%
						30.4	0.40	4.3	344
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						to	to	to	to
						22.8	0.30	3.2	258
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
SUBTOTAL						60%	60%	40%	100%
						18.2	0.24	3.4	69
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						to	to	to	to
						9.1	0.12	1.9	0
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
SUBTOTAL						60%	60%	40%	100%
						10.9	0.14	2.7	14
DEP DESIGN 14 GRASS SWALE						to	to	to	to
						3.6	0.05	1.2	0
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
SUBCATCHMENT 2.1SA SUBTOTAL						40%	40%	40%	40%
						8.8	0.12	2.2	11
						to	to	to	to
						2.2	0.03	0.7	0

SUBCATCHMENT 2.1SB


Land use/Ground Cover	Area (Acres)	Rates (lb/ac/yr)				Annual Loads (lb/yr)			
		BOD	TP	TN	TSS	BOD	TP	TN	TSS
Multifamily Residential	3.80	50.0	0.63	5.0	395.0	190.0	2.39	19.0	1501
Grass	1.80	6.0	0.12	3.7	308	10.8	0.22	6.7	554
TOTAL						200.8	2.61	25.7	2055
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
SUBTOTAL						60%	60%	40%	100%
						120.5	1.57	20.5	411
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						to	to	to	to
						80.3	1.04	15.4	0
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
SUBTOTAL						60%	60%	40%	100%
						72.3	0.94	16.4	82
DEP DESIGN 14 GRASS SWALE						to	to	to	to
						32.1	0.42	9.2	0
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
SUBCATCHMENT 2.1SB SUBTOTAL						40%	40%	40%	40%
						57.8	0.75	13.1	66
						to	to	to	to
						19.3	0.25	5.5	0

SUBCATCHMENT 2.2S									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Grass	0.90	6.0	0.12	3.7	308	5.4	0.11	3.3	277
TOTAL						5.4	0.11	3.3	277
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
						60%	60%	40%	100%
SUBTOTAL						3.2	0.06	2.7	55
						to	to	to	to
						2.2	0.04	2.0	0
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
						40%	40%	40%	40%
SUBCATCHMENT 2.2S SUBTOTAL						2.6	0.05	2.1	44
						to	to	to	to
						1.3	0.03	1.2	0
SUBCATCHMENT 2.3S									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	2.80	6.0	0.10	1.8	77	16.8	0.28	5.0	216
SUBCATCHMENT 2.3 S SUBTOTAL						16.8	0.28	5.0	216
DESIGN POINT 2 POST-DEVELOPMENT TOTALS						86.0	1.20	22.5	337
						to	to	to	to
						39.6	0.59	12.5	216
SUBCATCHMENT 3.1SA									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Multifamily Residential	0.60	50.0	0.63	5.0	395.0	30.0	0.38	3.0	237
Grass	0.40	6.0	0.12	3.7	308	2.4	0.05	1.5	123
TOTAL						32.4	0.43	4.5	360
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
						40%	40%	40%	40%
SUBTOTAL						25.9	0.34	3.6	288
						to	to	to	to
						19.4	0.26	2.7	216
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
						60%	60%	40%	100%
SUBTOTAL						15.6	0.20	2.9	58
						to	to	to	to
						7.8	0.10	1.6	0
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
						60%	60%	40%	100%
SUBTOTAL						9.3	0.12	2.3	12
						to	to	to	to
						3.1	0.04	1.0	0
DEP DESIGN 14 GRASS SWALE						20%	20%	20%	20%
						to	to	to	to
						40%	40%	40%	40%
SUBCATCHMENT 3.1SA SUBTOTAL						7.5	0.10	1.8	9
						to	to	to	to
						1.9	0.02	0.6	0

SUBCATCHMENT 3.1SB									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Pavement	1.5	111.0	0.98	2.1	446	166.5	1.4685	3.15	669
Multifamily Residential	2.40	50.0	0.63	5.0	395.0	120.0	1.51	12.0	948
Grass	2.70	6.0	0.12	3.7	308	16.2	0.32	10.0	832
Woods	0.50	6.0	0.10	1.8	77	3.0	0.05	0.9	39
TOTAL						305.7	3.35	26.0	2487
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
						60%	60%	40%	100%
SUBTOTAL						183.4	2.0	20.8	497
						to	to	to	to
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						122.3	1.3	15.6	0
						40%	40%	20%	80%
						to	to	to	to
SUBTOTAL						110.1	1.21	16.7	99
						to	to	to	to
DEP DESIGN 14 GRASS SWALE						48.9	0.54	9.4	0
						20%	20%	20%	20%
						to	to	to	to
SUBCATCHMENT 3.1SB SUBTOTAL						40%	40%	40%	40%
						88.0	0.97	13.3	80
						to	to	to	to
						29.3	0.32	5.6	0
SUBCATCHMENT 3.2S									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Grass	0.60	6.0	0.12	3.7	308	3.6	0.07	2.2	185
TOTAL						3.6	0.07	2.2	185
DEP DESIGN 2 DETENTION POND REMOVAL EFFICIENCIES						40%	40%	20%	80%
						to	to	to	to
						60%	60%	40%	100%
SUBCATCHMENT 3.2S SUBTOTAL						2.2	0.04	1.8	37
						to	to	to	to
						1.4	0.03	1.3	0
						SUBCATCHMENT 3.3S			
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	2.70	6.0	0.10	1.8	77	16.2	0.27	4.9	208
Grass	0.20	6.0	0.12	3.7	308	1.2	0.02	0.7	62
SUBCATCHMENT 3.3S SUBTOTAL						17.4	0.29	5.6	270
DESIGN POINT 3 POST-DEVELOPMENT TOTALS						115.1	1.40	22.5	395
						to	to	to	to
						50.1	0.67	13.1	270

SUBCATCHMENT 4.1S									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Woods	8.00	6.0	0.10	1.8	77	48.0	0.80	14.4	616
DESIGN POINT 4 POST-DEVELOPMENT TOTALS						48.0	0.80	14.4	616
SUBCATCHMENT 5.1S									
		Rates (lb/ac/yr)				Annual Loads (lb/yr)			
Land use/Ground Cover	Area (Acres)	BOD	TP	TN	TSS	BOD	TP	TN	TSS
Grass	1.00	6.0	0.12	3.7	308	6.0	0.12	3.7	308
Woods	3.30	6.0	0.10	1.8	77	19.8	0.33	5.9	254
DESIGN POINT 5 POST-DEVELOPMENT TOTALS						25.8	0.45	9.6	562
						274.8	3.85	69.1	1910
							to	to	to
OVERALL POST-DEVELOPMENT TOTALS						163.4	2.50	49.7	1663

FIGURES



LEGEND


- POST 2.1P SUBSTATION
- 2.1P POND STORMWATER MANAGEMENT PRACTICE
- TO TOE OF CONCENTRATION FLOW PATH
- SOILS BOUNDARY

SOILS LEGEND

SOILS	DESCRIPTION	HYDROLOGICAL GROUP
C1E	Chariton loam, 2SE to 2SE slopes	B
P1B	Parson fine sandy loam, 2E to 2E slopes	C
P1C	Parson fine sandy loam, 8E to 10E slopes	C
P1D	Parson fine sandy loam, 15E to 25E slopes	C

NO.	DATE	REVISION	BY
PROJECT: THE HAMLET AT CARMEL MULTI-FAMILY HOUSING DEVELOPMENT STONELEIGH AVENUE, TOWN OF CARMEL, PUTNAM COUNTY, NEW YORK			
DRAWING: POST DEVELOPMENT DRAINAGE MAP			
PROJECT NUMBER	14211-100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	C.M.S.
SCALE	1" = 50'	CHECKED BY	E.J.P.
			DRAWING NO. FIG-1

ALTERNATION OF THIS DOCUMENT, UNLESS UNDER THE SIGNATURE OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



LEGEND

- PRE 1.0B SUBCATCHMENT
- TO DIRECTION OF CONCENTRATION FLOW PATH
- SOILS BOUNDARY

SOILS LEGEND

SOILS	DESCRIPTION	HYDROLOGICAL GROUP
ChE	Charlton loam, 20% to 30% slopes	B
PhB	Putnam fine sandy loam, 2% to 4% slopes	C
PhC	Putnam fine sandy loam, 4% to 15% slopes	C
PhD	Putnam fine sandy loam, 15% to 25% slopes	C

NO.	DATE	REVISIONS PER HISTORY COMMENTS	BY
1	11-4-09	REVISION	

INSITE
ENGINEERING SURVEYING & LANDSCAPE ARCHITECTURE, P.C.
3 Carroll Place
Carmel, NY 12517
(518) 235-8997
(518) 235-8997 fax
www.insite-erg.com


PROJECT: **THE PUTNAM COMMUNITY FOUNDATION**
STONELEIGH AVENUE, TOWN OF CARMEL, PUTNAM COUNTY, NEW YORK

DRAWING: **PRE DEVELOPMENT DRAINAGE MAP**

PROJECT NUMBER: 03198.100 PROJECT MANAGER: J.L.C. DRAWING NO: Fig. 2
DATE: 1-15-09 DRAWN BY: E.M.S.
SCALE: 1" = 50' CHECKED BY:

THIS FIGURE 2, PRE DEVELOPMENT DRAINAGE MAP WAS TAKEN FROM THE APPROVED STORMWATER POLLUTION PREVENTION PLAN FOR THE PUTNAM COMMUNITY FOUNDATION, DATED MARCH 9, 2010.

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2005 OF ARTICLE 146 OF THE EDUCATION LAW.



THIS FIGURE 3, POST DEVELOPMENT DRAINAGE MAP WAS TAKEN FROM THE APPROVED STORMWATER POLLUTION PREVENTION PLAN FOR THE PUTNAM COMMUNITY FOUNDATION, DATED MARCH 9, 2010.

LEGEND

	SEGMENTATION
	STORMWATER MANAGEMENT PRACTICE
	TYPE OF CONCENTRATION FLOW PATH
	SOILS BOUNDARY

SOILS LEGEND

SOILS	DESCRIPTION	HYDROLOGICAL GROUP
ONE	Chertan loam, 25% to 35% slopes	B
P1B	Parton fine sandy loam, 25 to 35% slopes	C
P1C	Parton fine sandy loam, 35 to 15% slopes	C
P1D	Parton fine sandy loam, 15% to 25% slopes	C

NO.	DATE	REVISION	BY
3	3-9-10	REVISIONS PER P1000 AND HYDRO COMMENTS	BMF
2	2-12-10	REVISIONS PER HYDRO COMMENTS	DMT
1	11-4-09	REVISIONS PER HYDRO COMMENTS	BMF

INSITE
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.


3 Corbett Place
Coral Gables, FL 33134
(305) 225-9999
(305) 225-9977 fax
www.insite-eng.com

PROJECT: THE PUTNAM COMMUNITY FOUNDATION
STONELIGH AVENUE, TOWN OF CORAL GABLES, PUTNAM COUNTY, NEW YORK

DRAWING: POST DEVELOPMENT DRAINAGE MAP



PROJECT NUMBER: 03198.100	PROJECT MANAGER: J.L.C.	DRAWING NO.:
DATE: 1-15-09	DRAWN BY: E.M.S.	Fig. 3
SCALE: 1" = 50'	CHECKED BY:	

ALLOCATION OF THIS DOCUMENT UNDER THE PROVISIONS OF A LICENSED PROFESSIONAL ENGINEER, OR A VIOLATION OF SECTION 2005 OF ARTICLE 146 OF THE ENGINEERING LAW.



500' ADJOINERS

- N/F METS ON THE LAKES, INC
- N/F PUTNAM HOSPITAL CENTER CITY OF NEW YORK
- N/F PUTNAM HOSPITAL CENTER
- N/F SAKS, A & KAROL, N.
- N/F CITY OF NEW YORK



R - ZONE REQUIREMENTS:

	Result	Prohibit
Min. Lot Area	120,000 SF	1,536,011 SF ±
Min. Lot Width	200'	1,170' ±
Min. Lot Depth	200'	1,161' ±
Min. Yard Setback		
Front	40'	660'
Side	25'	102'
Rear	40'	115'
Max. Building Height	35'	<35'
Min. Building Coverage	15 %	5.7%

* See §16-28 Multi-Family Dwellings Zoning Requirements below.

§156-28 MULTI-FAMILY DWELLINGS ZONING REQUIREMENTS: *

	Result/Permissible	Prohibit
Min. Lot Area	272,800 SF (10.2 AC)	1,536,011 SF ± (35.29 AC)
Max. Density (Units/Acre)	5.0	4.25
Max. Dwelling Units	150	150
Min. Building Coverage	30%	5.7%
Min. Property Line Setback	100'	102'
Max. Building Height/ Stories	35' / 2	Not Over 35' / 2
Distance Between Buildings	50'	50'
Min. Building Length	200'	200'
Min. Recreation Space	300 SF / unit	301 SF / unit

PARKING REQUIREMENTS: *

2.0 spaces per unit x 150 units = Required	= 300 spaces
Total Spaces Provided	= 300 spaces


* Per §16-28 of the Town of Carmel Zoning Code.

RECREATION REQUIREMENTS:

- Indoor Common Space: 2,746 SF
- Patio Area: 840 SF
- Active Recreation: 10,500 SF (Playground, Sports Courts)
- Walking Path Area: 11,000 SF
- Common Green: 30,000 SF

TOTAL RECREATION PROVIDED: 45,186 SF

TOTAL RECREATION REQUIRED: 45,000 SF (2.0 SF/unit x 150 Units)



CONSTRUCTION NOTES:

- The contractor is advised that additional notes will be found on subsequent drawings and such notes will pertain to the specific drawings they are placed in, also supplement the construction notes listed herein.
- All work and materials shall be in accordance with these plans and project specifications.
- The contractor shall notify the Engineer 72 hours prior to start of work.
- The subject project has coverage under the New York State Department of Environmental Conservation (DEC) General Permit for Stormwater Discharges from Construction Activity, permit No. GP-20-0000. As required by the permit all contractors and subcontractors are required to sign a certification statement that they understand and agree to comply with the requirements of GP-20-0000.
- The contractor shall have a representative onsite that is a NYDEC Trained Contractor at all times with work to be performed under this contract. The contractor shall provide a contractor's certification as contained in the NYDEC Construction Site Logbook to the project engineer upon start of construction.
- The contractor shall coordinate the layout of the work with the owner, and the project engineer, and ensure all conflicts including but not limited to utility location conflicts, prior to commencement of any proposed work.
- The contractor shall coordinate their construction operations with the project engineer and any other contractors/subcontractors and construction activities occurring simultaneously on the property.
- It shall be the contractor's/subcontractor's responsibility to provide sanitary facilities (i.e. porta-potties) and other necessary temporary facilities throughout the duration of construction.
- The contractor shall be responsible for providing all power, water, and other resources necessary to complete the project work.
- Minimum OSHA site standards must be maintained including personal protective equipment and safety. The contractor shall be responsible for enforcing all safety regulations in accordance with the latest edition and current OSHA requirements.
- The contractor shall field verify all dimensions relative to the scope of work.
- The contractor shall ensure that the limits of clearing shall be marked with the project engineer prior to the start of clearing operations. Existing trees to remain outside the limits of clearing shall be protected for the duration of the project.
- It shall be the contractor's responsibility to identify and protect all underground utilities. The contractor shall contact Dig Safe New York at 811 or 1-800-962-7962 and any other required utility locators prior to the start of construction.
- The contractor shall field verify the existing location of utility locations prior to commencement of any work. Any discrepancy shall be reported to the project engineer when identified.
- The contractor shall perform all work with care so that any materials which are to remain in place, or which are to remain on the property, shall not be damaged. The contractor will be held responsible for all damage caused to existing utilities / features / facilities / vegetation during execution of the work not proposed to be installed or removed by these plans. All damage to any existing utility or feature, regardless of responsibility, shall be repaired by the contractor. All damage to any utility shall be repaired or replaced by the contractor to the satisfaction of the owner or his additional cost.
- Original condition shall mean the condition in which the feature was found (or better) at the start of construction.
- The contractor shall be responsible for the implementation and maintenance of erosion and sediment controls (shown on plan) as necessary to prevent erosion and migration of sediment from the construction site. Erosion and sediment controls shall include but not be limited to silt fences, stabilized construction entrances, berms and best practices. All erosion and sediment controls shall be installed in accordance with the New York State Standards and Specifications for Erosion and Sediment Control. Additional erosion and sediment controls may be required during construction by the project engineer. All erosion and sediment controls shall be stabilized in accordance with the Erosion & Sediment Control Notes and details.
- Site fence shall be installed parallel to the boundaries.
- Contractor is responsible for protecting soil stockpiles, trenches, and building excavations against weather. No additional soil to be placed to the contractor for removal and replacement of suitable soils due to degradation from weather related events.
- During execution of the work, the contractor shall be responsible for dewatering and control of surface water in accordance with the New York State Standards and Specifications for Erosion and Sediment Control. The New York State Standards and Specifications for Erosion and Sediment Control can be found at <http://www.dec.ny.gov/interior/29066.htm>.
- All surface material shall be cleaned and swept prior to the completion of construction.
- The contractor shall provide temporary construction fence for all work areas including the material storage/stacking areas.
- All personal vehicles, materials, and construction equipment must be kept within the construction staging area. Use of additional onsite storage areas must be pre-authorized by the owner of the property.
- Trees shown on the plans for reference only. All trees and vegetation within the contract limit shall be removed unless otherwise labeled to be protected and saved. All trees to be removed may be shown.
- Tree clearing can only be performed between October 1st and March 31st.
- Topsoil and subsoil shall be striped, stored, and stockpiled in locations shown for future use. The contractor must keep enough topsoil on site for final restoration. Four inches of screened topsoil shall be placed and used to finish grade over all disturbed areas not covered by pavement, concrete and/or gravel surfaces, unless otherwise noted.
- The contractor shall maintain existing grades unless otherwise noted.
- Contractor shall be responsible for removal of all excess rock, subsoil, and construction debris from the site.
- There shall be no debts of construction and demolition (C&D) debts or claims on site. All C&D debts and claims must be removed by the contractor and cleared of site at the start of construction. All temporary permits shall be renewed prior to expiration of their term.
- All pre-cast concrete drainage structures, frames, and grates on 18" D-30 loading requirements.
- Design Engineer to approve locations and elevations of all structures prior to placement of the drainage structure.
- Where site work items are proposed the Contractor shall extend the upstream easement to the site limit of the drainage structure.
- Unless otherwise shown on the drawings the contractor shall match the material, thickness and quality of all existing pavements that are to be replaced.
- Temporary asphalt edges shall be placed at all areas open to vehicular access. The edges shall be finished between any surface abrupt grade changes in excess of 1" or at least of construction. All temporary edges shall be renewed prior to placement of capital courses.
- The contractor will be responsible for the implementation of all maintenance and protection of traffic (MPT) measures if necessary. MPT shall include but not be limited to placement of traffic cones and warning equipment work areas. Safe and adequate pedestrian vehicular traffic flow shall be maintained at all times to the existing pavement, with the work in progress. The contractor shall submit for approval of the Engineer, a construction sequence schedule and plan for pedestrian and vehicular traffic flow.
- A retaining wall design signed and sealed by a NYS Licensed Engineer shall be submitted to the Consulting Team Engineer prior to the construction of any wall greater than 4 feet in height.

LOCATION MAP SCALE: 1" = 3000'


RECORD OWNER/APPLICANT: Title Area: 3528 AC ±
1777 Route 6
Carmel, NY 10512

SITE DATA: Tax Map No: 66-2-58
Zoning District: R (Residential)
Proposed Use: Multi-Family Residential

- GENERAL NOTES:**
- Property boundary shown herein taken from subdivision plat entitled Boundary Line Adjustment prepared by the Carmel Community Foundation and Putnam Hospital Center, filed January 4, 2006 as map no. 3008.
 - Existing conditions and topography shown herein taken from survey entitled "Topographic Survey prepared for the Carmel Community Foundation," prepared by Terry Bergendoff Collins, L.S., last revised April 26, 2007.
 - The NYDEC permit items indicated on these plans were originally detected by the NYDEC on October 4, 2006 & August 26, 2008 and were reconfirmed by the field by NYDEC on November 13, 2011.
 - The proposed roads shown herein shall be privately owned, and are not intended to be dedicated to the Town of Carmel.
 - As access to utility easements is to be granted to the multi-use green park, giving to tenants lights and access to the site across the portion of the private road that is part of the easement area.

LIST OF DRAWINGS

DRAWING NO.	DRAWING NAME	SHEET
SP-1	Overall Site Plan	1
SP-2	Existing Conditions Plan	2
SP-2	Layout, Landscaping, & Lighting Plan	3
SP-3	Grading & Utilities Plan	4
SP-4	Erosion Control & Paving Plan	5
D-1	Site Details	6
D-2	Site Details	7
D-3	Site Details	8
D-4	UTILITY DETAILS	9
D-5	Stormwater Pond Details	10
D-6	Stormwater Pond Details	11



NO.	DATE	REVISION	BY
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN			
DRAWING: OVERALL SITE PLAN			
PROJECT NO.	142111-100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	M.E.U.
SCALE	1" = 100'	CHECKED BY	A.D.T.


3 Carmel Plaza
(845) 225-9999
(845) 225-9999
www.insite-eng.com

PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN
DESIGNED BY: DATE OF PLAN: PLOTTED: 04/10/24

DRAWING: OVERALL SITE PLAN

PROJECT NO. 142111-100 PROJECT MANAGER R.D.W.
DATE 4-10-24 DRAWN BY M.E.U.
SCALE 1" = 100' CHECKED BY A.D.T.

SHEET 1 OF 11



LEGEND


	EXISTING PROPERTY LINE
	EXISTING STONE WALL
	EXISTING WATERCOURSE
	EXISTING STREAM BUFFER
	EXISTING 10' CONTOUR
	EXISTING 2' CONTOUR
	EXISTING TREE LINE

AS-BUILT NOTES

1. The as-built conditions shown herein are taken from a progress re-survey survey prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., dated December 2, 2023.


- REMOVAL NOTES**
1. Prior to submitting the AIA, the contractor shall walk the site and familiarize themselves with the site conditions and existing improvements to be removed.
 2. The contractor shall provide all removal incidental and necessary to execute the work prescribed in the contract documents. All existing features specified to be removed shall be removed in their entirety unless otherwise authorized in writing by the owner or the project engineer.
 3. These drawings are intended to show an overall Limit of Disturbance and general features to be removed. Not all features incidental to the removal scope of the site work have been shown to be removed. The contractor shall be responsible for all removal within the limits of both above and below grade features, necessary for the construction of the site improvements shown herein.
 4. All underground utility piping (water, sewer, telephone, etc.) shall be capped and abandoned in place. All abandoned pipes left in place shall be filled with controlled low strength material (CLSM) sealing both ends. Any exposed utility shall be cut and removed such that a minimum of 1' of soil cover is maintained on all pipes that are to be capped and abandoned in place.
 5. All building materials shall be demolished and removed from the site.
 6. For any below grade slab or bottom of tank that is to be demolished and abandoned in place, the concrete shall be pulverized so that there are no pieces of concrete remaining that are larger than 3" R or 3" C.

NO.	DATE	REVISION	BY
 INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.			
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN <small>STONEHAM PARK, TOWN OF CARMEL, PUTNAM COUNTY, NEW YORK</small>			
DRAWING: EXISTING CONDITIONS PLAN			
PROJECT NO.	14211.100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	A.D.T.
SCALE	1" = 50'	CHECKED BY	A.D.T.




EX-1

SHEET 2 OF 15



SIGN DATA TABLE				
LOCATION NO.	TEXT	M.U.T.C.O. NUMBER	SIZE OF SIGN (S.F.)	DESCRIPTION
1	RES	NY R7-2	12' x 18'	Green on White Blue Symbol
	RES	R7-BP	12' x 6'	Green on White
2	RES	R7-1	12' x 18'	Red on White

PLANT LIST				
BOTANICAL/COMMON NAME	SIZE	ROOT	REMARKS	
SHADE TREES				
Acer rubrum 'October Glory' / October Glory Red Maple	2 1/2" - 3" CAL.	B # B		
Liquidambar styraciflua / Sweetgum	2 1/2" - 3" CAL.	B # B		
Quercus prinus / Pin Oak	2 1/2" - 3" CAL.	B # B		
Styphion perfoliatus / Flower Stick	8" - 10" HT.	B # B		Multi-stem
Quercus bicolor / Honey Locust	8" - 10" HT.	B # B		
Rhus copallina / Little Leaf Linden	8" - 10" HT.	B # B		
FLOWERING TREES				
Prunella serotina 'Bradford' / Bradford Pear	2" - 2 1/2" CAL.	B # B		
Camelia sasanqua / Camellia	7" - 8" HT.	B # B		
Camelia sasanqua / Camellia	8" - 10" HT.	B # B		
Amelanchier canadensis / Shadbush Sandcherry	8" - 10" HT.	B # B		Multi-stem
Crataegus phoenicifolia / Washington Hawthorn	2" - 2 1/2" CAL.	B # B		
Prunus pennsylvanica / Purple Leaf Plum	2" - 2 1/2" CAL.	B # B		
Malus floribunda / Japanese Flowering Crabapple	2" - 2 1/2" CAL.	B # B		
SHRUBS & ORNAMENTALS				
Arundo donax / Reed Canadensis	3 GAL.	CONT.		
Potentilla multicolor 'Sunset' / Sunset Potentilla	2 GAL.	CONT.		
Hemerocallis 'Stella Blue' / Asterella Daylily	2 GAL.	CONT.		
Juncus horizontalis 'Pharos' / Dwarf Andrea Juniper	2 GAL.	CONT.		
Juncus sargentii / Sargent's Juniper	2 GAL.	CONT.		
Juncus horizontalis 'New England' / Blue Rug Juniper	2 GAL.	CONT.		
Rhododendron 'TAM' / P.M. Rhododendron	2" - 2 1/2" HT.	B # B		
Rhododendron 'Purple Gem' / Purple Gem Rhododendron	3 GAL.	CONT.		
Conoclinium opulifolium / Crackerberry Columbine	3 GAL.	CONT.		
Veronica spicata / Holly	4" - 5" HT.	B # B		
Camelia sasanqua / Red Twig Dogwood	4" - 5" HT.	B # B		
Spiraea japonica 'Anthony Waterer' / Anthony Waterer Spiraea	3" - 4" HT.	B # B		
Phlox japonica 'Mt. Fuji' / Mt. Fuji Andromeda	2" - 2 1/2" HT.	CONT.		
Rhododendron cataractarum / Cataract Rhododendron	2 1/2" - 3" HT.	CONT.		
Veronica spicata / Dwarf Juniper	18" - 24" HT.	CONT.		
Heuchera 'Tapestry' / English Tree	18" - 24" HT.	CONT.		
Forsythia x intermedia / Border Forsythia	4" - 5" HT.	CONT.		
Heuchera angustifolia / Leadwort Heuchera	3 GAL.	CONT.		
Burmannia purpurea / Resurrection Lilies	2 1/2" - 3" HT.	B # B		
Hydrangea arborescens 'Annabelle' / Hydrangea	3 GAL.	CONT.		



LIGHTING NOTES:


- All site lighting shall be solar powered.
- Model, style and finish of all luminaires to be selected by owner and approved by the Planning Board.
- Proposed lights will run on photovoltaic.
- Type, location, and shading of all proposed lighting shall prevent the spillage of light onto adjacent residential properties.
- All light fixtures to be full cutoff to comply with dark sky guidelines.

LUMINAIRE SCHEDULE					
Qty.	Symbol	Category Number	Description	Mounting Height	Notes
19	DSXD LED		LUMINAIRE LIGHTING - DSXD LED WITH PHOTOCELL, 3000K, TYPE 3 DISTRIBUTION WITH HOUSE SIDE SHIELD	18'	89


* Light fixtures to be fitted with Evergen Solar Lighting System or approval equal.



NO.	DATE	REVISION	BY
INSITE			
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.			
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN			
DRAWING: LAYOUT, LANDSCAPING & LIGHTING PLAN			
PROJECT NO.	14211.100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	BY	M.E.U.
SCALE	1" = 50'	CHECKED BY	A.D.T.
DRAWING NO. SP-2			SHEET 3



DATE PLOTTED: 04/10/2024 10:00:00 AM



LEGEND	
—	Property Line
—	Existing 2" Contour
—	Existing Spot Grade
—	Existing Drain and Channel Flow
—	Proposed 2" Contour
—	Proposed 10" Contour
—	Existing Stone Wall to be Removed
—	Proposed Retaining Wall
—	Proposed Retaining Wall (Close As Noted)
—	Proposed Existing Drain
—	Proposed Sewer Manhole
—	Proposed Catch Basin/Drain Inlet
—	Proposed Drainage Machine
—	Proposed Outlet Structure
—	Proposed Cross Slope
—	Proposed Flange Grade
—	Proposed 2" PVC D14
—	Proposed Fire Hydrant and Gate Valve
—	Proposed 12" PVC 30' S/S Sewer Service Line W/Down Out
—	Proposed 12" PVC 14' S/S Sewer Service Line w/Down Out
—	Proposed 12" PVC 14' S/S Sewer Service Line w/Down Out (Wind Size Per Fire Protection Code)
—	Proposed Gate Valve
—	Proposed Down Spout

WINTER SITE STABILIZATION NOTES:

- All bare / exposed soils must be stabilized by an established vegetation, straw or mulch, or other approved product such as erosion control blankets.
- Sediment barriers must be properly installed at all necessary perimeter and sensitive locations.
- All erosion / exposed soils must be properly stabilized with approved methods. Final erosion control products must be used on all slopes greater than 3:1, or where conditions for erosion dictate such measures.
- Stabilized soils must be protected by the use of established vegetation, an approved straw or mulch, or other erosion control product to be installed around the site to prevent erosion away from the site.
- All entrances / exit locations to the site must be properly stabilized and must be maintained to accommodate snow management as set forth in the NYC Standard Specifications for Erosion and Sediment Control.
- Snow management must not destroy or degrade erosion and sediment control devices.

EXCAVATION NOTES:

- All excavations to be saw cut to full depth by the contractor prior to installation.
- The Contractor shall provide shoring, shoring, or braced excavation, or a rigid extension for all excavations 3.0 feet or greater in depth.
- All shoring and shoring protective systems used for excavation shall be designed and installed by a NYE Licensed Professional Engineer.
- Where construction crosses or is adjacent to existing utility lines (i.e., water, gas, telephone, electric or communication), the contractor shall carefully locate and identify all utility lines and shall take all appropriate precautions to avoid damage to existing utility lines. The contractor shall keep any existing utility lines in service at all times.
- Trench excavation outside of temporary construction fence is to be backfilled on the same day of excavation. Temporary access construction fence is required around this work area for on going work.
- All utility trenches in use adjacent to roadway shall be identified prior to the end of the work day, unless otherwise authorized by the Engineer. Items shall be temporarily brought to the surface of the roadway during the work day and shall be returned to the roadway as soon as possible.

REQUIRED EROSION CONTROL SWPPP CONTENTS:

- Permitted by the NYSDDEC Stormwater Permit for Stormwater Discharge from Construction Activity (GP-2-20-01), Stormwater Pollution Prevention Plan's (SWPPP) shall include and address the following:
- Background information: The subject project consists of the construction of a multi-family residential development with 10 buildings totaling 150 units, and associated appurtenances.
 - Site map / construction drawings: This plan serves to satisfy this SWPPP requirement for planimetric design and details.
 - Description of the soils present at the site: Detailed soils located within the proposed limits of disturbance consist of Paxton fine sandy loam (Pfl), Pfl, Pfl and Charlton loam (Ck), as identified on the Soil Conservation Service Map Soil Survey. The Paxton type belongs to the Hydrologic Soil Group "C", and the Charlton soil belongs to Hydrologic Soil Group "D".
 - Construction phasing plan / sequence of operations: A Construction Sequence and Erosion and Sediment Control Maintenance Schedule has been provided. The Sedimentation and Erosion Control Notes contained herein outline a general sequence of operations for the proposed project. In general, erosion and sediment control facilities shall be installed prior to commencement with land disturbing activities, and areas of disturbance shall be limited to the shortest period of time as practicable. As greater than the shortest period of time is required, the project will be completed in phases with disturbance of less than the area. Description of erosion and sediment control practices: This plan and details of erosion control practices serve to satisfy this SWPPP requirement.
 - Temporary and permanent soil stabilization plan: The Sedimentation and Erosion Control Notes and Details provided herein identify temporary and permanent stabilization measures to be employed with respect to specific elements of the project, and of the various stages of development.
 - Site map / construction drawings: This plan serves to satisfy this SWPPP requirement for erosion control notes and details.
 - The dimensions, material specifications, installation details, and operation and maintenance schedules for all erosion control facilities are provided in the Details, Sedimentation and Erosion Control Notes and Erosion and Sediment Control Maintenance Schedule serve to satisfy this SWPPP requirement.
 - An inspection schedule: Inspections are to be performed weekly, and by a qualified professional as required by the General Permit (GP-2-20-01), in addition to the NYSDDEC Trained Contractor shall perform additional inspections as cited in the Sedimentation and Erosion Control Notes.
 - A description of pollution prevention measures that will be used to control site construction chemicals and sediment: This plan and details of erosion control practices serve to satisfy this SWPPP requirement.
 - A description of any elements of the design that are not in conformance with the technical standards: "New York Standard and Specifications for Erosion and Sediment Control." All proposed elements of this SWPPP have been designed in accordance with the New York Standard and Specifications for Erosion and Sediment Control.

PERMANENT STORMWATER FACILITIES MAINTENANCE SCHEDULE					
PRACTICE/FACILITY	MONTHLY	AFTER MAJOR STORM EVENTS	BI-ANNUALLY	YEARLY	EVERY 10 YEARS
GRASS SWALES	Mow & remove debris	Mow & remove debris	Mow & remove debris	Mow & remove debris	Mow & remove debris
SUBSURFACE STORMWATER COLLECTION SYSTEMS	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris
STORMWATER BASIN	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris	Inspect for the presence of debris

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF THE ENGINEER AND SHALL BE KEPT IN THE OFFICE OF THE ENGINEER. NO PART OF THESE PLANS AND SPECIFICATIONS SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.


The party responsible for the permanent maintenance schedule is the Hamlet at Carmel Associates, LLC, 207 Carmel, NY 10503

GRAPHIC SCALE
1" = 50'

NO.	DATE	REVISION	BY
INSITE			
ENGINEERING SURVEYING LANDSCAPE ARCHITECTURE, P.C.			
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN			
DRAWING: GRADING & UTILITIES PLAN			
PROJECT NO.	14211-10	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN	M.E.T.
SCALE	1" = 50'	CHECKED BY	A.G.

3 Carroll Place
(914) 235-9900
www.insite-ny.com


SHEET 3 OF 15



LEGEND

- Property Line
- Existing 2' Contour
- Existing 1' Contour
- Existing Stone Wall
- Proposed 2' Contour
- Proposed 10' Contour
- Proposed Stone Retaining Wall
- Proposed Drain Inlet Protection
- Proposed Silt Fence
- Proposed Stone Check Dam
- Proposed Limits of Disturbance
- Proposed Soil Stockpile
- Stabilized Construction Entrance
- Phasing Line

- GENERAL CONSTRUCTION SEQUENCE NOTES:**
- Each phase of work implies that all sediment and erosion control measures will be installed in accordance with best management practices and prior to any clearing and grading operations.
 - Each phase of work implies the removal of existing trees and grubbing of all tree roots systems.
 - All topsoil to be stripped and stockpiled in appropriate locations for future use on the site. All stockpiled soil areas are to be appropriately stabilized and protected.
 - All finished slopes 20:1 or steeper are to be immediately stabilized and covered with erosion control blanket unless 1:1 by American Excavator Co. or approved equal.
 - No more than 2 cubic yards of disturbance shall be permitted at any one time without prior written approval from the New York State Department of Environmental Conservation.
 - Should groundwater be encountered during excavation the contractor shall contact the project's certified erosion control specialist immediately to assess the situation. If groundwater is encountered a sump pit shall be constructed as directed by the engineer or erosion control specialist. Groundwater should be pumped to a sump pit or discharge to a storm sewer or other approved location with all fence down gradient. Final location as directed by the engineer or erosion control specialist.
 - All excess soil material not needed for grading/finishing shall be removed from the site.
 - No stockpiling of excavated material other than topsoil as shown on these plans shall be done without prior approval from NYSDOT.



EROSION AND SEDIMENT CONTROL MAINTENANCE SCHEDULE

PRACTICE	MONITORING REQUIREMENTS		MAINTENANCE REQUIREMENTS	
	DAILY	WEEKLY	DURING CONSTRUCTION	AFTER CONSTRUCTION
SILT FENCE	-	Inspect	Inspect	Remove
STABILIZED CONSTRUCTION ENTRANCE	Inspect	-	Inspect	Remove
DUST CONTROL	Inspect	-	Inspect	Mulching/Seeding
VEGETATIVE ESTABLISHMENT	-	Inspect	Inspect	Need to ROW Coverage
PROTECTION	-	Inspect	Inspect	Remove
SOIL STOCKPILES	-	Inspect	Inspect	Remove
SWALES	-	Inspect	Inspect	Clear/Mulch/Repair
CHECK DAMS	-	Inspect	Inspect	Clear/Mulch/Repair
CHANNEL DRAINAGE STRUCTURES	-	Inspect	Inspect	Clear/Mulch/Repair
DRAINAGE PIPES	-	Inspect	Inspect	Clear/Repair
ROAD & PAVEMENT	-	Inspect	Inspect	Clear
STORMWATER TRAP/BASIN	-	Inspect	Inspect	Clear/Mulch/Repair/Seal

GENERAL NOTES:
1. For General Notes see drawing SP-3.

SEDIMENTATION & EROSION CONTROL NOTES:

- The Erosion Control Plan is only to be referred to for the installation of sedimentation and erosion control measures. For all other construction related activities, including, but not limited to, grading and utilities, refer to the appropriate drawings.
- All soil erosion and sediment control practices shall be installed in accordance with New York State Standards and Specifications for Erosion & Sediment Control, latest edition.
- Whenever feasible, natural vegetation should be retained and protected.
- When land is exposed during development, the exposure shall be kept to the shortest practical period of time.
- Silt fence and hay bales shall be installed as shown on drawing prior to beginning any clearing and grubbing or earthwork.
- All topsoil to be stripped from the area being developed shall be stockpiled and immediately seeded with 4-31 Perennial Tall Fescue.

- Any graded areas not subject to further disturbance or construction traffic shall, within 10 days of final grading, receive permanent vegetation cover in combination with a suitable mulch. All seeded areas to receive a minimum 4" layer of Seed mixture to be planted between April 1 and May 15, or between August 15 and October 15 or as directed by project representative at a rate of 50 pounds per acre in the following proportions:
Kentucky Bluegrass 20%
Crested Top Fescue 50%
Annual Ryegrass 20%
- Multi: Hay or small grain straw applied at a rate of 90 lbs./1000 s.f. or 2 tons/acre, to be applied and irrigated according to New York State Standards and Specifications for Erosion & Sediment Control, latest edition.
Grass seed mix may be applied by either mechanical or hand-seeding methods. Hand-seeding shall be performed in accordance with the current edition of the NYSDOT Standard Specifications, Construction and Materials, Section 410-2.02, Section 10-2.

- On 4:1 or flatter slopes than 2:1 shall be stabilized immediately after grading.
- Powered roofcages shall be kept clean at all times.
- The site shall at all times be graded and maintained such that all stormwater runoff is directed to soil erosion and sediment control facilities.
- All storm drainage facilities shall be installed as required before the discharge points become operational.
- Stormwater from disturbed areas must be passed through erosion control devices before discharge beyond disturbed areas or discharge into other drainage.
- Sedimentation and erosion control measures shall be inspected and maintained on a daily basis by NYSDOT Trained Contractor to insure their effectiveness. Temporary and permanent ditches and piles on sites of earth, that embankments and berms have not been lowered and that all view lines and all fences are intact. Any failure of sediment and erosion control measures shall be immediately reported by the contractor and inspected for approval by the NYSDOT Trained Contractor and/or site engineer.









- Dust shall be controlled by spraying or other approved methods as necessary, or as directed by the NYSDOT Trained Contractor.
- Out and fill shall not endanger adjoining property, nor divert water onto the property of others.
- All fills shall be compacted to provide stability of material and to prevent potholes from forming.
- The NYSDOT Trained Contractor shall inspect downstream conditions for evidence of sedimentation on a weekly basis and after rainstorms.
- As warranted by field conditions, special additional sedimentation and erosion control measures, as specified by the site engineer and/or Town Engineer shall be installed by the contractor.
- Erosion control measures shall remain in place until all disturbed areas are suitably stabilized.

Permanent vegetation is considered established when 80% of the plant density is established. Erosion control measures shall remain in place until all disturbed areas are permanently stabilized. The party responsible for implementation of the maintenance schedule during and after construction is:

The Board of General Associates, LLC
27 Route 6, Suite 207
Carmel, NY 12026
and/or the current owner(s) of the subject property.


INSITE
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.
3 Carvet Place
Carmel, NY 12016
(845) 235-8900
(845) 235-8999
(845) 235-8917
www.insite-ny.com

NO.	DATE	REVISION	BY
THE HAMLET AT CARMEL			
AMENDED SITE PLAN			
SHELDON AVENUE, TOWN OF CARMEL, POLYNO COURT, NEW YORK			
EROSION CONTROL & PHASING PLAN			
PROJECT NO.	14211.100	PROJECT MANAGER	R.W.K.
DATE	4-10-24	DRAWN BY	M.E.M.
SCALE	1" = 50'	CHECKED BY	SP-4
			5
			15




NOTES:
 1. ALL WOOD TO BE SEASONED NO.1 DOUGLAS FIR.
 2. ALL WOOD TO BE TREATED WITH AN APPROVED WOOD PRESERVATIVE SUITABLE FOR INSTALLATION IN AND ADJACENT TO GROUND SURFACES.

WOOD GUIDE RAIL DETAIL
 (N.T.S.)




TRAFFIC SIGN DETAIL
 (N.T.S.)





NOTES:
 INSTALLATION TO CONFORM WITH CURRENT NYSDOT STANDARDS AND SPECIFICATIONS.


CROSSWALK MARKING DETAIL
 (N.T.S.)




NOTES:
 ALL HANDICAP STRIPING SHALL BE 4\"/>



SK-9 LIGHT POLE BASE FOR MIP SERIES FIXTURES DETAIL
 (N.T.S.)




SHRUB PLANTING DETAIL
 (N.T.S.)



TREE PLANTING DETAIL
 (N.T.S.)



NO.	DATE	REVISION	BY
<p align="center">INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.</p>			
<p>PROJECT: THE HAMLET AT CARMEL MULTI-FAMILY HOUSING DEVELOPMENT SHERBORN PARKS, TOWN OF CARMEL, SULLIVAN COUNTY, NEW YORK</p>			
<p>DRAWING: SITE DETAILS</p>			
PROJECT NO.	14211100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	M.E.U.
SCALE	AS SHOWN	CHECKED BY	A.D.T.
DRAWING NO.		DESIGNED BY	
SHEET		D-1	
OF		15	






**MANEUVERING PLAN
E-ONE AERIAL FIRE TRUCK
1" = 100**

Note: See drawing SP-1 for maneuvering through Fulton Hospital site to Stonewall Avenue.




**CATCH BASIN DETAIL
(N.T.S.)**

(STRUCTURE AND GRADE TO BE DESIGNED FOR H-20 LOADING)




**SIDE DRAIN INLET DETAIL
(N.T.S.)**


(STRUCTURE AND GRADE TO BE DESIGNED FOR H-20 LOADING)




**TYPICAL GEOTEXTILE ANCHORING DETAIL
(N.T.S.)**




**DEEP SUMP SIDE DRAIN INLET DETAIL
(N.T.S.)**




**DRAINAGE LINE TRENCH DETAIL
(N.T.S.)**




**RIP RAP APRON DETAIL
(N.T.S.)**




**GRASS SWALE #1 DETAIL
(N.T.S.)**




**GRASS SWALE #2 DETAIL
(N.T.S.)**




**GRASS SWALE #3 DETAIL
(N.T.S.)**




**RIP RAP SWALE #2 DETAIL
(N.T.S.)**




**GRASS SWALE #3 DETAIL
(N.T.S.)**




**END SECTION DETAIL
(N.T.S.)**




**END SECTION DETAIL
(N.T.S.)**




**RIP RAP SWALE #4 DETAIL
(N.T.S.)**




**GRASS SWALE DETAIL
(N.T.S.)**



**STONE SWALE DETAIL
(N.T.S.)**




**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**




**STABILIZED CONSTRUCTION ENTRANCE DETAIL
(N.T.S.)**




**SILT FENCE DETAIL
(N.T.S.)**




**EXCAVATED DROP INLET PROTECTION DETAIL
(N.T.S.)**




**STONE DAM DETAIL
(N.T.S.)**




**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**




**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**




**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**



**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**



**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**



**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**



**TEMPORARY SOIL STOCKPILE DETAIL
(N.T.S.)**

- INSTALLATION NOTES**
- STONE SIZE - USE 3" STONE
 - LENGTH - AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY)
 - THICKNESS - NOT LESS THAN SIX (6) INCHES
 - WIDTH - 10 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCUR
 - FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENCE LOT
 - SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION OPERATIONS SHALL BE KEPT ACROSS THE ENTIRE LENGTH OF SWALE BY MAINTAINING THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OF FLOoding OF SEWAGE INTO PUBLIC RIGHT OF WAY THIS MAY REQUIRE PERIODIC TOP COATING WITH ADDITIONAL STONE UNDER VARYING CONDITIONS OF WEAR AND/OR CLEANOUT OF SWALE MEASURES USED TO PREVENT TRACKING OF FLOoding INTO PUBLIC RIGHT OF WAY SHALL BE MAINTAINED
 - MAINTENANCE - SWALES SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE INTO PUBLIC RIGHT OF WAY. MAINTENANCE IS REQUIRED. IT SHALL BE DONE ON ALL AREAS STABILIZED WITH STONE AND SHOULD GOING INTO AN "AS BUILT" DOCUMENT
 - PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN

- NOTES**
- STONE SHALL BE PLACED ON A FILTER FABRIC FOUNDATION STONE TO BE WELL-GRADED 2" TO 3" SANDER
 - SET GRADING OF CHECK DAMS SO THAT THE ELEVATIONS OF THE CREST OF THE CONSTRUCTION DAM IS AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM
 - EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE BOTH SIDES TO PREVENT TRACKING AROUND THE DAM
 - PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND INGRESS WITH STONE UNDER VARYING CONDITIONS
 - ENSURE THAT CHANNEL APPROPRIATE SUCH AS CURBENT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM OVERLAPED STONE

- NOTES**
- AREA CHOSEN FOR STOCKPILE LOCATION SHALL BE DRY AND STABLE
 - MINIMUM SIZE OF STOCKPILE SHALL BE 2:1
 - UPON COMPLETION OF USE, STOCKPILE, EACH PILE SHALL BE IMMEDIATELY SEEDING WITH 30% PERENNIAL TALL FESCUE
 - ALL STOCKPILES SHALL BE PROTECTED WITH SILT FENCING INSTALLED ON THE DOWNWIND SIDE

- CONSTRUCTION NOTES FOR FABRICATED SILT FENCE**
- FILTER CLOTH TO BE FASTENED SECURELY TO POSTS EITHER 1" OR 1 1/2" OR 2" HARBORWOOD
 - WHEN TWO SECTIONS OF FILTER CLOTH JOIN, FILTER CLOTH FOR EACH OTHER MUST BE OVERLAPPED BY 12" MINIMUM, STABILIZED WITH 30% PERENNIAL TALL FESCUE AND FUELED
 - MAINTENANCE SHALL BE PERFORMED AS NEEDED (PREPARED UNCL. SERIALS AND MATRICE REMOVED FROM "TRUCKS" AND EQUIPMENT OF APPROVED DEVELOP IN THE SILT FENCE

**SILT FENCE DETAIL
(N.T.S.)**

NO.	DATE	REVISION	BY

INSITE
ENGINEERING, SURVEYING &
LANDSCAPE ARCHITECTURE, P.C.


3 Carroll Place
New York, NY 10017
(914) 235-8999
(914) 235-8997
www.insite-eng.com

PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN
DRAWING: SITE DETAILS

PROJECT NO. 14211.100 PROJECT MANAGER R.D.M.
DATE 4-10-24 DRAWN BY M.E.U.
SCALE AS SHOWN CHECKED BY A.D.T.

DRAWING NO. 12
SHEET 3

A CERTIFICATION OF THIS DOCUMENT UNDER THE JURISDICTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2209 OF ARTICLE 148 OF THE EDUCATION LAW




STORMWATER BASINS 2.1P AND 2.2P ENLARGED PLAN VIEW
Scale: 1"=30'

STORMWATER BASIN OUTLET NOTES


- THE BASINS ARE PROPOSED TO BE UTILIZED AS TEMPORARY SEDIMENT TRAPS (TST) DURING CONSTRUCTION.
- AFTER THE CONTRIBUTING AREAS TO THE BASINS HAVE BEEN PERMANENTLY STABILIZED, THE FOLLOWING SHALL BE ACCOMPLISHED:
 - CLEAN BASINS AND OUTLET STRUCTURES AND REMOVE 6" PERFORATED VERTICAL RISER PIPE, CRUSHED STONE AND FILTER FABRIC.
 - ADD INCREASED CAP WITH ORIFICE AT DISCHARGE END OF 6" SOLID PVC SDR 35 PIPES PER DETAIL.
 - REPLACE THE PERFORATED PIPE AND CRUSHED STONE. DO NOT REPLACE FILTER FABRIC.
 - ESTABLISH THE FINAL VEGETATION IN THE BASINS IN ACCORDANCE WITH THE STORMWATER BASIN PLANTING DETAILS.
 - FOR BASINS 2.1P AND 2.2P EXCAVATE BOTTOM OF TST TO PERMANENT STORMWATER BASIN BOTTOM. ANY EXCESS SOIL SHALL BE RELOCATED OFF SITE AND BE PLACED IN A MANNER SO IT WILL NOT ERODE OR CAUSE EROSION.
 - CONVERSION OF TST'S SHALL BE ACCOMPLISHED ONE AT A TIME. TST'S SHALL REMAIN OPEN TO THE FINAL LANDSCAPE CONVERSION UNTIL THE TST'S ARE FULLY STABILIZED. THE FIRST STABILIZED TST SHALL BE CLOSED AND THE SECOND TST SHALL NOT START CONVERSION UNTIL THE PREVIOUS BASIN IS STABILIZED.
- THE 6" PERFORATED VERTICAL RISER SHALL BE CONSTRUCTED AS FOLLOWS:
 - WHEN INITIALLY USED AS THE TEMPORARY SEDIMENT TRAP (DRAINING DEVICE) THE RISER SHALL BE BEARING WITH TYPAR 300 GEOTEXTILE OR APPROVED EQUAL AND SURROUNDED WITH 2" LAYER OF 2" CRUSHED STONE. THE TOP OF THE RISER SHALL BE SET AT THE SAME ELEVATION AS THE RISER AS SHOWN IN THE STORMWATER BASIN OUTLET STRUCTURE DETAIL.
 - WHEN THE PERMANENT RISER FOR BASIN IS CONSTRUCTED THE RISER SHALL BE UNBARRICAD WITH THE TOP ELEVATION SET AT SPECIFIED ELEVATION.

PLANTING NOTES:


- All proposed planting beds to receive a 12" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
- Any new soils added shall be amended as required by results of soil testing and placed using a method that will not cause erosion.
- No fertilizer shall be added in stormwater basin plantings. Nutrient requirements to be met by incorporation of acceptable organic matter.
- All plant material to be nursery green.
- Plants shall conform with ANSI Z601 American Standard for Nursery Stock in all ways including dimensions.
- Plant material shall be taken from healthy nursery stock.
- All plants shall be grown under climate conditions similar to those in the locality of the project.
- The location and layout of landscape plants shown on this plan shall take precedence in any discrepancies between the quantities of plants shown on the plans and the quantity of plants in the Plant List.
- Provide a 2" layer of shredded pine bark mulch (or an equivalent) over entire existing surface of all tree pits or over entire planting beds. Do not place mulch within 3" of tree or shrub trunk.
- All landscape plantings shall be maintained in a healthy condition at all times. Any dead or diseased plants shall immediately be replaced "in kind" by the contractor (during warranty period) or project owner.
- For all areas to be planted with emergent vegetation, soil shall be decompacted using tilling or other method approved by landscape architect and amended as required by results of soil testing to a depth of at least 12".
- Green lawn grading and placement of topsoil and any needed soil amendments, along to receive permanent vegetation cover in combination with suitable mulch as follows:
 - Fertilizer applied at the manufacturer's recommended rate using Lanco 150-0-18 (60 phosphorous) fertilizer or equivalent.
 - Mulch: soil type or small grain straw applied at a rate of 90 lbs./1000 s.f.c. or 2 tons/acre, to be applied and worked according to New York State Standards and Specifications for Erosion and Sediment Control, August 2005.
 - If the erosion prevention the requirement of a permanent vegetation cover.
- All proposed needed areas to stormwater basins to receive 6" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
- The Stormwater Basin seed mixes as specified on these drawings from New England Perennial Plants, Inc. shall be as follows:
 - Seed Mix #1 at a rate of 35 lbs. per acre.
 - Seed Mix #2 at a rate of 23 lbs. per acre.
 - Seed Mix #3 at a rate of 25 lbs. per acre.
 - Seed Mix #4 at a rate of 35 lbs. per acre.
 - Seed Mix #5 at a rate of 18 lbs. per acre.
- Interior of ponds including aquatic bench to be seeded. Permanent water to be drawn down below second grass strip vegetation establishment.




PERMANENT STORMWATER BASIN 2.1P OUTLET STRUCTURE DETAIL
(N.T.S.)




TEMPORARY SEDIMENT BASIN TRAP 2.1P OUTLET DETAIL
(N.T.S.)



STORMWATER BASIN 2.1P SCHEMATIC SECTION D-D
N.T.S.



PERMANENT STORMWATER BASIN 2.2P OUTLET STRUCTURE DETAIL
(N.T.S.)










STORMWATER BASIN 2.2P SCHEMATIC SECTION E-E
N.T.S.

ATTENTION: THIS DOCUMENT HAS BEEN THE PROPERTY OF A LICENSED PROFESSIONAL ENGINEER, OF A VIOLATION OF SECTION 7009 OF ARTICLE 17B OF THE EDUCATION LAW.

NO.	DATE	REVISION	BY
INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.			3 Carroll Place New York, NY 10017 (914) 235-8900 (914) 235-8917 www.insite-ny.com
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN SHEET NO. 4-10-24			
STORMWATER POND DETAILS			
PROJECT NO.	14211.100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	M.E.U.
SCALE	AS SHOWN	CHECKED BY	A.D.T.





- ### STORMWATER BASIN OUTLET NOTES
- THE BASINS ARE PROPOSED TO BE UTILIZED AS TEMPORARY SEDIMENT TRAPS (STP) DURING CONSTRUCTION.
 - AFTER THE CONTRIBUTING AREAS TO THE BASINS HAVE BEEN PERMANENTLY STABILIZED, THE FOLLOWING SHALL BE ACCOMPLISHED:
 - CLEAN BASINS AND OUTLET STRUCTURES AND REMOVE 6" PERFORATED RISER PIPES.
 - ADD THREADED CAP WITH ORIFICE AT DISCHARGE END OF 6" SOLID PVC SDR 35 RISE PER DETAIL.
 - REPLACE THE PROPOSED RISE AND CRUSHED STONE. DO NOT REPLACE FILTER FABRIC.
 - ESTABLISH THE FINAL VEGETATION IN THE BASINS IN ACCORDANCE WITH THE STORMWATER BASIN PLANTING DETAILS.
 - FOR BASINS 3.1P AND 3.2P, DEGRADE BOTTOM OF THE PERMANENT STORMWATER BASIN BOTTOM. ANY EXCESS SOIL SHALL BE REMOVED TO THE NEARBY CONSTRUCTION AREA. THE SOIL SHALL NOT START CAUSE PROBLEMS.
 - CONSTRUCTION OF STITS SHALL BE ACCOMPLISHED ON A 2" TYP. 10" DIA. ALLOW FOR THE TRAP, INCLUDING CRUSHED STONE. CRUSHED STONE SHALL BE 2" DIA. AND 1/2" THICK. THE STITS SHALL NOT START CAUSE PROBLEMS.
 - THE 6" PERFORATED RISER SHALL BE CONSTRUCTED AS FOLLOWS:
 - WHEN INITIALLY USED AS THE TEMPORARY SEDIMENT TRAP, VEGETATION UNDER THE RISER SHALL BE WRAPPED WITH 2" DIA. STONE. THE TOP OF THE RISER SHALL BE SET AT THE SAME ELEVATION AS THE RISERS AS SHOWN IN THE STORMWATER BASIN OUTLET STRUCTURE DETAILS.
 - WHEN THE PERMANENT RISER FOR BASIN IS CONSTRUCTED THE RISER SHALL BE UNWRAPPED WITH THE TOP ELEVATION SET AT SPECIFIED ELEVATIONS.

- ### PLANTING NOTES:
- All proposed planting beds to receive a 12" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
 - Any new soils added will be amended as required by results of soil testing and placed using a method that will not cause compaction.
 - No fertilizer shall be added in stormwater basin plantings. Nutrient requirements to be met by incorporation of acceptable organic matter.
 - All plant material to be nursery grown.
 - Plants shall conform with ANSI Z661 American Standard for Nursery Stock as well as applicable specifications.
 - Plant material shall be taken from healthy nursery stock.
 - All plants shall be grown under climate conditions similar to those in the locality of the project.
 - Plants shall be planted in all locations depicted on the plan or as indicated in the field by the Landscape Architect and landscape plants shown on the site plan shall take precedence in any discrepancies between the quantities of plants shown on the plans and the quantity of plants in the Plant List.
 - Provide a 3" layer of shredded pine bark mulch (or as specified) over entire wetting surface of all tree pits or over entire planting bed. Do not place mulch within 3" of tree or shrub trunk.
 - All landscape plantings shall be maintained in a healthy condition at all times. Any dead or diseased plants shall immediately be replaced "in kind" by the contractor (during warranty period) or project owner.
 - For all areas to be planted with emergent vegetation, and shall be decomposed using (filing or other method approved by Landscape Architect and amended as required by results of soil testing to a depth of at least 12").
 - Use that grading and placement of topsoil and any required soil amendments, areas to receive permanent vegetation cover a combination with suitable mulch as follows:
 - mulch: heavy mulch per manufacturer and meeting notes.
 - fertilizer: applied at the manufacturer's recommended rate using label.
 - mulch: 10-18 (in phenological) fertilizer or equivalent.
 - mulch: 10-18 (in phenological) fertilizer or equivalent.
 - or 2 1/2 tons/acre, to be applied and amended according to New York State Department of Environmental Conservation and Specifications for Erosion and Sediment Control, August 2006.
 - if the season prevents the establishment of a permanent vegetation cover, the disturbed areas will be mulched with straw or equivalent.
 - All proposed seeded areas to stormwater basins to receive 4" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
 - The Stormwater Basin seed mixes as specified on these drawings from New England Wetland Plants, Inc. of Amherst, MA, are as follows:
 - Seed Mix #1 at a rate of 35 lbs. per acre. Use English Orchard Control/Restoration Mix (for Detention basins and Moist Sites).
 - Seed Mix #2 at a rate of 23 lbs. per acre. Use English Orchard Moist Mix.
 - Seed Mix #3 at a rate of 25 lbs. per acre. Use English Orchard Moist Mix.
 - Seed Mix #4 at a rate of 25 lbs. per acre. Use English Orchard Moist Mix.
 - Seed Mix #5 at a rate of 18 lbs. per acre. Use English Orchard Moist Mix.
 - Invoicing of seeds including aquatic bench to be seeded. Permanent water to be drawn down when seeded areas until vegetation establishes.

ALTERNATION OF THIS DOCUMENT SHALL BE UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, AS A VIOLATION OF SECTION 7009 OF ARTICLE 17B OF THE ENVIRONMENTAL LAW.

NO.	DATE	REVISION	BY
INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.			
PROJECT: THE HAMLET AT CARMEL AMENDED SITE PLAN			
DRAWING: STORMWATER POND DETAILS			
PROJECT NO.	14211.100	PROJECT MANAGER	R.D.W.
DATE	4-10-24	DRAWN BY	M.E.U.
SCALE	AS SHOWN	CHECKED BY	A.D.T.
DRAWING NO.	4-10-24	SHEET	15
			D-6

Reservoir Place

Stoneleigh Ave,
 Town of Carmel, NY

Building A
 First & Second Floor Plans

REVISIONS

DATE


11/2/23

PROJECT NUMBER


23-09

SHEET NUMBER

A1



1 Building A Second Floor Plan
 A1 Scale: 1/8"=1'-0"




2 Building A First Floor Plan
 A1 Scale: 1/8"=1'-0"


Reservoir Place - Unit and Area Breakdown

Building #	1 Br Apartment	2 Br Apartment	3 Br Apartment	Total
	745 s.f. int.	970 s.f. int.	1172 s.f. int.	
A	4	8	4	16
B	0	8	0	8
C	4	10	6	20
D	5	7	3	15
E	4	8	4	16
TOTALS	17	41	17	75
Total Int. Area	12605	30770	19624	73000

(1) First floor units are variable and adaptable.
 (2) Units will be Mobility Adapted.
 (3) Units will be A/V Adapted.




1 East (Rear) Elevation
A4 Scale: 1/8"=1'-0"



2 North (Left Side) Elevation
A4 Scale: 1/8"=1'-0"

Typical Exterior Finishes:
 Hardie fibercement siding & shakes-
 Siding (Light Mist & Deep Ocean)
 Shakes (Light Mist)
 Fiberglass Shingles- GAF Slate
 Composite Trim Boards- White
 Energy Star Windows- White
 Vinyl Shutters- Mid America Midnight Blue
 Composite Columns- White



3 South (Right Side) Elevation
A4 Scale: 1/8"=1'-0"



4 West (Front) Elevation
A4 Scale: 1/8"=1'-0"

REVISIONS
DATE
11/2/23
PROJECT NUMBER
23-09
SHEET NUMBER



Design, Architecture & Planning
 6 Old North Plank Road
 Suite 101
 Newburgh, NY 12550
 TEL: 845-561-3559
 FAX: 845-561-2051
 ajcoppola@coppola-associates.com

LICENSE NUMBER: 018849

PROPOSED MULTIFAMILY DWELLINGS FOR

Reservoir Place

Stoneleigh Ave,
 Town of Carmel, NY

**Building C
 First Floor Plan**

REVISIONS

NO.	DATE	DESCRIPTION

DATE


11/2/23

PROJECT NUMBER


23-09

SHEET NUMBER

A5




1 Building C First Floor Plan
A5 Scale: 1/8"=1'-0"



FIRE RATED ASSEMBLIES:
 1. EXTERIOR WALLS- 1 HOUR
 2. STAIRWELL WALLS- 1 HOUR
 3. EXTERIOR WALLS- 1 HOUR
 4. FINISH FLOOR/CEILING- 1 HOUR
 5. ROOF SYSTEM- 1 HOUR

1 Building C Third Floor Plan
 A6 Scale: 1/8"=1'-0"


8,603 s.f.
 8,344 s.f. int.
 (2) 1 BR Units
 (4) 2 BR Units
 (2) 3 BR Units



FIRE RATED ASSEMBLIES:
 1. EXTERIOR WALLS- 1 HOUR
 2. STAIRWELL WALLS- 1 HOUR
 3. EXTERIOR WALLS- 1 HOUR
 4. FINISH FLOOR/CEILING- 1 HOUR
 5. ROOF SYSTEM- 1 HOUR

2 Building C Second Floor Plan
 A6 Scale: 1/8"=1'-0"

8,603 s.f.
 8,344 s.f. int.
 (2) 1 BR Units
 (4) 2 BR Units
 (2) 3 BR Units



Design, Architecture & Planning
 6 Old North Plank Road
 Suite 101
 Newburgh, NY 12550
 TEL: 845-561-3559
 FAX: 845-561-2051
 ajcoppola@coppola-associates.com

LICENSE NUMBER: 018849

* PROPOSED MULTIFAMILY DWELLINGS FOR *

Reservoir Place

Stoneleigh Ave.
 Town of Carmel, NY

**Building C
 Second & Third
 Floor Plans**


REVISIONS	DATE

PROJECT NUMBER
23-09
 SHEET NUMBER

A6




1 West (Rear) Elevation
A7 Scale: 1/8"=1'-0"



2 North (Right Side) Elevation
A7 Scale: 1/8"=1'-0"


Typical Exterior Finishes:
 Hardie fibercement siding & shakes-
 Siding (Countrylane Red & Navajo Beige)
 Shakes (Navajo Beige)
 Fiberglass Shingles- GAF Pewter Gray
 Composite Trim Boards- White
 Energy Star Windows- White
 Vinyl Shutters- Mid America Clay
 Composite Columns- White




3 South (Left Side) Elevation
A7 Scale: 1/8"=1'-0"





4 East (Front) Elevation
A7 Scale: 1/8"=1'-0"



1 Building D Third Floor Plan
 A9 Scale: 1/8"=1'-0"




2 Building D Second Floor Plan
 A9 Scale: 1/8"=1'-0"






1 East (Rear) Elevation
A12 Scale: 1/8"=1'-0"



2 North (Left Side) Elevation
A12 Scale: 1/8"=1'-0"

Typical Exterior Finishes:
 Hardie fiber cement siding & shakes-
 Siding (Countrylane Red & Navajo Beige)
 Shakes (Navajo Beige)
 Fiberglass Shingles- GAF Pewter Gray
 Composite Trim Boards- White
 Energy Star Windows- White
 Vinyl Shutters- Mid America Clay
 Composite Columns- White



3 South (Right Side) Elevation
A12 Scale: 1/8"=1'-0"



4 West (Front) Elevation
A12 Scale: 1/8"=1'-0"

JOHN KARELL, JR., P.E.
121 CUSHMAN ROAD
PATTERSON, NEW YORK, 12563
845-878-7894 FAX 845 878 4939
jack4911@yahoo.com

April 10, 2024

To: Town of Carmel Planning Board

Re: **Site Plan Lantern Pub Reconstruction**
728 Route 6, LLC
728 Route 6, Mahopac; TM # 76.22-1-54

The below is a response to comments from the Town Consultants and Staff as follows:

Richard Franzetti, P.E., Town Engineer dated April 8, 2024

- **Page 2 of 3 Completeness Form**
Item 18 and 20 have been completed yes
The well was shown on the plan but was not clearly evident. Added new Label.
The sewer line has been shown from the former site plan consisting of an existing 1000 gallon concrete grease .trap. and connection to the Town Sanitary Sewer
- **Page 2 of 4 Site Plan Application**
Water supply has been indicated NO, existing well and the boxes for storm sewer, electric service, gas service and telephone cable lines have been checked yes.



John Karell, Jr., P.E.



TOWN OF CARMEL SITE PLAN APPLICATION INSTRUCTIONS



The Town of Carmel Planning Board meetings are held twice a month, on the second **Thursday** and fourth **Wednesday**, at 7:00 PM at Carmel Town Hall, 60 McAlpin Avenue, Carmel

The submission deadline is 10 days prior to the Planning Board meeting. New site plan applications that have been deemed complete will be placed on the agenda in the order they are received.

No application will be placed on the agenda that is incomplete

Pre-Submission:

Prior to the formal submission of the site plan, a pre-submission conference may be requested by the applicant to be conducted with representatives from the Town, which may include the Town Planner, Town Engineer, Director of Code Enforcement and/or the Planning Board Attorney. This conference will serve to educate the applicant on the process he/she must follow, clarify the information required to submit a complete site plan application, and to highlight any specific areas of concern. You may arrange a pre-submission conference through the Planning Board Secretary at (845) 628-1500 extension 190.

Submission Requirements:

At least 10 days prior to the Planning Board meeting, the site plan application shall be submitted to the Planning Board Secretary as follows:

All site plans shall be signed, sealed and folded with the title box legible. The application package shall include:

- 5 copies of the Site Plan Application Form, signed and notarized.
- 5 copies of the SEQR Environmental Assessment Form (use of short form or long form shall be determined at pre-submission conference).
- 5 full size sets of the Site Plan (including floor plans and elevations)
- 1 CD (in pdf. format) containing an electronic version of the Site Plan
- 2 copies of the Disclosure Statement
- 5 copies of the Site Plan Completeness Certification Form
- All supplemental studies, reports, plans and renderings.
- 2 copies of the current deed. *submitted previously*
- 2 copies of all easements, covenants and restrictions. *none*
- The appropriate fee, determined from the attached fee schedule. Make checks payable to the *Town of Carmel*.

Rose Yonelotta 4/11/24

 Planning Board Secretary; Date

[Signature] 4/11/24

 Town Engineer; Date



TOWN OF CARMEL SITE PLAN APPLICATION



Per Town of Carmel Code – Section 156 - Zoning

SITE IDENTIFICATION INFORMATION			
Application Name: T28 ROUTE 6, LLC		Application # 24-0010	Date Submitted: 4/1/24
Site Address: No. 168 Street: EAST LAKE BLVD Hamlet: MAHOPAC			
Property Location: (Identify landmarks, distance from intersections, etc.) T28 ROUTE 6			
Town of Carmel Tax Map Designation: Section 76.22 Block 1 Lot(s) 54		Zoning Designation of Site: C	
Property Deed Recorded in County Clerk's Office Date _____ Liber _____ Page _____		Liens, Mortgages or other Encumbrances Yes _____ No _____	
Existing Easements Relating to the Site No _____ Yes _____ Describe and attach copies: _____		Are Easements Proposed? No _____ Yes _____ Describe and attach copies: _____	
Have Property Owners within a 500' Radius of the Site Been Identified? Yes _____ No _____ Attached List to this Application Form			
APPLICANT/OWNER INFORMATION			
Property Owner: MICHAEL GUO		Phone #: Fax#:	Email:
Owners Address: No. 168 Street: EAST LAKE BLVD Town: MAHOPAC State: NY Zip: 10541			
Applicant (If different than owner): same as owner		Phone #: 914 523 9450 Fax#:	Email: GUO16838@YH CO. COM
Applicant Address (If different than owner): No. _____ Street: _____ Town: _____ State: _____ Zip: _____			
Individual/ Firm Responsible for Preparing Site Plan: John Karell, Jr. P.E.		Phone #: 845 721 0455 Fax#:	Email: JACK4911@YAHOO .COM
Address: No. 121 Street: CUSHMAN ROAD Town: PATTERSON State: NY Zip: 12563			
Other Representatives:		Phone #: Fax#:	Email:
Owners Address: No. _____ Street: _____ Town: _____ State: _____ Zip: _____			
PROJECT DESCRIPTION			
Describe the project, proposed use and operation thereof: RENOVATION OF AN EXISTING SECOND FLOOR OFFICE AND STORAGE SPACE TO THREE 2 BEDROOM APARTMENTS			

TOWN OF CARMEL SITE PLAN APPLICATION

PROJECT INFORMATION			
Lot size: Acres: <u>0.53</u>	Square Feet: <u>23,087</u>	Square footage of all existing structures (by floor):	
# of existing parking spaces: <u>31</u>	# of proposed parking spaces: <u>0</u>		
# of existing dwelling units: <u>0</u>	# of proposed dwelling units: <u>3</u>		
Is the site served by the following public utility infrastructure:			
<ul style="list-style-type: none"> ▪ Is project in sewer district or will private septic system(s) be installed? <u>SEWER</u> ▪ If yes to Sanitary Sewer answer the following: <u>DISTRICT</u> <ul style="list-style-type: none"> ▶ Does approval exist to connect to sewer main? Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> ▶ Is this an in-district connection? <u>YES</u> Out-of district connection? _____ ▶ What is the total sewer capacity at time of application? _____ ▶ What is your anticipated average and maximum daily flow <u>660 GPD AVG</u> 			
For Town of Carmel Town Engineer			
▶ What is the sewer capacity _____			
<ul style="list-style-type: none"> ▪ Water Supply Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> <u>EX. WELL</u> 			
If Yes: ▶ Does approval exist to connect to water main? Yes: <input type="checkbox"/> No: <input type="checkbox"/>			
▶ What is the total water capacity at time of application? _____			
▶ What is your anticipated average and maximum daily demand _____			
<ul style="list-style-type: none"> ▪ Storm Sewer Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> ▪ Electric Service Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> ▪ Gas Service Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> • Telephone/Cable Lines Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> 			
For Town of Carmel Town Engineer			
Water Flows <u>PP</u> 4/10/12			
Sewer Flows _____			
Town Engineer; Date _____			
What is the predominant soil type(s) on the site? <u>N/A</u>		What is the approximate depth to water table? <u>N/A</u>	
Site slope categories: 15-25% <u>—</u> % 25-35% <u>—</u> % >35% <u>—</u> %			
Estimated quantity of excavation: Cut (C.Y.) <u>0</u>		Fill (C.Y.) <u>0</u>	
Is Blasting Proposed Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> Unknown: <input type="checkbox"/>			
Is the site located in a designated Critical Environmental Area? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>			
Does a curb cut exist on the site? Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/>		Are new curb cuts proposed? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
What is the sight distance? Left <u>7200</u> Right <u>7200</u>			
Is the site located within 500' of:			
<ul style="list-style-type: none"> • The boundary of an adjoining city, town or village Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> • The boundary of a state or county park, recreation area or road right-of-way Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> • A county drainage channel line. Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> • The boundary of state or county owned land on which a building is located Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> 			

TOWN OF CARMEL SITE PLAN APPLICATION

Is the site listed on the State or Federal Register of Historic Place (or substantially contiguous)
 Yes: No:

Is the site located in a designated floodplain?
 Yes: No:

Will the project require coverage under the Current NYSDEC Stormwater Regulations
 Yes: No:

Will the project require coverage under the Current NYCDEP Stormwater Regulations
 Yes: No:

Does the site disturb more than 5,000 sq ft
 Yes: No:

Does the site disturb more than 1 acre
 Yes: No:

Does the site contain freshwater wetlands?
 Yes: No:

Jurisdiction:
 NYSDEC: Town of Carmel:

If present, the wetlands must be delineated in the field by a Wetland Professional, and survey located on the Site Plan.

Are encroachments in regulated wetlands or wetland buffers proposed? Yes: No:

Does this application require a referral to the Environmental Conservation Board? Yes: No:

Does the site contain waterbodies, streams or watercourses? Yes: No:

Are any encroachments, crossings or alterations proposed? Yes: No:

Is the site located adjacent to New York City watershed lands? Yes: No:

Is the project funded, partially or in total, by grants or loans from a public source?
 Yes: No:

Will municipal or private solid waste disposal be utilized?
 Public: Private:



Has this application been referred to the Fire Department? Yes: No:

What is the estimated time of construction for the project?
 TO BEGIN JULY 1, 2024; TAKING 6 MONTHS

ZONING COMPLIANCE INFORMATION			
Zoning Provision	Required	Existing	Proposed
Lot Area SF	40 000	23 262	SAME
Lot Coverage %	30	27.4	↓
Lot Width FT	200	150	
Lot Depth FT	200	153	
Front Yard FT	40	15	
Side Yard FT	25	17.3	
Rear Yard FT	30	47.3	
Minimum Required Floor Area SF	5000	6180	
Floor Area Ratio			
Height FT	35	30	
Off-Street Parking *	40	37	
Off-Street Loading			↓

* VARIANCE FOR ADDITIONAL 80 SPACES GRANTED 3 of 4

TOWN OF CARMEL SITE PLAN APPLICATION

Will variances be required? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	If yes, identify variances:
PROPOSED BUILDING MATERIALS:	
Foundation	N/A
Structural System	N/A
Roof	N/A
Exterior Walls	N/A
APPLICANT'S ACKNOWLEDGEMENT	
I hereby depose and certify that all the above statements and information, and all statements and information contained in the supporting documents and drawings attached hereto are true and correct.	
<u>Michael Guo</u> Applicants Name	 Applicants Signature
Sworn before me this <u>1st</u> day of <u>April</u> 20 <u>24</u>	Denise Nizolek Notary Public, State of New York Registration no. 01N16218997 Qualified in Putnam County Commission Expires March 15, 20 <u>26</u>
 Notary Public	



TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



All Site Plans submitted to the Planning Board for review shall include the following information and details, as set forth in Section 156-61 B of the Town of Carmel Zoning Ordinance.

This form shall be included with the site plan submission

	<i>Requirement Data</i>	<i>To Be Completed by the Applicant</i>	<i>Waived by the Town</i>
1	Name and title of person preparing the site plan	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2	Name of the applicant and owner (if different from applicant)	N <input checked="" type="checkbox"/> A	<input type="checkbox"/>
3	Original drawing date, revision dates, scale and north arrow	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4	Tax map, block and lot number(s), zoning district	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5	All existing property lines, name of owner of each property within a 500' radius of the site	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6	Contour lines at two-foot intervals, grades of all roads, driveways, sanitary and storm sewers	<input type="checkbox"/>	<input type="checkbox"/>
7	The location of all water bodies, streams, watercourses, wetland areas, wooded areas, rights-of-way, streets, roads, highways, railroads, buildings, structures	EX. NO GRADING <input checked="" type="checkbox"/>	<input type="checkbox"/>
8	The location of all existing and proposed easements	N <input checked="" type="checkbox"/> A none	<input type="checkbox"/>
9	The location of all existing and proposed structures, their use, setback dimensions, floor plans, front, side and rear elevations, buildable area.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
10	On site circulation systems, access, egress ways and service roads, emergency service access and traffic mitigation measures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
11	Sidewalks, paths and other means of pedestrian circulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12	On-site parking and loading spaces and travel aisles with dimensions	<input checked="" type="checkbox"/>	<input type="checkbox"/>
13	The location, height and type of exterior lighting fixtures	EX. <input checked="" type="checkbox"/>	<input type="checkbox"/>
14	Proposed signage	EX. <input checked="" type="checkbox"/>	<input type="checkbox"/>
15	For non-residential uses, an estimate of the number of employees who will be using the site, description of the operation, types of products sold, types of machinery and equipment used	EX <input checked="" type="checkbox"/>	<input type="checkbox"/>



TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



	Requirement Description	Is the requirement met by the Applicant	Warranted by the Town
16	The location of clubhouses, swimming pools, open spaces, parks or other recreational areas, and identification of who is responsible for maintenance	N <input checked="" type="checkbox"/> A	<input type="checkbox"/>
17	The location and design of buffer areas, screening or other landscaping, including grading and water management. A comprehensive landscaping plan in accordance with the Tree Conservation Law	N <input checked="" type="checkbox"/> A	<input type="checkbox"/>
18	The location of public and private utilities, maintenance responsibilities, trash and garbage areas	<input checked="" type="checkbox"/>	<input type="checkbox"/>
19	A list, certified by the Town Assessor, of all property owners within 500 feet of the site boundary	<input checked="" type="checkbox"/>	<input type="checkbox"/>
20	Any other information required by the Planning Board which is reasonably necessary to ascertain compliance with this chapter	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Applicants Certification (to be completed by the licensed professional preparing the site plan:

I, John Karell, Jr. hereby certify that the site plan to which I have attached my seal and signature, meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:


Signature - Applicant

March 31, 2024
Date



Professionals Seal


Signature - Owner

Date



TOWN OF CARMEL
SITE PLAN COMPLETENESS
CERTIFICATION FORM



Town Certification (to be completed by the Town)

I _____ hereby confirm that the site plan meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:

Rose Yonkietta
Signature - Planning Board Secretary

4/11/24
Date

[Signature]
Signature - Town Engineer

4/11/24
Date

Short Environmental Assessment Form

Part 1 - Project Information


Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.


Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information			
Name of Action or Project: 728 ROUTE 6, BUILDING RENOVATION			
Project Location (describe, and attach a location map): 728 ROUTE 6, MAHOPAC, NY			
Brief Description of Proposed Action: RENOVATION OF AN EXISTING SECOND FLOOR OFFICE AND STORAGE SPACE TO THREE 2 BEDROOM APARTMENTS			
Name of Applicant or Sponsor: MICHAEL GUO		Telephone:	
Address: 168 EAST LAKE BOULEVARD		E-Mail:	
City/PO: MAHOPAC		State: NY	Zip Code: 10541
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.			NO <input type="checkbox"/>
2. Does the proposed action require a permit, approval or funding from any other government Agency? If Yes, list agency(s) name and permit or approval:			YES <input type="checkbox"/>
3. a. Total acreage of the site of the proposed action? _____ 0.53 acres			
b. Total acreage to be physically disturbed? _____ 0 acres			
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor? _____ 0.53 acres			
4. Check all land uses that occur on, are adjoining or near the proposed action:			
5. <input type="checkbox"/> Urban <input type="checkbox"/> Rural (non-agriculture) <input type="checkbox"/> Industrial <input checked="" type="checkbox"/> Commercial <input type="checkbox"/> Residential (suburban)			
<input type="checkbox"/> Forest <input type="checkbox"/> Agriculture <input type="checkbox"/> Aquatic <input type="checkbox"/> Other(Specify):			
<input type="checkbox"/> Parkland			

5. Is the proposed action,	NO	YES	N/A
a. A permitted use under the zoning regulations?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. Consistent with the adopted comprehensive plan?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?	NO	YES	
If Yes, identify: _____	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	NO	YES	
b. Are public transportation services available at or near the site of the proposed action?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
9. Does the proposed action meet or exceed the state energy code requirements?	NO	YES	
If the proposed action will exceed requirements, describe design features and technologies: _____ _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
10. Will the proposed action connect to an existing public/private water supply?	NO	YES	
If No, describe method for providing potable water: _____ _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
11. Will the proposed action connect to existing wastewater utilities?	NO	YES	
If No, describe method for providing wastewater treatment: _____ _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on the National or State Register of Historic Places, or that has been determined by the Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places?	NO	YES	
b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO	YES	
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
_____ _____			



Part 1 / Question 7 [Critical Environmental Area]	No
Part 1 / Question 12a [National or State Register of Historic Places or State Eligible Sites]	No
Part 1 / Question 12b [Archeological Sites]	Yes
Part 1 / Question 13a [Wetlands or Other Regulated Waterbodies]	Yes - Digital mapping information on local and federal wetlands and waterbodies is known to be incomplete. Refer to EAF Workbook.
Part 1 / Question 15 [Threatened or Endangered Animal]	Yes
Part 1 / Question 15 [Threatened or Endangered Animal - Name]	Northern Long-eared Bat
Part 1 / Question 16 [100 Year Flood Plain]	No
Part 1 / Question 20 [Remediation Site]	No



*1 ex upstairs
1 office - red string
proposed*

*1 2br apt
1 2 B apt
1 2 R apt
GSR*

SECOND FLOOR PLAN

RENOVATION OF
EXISTING SECOND FLOOR
728 ROUTE SIX
MAHOPAC, NEW YORK

CONCEPT PLAN
PRELIMINARY
SUBJECT TO CHANGE



NOTE
THESE PLANS ARE NOT VALID FOR BUILDING PERMITS OR CONSTRUCTION
UNLESS STAMPED AND SIGNED BY A STATE LICENSED ARCHITECT OR ENGINEER.

BOB STROM DESIGN
& CONSTRUCTION INC.
728 ROUTE SIX LLC
168 EAST LAKE BLVD
MAHOPAC, NEW YORK
945-628-1423

APARTMENT SCHEMATIC
728 ROUTE SIX LLC
168 EAST LAKE BLVD
MAHOPAC, NEW YORK
MAR. 22, 2024 JOB NO. 2552

ENGINEER OF RECORD
JOHN KARELL, JR. P.E.
CUSHMAN ROAD
PATTERSON, NEW YORK
(845) 878-7894

FLOOR PLAN
A1
SCALE 1/4" = 1'-0"

RALPH G. MASTROMONACO, P.E., P.C.

Consulting Engineers

13 Dove Court, Croton-on-Hudson, New York 10520

Tel: (914) 271-4762 Fax: (914) 271-2820

Civil / Site / Environmental

www.rgmpepc.com

Rose Trombetta
Planning Office
Carmel Town Hall
60 McAlpin Avenue
Mahopac, NY 10541

April 15, 2024

Hand Deliver

rtrombetta@ci.carmel.ny.us

Re: Site Plan for Greg Lamanna
Mahopac, NY


Dear Rose:

Enclosed are five (5) sets of the following information:

1. Stormwater Report – Lamanna Auto Body Town of Carmel dated April 15, 2024,
2. Sets of plans as follows:
 - a. Site Plan, Proposed Addition prepared for Gabriel Lamanna dated January 30, 2024 revised April 15, 2024, Sheet 1 of 3,
 - b. SU-30 Trick Access Plan, Proposed Addition prepared for Gabriel Lamanna dated April 15, 2024, Sheet 2 of 3,
 - c. Details / Notes, Proposed Addition prepared for Gabriel Lamanna dated January 30, revised April 15, 2024 Sheet 3 of 3,

Please call if you have any questions or require additional information.


Sincerely,



Ralph G. Mastromonaco, PE

Cc: Greg Lamanna

STORMWATER REPORT - LAMANNA AUTO BODY
TOWN OF CARMEL, NY
APRIL 12, 2024




EXISTING



PROPOSED

RESULTS			
Event	Rainfall (inches)	Existing Runoff (cfs)	Proposed Primary (cfs)
1 YR	5.01	0.33	0.26
2 YR	3.34	0.19	0.12
10 YR	5.01	0.33	0.26
100 YR	9.01	0.69	0.68

NOTE: All flows are reduced.



CHAMBERS





FINAL

RALPH G. MASTROMONACO, P.E., P.C.
Consulting Engineers
13 Dove Court, Croton-on-Hudson, New York 10520
(914) 271-4762



Ralph G. Mastromonaco



Routing Diagram for lam_1

Prepared by RGM PEPC Consulting Engineers, Printed 4/12/2024
HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

Summary for Subcatchment EX: EXISTING

Runoff = 0.33 cfs @ 12.21 hrs, Volume= 0.030 af, Depth> 3.17"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1 YR Rainfall=5.01"

Area (sf)	CN	Description
2,208	98	Roofs, HSG C
2,685	74	>75% Grass cover, Good, HSG C
4,893	85	Weighted Average
2,685		54.87% Pervious Area
2,208		45.13% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment EX: EXISTING

Hydrograph



Summary for Subcatchment PR: PROPOSED

Runoff = 0.42 cfs @ 12.20 hrs, Volume= 0.041 af, Depth> 4.43"
Routed to Pond 3P : CHAMBERS


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 1 YR Rainfall=5.01"

	Area (sf)	CN	Description
*	2,208	98	
	2,685	98	Roofs, HSG C
	4,893	98	Weighted Average
	4,893		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment PR: PROPOSED

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers

HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Type III 24-hr 1 YR Rainfall=5.01"

Printed 4/12/2024

Page 4

Summary for Pond 3P: CHAMBERS

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 4.43" for 1 YR event
 Inflow = 0.42 cfs @ 12.20 hrs, Volume= 0.041 af
 Outflow = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af, Atten= 38%, Lag= 12.6 min
 Primary = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af
 Routed to Link FIN : FINAL

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 2.21' @ 12.41 hrs Surf.Area= 0.006 ac Storage= 0.009 af

Plug-Flow detention time= 21.7 min calculated for 0.041 af (100% of inflow)
 Center-of-Mass det. time= 19.5 min (761.2 - 741.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	0.00'	0.006 af	11.00'W x 24.98'L x 3.50'H Field A 0.022 af Overall - 0.006 af Embedded = 0.016 af x 40.0% Voids
#2A	0.50'	0.006 af	ADS_StormTech SC-740 +Cap x 6 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56"L with 0.44' Overlap 6 Chambers in 2 Rows
		0.013 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	2.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	2.00'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.26 cfs @ 12.41 hrs HW=2.21' (Free Discharge)

- └─1=Orifice/Grate (Orifice Controls 0.15 cfs @ 7.02 fps)
- └─2=Orifice/Grate (Orifice Controls 0.10 cfs @ 1.55 fps)

Pond 3P: CHAMBERS




Summary for Link FIN: FINAL

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 4.41" for 1 YR event
Inflow = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af
Primary = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link FIN: FINAL

Hydrograph



Summary for Subcatchment EX: EXISTING

Runoff = 0.19 cfs @ 12.21 hrs, Volume= 0.016 af, Depth> 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2 YR Rainfall=3.34"

Area (sf)	CN	Description
2,208	98	Roofs, HSG C
2,685	74	>75% Grass cover, Good, HSG C
4,893	85	Weighted Average
2,685		54.87% Pervious Area
2,208		45.13% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment EX: EXISTING

Hydrograph



Summary for Subcatchment PR: PROPOSED

Runoff = 0.28 cfs @ 12.20 hrs, Volume= 0.027 af, Depth> 2.90"
 Routed to Pond 3P : CHAMBERS


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2 YR Rainfall=3.34"

	Area (sf)	CN	Description
*	2,208	98	
	2,685	98	Roofs, HSG C
	4,893	98	Weighted Average
	4,893		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment PR: PROPOSED

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers

HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Type III 24-hr 2 YR Rainfall=3.34"

Printed 4/12/2024

Page 9

Summary for Pond 3P: CHAMBERS

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 2.90" for 2 YR event
 Inflow = 0.28 cfs @ 12.20 hrs, Volume= 0.027 af
 Outflow = 0.12 cfs @ 12.51 hrs, Volume= 0.027 af, Atten= 56%, Lag= 18.8 min
 Primary = 0.12 cfs @ 12.51 hrs, Volume= 0.027 af
 Routed to Link FIN : FINAL

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 1.46' @ 12.51 hrs Surf.Area= 0.006 ac Storage= 0.006 af

Plug-Flow detention time= 19.7 min calculated for 0.027 af (99% of inflow)
 Center-of-Mass det. time= 17.2 min (762.1 - 744.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	0.00'	0.006 af	11.00'W x 24.98'L x 3.50'H Field A 0.022 af Overall - 0.006 af Embedded = 0.016 af x 40.0% Voids
#2A	0.50'	0.006 af	ADS_StormTech SC-740 +Cap x 6 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 6 Chambers in 2 Rows
		0.013 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	2.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	2.00'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.12 cfs @ 12.51 hrs HW=1.46' (Free Discharge)

└─1=Orifice/Grate (Orifice Controls 0.12 cfs @ 5.65 fps)
 └─2=Orifice/Grate (Controls 0.00 cfs)

Pond 3P: CHAMBERS




Summary for Link FIN: FINAL

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 2.89" for 2 YR event
Inflow = 0.12 cfs @ 12.51 hrs, Volume= 0.027 af
Primary = 0.12 cfs @ 12.51 hrs, Volume= 0.027 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link FIN: FINAL

Hydrograph



Summary for Subcatchment EX: EXISTING

Runoff = 0.33 cfs @ 12.21 hrs, Volume= 0.030 af, Depth> 3.17"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10 YR Rainfall=5.01"

Area (sf)	CN	Description
2,208	98	Roofs, HSG C
2,685	74	>75% Grass cover, Good, HSG C
4,893	85	Weighted Average
2,685		54.87% Pervious Area
2,208		45.13% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment EX: EXISTING

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers
HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Type III 24-hr 10 YR Rainfall=5.01"
Printed 4/12/2024
Page 13

Summary for Subcatchment PR: PROPOSED

Runoff = 0.42 cfs @ 12.20 hrs, Volume= 0.041 af, Depth> 4.43"
Routed to Pond 3P : CHAMBERS


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10 YR Rainfall=5.01"

	Area (sf)	CN	Description
*	2,208	98	
	2,685	98	Roofs, HSG C
	4,893	98	Weighted Average
	4,893		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment PR: PROPOSED

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers

HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

Summary for Pond 3P: CHAMBERS

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 4.43" for 10 YR event
 Inflow = 0.42 cfs @ 12.20 hrs, Volume= 0.041 af
 Outflow = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af, Atten= 38%, Lag= 12.6 min
 Primary = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af
 Routed to Link FIN : FINAL

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 2.21' @ 12.41 hrs Surf.Area= 0.006 ac Storage= 0.009 af

Plug-Flow detention time= 21.7 min calculated for 0.041 af (100% of inflow)
 Center-of-Mass det. time= 19.5 min (761.2 - 741.7)


Volume	Invert	Avail.Storage	Storage Description
#1A	0.00'	0.006 af	11.00'W x 24.98'L x 3.50'H Field A 0.022 af Overall - 0.006 af Embedded = 0.016 af x 40.0% Voids
#2A	0.50'	0.006 af	ADS_StormTech SC-740 +Cap x 6 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 6 Chambers in 2 Rows
		0.013 af	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	2.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	2.00'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.26 cfs @ 12.41 hrs HW=2.21' (Free Discharge)
 1=Orifice/Grate (Orifice Controls 0.15 cfs @ 7.02 fps)
 2=Orifice/Grate (Orifice Controls 0.10 cfs @ 1.55 fps)

Pond 3P: CHAMBERS




Summary for Link FIN: FINAL

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 4.41" for 10 YR event
Inflow = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af
Primary = 0.26 cfs @ 12.41 hrs, Volume= 0.041 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link FIN: FINAL

Hydrograph



Summary for Subcatchment EX: EXISTING

Runoff = 0.69 cfs @ 12.20 hrs, Volume= 0.063 af, Depth> 6.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100 YR Rainfall=9.01"

Area (sf)	CN	Description
2,208	98	Roofs, HSG C
2,685	74	>75% Grass cover, Good, HSG C
4,893	85	Weighted Average
2,685		54.87% Pervious Area
2,208		45.13% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment EX: EXISTING

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers
HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Type III 24-hr 100 YR Rainfall=9.01"
Printed 4/12/2024
Page 18

Summary for Subcatchment PR: PROPOSED

Runoff = 0.76 cfs @ 12.20 hrs, Volume= 0.075 af, Depth> 8.06"
Routed to Pond 3P : CHAMBERS


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100 YR Rainfall=9.01"

	Area (sf)	CN	Description
*	2,208	98	
	2,685	98	Roofs, HSG C
	4,893	98	Weighted Average
	4,893		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.0					Direct Entry,

Subcatchment PR: PROPOSED

Hydrograph



lam_1

Summary for Pond 3P: CHAMBERS

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 8.06" for 100 YR event
 Inflow = 0.76 cfs @ 12.20 hrs, Volume= 0.075 af
 Outflow = 0.68 cfs @ 12.27 hrs, Volume= 0.075 af, Atten= 10%, Lag= 4.3 min
 Primary = 0.68 cfs @ 12.27 hrs, Volume= 0.075 af
 Routed to Link FIN : FINAL

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 2.81' @ 12.27 hrs Surf.Area= 0.006 ac Storage= 0.011 af

Plug-Flow detention time= 18.6 min calculated for 0.075 af (99% of inflow)
 Center-of-Mass det. time= 16.8 min (756.1 - 739.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	0.00'	0.006 af	11.00'W x 24.98'L x 3.50'H Field A 0.022 af Overall - 0.006 af Embedded = 0.016 af x 40.0% Voids
#2A	0.50'	0.006 af	ADS_StormTech SC-740 +Cap x 6 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 6 Chambers in 2 Rows
		0.013 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	2.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	2.00'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.67 cfs @ 12.27 hrs HW=2.79' (Free Discharge)

- └─1=Orifice/Grate (Orifice Controls 0.17 cfs @ 7.92 fps)
- └─2=Orifice/Grate (Orifice Controls 0.50 cfs @ 3.68 fps)

Pond 3P: CHAMBERS




Summary for Link FIN: FINAL

Inflow Area = 0.112 ac, 100.00% Impervious, Inflow Depth > 8.03" for 100 YR event
Inflow = 0.68 cfs @ 12.27 hrs, Volume= 0.075 af
Primary = 0.68 cfs @ 12.27 hrs, Volume= 0.075 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link FIN: FINAL

Hydrograph



lam_1

Prepared by RGM PEPC Consulting Engineers
HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Multi-Event Tables
Printed 4/12/2024
Page 22

Events for Subcatchment EX: EXISTING

Event	Rainfall (inches)	Runoff (cfs)	Volume (acre-feet)	Depth (inches)
1 YR	5.01	0.33	0.030	3.17
2 YR	3.34	0.19	0.016	1.75
10 YR	5.01	0.33	0.030	3.17
100 YR	9.01	0.69	0.063	6.78

Events for Subcatchment PR: PROPOSED

Event	Rainfall (inches)	Runoff (cfs)	Volume (acre-feet)	Depth (inches)
1 YR	5.01	0.42	0.041	4.43
2 YR	3.34	0.28	0.027	2.90
10 YR	5.01	0.42	0.041	4.43
100 YR	9.01	0.76	0.075	8.06

Soil Mapping



lam_1

Prepared by RGM PEPC Consulting Engineers

HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Multi-Event Tables

Printed 4/12/2024

Page 24

Events for Pond 3P: CHAMBERS

Event	Inflow (cfs)	Primary (cfs)	Elevation (feet)	Storage (acre-feet)
1 YR	0.42	0.26	2.21	0.009
2 YR	0.28	0.12	1.46	0.006
10 YR	0.42	0.26	2.21	0.009
100 YR	0.76	0.68	2.81	0.011

lam_1

Prepared by RGM PEPC Consulting Engineers

HydroCAD® 10.20-4b s/n 12817 © 2023 HydroCAD Software Solutions LLC

LAM
Multi-Event Tables

Printed 4/12/2024

Page 25


Events for Link FIN: FINAL

Event	Inflow (cfs)	Primary (cfs)	Elevation (feet)
1 YR	0.26	0.26	0.00
2 YR	0.12	0.12	0.00
10 YR	0.26	0.26	0.00
100 YR	0.68	0.68	0.00


ZONING SCHEDULE

LAMANNA AUTO BODY DISTRICT: C-COMMERCIAL SECTION: 86.7 BLOCK 1 LOT 37 TOTAL LOT AREA: 0.624 ACRES OR 27,191 SF CHAPTER 156-30 - AUTOMOTIVE USES	REQUIRED	EXISTING	PROPOSED	VARIANCE
MINIMUM LOT AREA	20,000 SF	27,191 SF	NO CHANGE	NO
MINIMUM LOT WIDTH	200'	233'	NO CHANGE	NO
MINIMUM LOT DEPTH	200'	146'*	NO CHANGE	YES, 54'
MINIMUM YARD DIMENSIONS				
FRONT	40'	32'*	29'*	YES, 11'
SIDE	25'	29'	15'	YES, 10'
REAR	30'	28'*	28'*	YES, 2'
MAXIMUM LOT COVERAGE	30% OR 8,157 SF	8% 2,208 SF	18% 4,893 SF	NO
MINIMUM FLOOR AREA FOR BUILDINGS	5,000 SF	2,208 SF	4,893 SF	YES (170 SF)
MAXIMUM HEIGHT (IN FEET)	35'	13' 2"	NO CHANGE	NO
OFF STREET PARKING CHAPTER 156-30, D	1/1500 SF	6	6	NO
STORMWATER: GP-0-15-002 APPENDIX B DISTURBANCE >5,000 SF-C1 ACRE	EROSION CONTROL		PROVIDED	

* = EXISTING NON-CONFORMING



LOCATION MAP
N.T.S.



- LEGEND**
- | EXISTING | PROPOSED | |
|----------|----------|--------------------|
| [Symbol] | [Symbol] | CATCH BASIN |
| [Symbol] | [Symbol] | DRAIN MANHOLE |
| [Symbol] | [Symbol] | SAN. SEWER MANHOLE |
| [Symbol] | [Symbol] | HYDRANT |
| [Symbol] | [Symbol] | DRAIN INLET |
| [Symbol] | [Symbol] | WATER VALVE |
| [Symbol] | [Symbol] | HEADWALL |
| [Symbol] | [Symbol] | WELL |
| [Symbol] | [Symbol] | SIGN |
| [Symbol] | [Symbol] | STREET LIGHT |
| [Symbol] | [Symbol] | MONUMENT |
| [Symbol] | [Symbol] | CONTOUR LINE |

RALPH G. MASTROMONACO, P.E., P.C.
Consulting Engineers
13 Dove Court, Croton-on-Hudson, New York 10520
(914) 271-4762 (914) 271-2820 Fax




SITE PLAN
PROPOSED ADDITION
PREPARED FOR
GABRIEL LAMANNA
TOWN OF CARMEL
PUTNAM COUNTY, NY
JANUARY 30, 2024



BASE MAPPING BY: LINK LAND SURVEYORS P.C.
Unauthorized alterations or additions to this drawing is
a violation of Section 7209 (2) of the New York State
Education Law.

REVISED: 4/15/2024
REVISED: 3/19/2024

SHEET 1 OF 3 SHEETS



SU-30 TRUCK



LEGEND


EXISTING	PROPOSED	DESCRIPTION
		CATCH BASIN
		DRAIN MANHOLE
		SAN. SEWER MANHOLE
		HYDRANT
		DRAIN INLET
		WATER VALVE
		HEADWALL
		WELL
		SIGN
		STREET LIGHT
		MONUMENT
		CONTOUR LINE

RALPH G. MASTROMONACO, P.E., P.C.
Consulting Engineers
13 Dove Court, Croton-on-Hudson, New York 10520
(914) 271-4762 (914) 271-2820 Fax



SU-30 TRUCK ACCESS PLAN
PROPOSED ADDITION
PREPARED FOR
GABRIEL LAMANNA
TOWN OF CARMEL
PUTNAM COUNTY, NY
APRIL 15, 2024

BASE MAPPING BY: LINK LAND SURVEYORS P.C.
Unauthorized alterations or additions to this drawing is a violation of Section 7209 (2) of the New York State Education Law.



TO BE USED WHERE TOPSOIL PRESERVATION IS NECESSARY FOR REGRADING AND VEGETATING DISTURBED AREAS. TOPSOIL IS APPLIED TO SUBSOILS THAT ARE BROUGHT UP (HAVING LOW AVAILABLE MOISTURE FOR PLANTS), STONY, SALTY, HAVE LOW PERMEABILITY, OR ARE EXTREMELY ACID. IT IS ALSO USED TO BACKFILL AROUND SHRUBS AND TREE TRANSPLANTS. PRESERVATION OF EXISTING TOPSOIL IS BENEFICIAL FOR ALL TYPES OF LAWN OR ORNAMENTAL PLANTINGS.


TEMPORARY STOCKPILE STABILIZATION MEASURES INCLUDE VEGETATIVE COVER, MULCH, NON-VEGETATIVE COVER, AND PERIPHERAL SEDIMENT TRAPPING BARRIERS. THE STABILIZATION MEASURES SELECTED SHOULD BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, AND REQUIRED DURATION OF USE.

INSTALLATION NOTES


1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2.
3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAW BALES, THEN STABILIZED WITH VEGETATION OR COVERED.

SOIL STOCKPILING N. T. S.


MAINTENANCE NOTES:
 1. INSPECT INFILTRATION CHAMBER PORT EVERY SIX MONTHS.
 2. REMOVE SILT INSIDE CHAMBER IF ACCUMULATION REACHES SIX INCHES.



SUBSURFACE DETENTION SYSTEM 6 - SC740 CHAMBERS N. T. S.



WATER SERVICE BEDDING N. T. S.




CONSTRUCTION SPECIFICATIONS


1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER 1" OR 1 1/2" TYPE OR HARDWOOD.
2. FILTER CLOTH TO BE TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. FENCE SHALL BE WOVEN WIRE, 12 1/2 GAUGE, 4" MAXIMUM MESH OPENING.
3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X, MIGHTY TUCK, STABILINA T-100, OR APPROVED EQUIVALENT.
4. PREFABRICATED UNITS SHALL BE GEOTAB, ENVROFENCE, OR APPROVED EQUIVALENT.
5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BAUGES" DEVELOP IN THE SILT FENCE.

U.S. DEPARTMENT OF AGRICULTURE
 NATIONAL RESOURCES CONSERVATION SERVICE
 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
 NEW YORK STATE SOIL & WATER CONSERVATION COMMITTEE


SILT FENCE



DRAIN PIPE BEDDING N. T. S.



STORM DRAIN/ WATER MAIN CROSSING N. T. S.



CONSTRUCTION SPECIFICATIONS

1. STONE SIZE - USE 2" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
2. LENGTH - NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
3. THICKNESS - NOT LESS THAN SIX (6) INCHES.
4. WIDTH - THREE (3) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.
5. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.
6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE, IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
7. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
8. WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

U.S. DEPARTMENT OF AGRICULTURE
 NATIONAL RESOURCES CONSERVATION SERVICE
 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
 NEW YORK STATE SOIL & WATER CONSERVATION COMMITTEE

STABILIZED CONSTRUCTION ENTRANCE

Schedule For Construction:

1. Install erosion controls as shown on the Site Plan,
2. Remove trees, brush, grub stumps, strip topsoil,
3. Excavate for footings,
4. Install footings, foundation, slabs,
5. Install water service, seal off well,
6. Building construction,
7. Install storm drainage structures and piping
8. Spread topsoil, seed and mulch,
9. Install landscaping,
10. Remove erosion controls from areas which are stabilized

Sewers shall be laid on at least 10 feet (3.0 m) horizontally from any existing or proposed water main. The distance shall be measured with to each end of a sewer where it is not practical to maintain a ten foot separation, the appropriate reviewing agency may allow deviation on a case-by-case basis. It is understood by both the design engineer and the contractor that any deviation may allow installation of the sewer closer to a water main, provided that the water main is in a separate trench or on an undisturbed earth shall located on one side of the sewer and at an elevation on the bottom of the water main is at least 18 inches (46 cm) above the top of the sewer.

STORM SEWER/WATER SEPARATION N. T. S.

CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL LOCATE AND VERIFY IN THE FIELD ALL UTILITIES - GAS, WATER, ELECTRICAL BEFORE THE START OF CONSTRUCTION. CONTRACTOR SHALL CALL CODE 753 (FORMERLY CODE 53)
2. EROSION CONTROL MEASURES, INCLUDING SILT FENCE, SHALL BE REQUIRED AS DIRECTED BY THE TOWN.
3. ALL PROPERTY DISTURBED IN THE P.O.W. OR ON PRIVATE LANDS, SHALL BE RESTORED TO NEW CONDITIONS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL APPLICATIONS AND PERMITS REQUIRED FOR CONSTRUCTION.
5. UNDERGROUND GAS AND ELECTRIC SHALL BE AS REQUIRED BY THE TOWN AND LOCAL POWER COMPANY.

EROSION AND SEDIMENT CONTROL NOTES:

1. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION AND MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
2. ALL EROSION AND SEDIMENTATION CONTROL MEASURES AND PROCEDURES SHALL COMPLY WITH THE STANDARDS AND SPECIFICATIONS OF THE TOWN OF CARMEL.
3. PRIOR TO ANY EXCAVATION, SILT FENCE SHALL BE INSTALLED AT THE APPROPRIATE LOCATIONS NOTED ON EROSION CONTROL PLAN. SILT FENCING SHALL BE INSTALLED AS DIRECTED BY THE OWNER'S REPRESENTATIVE IN THE FIELD AND INSTALLED AS PER THE INSTRUCTIONS OF THE MANUFACTURER. ADDITIONAL SILT FENCE MAY BE PLACED BY THE OWNER'S REPRESENTATIVE IN THE FIELD. SILT FENCING SHALL BE MAINTAINED IN OPERABLE CONDITION AND SHALL NOT BE REMOVED UNTIL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
4. ALL FINISHED SLOPES AND ALL UPRIGHT CUT SLOPES TO REMAIN OPEN FOR EXTENDED PERIODS IMMEDIATELY TOPSOIL SEED WITH A MIXTURE OF PERENNIAL RYE GRASS, ANNUAL RYE GRASS AND WINTER RYE AND MULCH WITH 6" OF PAST.
5. ALL SLOPES CONSTRUCTED WITH FILL MATERIAL AND ALL SLOPES WITH GRADE 3:1 OR STEEPER SHALL BE TOPSOILED, SEED, AND MULCHED AND STABILIZED WITH STAKED JUTE NETTING, UNLESS OTHERWISE NOTED.
6. ALL AREAS OF DISTURBED SOIL SHALL BE STABILIZED, IN ADDITION TO ALL SLOPES, BY THE USE OF EROSION CONTROL DEVICES. THE CONTRACTOR SHALL TAKE ALL STEPS PRUDENT AND NECESSARY TO STABILIZE THE SITE AT ALL TIMES.
7. DO NOT STOCKPILE MATERIALS ON STEEP SLOPES, IN DRAINAGE SWALES OR IN WETLAND AREAS. SURROUND ALL STOCKPILE AREAS WITH SILT SCREEN AND MULCH WITH THE ANNUAL RYE GRASS.
8. ALL CATCH BASINS ARE TO BE PROTECTED WITH HAYBALE FILTERS THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
9. HAYBALES SHALL BE USED AT THE TOPS AND TOES OF SLOPES, AS NECESSARY, TO COLLECT SILT AND DIVERS FLOWS. SILT SCREENS WILL BE USED IN AREAS OF UNCONCENTRATED FLOWS TO COLLECT SILT, HAYBALES AND SILT SCREEN ON PLANS MAY BE AUGMENTED IN THE FIELD AS NECESSARY.
10. UTILITY LINE EXCAVATED MATERIAL SHALL BE TEMPORARILY STOCKPILED ON HIGH SIDE OF EXCAVATION SO RUNOFF IS DIRECTED AWAY FROM TRENCH. AFTER BACK-FILLING, AREA IS TO BE TOPSOILED, SEED, AND MULCHED.
11. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
12. SEDIMENT DEPOSITS SHALL BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. SEDIMENT SHALL BE DISPOSED OF IN A MANNER THAT DOES NOT RESULT IN ADDITIONAL EROSION OR POLLUTION.
13. INSTALL GRAVEL BED AT CONSTRUCTION ENTRANCE TO SERVE AS ANTI-TRACKING PAD. GRAVEL BED TO BE 2" DIAMETER CRUSHED STONE 6" DEEP, OVER GEOTEXTILE SUPPORT FABRIC, ANTI-TRACKING PADS TO MEASURE 30' MIN. LENGTH BY THE ROADWAY WIDTH.
14. BLASTING AREAS - ROCK, RIPPING WILL BE USED WHEREVER POSSIBLE. LASTING WILL OCCUR ACCORDANCE WITH REGULATIONS AND STANDARDS PRESCRIBED BY THE TOWN OF CARMEL.

RALPH G. MASTROMONACO, P.E., P.C.
 Consulting Engineers
 13 Dove Court, Croton-on-Hudson, New York 10520
 (914) 271-4762 (914) 271-2820 Fax



DETAILS/NOTES
 PROPOSED ADDITION
 PREPARED FOR
 GABRIEL LAMANNA
 TOWN OF CARMEL
 PUTNAM COUNTY, NY
 JANUARY 30, 2024
 SHEET 3 OF 3 SHEETS



① FRONT (NORTH) ELEVATION
1/4" = 1'-0"



③ WEST ELEVATION
1/4" = 1'-0"



② EAST ELEVATION
1/4" = 1'-0"



④ SOUTH (REAR) ELEVATION
1/4" = 1'-0"



NOTE:
DO NOT SCALE DRAWINGS. REFER TO WRITTEN MEASUREMENTS FOR ACCURACY. OR CONTACT ARCHITECT - CONTACT ARCHITECT IF THERE ARE ANY DISCREPANCIES. ALL DIMENSIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF NEW YORK STATE EDUCATIONAL LAW. Copyright 2020 MICHAEL PICCIRILLO ARCHITECTURE

EXISTING BRICK VENEER
NEW STANDING SEAM METAL ROOF

GARAGE FLOOR
699' - 6"

No.	DATE	ISSUE
1	4/5/24	DESIGN REVIEW
2	4/11/24	ISSUED FOR PB

PROJECT NAME:
GABRIEL'S AUTO BODY

PROJECT ADDRESS:
255 NYS ROUTE 6
MAHOPAC, NY



MICHAEL A. PICCIRILLO, AIA
345 KEAR STREET, SUITE 203
YORKTOWN HEIGHTS, NY 10598
TELEPHONE: 914-368-9838
FACSIMILE: 914-368-9839
michael@piccirilloarchitect.com
www.mpiccirilloarchitect.com

ELEVATIONS

A200



① PERSPECTIVE 1



② PERSPECTIVE 2

No.	DATE	ISSUE
1	4/5/24	DESIGN REVIEW
2	4/11/24	ISSUED FOR PB

PROJECT NAME:
GABRIEL'S AUTO
BODY

PROJECT ADDRESS:
255 NYS ROUTE 6
MAHOPAC, NY



MICHAEL A. PICCIRILLO, AIA
345 KEAR STREET, SUITE 203
YORKTOWN HEIGHTS, NY 10598

TELEPHONE: 914-368-9838
FACSIMILE: 914-368-9839
michael@mpiccirilloarchitect.com
www.mpiccirilloarchitect.com

PERSPECTIVES

A201



TOWN OF CARMEL SITE PLAN APPLICATION INSTRUCTIONS



The Town of Carmel Planning Board meetings are held twice a month, on the second **Thursday** and fourth **Wednesday**, at 7:00 PM at Carmel Town Hall, 60 McAlpin Avenue, Carmel

The submission deadline is 10 days prior to the Planning Board meeting. New site plan applications that have been deemed complete will be placed on the agenda in the order they are received.

No application will be placed on the agenda that is incomplete

Pre-Submission:

Prior to the formal submission of the site plan, a pre-submission conference may be requested by the applicant to be conducted with representatives from the Town, which may include the Town Planner, Town Engineer, Director of Code Enforcement and/or the Planning Board Attorney. This conference will serve to educate the applicant on the process he/she must follow, clarify the information required to submit a complete site plan application, and to highlight any specific areas of concern. You may arrange a pre-submission conference through the Planning Board Secretary at (845) 628-1500 extension 190.

Submission Requirements:

At least 10 days prior to the Planning Board meeting, the site plan application shall be submitted to the Planning Board Secretary as follows:

All site plans shall be signed, sealed and folded with the title box legible. The application package shall include:

- 5 copies of the Site Plan Application Form, signed and notarized.
- 5 copies of the SEQR Environmental Assessment Form (use of short form or long form shall be determined at pre-submission conference).
- 5 full size sets of the Site Plan (including floor plans and elevations)
- 1 CD (in pdf. format) containing an electronic version of the Site Plan
- 2 copies of the Disclosure Statement
- 5 copies of the Site Plan Completeness Certification Form
- All supplemental studies, reports, plans and renderings.
- 2 copies of the current deed.
- ^{all} 2 copies of all easements, covenants and restrictions.
- The appropriate fee, determined from the attached fee schedule. Make checks payable to the *Town of Carmel*.

Rose Yrombetta 4/16/24

 Planning Board Secretary; Date

[Signature] 4/16/24

 Town Engineer; Date



TOWN OF CARMEL SITE PLAN APPLICATION



Per Town of Carmel Code – Section 156 - Zoning

SITE IDENTIFICATION INFORMATION		
Application Name: 2 CLARK PL, LLC	Application # 24-0012	Date Submitted: 3/12/2024
Site Address: No. 2 Street: CLARK PL Hamlet: MAHOPAC		
Property Location: <i>(Identify landmarks, distance from intersections, etc.)</i> CORNER OF CLARK PLACE AND ROUTE 6		
Town of Carmel Tax Map Designation: Section 75.12 Block 1 Lot(s) 42-43	Zoning Designation of Site: C	
Property Deed Recorded in County Clerk's Office Date _____ Liber _____ Page _____	Liens, Mortgages or other Encumbrances Yes _____ No _____	
Existing Easements Relating to the Site No Yes Describe and attach copies: NA	Are Easements Proposed? No Yes Describe and attach copies: X	
Have Property Owners within a 500' Radius of the Site Been Identified? Yes No Attached List to this Application Form		
APPLICANT/OWNER INFORMATION		
Property Owner: 2 CLARK PL, LLC	Phone #: 914 497 9324	Email:
Owners Address: No. _____ Street: _____ Town: _____ State: _____ Zip: _____		
Applicant (If different than owner): WILLIAM BESHARAT	Phone #: 914 330 4999	Email:
Applicant Address (If different than owner): No. _____ Street: _____ Town: _____ State: _____ Zip: _____		
Individual/ Firm Responsible for Preparing Site Plan: RAYEX DESIGN	Phone #: 914 330 4999	Email: RAYEXDESIGN@GMAIL.COM
Address: No. 266 Street: Shear Hill Rd Town: MAHOPAC State: NY Zip: 10541		
Other Representatives:	Phone #:	Email:
Owners Address: No. _____ Street: _____ Town: _____ State: _____ Zip: _____		
PROJECT DESCRIPTION		
Describe the project, proposed use and operation thereof: LEGALIZE EXISTING 2 APARTMENTS ON THE SECOND FLOOR. NO CONSTRUCTION IS PROPOSED. NO CHANGE IS PROPOSED TO EXISTING PARKING LOT.		

TOWN OF CARMEL SITE PLAN APPLICATION

PROJECT INFORMATION			
Lot size:		Square footage of all existing structures (by floor):	
Acres:	Square Feet:	4238 SF	
# of existing parking spaces:		# of proposed parking spaces:	
# of existing dwelling units:		# of proposed dwelling units:	
<p>Is the site served by the following public utility infrastructure:</p> <ul style="list-style-type: none"> • Is project in sewer district or will private septic system(s) be installed? _____ • If yes to Sanitary Sewer answer the following: <ul style="list-style-type: none"> ▶ Does approval exist to connect to sewer main? Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> ▶ Is this an in-district connection? _____ Out-of district connection? _____ ▶ What is the total sewer capacity at time of application? _____ ▶ What is your anticipated average and maximum daily flow <u>850</u> <p><i>For Town of Carmel Town Engineer</i></p> <ul style="list-style-type: none"> ▶ What is the sewer capacity <u>ALREADY CONNECTED</u> <i>RF 4/11/14</i> 			
<ul style="list-style-type: none"> • Water Supply Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> 		<ul style="list-style-type: none"> If Yes: <ul style="list-style-type: none"> ▶ Does approval exist to connect to water main? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> ▶ What is the total water capacity at time of application? _____ ▶ What is your anticipated average and maximum daily demand _____ 	
<ul style="list-style-type: none"> • Storm Sewer Yes: <input type="checkbox"/> No: <input type="checkbox"/> 			
<ul style="list-style-type: none"> • Electric Service Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> 			
<ul style="list-style-type: none"> • Gas Service Yes: <input type="checkbox"/> No: <input type="checkbox"/> 			
<ul style="list-style-type: none"> • Telephone/Cable Lines Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> 			
<p><i>For Town of Carmel Town Engineer</i></p> <p>Water Flows <u><i>RF 4/11/14</i></u></p> <p>Sewer Flows <u><i>already connected</i></u></p> <p>_____ Town Engineer; Date</p>			
What is the predominant soil type(s) on the site?		What is the approximate depth to water table?	
Site slope categories:		15-25% <input checked="" type="checkbox"/> %	25-35% <input type="checkbox"/> %
Estimated quantity of excavation:		Cut (C.Y.) _____	Fill (C.Y.) _____
Is Blasting Proposed		Yes: <input type="checkbox"/> No: <input type="checkbox"/> Unknown: <input type="checkbox"/>	
Is the site located in a designated Critical Environmental Area?		Yes: <input type="checkbox"/> No: <input type="checkbox"/>	
Does a curb cut exist on the site? Yes: <input type="checkbox"/> No: <input type="checkbox"/>	Are new curb cuts proposed? Yes: <input type="checkbox"/> No: <input type="checkbox"/>	What is the sight distance? Left _____ Right _____	
<p>Is the site located within 500' of:</p> <ul style="list-style-type: none"> • The boundary of an adjoining city, town or village Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> • The boundary of a state or county park, recreation area or road right-of-way Yes: <input checked="" type="checkbox"/> No: <input type="checkbox"/> • A county drainage channel line. Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> • The boundary of state or county owned land on which a building is located Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/> 			

TOWN OF CARMEL SITE PLAN APPLICATION

Is the site listed on the State or Federal Register of Historic Place (or substantially contiguous) Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Is the site located in a designated floodplain? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Will the project require coverage under the Current NYSDEC Stormwater Regulations Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Will the project require coverage under the Current NYCDEP Stormwater Regulations: Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Does the site disturb more than 5,000 sq ft	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Does the site disturb more than 1 acre	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Does the site contain freshwater wetlands? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Jurisdiction: NYSDEC: <input type="checkbox"/> Town of Carmel: <input checked="" type="checkbox"/>	
<i>If present, the wetlands must be delineated in the field by a Wetland Professional, and survey located on the Site Plan.</i>	
Are encroachments in regulated wetlands or wetland buffers proposed?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Does this application require a referral to the Environmental Conservation Board?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Does the site contain waterbodies, streams or watercourses?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Are any encroachments, crossings or alterations proposed?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Is the site located adjacent to New York City watershed lands?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Is the project funded, partially or in total, by grants or loans from a public source? Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>	
Will municipal or private solid waste disposal be utilized? Public: <input type="checkbox"/> Private: <input type="checkbox"/>	NO
Has this application been referred to the Fire Department?	Yes: <input type="checkbox"/> No: <input checked="" type="checkbox"/>
What is the estimated time of construction for the project?	NO CONSTRUCTION

ZONING COMPLIANCE INFORMATION

Zoning Provision	Required	Existing	Proposed
Lot Area	40,000	12,075	
Lot Coverage	30%	19.5%	
Lot Width	200	209.1	
Lot Depth	200	65.2	
Front Yard	40	6.2' & 4.7'	
Side Yard	N/A		
Rear Yard	30	100.6	
Minimum Required Floor Area	5000	4238	
Floor Area Ratio			
Height	35	34	
Off-Street Parking	15	15	
Off-Street Loading	1	1	

TOWN OF CARMEL SITE PLAN APPLICATION

Will variances be required? Yes: <input type="checkbox"/> No: <input type="checkbox"/>	If yes, identify variances:
PROPOSED BUILDING MATERIALS	
Foundation	
Structural System	
Roof	
Exterior Walls	
APPLICANTS ACKNOWLEDGEMENT	
I hereby depose and certify that all the above statements and information, and all statements and information contained in the supporting documents and drawings attached hereto are true and correct.	
<u>WILLIAM BESHARAT</u> Applicants Name	<u><i>William Besharat</i></u> Applicants Signature
Sworn before me this <u>14th</u> day of <u>March</u> 20 <u>24</u>	
<u><i>Alice Daly</i></u> Notary Public	ALICE DALY Notary Public, State of New York No. 01DA6345218 Qualified in Putnam County Commission Expires July 25, 2024



TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



All Site Plans submitted to the Planning Board for review shall include the following information and details, as set forth in Section 156-61 B of the Town of Carmel Zoning Ordinance.

This form shall be included with the site plan submission

Requirement Data		To Be Completed by the Applicant	Waived by the Town
1	Name and title of person preparing the site plan	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2	Name of the applicant and owner (if different from applicant)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3	Original drawing date, revision dates, scale and north arrow	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4	Tax map, block and lot number(s), zoning district	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5	All existing property lines, name of owner of each property within a 500' radius of the site	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6	Contour lines at two-foot intervals, grades of all roads, driveways, sanitary and storm sewers	<input type="checkbox"/>	<input checked="" type="checkbox"/>
7	The location of all water bodies, streams, watercourses, wetland areas, wooded areas, rights-of-way, streets, roads, highways, railroads, buildings, structures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
8	The location of all existing and proposed easements	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9	The location of all existing and proposed structures, their use, setback dimensions, floor plans, front, side and rear elevations, buildable area.	<input checked="" type="checkbox"/>	<input type="checkbox"/>
10	On site circulation systems, access, egress ways and service roads, emergency service access and traffic mitigation measures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
11	Sidewalks, paths and other means of pedestrian circulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12	On-site parking and loading spaces and travel aisles with dimensions	<input checked="" type="checkbox"/>	<input type="checkbox"/>
13	The location, height and type of exterior lighting fixtures	<input checked="" type="checkbox"/>	<input type="checkbox"/>
14	Proposed signage	<input checked="" type="checkbox"/>	<input type="checkbox"/>
15	For non-residential uses, an estimate of the number of employees who will be using the site, description of the operation, types of products sold, types of machinery and equipment used	<input checked="" type="checkbox"/>	<input type="checkbox"/>



TOWN OF CARMEL SITE PLAN COMPLETENESS CERTIFICATION FORM



Requirement Data		To Be Completed by the Applicant	Waived by the Town
16	The location of clubhouses, swimming pools, open spaces, parks or other recreational areas, and identification of who is responsible for maintenance	<input checked="" type="checkbox"/>	<input type="checkbox"/>
17	The location and design of buffer areas, screening or other landscaping, including grading and water management. A comprehensive landscaping plan in accordance with the Tree Conservation Law	<input type="checkbox"/>	<input checked="" type="checkbox"/>
18	The location of public and private utilities, maintenance responsibilities, trash and garbage areas	<input checked="" type="checkbox"/>	<input type="checkbox"/>
19	A list, certified by the Town Assessor, of all property owners within 500 feet of the site boundary	<input checked="" type="checkbox"/>	<input type="checkbox"/>
20	Any other information required by the Planning Board which is reasonably necessary to ascertain compliance with this chapter	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Applicants Certification (to be completed by the licensed professional preparing the site plan:

I Roy A. Fredriksen hereby certify that the site plan to which I have attached my seal and signature, meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:



Professionals Seal

William Bestant
Signature - Applicant

[Signature]
Signature - Owner

3/12/24
Date

3/12/24
Date



TOWN OF CARMEL
**SITE PLAN COMPLETENESS
CERTIFICATION FORM**



Town Certification (to be completed by the Town)

I _____ hereby confirm that the site plan meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:

Rose Gronlitta
Signature - Planning Board Secretary

4/16/24
Date

[Signature]
Signature - Town Engineer

4/16/24
Date

Short Environmental Assessment Form

Part 1 - Project Information


Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.


Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information			
Name of Action or Project: 2 CLARK PLACE LEGALIZATION			
Project Location (describe, and attach a location map): 2 CLARK PLACE MAHOPAC, NY. 10541			
Brief Description of Proposed Action: LEGALIZATION OF 2 EXISTING RESIDENTIAL APARTMENTS.			
Name of Applicant or Sponsor: WILLIAM BESHARAT		Telephone: 914 330-4999	
Address: 266 SHEAR HILL ROAD		E-Mail: RAYEXDESIGN@GMAIL.COM	
City/PO: MAHOPAC		State: NEW YORK	Zip Code: 10541
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.			NO <input checked="" type="checkbox"/>
2. Does the proposed action require a permit, approval or funding from any other government Agency? If Yes, list agency(s) name and permit or approval:			YES <input type="checkbox"/>
3. a. Total acreage of the site of the proposed action? _____ .35 acres b. Total acreage to be physically disturbed? _____ 0 acres c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor? _____ .35 acres			YES <input type="checkbox"/>
4. Check all land uses that occur on, are adjoining or near the proposed action:			
5. <input type="checkbox"/> Urban <input type="checkbox"/> Rural (non-agriculture) <input type="checkbox"/> Industrial <input checked="" type="checkbox"/> Commercial <input checked="" type="checkbox"/> Residential (suburban) <input type="checkbox"/> Forest <input type="checkbox"/> Agriculture <input type="checkbox"/> Aquatic <input type="checkbox"/> Other(Specify): <input type="checkbox"/> Parkland			

	NO	YES	N/A
5. Is the proposed action, a. A permitted use under the zoning regulations? b. Consistent with the adopted comprehensive plan?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area? If Yes, identify: _____	NO	YES	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
8. a. Will the proposed action result in a substantial increase in traffic above present levels? b. Are public transportation services available at or near the site of the proposed action? c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?	NO	YES	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
9. Does the proposed action meet or exceed the state energy code requirements? If the proposed action will exceed requirements, describe design features and technologies: _____ _____	NO	YES	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
10. Will the proposed action connect to an existing public/private water supply? If No, describe method for providing potable water: _____ _____	NO	YES	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
11. Will the proposed action connect to existing wastewater utilities? If No, describe method for providing wastewater treatment: _____ _____	NO	YES	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on the National or State Register of Historic Places, or that has been determined by the Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places? b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	NO	YES	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency? b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody? If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____ _____ _____	NO	YES	
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/>	<input type="checkbox"/>	



Part 1 / Question 7 [Critical Environmental Area]	No
Part 1 / Question 12a [National or State Register of Historic Places or State Eligible Sites]	No
Part 1 / Question 12b [Archeological Sites]	Yes
Part 1 / Question 13a [Wetlands or Other Regulated Waterbodies]	No
Part 1 / Question 15 [Threatened or Endangered Animal]	Yes
Part 1 / Question 15 [Threatened or Endangered Animal - Name]	Northern Long-eared Bat
Part 1 / Question 16 [100 Year Flood Plain]	No
Part 1 / Question 20 [Remediation Site]	Yes



SITE PLAN

SCALE 1" = 20'

ZONING TABLE

MIN. LOT AREA	REQUIRED	PROVIDED	VARIANCE REQUIRED
	40,000 SQ. FT.	12,875 SQ. FT.	
MIN. YARDS:			
FRONT	45 FT	6.2 FT AND 4.7 FT	
SIDE	25 FT	N/A	
REAR	30 FT	100.6 FT	
MIN. FRONTAGE	200 FT	442.15 FT	
MAX. BLDG. HEIGHT	35 FT	34 FT	
MIN. LOT WIDTH	200 FT	209.1 FT	
MIN. LOT DEPTH	200 FT	65.2 FT	
MIN. REQ. FLOOR AREA	5000 SQ. FT.	4238 SQ. FT.	
MAX. BLDG. COVERAGE	30%	19.5%	
PARKING REQ. FOR	2 SPACES PER APARTMENT 2119/ 200sf RETAIL		
	4 SPACES PER DOCTOR AND 1 PER EMPLOYEE		
	441 ± 5	TOTAL PROVIDED 13	

75.12-1-44
William Villanova
PO BOX 489
Mahopac, NY 10541

75.44-1-68
Filippo Canonaco
60 Longdale Rd
Mahopac, NY 10541

75.44-1-69
Joseph Duffy
16 Clark Pl
Mahopac, NY 10541

75.12-1-28
Youth Family Inev Trust
17 Mary Ave
Mahopac, NY 10541

75.12-1-41
Mario Carneiro
19 Mary Ave
Mahopac, NY 10541

75.44-1-75
Neomedica Bcoj
2 Mary Ave
Mahopac, NY 10541

75.12-1-19
Paul Shields
20 Mary Ave
Mahopac, NY 10541

75.44-1-65-2
Link Family Inev Trust
16 Spring Brook Dr
Mahopac, NY 10541

75.44-1-65-5
William Brighton
21 Clark Pl Sls 2B
Mahopac, NY 10541

75.51-1-17
William Ahrens
23 Ellen Ave
Mahopac, NY 10541

75.12-1-26
Rosemarie Sarli
21 Mary Ave
Mahopac, NY 10541

75.12-2-34
Ceresimo North LLC
2 Sheryl Ln
Mahopac, NY 10541

75.12-2-37
279 Buckshollow Rd., Inc.
23 Henry Ln
Mahopac, NY 10541

75.51-1-16
Steven Travis
28 Ellen Ave
Mahopac, NY 10541

75.12-1-37
Luke Marhaj
32 Ellen Ave
Mahopac, NY 10541

75.12-1-39
Mitek Zsq
44 Ellen Ave
Mahopac, NY 10541

75.12-2-30
Dunwest Associates
30 Virginia Rd
North White Plains, NY 10603

75.12-1-16
North Lakes Estates Prop Mgmt
483 North Lake Blvd
Mahopac, NY 10541

75.12-2-1
Lupinacci Mazzola Holding Cor
PO BOX 24
Mahopac, NY 10541

75.12-2-2
Lupinacci Mazzola Holding Cor
PO BOX 24
Mahopac, NY 10541

75.12-2-24
Nicole Stern
888 E
Mahopac, NY 10541

75.12-1-43
Anna Gilmore
25 Sunset Shore Dr
Nanagansett, RI 02882

75.12-1-32
Anthony Nardi
PO BOX 555
Mahopac, NY 10541

75.44-1-73
Richard Miller
8 Indian Ave
Mahopac, NY 10541

75.44-1-72
Richard Benack
PO BOX 306
Baldwin Place, NY 10505

75.12-1-17
Anthony Azuelan
14 Mary Ave
Mahopac, NY 10541

75.12-1-33
Andre Rytel
16 Ellen Ave
Mahopac, NY 10541

75.44-1-30
18 Clark, LLC
18 Clark Pl
Mahopac, NY 10541

75.12-1-34
Michael Tozzi
20 Ellen Ave
Mahopac, NY 10541

75.44-1-55
Main Old Stone Building Condominium
21 Clark Pl
Mahopac, NY 10541

75.44-1-55-3
Link Family Inev Trust
16 Spring Brook Dr
Mahopac, NY 10541

75.44-1-55-6
David O'Hara
21 Clark Pl
Mahopac, NY 10541

75.12-1-35
Keith Hoffman
24 Ellen Ave
Mahopac, NY 10541

75.12-2-32
Jay Weissberg Berms
255 Buckshollow Rd
Mahopac, NY 10541

75.12-2-35
Chak Sigurdsson
269 Buckshollow Rd
Mahopac, NY 10541

75.12-1-36
Zucchi Irrevocable Living Trust
28 Ellen Ave
Mahopac, NY 10541

75.12-1-25
Anthony Misano
29 Mary Ave
Mahopac, NY 10541

75.12-1-24
Natalie Wilson-Ancilotti
33 Mary Ave
Mahopac, NY 10541

75.12-1-13
Greta Family Realty, LLC
530 Route 6
Mahopac, NY 10541

75.12-1-15
546 Rt 6
Mahopac, NY 10541

75.12-2-28
Sky 545 Corp.
14-11 130th St
College Point, NY 11356

75.12-2-31
Dunwest Associates
30 Virginia Rd
North White Plains, NY 10603

75.12-2-25
568 Route 6 Partners LLC
566 Rt 6
Mahopac, NY 10541

75.44-1-54
Five Seventy Two, LLC
590 Commerce St
Thornwood, NY 10594

75.12-1-40
Stronghold Acquisitions LLC
324 Eastern Close
Yorktown Heights, NY 10598

75.12-1-50
Jermiah Sheehan
7 Mary Ave
Mahopac, NY 10541

75.12-1-23
Mary Hahn
40 Mary Ave
Mahopac, NY 10541

75.12-1-18
Rowley Development Corp Inc
c/o Thomson Reuters
PO BOX 400899
Houston, TX 77056

75.12-2-9
Rowley Development Corp Inc
c/o Thomson Reuters
PO BOX 400899
Houston, TX 77056

75.12-1-29
Richard Benack
13 Mary Ave
Mahopac, NY 10541

75.43-2-10
Melissa Mustafa
15 Indian Ave
Mahopac, NY 10541

75.12-1-18
Philly Canonaco
50 Longdale Rd
Mahopac, NY 10541

75.43-2-9
Declan Conroy
19 Ellen Ave
Mahopac, NY 10541

75.44-1-74
Christopher Paleo
2 Indian Ave
Mahopac, NY 10541

75.12-1-19
Emmy O'Brien
21 Clark Pl
Mahopac, NY 10541

75.44-1-55-1
The Glouc Group, LLC
PO BOX 201
Mahopac Falls, NY 10542

75.44-1-55-4
RSL Realty Holdings, LLC
21 Clark Place - Unit 4
Mahopac, NY 10541

75.12-1-27
Ronald Sale
21 Mary Ave
Mahopac, NY 10541

75.12-1-20
Anthony Fusciante
24 Mary Ave
Mahopac, NY 10541

75.12-2-33
Richard Sigurdsson
259 Buckshollow Rd
Mahopac, NY 10541

75.12-2-36
Shahir Rahman
1 California St
Hicksville, NY 11801

75.12-1-21
Sali Irrevocable Living Trust
28 Mary Ave
Mahopac, NY 10541

75.12-1-31
Cassandra Gonzalez
38 Ellen Ave
Mahopac, NY 10541

75.12-1-38
Shane O'Brien
38 Ellen Ave
Mahopac, NY 10541

75.12-1-14
Mistones Family Realty
21 Griffin Ln
Haverstraw, NY 12533

75.12-2-29
Dunwest Associates
30 Virginia Rd
North White Plains, NY 10603

75.12-2-27
Piero A Ana LLC
96 Greenway Terrace South
Mahopac, NY 10541

75.12-2-26
Downtown Mahopac Properties
23 Ridge Rd
Mahopac, NY 10541


75.12-2-3
Albano Buildings, LLC
566 Rt 6 & 11 Clarke Pl
Mahopac, NY 10541

75.12-2-23
Tylove Real Estate LLC
575 Route 6
Mahopac, NY 10541

75.12-2-42
Rowley Development Corp Inc
c/o Thomson Reuters
PO BOX 400899
Houston, TX 77056

75.44-1-71
Armasa Ortiz Corasno
7 Senior Ave
Mahopac, NY 10541

75.12-2-9
Rowley Development Corp Inc
c/o Thomson Reuters
PO BOX 400899
Houston, TX 77056



AREA MAP SCALE: 1" = 300' +/-

VICINITY MAP SCALE: 1" = 500' +/-

Approval hereby granted this _____ day of _____ 2024.
If building permit is not issued within 12 months from the above date,
this approval becomes null and void.

Signed this _____ day of _____, 2024 by _____
Town of Carmel Planning Board

Chairman

Secretary



ROY A. FREDRIKSEN, PE
DESIGN • PLANNING • CONSULTING ENGINEER

266 SHEAR HILL RD • MAHOPAC, NY 10541 • 845-621-4000

OWNER: 2 CLARK PLACE, LLC

JOB # _____

DRN BY: _____

CHKD BY: _____

PROJECT: SITE PLAN FOR THE PURPOSE OF

LEGALIZING EXISTING 2 APARTMENTS

LOCATED AT 2 CLARK PL, MAHOPAC, NY

TAX MAP # _____

SECTION: 75.12

BLOCK: 1

LOT: 42


SHEET TITLE: SITE PLAN AND

DETAILS


REVISIONS: _____

FEBRUARY 12, 2024





SECOND FLOOR PLAN 2,119 S.F.
SCALE 3/16" = 1'-0"



FIRST FLOOR PLAN 2,119 S.F.
SCALE 3/16" = 1'-0"



ROY A. FREDRIKSEN, PE
DESIGN • PLANNING • CONSULTING ENGINEERING
288 SHEAR HILL RD • MAHOPAC, NY 10541 • 845-621-4000
RAYEXDESIGN@GMAIL.COM

OWNER:	JOB #
2 CLARK PLACE LLC.	DRN BY:
	CHKD BY:

PROJECT: LEGALIZATION OF TWO EXISTING APARTMENTS LOCATED AT 2 CLARK PL IN MAHOPAC, NY.	TAX MAP #:
	15.12-1-2

SHEET TITLE: FLOOR PLANS
1 OF 1

REVISIONS: DATE: 3/14/2024





John Kellard, P.E.
David Sessions, RLA, AICP
Joseph M. Cermele, P.E., CFM
Jan K. Johannessen, AICP

VIA FEDERAL EXPRESS

April 8, 2024

Planning Board
Town of Carmel
60 McAlpin Avenue
Mahopac, New York 10541

Attn: Craig Paeprer, Chairman

RE: Western Bluff Subdivision
350 West Shore Drive
Section 66.14, Block 1, Lot 20

Dear Chairman Paeprer:

Enclosed please find the following materials relating to the request for an extension of the Final Subdivision Approval Resolution of the Planning Board of the Town of Carmel (#23-22) for the Western Bluff Subdivision:

- Check #588 in the Amount of \$2,500.00 – Extension Fee
- Final Subdivision Approval Resolution (#23-22), dated October 12, 2023

The Planning Board granted Final Subdivision Approval for the above-referenced subdivision, which is scheduled to expire on April 12, 2024. We are writing to request a 180-day extension of the Final Subdivision Approval.

At this time, our client is working to satisfy Conditions #2 through #4 regarding the Recreation Fee, Performance Bond and Engineering Inspection Fee. Our client anticipates satisfying all conditions of the Final Subdivision Approval.

CIVIL ENGINEERING | LANDSCAPE ARCHITECTURE | SITE & ENVIRONMENTAL PLANNING

500 MAIN STREET | ARMONK, NY 10504 | T: 914.273.2323 | F: 914.273.2329
WWW.KSCJCONSULTING.COM

Craig Paeprer, Chairman

April 8, 2024

Page 2

We would appreciate the Planning Board's consideration of our request at their next meeting.

Sincerely,

A handwritten signature in black ink, appearing to be "John Kellard", written over a series of horizontal lines.

John Kellard, P.E.

KSCJ Consulting

JK/dc

Enclosures

cc: Tom Kling
Dominick Santucci

FINAL SUBDIVISION APPROVAL
RESOLUTION OF THE PLANNING BOARD OF THE TOWN OF CARMEL
#23-22 October 12, 2023

Tax Map #66.14-1-20
WESTERN BLUFF SUBDIVISION

WHEREAS, the Planning Board of the Town of Carmel, located in Putnam County, New York, has received an application for Final Subdivision Approval, submitted by Dominick Santucci (herein after referred to as the “Applicant”); and

WHEREAS, the action involves the subdivision of the property to create 3 single-family lots of 4.74 acres, 5.44 acres and 4.61 acres respectively. Lot 1 will continue to be served by an existing driveway, and Lots 2 and 3 would be served by a new single curb-cut on West Shore Drive located across from Farview Road, which then branches off into two separate driveways serving each lot. The three new residences will be served by individual wells and subsurface septic disposal systems (hereinafter referred to as the “Project”); and

WHEREAS, the subject site is more specifically known and identified as Tax Map #66.14-1-20 (herein after referred to as the “Site”); and

WHEREAS, the Site is located within the R- Residential Zoning District; and

WHEREAS, the Final Subdivision Plat consists of the following plans, Kellard Sessions, dated January 13, 2017, last revised August 7, 2023:

---	Cover Sheet
1/10	Existing Conditions Plan
2/10	Subdivision Layout Plan
3/10	Sediment & Erosion Control Plan
4/10	Tree Removal & Landscaping Plan
5/10	Construction Details
6/10	Construction Details
7/10	Sediment & Erosion Control Details & Notes
8/10	Driveway Profiles
9/10	Drainage Profiles
10/10	Construction Management Plan

WHEREAS, the Town of Carmel has an ongoing need for parks, playgrounds and recreational facilities and the population generated by the Proposed Action will result in an incremental increase in the demand for these facilities; and

WHEREAS, the Land Subdivision Regulations recommend that such reservations shall be of suitable size, location, topography and general character for parks, playgrounds or other recreational purposes, and the Planning Board has found that a location for such a set-aside is not available on the site; and

WHEREAS, a duly noticed public hearing on the Proposed Action was held, at which time all interested parties were provided an opportunity to be heard on this matter; and

WHEREAS, the proposed action has been determined to be an Unlisted Action pursuant to SEQR 6 NYCRR Part 617; and

WHEREAS, on September 26, 2018, the Planning Board, serving as Lead Agency for the SEQR review of this application, adopted a Negative Declaration; and

WHEREAS, the requirements for final subdivision plat approval contained in the "Subdivision of Land Regulations of the Town of Carmel" have been met by said subdivision application.

NOW THEREFORE BE IT RESOLVED, that the Planning Board of the Town of Carmel hereby classifies the Proposed Action as a "Minor Subdivision" pursuant to §131-3 of the Land Subdivision Regulations

BE IT FURTHER RESOLVED, that upon full consideration of the above, the Planning Board of the Town of Carmel hereby grants Final Subdivision Plat Approval for the application submitted by Dominick Santucci, as depicted on the plans identified above, subject to the following conditions:

CONDITIONS PRIOR TO ENDORSEMENT OF FINAL PLAT

The following conditions shall be completed by the Applicant prior to the endorsement of the Final Subdivision Plat by the Planning Board Chairman:

1. Within one hundred eighty (180) days of the date of this resolution, the Applicant shall submit the Final Subdivision Plat, prepared in accordance with the standards and requirements set forth in §131-14 of the Subdivision of Land Regulations, in its final form, for endorsement by the Planning Board Chairman. This approval authorizes only the subdivision activities approved in the resolution and as delineated on the signed and filed Final Subdivision Plat. Any alteration or modification to the Final Subdivision Plat, or to the existing or approved facilities and site shall require the review and approval by the Planning Board of the Town of Carmel.
2. In accordance with §131-25A (3) of the Subdivision of Land Regulations, a payment in lieu of reservation of land ("recreation fee") in the amount established by the fee schedule adopted by the Town Board in effect at the date of this approval, which shall be paid by certified check to the Town of Carmel.

3. A performance bond, prepared in form to the satisfaction of the Town Attorney, and in the amount of Three Hundred Fifty Five Dollars (\$355,000.00), in accordance with the requirements set forth in §131-15E(1) of the Subdivision of Land Regulations, shall be provided to assure the completion of all improvements, if determined to be required.

Said improvements shall be completed within a maximum period of two (2) years and the performance bond shall so state the same. The developer may apply to the Planning Board for an extension of the completion period as set forth in §131-15F of the Subdivision of Land Regulations, provided said request is in writing, submitted a minimum of 45 days prior to the expiration, and describes in detail the reason for the requested extension.

4. An engineering inspection fee in the amount of Seventeen Thousand five Hundred Dollars (17,750.00), in accordance with the requirements set forth in §131-17C of the Subdivision of Land Regulations shall be paid to the Town of Carmel, if determined to be required.
5. The Final Subdivision Plat shall be endorsed by the Putnam County Health Department.
6. The Applicant shall furnish the Planning Board with one (1) mylar set and one (1) print set of the Final Subdivision Plat and Plans as described herein, for endorsement by the Planning Board Chairman upon payment of all required fees and compliance with all conditions of this resolution.
7. Upon payment of all required fees and the satisfaction of all conditions of this resolution and following the endorsement of the Final Subdivision Plat by the Planning Board Chairman, the mylar set will then be returned to the applicant for filing of the Final Subdivision Plat in the Office of the Putnam County Clerk, Division of Land Records as well as for copying; the print set will be retained by the Planning Board as a record copy.
8. No changes, additions, erasures, modifications or revisions shall be made to the Final Subdivision Plat following endorsement by the Planning Board Chairman. Any changes detected after endorsement of the Final Subdivision Plat as final, shall result in the immediate termination and revocation of this Resolution of Approval, thereby making it null and void.
9. Within ten (10) days after the Final Subdivision Plat has been filed in the in the Office of the Putnam County Clerk, Division of Land Records, the Applicant shall deliver to the Planning Board Secretary five (5) printed sets, collated and folded, of the Final Subdivision Plat and Plans, and five copies of all filed easements. No Building Permit shall be issued by the Building

Inspector until the required Final Subdivision Plat and Plans print sets are provided to the Planning Board Secretary.

CONDITIONS PRIOR TO ISSUANCE OF A BUILDING PERMIT

The following conditions shall be completed by the Applicant prior to the issuance of a Building Permit by the Building Inspector:

10. The Building Inspector shall not issue a Building Permit pertaining to the activities approved herein until the Applicant has complied with Conditions 1 – 9
11. Authorized issuance of a Building Permit by the Building Inspector shall be fully based on, and in accordance with this Resolution of Approval and the signed and filed Final Subdivision Plat and Plans. The Building Inspector shall include reference to the Final Subdivision Plat and Plans and this Resolution of Approval on any Building Permit.
12. The access, utility and drainage easements shall be reviewed and approved by the Planning Board attorney.
13. Prior to initiation of construction the Applicant or his representative will meet with the design engineer, Town Engineer, Highway Superintendent, Building Inspector, Site Contractor and/or any additional outside agencies that may have jurisdiction over aspects of the Project for a preconstruction conference to review all facets of construction and required inspections.

GENERAL CONDITIONS OF IMPLEMENTATION AND CONSTRUCTION

The following conditions shall apply during the implementation of the site improvements and construction of the Project:

14. The hours of construction activity shall take place in conformance with the applicable Town Regulations.
15. Prior to the commencement of any site work or construction activity, erosion and sedimentation controls shall be installed in accordance with the Final Subdivision Plan and the requirements of the Town Engineer, and any additional controls as may be required by the Building Inspector, Town Engineer, Highway Superintendent or their agents. Stormwater runoff shall be controlled at all times during construction to prevent erosion of the site area under construction and to prevent sedimentation and dust dispersal upon areas not under construction, particularly off-site locations. Silt fencing, hay bales, anti-tracking aprons and all other required erosion and sedimentation control measures shall be regularly inspected and maintained in an orderly and functioning manner in accordance with all Town of Carmel Ordinances and Laws, the New York Guidelines for Urban Erosion and Sediment Control, and

Best Management Practices. Additional supplies of silt fencing and hay bales shall be kept on the site during construction for immediate use if needed.

16. All conditions of the Putnam County Highway Work Permit shall be addressed.
17. All conditions of the New York City Department of Environmental Protection SWPPP approval shall be addressed.
18. The Applicant shall submit a stormwater maintenance agreement and maintenance guarantee per Town Code §156-85 and §156-87 B. to assure long-term maintenance of all stormwater management practices (SWMP).
19. Any and all new site utilities shall be installed underground.
20. The project shall maintain a zero% increase in the rate of runoff.
21. A clean and legible copy of this Resolution (as signed by the Planning Board Chairman) and a copy of the signed Final Subdivision Plat and Plans shall be maintained at the subject property at all times.

PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY

The following conditions shall be complied with prior to the issuance of a Certificate of Occupancy by the Building Inspector:

22. Prior to the issuance of an individual Certificate of Occupancy by the Building Inspector, and as a condition thereto, all site improvements (e.g. buildings, driveways, grading etc) associated with the lot requesting the Certificate of Occupancy, including all required utilities (e.g. water supply, sewage disposal, stormwater controls, electric, telephone, etc.) to serve said lot, shall be completed and operational. All disturbed areas shall be stabilized, reggraded and revegetated.
23. Prior to the issuance of a Certificate of Occupancy by the Building Inspector, an "As-Built" Plan showing the installed and completed improvements, certified by a New York State licensed Land Surveyor shall be prepared at the sole expense of the Applicant.
24. All improvements shall be maintained in strict accordance with all applicable rules, regulations, ordinances and laws as a condition of maintenance of a Certificate of Occupancy
25. Failure to comply with any of the conditions set forth herein shall be deemed a violation of this approval, which may lead to the revocation of the Approval and/or Certificate of Occupancy, in accordance with the applicable provisions of the Town of Carmel.

BE IT FURTHER RESOLVED, that this Final Subdivision Approval shall expire within one hundred eighty (180) days of the date of this resolution unless the Applicant submits for signature by the Planning Board Chairman, the Final Subdivision Plat, as endorsed by the Putnam County Department of Health and in conformance with the Land Subdivision Regulations.

BE IT FINALLY RESOLVED, that this Final Subdivision Plat Approval resolution shall have an effective date of October 12, 2023.

**PLANNING BOARD
TOWN OF CARMEL**


Chairman

10-12-2023
Dated:

This resolution was thereupon duly adopted