CRAIG PAEPRER Chairman

ANTHONY GIANNICO Vice Chairman

BOARD MEMBERS RAYMOND COTE ROBERT FRENKEL VICTORIA CAUSA JOHN NUCULOVIC

TOWN OF CARMEL PLANNING BOARD



60 McAlpin Avenue Mahopac, New York 10541 Tel. (845) 628-1500 – Ext.190 www.ci.carmel.ny.us

PLANNING BOARD AGENDA OCTOBER 12, 2023–7:00 P.M.

MICHAEL CARNAZZA Director of Code Enforcement

RICHARD FRANZETTI, P.E.,BCEE Town Engineer

PATRICK CLEARY, AICP,CEP,PP,LEED AP Town Planner

TAX MAP # PUB. HEARING MAP DATE COMMENTS

PU	BLIC	HEARING	

1.	Success Realty LLC (Weiss) – 11 Sunset Blvd	54.19-1-11	10/12/23	8/8/23	Public Hearing & Resolution
2.	Diamond Point Development – 4 Baldwin Place Rd	86.10-1-2 & 3	10/12/23	8/30/23	Site Plan

RESOLUTION

3. Western Bluff Subdivision – 350 West Shore Dr.	66.14-1-20	8/7/23	Final Subdivision
---	------------	--------	-------------------

SITE PLAN

4.	Evans Septic Tank Service – 53 Old Route 6	55.11-1-18	9/27/23	Site Plan
5.	Chang, John – 716 Route 6	76.30-1-26	9/1/23	Amended Site Plan

MISCELLANEOUS

6.	14 Nicole Way LLC (Zakon) – 14 Nicole Way	65.6-1-22	9/29/20	Bond Return
7.	70 Old Route 6, LLC – 70 Old Route 6, Carmel	55.11-1-15	12/8/16	Re-Approval of Final Site Plan



October 2, 2023

Town of Carmel Planning Board 60 McAlpin Avenue Mahopac, New York 10541

RE: Diamond Point Development 4 Baldwin Place Road Town of Carmel TM#'s: 86.10-1-2&3

Dear Chairman Paeprer and Members of the Board:

Please find enclosed the following plans and documents in support of the application for site plan approval for the above referenced project:

- Sixteen (16) sheet Site Plan Set, last revised October 2, 2023.
- Figure CPP-1 Conversion Parking Plan, dated October 2, 2023.
- Stormwater Pollution Prevention Plan (SWPPP), last revised October 2, 2023.
- Revised Architectural floor plans and elevations by Stinard Architecture Inc.
- Revised Architectural Street View Renderings.
- Self Storage Signage Design Drawings, dated September 28, 2023.
- Letter of No Concern from the NYS Office of Parks Recreation and Historic Preservation, dated September 19, 2023.

In response to open comments received from Director of Code Enforcement, Michael Carnazza, dated September 11, 2023, we offer the below responses. Please note that the below only responds to comments not indicated as previously addressed:

- 2. There will be one sign near the Route 6 entrance and one building mounted sign. See the enclosed Signage Design Drawings.
- 3. See the enclosed Conversion Parking Plan.
- 4. The building has been sited based on a number of factors. These include cut fill analysis, driveway slopes, and the need for stormwater practices downhill of the proposed development. This being the case, the current location of the main storage building cannot be moved closer to the road. It is also believed that by moving it closer to the road would give the building a bigger presence along the property frontage.

In response to open comments received from Town Engineer Richard Franzetti, PE, dated September 6, 2023, we offer the following responses:

Detailed Comments

1. Site distances and driveway profiles are provided.

- As discussed, work is proposed in both the New York State Department of Transportation (NYSDOT) and Putnam County Department of Highways and Facilities (PCDHF), and the applicant is coordinating with both agencies to secure the required permits. A meeting was recently had onsite with the NYSDOT to review the proposed improvements, which were initially well received.
- 3. Details on the well and septic system have been added to the plans. The proposed fire protection tanks are shown on drawing SP2.2. Construction details for the system will be submitted by the applicant's MEP Engineer separately.
- 4. Landscape & Layout Plan
 - a. A note regarding the plants being verified by the Town of Carmel Wetland Inspector has been added to drawing SP-1.1.
 - b. Photometric lighting plans (drawings LP-1.1 & LP-1.2) has been added to the drawing set.
- 5. Grading & Utilities Plan
 - a. Rims and inverts for the drainage collection system have been added to the drawings.
 - b. The enclosed SWPPP has been updated to include pipe sizing calculations. See Appendix G.
 - c. Buildings will connect to the existing on-site electrical service. The proposed electrical lines, well and sewer / septic components are shown on the plans, and will be buried. Additional details regarding the well and sewer / septic components have been added to the detail sheets.
 - d. Additional details regarding the proposed SSTS system can be found on Drawing D-3.
 - e. A note has been added to drawing OP-1 indicating that all on site utilities are to be buried.

In response to open comments received from Town Planner, Patrick Cleary, AICP, dated September 14, 2023, we offer the following responses:

1. Building Architecture

The applicant's architect looked at the option to use the gambrel style roofline. It was determined that the gambrel style could feasibly be added on the end peaks of the building. See the enclosed revised architectural elevations. Adding the gambrel style roofline to the central peak was studied, but it was determined that it would significantly increase the height of the building and would cause structural challenges. For this reason the gable style remains on the central roof line.

We respectfully request the project be placed on the October 12, 2023 Planning Board agenda for a public hearing and discussion of the project with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:

Richard D. Williams, PE Senior Principal Engineer

RDW/adt

Enclosures

cc: (All via email only) Aaron Sommer, Jason Sommer, Jennifer Grey, Esq, Scott Stinard, John Anastasiou, AIA







PRELIMINARY STORMWATER POLLUTION PREVENTION PLAN

For

DPD – Self Storage 4 Baldwin Place Town of Carmel, New York

October 2, 2023

Owner Information:

Bernad Creations LTD 124 Ridge Road Montgomery, NY 12549

Applicant Information:

Diamond Point Development 880 Marietta Highway, Suite 630-243 Roswell, GA 30075



Note: This report in conjunction with the project plans make up the complete Stormwater Pollution Prevention Plan.

Prepared by: Insite Engineering, Surveying & Landscape Architecture, P.C. 3 Garrett Place Carmel, New York 10512

CONTENTS

1.0	INTF	RODUCTION	1
	1.1	Project Description	1
	1.2	Existing Site Conditions (Pre-Development)	1
	1.3	Proposed Site Conditions (Post Development)	2
2.0	STO	RMWATER MANAGEMENT	3
	2.1	Chapter 10: Enhanced Phosphorus Removal Standards	5
	2.2	NYSDEC Runoff Reduction Volume (RRv)	5
	2.3	NYSDEC Water Quality Volume (WQv)	6
	2.4	NYSDEC Stream Channel Protection Volume (CPv)	8
	2.5	NYSDEC Overbank Flood Control $(Q_p),$ and Extreme Flood Control (Q_f)	8
	2.6	NYCDEP Requirements	9
3.0	STO	RMWATER CONVEYANCE SYSTEM 1	1
4.0	ERO	SION AND SEDIMENT CONTROL 1	1
	4.1	Temporary Erosion and Sediment Control Facilities 1	1
	4.2	Permanent Erosion and Sediment Control Facilities 1	2
5.0	IMPI	LEMENTATION AND MAINTENANCE 1	3
	5.1	Construction Phase 1	3
	5.2	Soil Restoration 1	4
	5.3	Long Term Maintenance Plan 1	5

APPENDICES

Appendix A	Runoff Reduction (RRv) Calculation Worksheets
Appendix B	Pre-Development Computer Data
Appendix C	Post-Development Computer Data
Appendix D	NYSDEC SPDES for Construction Activities Construction Site Log Book
Appendix E	Project and Owner Information
Appendix F	Bioretention Filter Sizing Calculations
Appendix E	Pipe Sizing Calculations

FIGURES

Figure 1: Location Map Figure 2: Pre-Development Drainage Map Figure 3: Post-Development Drainage Map

1.0 INTRODUCTION

1.1 Project Description

The subject project is located on two adjacent parcels totaling 30.53± acres on Baldwin Place Road in the Town of Carmel. The parcel and its surroundings are delineated on the attached Location Map (Figure 1). Designated as Tax Map Numbers 86.10-1-2 and 86.10-1-3 and are in the C/BP & C zoning districts, respectively. Portions of the property are currently developed with buildings and associated paved and gravel driveways. The remaining areas of the property consist of grass and wooded areas. It is proposed to construct two (2) self-storage buildings, an office building for leasing & administration, and associated site improvements such as driveways and parking areas. The overall project proposes to develop 4.6 +/- acres of new impervious surfaces on the site. It is proposed to capture and treat the stormwater runoff associated with the proposed improvements in a series of stormwater management practices designed to meet Town of Carmel, NYSDEC and NYCDEP requirements. A proposed drilled well and septic system will service the project. The project site is located in the Amawalk Reservoir Watershed.

The following permits are required for the project:

NEW YORK CITY DEPARTMENT OF ENVIROMENTAL PROTECTION
SWPPP & Septic Approval
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
SWPPP General Permit Coverage (GP-0-20-001) Freshwater Wetland Permit
PUTNAM COUNTY DEPARTMENT OF HEALTH
SSTS & Well Improvement Approval
TOWN OF CARMEL
Site Plan Approval/ Wetland Permit
Site Plan Approval/ Wetland Permit NEW YORK STATE DEPARTMENT OF TRANSPORTATION
Site Plan Approval/ Wetland Permit NEW YORK STATE DEPARTMENT OF TRANSPORTATION Highway Work Permit
Site Plan Approval/ Wetland Permit NEW YORK STATE DEPARTMENT OF TRANSPORTATION Highway Work Permit PUTNAM COUNTY DEPARTMENT OF HIGHWAYS AND FACILITIES

There are no known enforcement actions, and no lawsuits or administrative proceedings, commenced against the applicant, or any principal affiliate of the applicant, for any alleged violations of law related to the applicant of the site, in the five years preceding this application.

With regard to NYCDEP requirements, Section 18-39(b)(4)(iii) and Section 18-39(b)(4)(iv) of the Rules and Regulations require a SWPPP Approval for this project. This project meets two (2) of the thresholds that require SWPPP approval from the NYCDEP. For further discussion on NYCDEP requirements, refer to Section 2.6 below.

1.2 Existing Site Conditions (Pre-Development)

The subject property is located in the Town of Carmel on Baldwin Place Road adjacent to Route 6. The property is currently developed with multiple buildings, roadways, fields and woods. There is a high point located along the north property line. From the high point, stormwater runoff generally slopes to the south and west towards Baldwin Place Road or east towards Route 6 and a New York State Department of Environmental Conservation (NYSDEC) Wetland on the adjacent property.

1

The stormwater analysis included in this SWPPP utilizes five (5) design points. The design points can be seen on Figures 2 and 3, and are identified as Design Point 1, Design Point 2, Design Point 3, Design Point 4, and Design Point 5. The Subcatchments for each Design Point are identified as PRE 1, PRE 2, PRE 3, PRE 4 and PRE 5 in the predevelopment model and are shown on Figure 2. See below for a summary of each design point:

- Design Points 1 and 2 are located at existing culverts along Baldwin Place Road. Runoff is conveyed to Design Point 1 via existing roadside swales that shall remain.
- Design Point 3 represents a point on an existing open channel conveyance system south of Kennard Road. Runoff is conveyed to Design Point 3 via the stormwater collection system located along US Route 6, and Baldwin Place Road.
- Design Point 4 is located at an existing drain inlet in Baldwin Place Road. Runoff is conveyed to Design Point 4 via the stormwater collection system located along US Route 6.
- Design Point 5 is located at an existing headwall adjacent to Baldwin Place Road. Runoff is conveyed to Design Point 5 via an existing swale that discharges from the NYSDEC Wetland and Pond that runs along US Route 6.

It is noted there are existing flooding issued along Baldwin Place Road both in front of the Mobil Station and at the culvert crossing by Kennard Road during certain rainfall events. This project will serve to alleviate those flooding problems by reducing peak flows to below pre-development areas as well as capturing runoff and more securely conveying it to the existing infrastructure.

The hydrologic soil groups for the project consists of "B", "C" & "D" soils. The designation of the onsite soils located within the proposed limits of disturbance primarily consist of Paxton fine sandy loam (PnB, PnC & PnDs identified on the Soil Conservation Service Web Soil Survey. The soils boundaries are shown on Figure 2 and 3 of this report. The following soil group descriptions are as defined by the Soil Conservation Service Web Soil Survey.

1.3 Proposed Site Conditions (Post Development)

As mentioned above, the proposed project includes the construction of two (2) self-storage buildings, an office building for leasing & administration, and associated site improvements such as driveways and parking areas. The redevelopment project will include an increase in impervious surfaces (approximately 4.6 +/- acre increase). As such, treatment and mitigation for the newly created impervious surfaces will be provided in the form of proposed stormwater management practices (SMP) discussed further in later sections of this report. The proposed SMP's will be designed to capture and treat runoff from the impervious surfaces associated with the proposed project.

It is proposed to maintain the existing drainage patterns on the site to the maximum extent practical to minimize the impact to the existing downstream areas. Stormwater treatment for the subject development will be accomplished through the use of two (2) infiltration basins (NYSDEC I-2), a Wet Swale (NYSDEC O-2) and a Bioretention Filter (NYSDEC F-5) as SMPs.

As shown in the following sections of this report, the stormwater quality and quantity for the proposed development have been mitigated in accordance with the Town of Carmel, NYSDEC and NYCDEP design standards. Additionally, an erosion and sediment control plan has been prepared in accordance with the *New York State Standards and Specifications for Erosion and Sediment Control* to protect downstream features during construction activities.

2.0 STORMWATER MANAGEMENT

The proposed stormwater management system for the project has been designed to meet the requirements of local, regional, and state stormwater ordinances and guidelines, including but not limited to the NYCDEP and the NYSDEC. Specifically, the following codes / regulations have been used to design this SWPPP:

- NYSDEC SPDES General Permit for Stormwater Discharges from Construction Activities, General Permit GP-0-20-001 (GP-0-20-001).
- NYCDEP Rules and Regulations for the Protection from Contamination, Degradation, and Pollution of the New York City Water Supply and its Sources (Rules and Regulations).
- Town of Carmel Town Code, Chapter 156 Stormwater Management, Soil Erosion and Sediment Control.

Since the subject project proposes the disturbance of more than 1 acre, coverage under the New York State Department of Environmental Conservation (NYSDEC) SPDES General Permit for Stormwater Discharges from Construction Activities (GP-0-20-001) is required. It should be noted that the requirements set forth by GP-0-20-001 discussed below will also incorporate the requirements for redevelopment projects in future iterations of this SWPPP.

In order to meet the requirements, set forth by GP-0-20-001, and the latest edition of the NYSDEC *New York State Stormwater Management Design Manual* (NYSSMDM), including the requirements listed in Chapter 10: *Enhanced Phosphorus Removal Standards* (Chapter 10) was referenced for the design of the proposed stormwater collection, conveyance and treatment system. The Design Manual specifies five design criteria that are discussed in detail below. They are Runoff Reduction Volume (RR_v), Water Quality Volume (WQ_v), Stream Channel Protection Volume (CP_v), Overbank Flood Control (Q_t), and Extreme Storm Control (Q_p). Stormwater collection, conveyance and treatment systems have been designed in general accordance with both the General Permit (GP-0-20-001) and the NYSSMDM. The first two requirements relate to treating water quality, while the later pertain to stormwater quantity (peak flow) attenuation. As noted in previous sections of this report, this project is a redevelopment project with an overall increase in impervious area. Per Chapter 9, 25% of the existing impervious area within the subcatchments is required to be treated to meet the WQv requirements for redevelopment projects. The final SWPPP will incorporate the existing redeveloped impervious areas to calculate the WQv.

Where WQv/RRv treatment is required, the following post construction stormwater management practices are proposed for the project:

SMP ID	Proposed Subcatchment	NYSSMDM Ch. 6 Design Designation	NYSDEC Uniform Stormwater Sizing Criteria Satisfied	NYCDEP Requirement Satisfied
3.1P	3.1S	I-2 Infiltration Basin	RRv, WQ _v , CP _v ¹	Only Practice Required to be Provided.
4.1AP	115	O-2 Wet Swale	WQv	First Practice in Series
4.1BP	4.10	F-5 Bioretention Filter	RRv, WQ _v	Second Practice in Series
5.1P	5.1S	I-2 Infiltration Basin	RRv, WQ _v , CP _v ¹	Only Practice Required to be Provided.

 Table 2.0.1 – Proposed GIP/SMP Design Criteria Summary Table

¹ The infiltration basin achieves the CP_v requirement as they are designed to infiltration the 1-year storm as a result of Chapter 10 requirements.

To address stormwater quantity requirements of the NYSDEC, the "HydroCAD" Stormwater Modeling System," by HydroCAD Software Solutions LLC in Tamworth, New Hampshire, was used to model and assess the peak stormwater flows for the subject project. HydroCAD is a computer aided design program for modeling the hydrology and hydraulics of stormwater runoff. It is based primarily on hydrology techniques developed by the United States Department of Agriculture, Soil Conservation Service (USDA, SCS) TR-20 method combined

with standard hydraulic calculations. For details on the input data for the subcatchments and design storms, refer to Appendices A through C and for the supporting data relative to the soils breakdown within the overall contributing area shown in the HydroCAD analysis, see Appendix A of this report:

The input requirements for the HydroCAD computer program are as follows:

Subcatchments (contributing watershed/sub-watersheds)

- Design storm rainfall in inches
- CN (runoff curve number) values which are based on soil type and land use/ground cover
- Tc (time of concentration) flow path information

Flow Splitters / Subsurface Infiltration System

- Surface area at appropriate elevations
- Flood elevation
- Outlet structure information

The following is a general description of the input data used to calculate the pre- and post-development stormwater runoff values. For detailed information for each subcatchment and pond, see Appendices B & C. The precipitation values for the 1-Year, 10-Year, 100-Year 24-hour design storm events and rainfall distribution curves utilized for this report were obtained from the information provided by Northeast Regional Climate Center (NRCC) and the Natural Resources Conservation Service (NRCS) which is available online at *www.precip.eas.cornell.edu*. The values provided for all design storms analyzed are listed below.

24-Hour Rainfall
2.71"
4.86"
8.63"

The CN (runoff curve number) values utilized in this report were referenced from the USDA, SCS publication *Urban Hydrology for Small Watersheds*. The following is a summary of the various land uses/ground covers and the associated CN values and soil types utilized in this report.

Land Use/Ground Cover	CN Value
>75% Grass Cover, Good, HSG B	61
>75% Grass Cover, Good, HSG C	74
>75% Grass Cover, Good, HSG D	80
Gravel Surface, HSG C	96
Meadow, non-grazed, HSG C	71
Paved Parking	98
Water Surface, HSG D	98
Woods, Good, HSG B	55
Woods, Good, HSG C	70
Woods, Good, HSG D	77
Woods/grass comb., Good, HSG C	72

Table 2.0.2 – Projec	t Ground Cover and	Associated Cur	ve Numbers (CN)
----------------------	--------------------	----------------	-----------------

2.1 Chapter 10: Enhanced Phosphorus Removal Standards

As noted above, the New York City East of Hudson Watershed has been identified in the SPDES General Permit GP-0-20-001 as a watershed requiring compliance with the Enhanced Phosphorus

Removal Standards when post-construction stormwater management practices are proposed. Chapter 10 establishes four goals to meet sizing performance standards:

- Goal 1: Reducing Runoff Volumes
- Goal 2: Effective Bypass Treatment
- Goal 3: Achieving Effluent Concentrations for Particulate Phosphorus
- Goal 4: Achieving Effluent Concentrations for Dissolved Phosphorus

In order to achieve the first goal, the site design shall," assess the feasibility of hydrological source controls and reduce the total water quality volume by source control, implementation of green infrastructure, or standard SMP's with RR_v capacity, according to the process defined in Chapters 3 and 4 of the Design Manual. Each plan must include a rationale for acceptance and rejection of the various controls." A discussion on RR_v can be found in section 2.2 below. Based on mapped soil classifications, the soils onsite are suitable for infiltration. Therefore, the use of infiltration practices (classified as Standard SMP's with RRv capacity) has been maximized. As such, Goal 1 has been achieved in this SWPPP.

Goal 2 cites that proposed stormwater management practices should achieve less than 15% effective treatment bypass of the long-term runoff volume. Chapter 10 further notes this goal is satisfied by capturing and treating the 1-year 24-hour design storm. The NYSDEC stormwater quality treatment practices proposed for this have been designed in accordance with Chapter 10 by utilizing the 1-yr, 24-hour design storm to generate the WQ_v / RR_v . As such, Goal 2 has been achieved in this SWPPP.

Achieving effluent concentrations for particulate phosphorus, Goal 3, is satisfied by achieving an 80% net removal of particulate phosphorus for a median influent concentration of 0.5mg/l. Chapter 10 states that through designing proposed SMP's in accordance with Section 10.4 this goal will be achieved. The proposed infiltration basins and bioretention filter have been designed in accordance with Section 10.4.4 of Chapter 10 thus satisfying the requirements Goal 3.

Goal 4, achieving effluent concentration for dissolved phosphorus, is achieved by obtaining a 60% net removal of dissolved phosphorus given a median influent concentration of 0.15mg/l. As with Goal 3, Goal 4 is achieved by designing the proposed SMP's in accordance with Section 10.4 of Chapter 10. As noted above the SMP's have been designed in accordance with section 10.4.4 of Chapter 10 thus satisfying the requirements of this goal.

2.2 NYSDEC Runoff Reduction Volume (RR_v)

The Runoff Reduction Volume (RR_v) criterion is intended to replicate pre-development hydrology by maintaining preconstruction infiltration, peak flow runoff, discharge volume, as well as minimizing concentrated stormwater flow. As stated in Chapter 4 of the NYSSMDM, RR_v may be treated with standard stormwater management practices (SMP's) sized in accordance with the Chapter 4/6 requirements, or with green infrastructure practices (GIP's) sized in accordance with the requirements set forth for each practice in Chapter 5. This requirement has been achieved on the subject project providing an infiltration practice, designed as a SMP in accordance with the latest design standards. Runoff reduction is achieved when runoff from a percentage of the impervious area on the site is captured, routed through a SMP or a GIP, infiltrated to the ground, reused, reduced by evapotranspiration, and eventually removed from the stormwater discharge from the site. Through this implementation, the design of the infiltration basin as a SMP with the runoff reduction capacity equal to 100% of the WQ_v the RRv requirements will be achieved.

Section 4.3 of the NYSSMDM states for sites that do not achieve runoff reduction to preconstruction condition must, at a minimum reduce a percentage of the runoff from impervious areas to be constructed on the site a minimum RR_v. The following equation can be used to determine the minimum runoff reduction volume:

The minimum runoff reduction volume shall be RRv_{minimum} = $(P)(R_v)(Ai)$

12

5

Where,	
S	= Hydrologic Soil Group (HSG) Specific Reduction Factor
A <i>i</i> c	= Total Area of New Impervious Cover
Ai	= Impervious cover targeted for Runoff Reduction
	= (S)(A <i>i</i> c)
Rv	= 0.95

For detailed calculations of the runoff reduction for the proposed SMP's see Appendix A. Listed in Table 2.2.1 below is a summary of the NYSDEC compliant practice, and its satisfaction of the NYSDEC RRv requirements:

Design Point	Subcatchment	RR _{v Required} = WQ _v (c.f.) From Appendix C	RR _{v Minimum} (c.f.) Calculated in Appendix A	NYSDEC Practice Designation	Allowable % of WQv provided to be applied towards RRv	Storage Volume Provided below System Outlet (c.f.) (From Appendix C)	RRv Provided (c.f.)
3	3.1S	22,695	2,462	I-2 Infiltration Basin	100%	23,484	22,695
4	4.1S	3,267	290	F-5 Bioretention Filter	40%	2,544	1,307
5	5.1S	28,793	3,621	I-2 Infiltration Basin	100%	48,675	28,793

Table 2.2.1 Runoff Reduction Volume Summary

As shown in the table above the RRv provided in the Subcatchments 3.1S, 5.1S and 5.2S is equal to the RRv_{required}, therefore the RRv requirement has been met for these Subcatchments. The RRv_{provided} for Subcatchment 4.1S is less than the RRv_{required}. 100% of the RRv_{Required} could not be provided for Design Point 4 due to existing onsite soil conditions and topography which limited the area where infiltration is feasible. However, the RRv_{provided} is greater than the RRv_{minimum} for each design point, therefore the RRv requirement has been met for the subject project.

2.3 NYSDEC Water Quality Volume (WQv)

The stormwater infiltration basin has been sized in accordance with Chapter 4 of the Design Manual, as it has been sized to capture and treat the entire water quality volume (WQ_v) from the proposed improvements. The subject project is located in the New York City Watershed, which is listed as a phosphorus-limited watershed per the NYSDEC regulations. Therefore, the stormwater management practice has been designed in general accordance with the Enhanced Phosphorus Removal Supplement (Chapter 10) of the Design Manual. As outlined in Chapter 10, the treatment volume for the WQv is the runoff volume produced during the 1-year 24-hour design storm. See table 2.6.1 and Appendix C for a summary of the WQv that would be generated by the proposed project during the 1-year, 24-hour storm.

Table 2.2.1 above and the tables below summarize the WQv treatments and the proposed practices, sized in accordance with Chapters 3 and 6 of the NYSSMDM for the proposed practice.

The infiltration basins have been sized to provide 100% storage of the water quality volume between the bottom of the practice and the outlet weir of the basins. By providing 100% storage of the WQv in the infiltration basin the water quality volume storage requirements set forth in the Design Manual have been met for the proposed basin. By meeting the Water Quality Volume requirements through employment of the infiltration basin, the water quality objectives of the NYSDEC will be met.

The infiltration basins area designed as offline practices that fully infiltrate the WQv from the contributing area. A flowsplitter or pretreatment sediment forebay is proposed upstream of the basins to make the practiced offline. The flowsplitter and sediment forebays are sized to convey at a minimum the

peak WQv flow (1-year 24-hour) to the infiltration basin, while allowing portions of larger storms to bypass the infiltration units as allowed by the Design Manual. Pretreatment has been provided for the infiltration basins in the form of a sediment forebay basin or a hydrodynamic separator. The pretreatment basins will temporarily store greater than the volume required.

As noted below, the infiltration basins have been sized to meet both the RRv and WQv requirements.

Subcatchment	Treatmen t Practice	NYSDEC Design Practice Designation	WQ _v Required (c.f.)	Proposed WQ _v (Storage Volume below outlet) ^{1,2} (c.f.)
3.1S	3.1P	Infiltration Basin I-2	22,695	23,484
5.1S	5.1P	Infiltration Basin I-2	28,793	48,675

Table 2.3.1 Infiltration Area Water Quality Volume Treatment Summary

The Bioretention Filter (4.1BP) has been designed to treat the WQv in accordance with the Design Manual as noted in the table below and in Appendix F. A grass filter strip has been provided as Pretreatment for the Bioretention filter. Also, the bioretention filter has been designed as offline practices that will receive the WQv from the contributing area. The Wet Swale (1.4AP) outlet structure has been designed as the flow splitter for the bioretention filter to convey at a minimum the peak WQv flow.

Subcatchment	Treatment Practice	NYSDEC Design Practice Designation	Required Filter Area (s.f.)	Provided Filter Area (s.f.)	Minimum Storage Volume Required (75% WQv) (c.f.)	Storage Volume Provided Below Outlet (c.f.)
4.1S	4.1BP	F-5	2,800	4,000	2,450	2,544

* Information regarding required filter area is calculated and shown in Appendix F.

A Wet Swale (1.4AP) is proposed upstream of the Bioretention Filter (1.4BP) and has been designed to treat the WQv required from the contributing area. In accordance with the Design Manual, the swales have been designed to provide 30-minutes of detention of the 1-year 24-hour storm runoff volume, therefore treating 100% of the WQv as shown in Appendix C.

It should be noted that the above tables illustrate the water quality volume storage requirements set forth in the Design Manual have been met for the Infiltration Basins, Wet Swale and Bioretention Filter.

2.4 NYSDEC Stream Channel Protection Volume (CPv)

The Stream Channel Protection (CP_v) criterion is intended to protect stream channels from erosion and is accomplished by the 24-hour extended detention of the center-of-mass of the one-year, 24-hour storm event. As noted in Table 2.1.1 the stormwater infiltration system has been designed with a storage volume greater than the volume of stormwater runoff from the 1-year storm. By providing a stormwater infiltration practice to fully infiltrate the volume of stormwater runoff from the 1-year, 24-hour design storm, the CP_v has been met for the project. Soil and infiltration testing was performed in the locations of the proposed stormwater management practices and witnessed by the NYCDEP. The test results verify the design requirements for infiltration practice set forth in the NYSSMDM. All infiltration rates in the areas of the proposed infiltration practice exceed the minimum 0.5 inches/hour requirement.

2.5 NYSDEC Overbank Flood Control (Q_p), and Extreme Flood Control (Q_f)

The Overbank Flood Control (Q_p) requirement is intended to prevent an increase in the frequency and magnitude of out-of-bank flooding events generated by urban development. Overbank control requires storage to attenuate the post-development 10-year, 24-hour peak discharge to pre-development rates. The Extreme Flood Control (Q_f) requirement is intended to prevent the increased risk of flood damage from large storm events, maintain the boundaries of the pre-development 100-year flood plain, and protect the physical integrity of stormwater management practice. Extreme flood control requires storage to attenuate the post-development 100-year, 24-hour peak discharge to pre-development rates. As shown in Table 2.5.1 attenuation for both the 10-year and 100-year 24-hour storms has been provided thus satisfying the Q_p and Q_f requirements.

5 1 1 1 1 1 1 1									
24-HOUR DESIGN STORM PEAK FLOWS (c.f.s.)									
	1-YI (Channel I Volu	EAR Protection Ime)	10-Y (Overbank Fl	EAR ood Control)	100-\ Extreme Flo	YEAR ood Control)			
	Pre	Post	Pre	Post	Pre	Post			
Design Point 1	3.5	2.8	15.2	14.1	39.8	38.9			
Design Point 2	1.6	0.8	5.6	4.1	13.7	11.3			
Design Point 3	5.5	2.5	15.7	11.8	34.7	33.4			
Design Point 4	7.2	5.1	16.0	11.9	30.6	23.9			
Design Point 5	17.7	17.2	53.6	52.8	123.3	120.4			

Table 2.5.1– Existing and Proposed Conditions Peak Flows

Table 2.5.2– Existing and Proposed Conditions Runoff Volumes

24-HOUR DESIGN STORM RUNOFF VOLUMES (a.f.)									
	1-YEAR (Channel Protection Volume) 10-YEAR (Overbank Flood Control)		100-YEAR (Extreme Flood Control)						
	Pre	Post	Pre	Post	Pre	Post			
Design Point 1	0.460	0.406	1.640	1.550	4.319	4.223			
Design Point 2	0.150	0.116	0.488	0.441	1.225	1.201			
Design Point 3	0.634	0.292	1.772	1.252	4.084	3.704			
Design Point 4	0.614	0.429	1.446	1.026	3.009	2.158			
Design Point 5	3.413	3.276	9.775	9.327	22.835	22.080			

As shown in the above tables, the peak flows and runoff volumes from the contributing areas to the design lines in the post development condition have been mitigated to below the existing condition levels, thus meeting the general requirements of the NYSDEC. As shown on drainage Figures 2 & 3, the alteration of the drainage boundaries from the pre to the post development condition have been minimized to the maximum extent practical.

2.6 NYCDEP Requirements

The proposed project meets two (2) of the thresholds that require SWPPP approval from the NYCDEP per Section 18-39 of the Rules and Regulations. The project meets the following thresholds listed in Section 18-39(b)(4) that require NYCDEP SWPPP approval:

- (iii) Construction of a new industrial, institutional, municipal, commercial, or multi-family residential project that will result in the creation of an impervious surface totaling over 40,000 square feet in size.
- (iv) A land clearing or land grading project, involving two or more acres, located at least in part within the limiting distance of 100 feet of a watercourse or wetland, or within the limiting distance of 300 feet of a reservoir, reservoir stem or controlled lake or on a slope exceeding 15 percent.

There is no proposed stormwater discharge from industrial activities for the proposed development.

The Rules and Regulations parallel the requirements of the NYSDEC, with the exception that two different NYSDEC standard SMP's are required in series when the drainage area to a SMP is greater than 20% impervious and an infiltration practice is not provided. The project proposes an infiltration practice for Subcatchments 3.1S and 5.1S and as such, does not require two different practices in series Subcatchment 4.1S does exceed the 20% impervious, and as two SMP's in series are provided (as shown in Table 2.6.2 below).

Per the Rules and Regulations, the stormwater treatment volume used shall be the greater of the runoff volume from the 1-year, 24-hour storm event or the volume generated by the 90% storm. The initial WQ_v from the 1-year storm event was discussed above. The following equation, per Chapter 4.2 and Chapter 9, was used to determine the water quality volume for the 90% storm each of the contributing areas to the treatment practices:

The water quality volume shall be: $WQ_v = (P)(R_v)(A)$

Where,

A ALICIC	ς,	
	WQv	= water quality volume (in acre-feet)
	Р	= 90% Rainfall Event Number = 1.4 inches
	А	= Subcatchment Area
	I	= (Ap)/(A-Ae)
	Rv	= 0.05 +0.009 (1%)

Table 2.6.1 - Water Qualit	y Volume Calculation Summar	y 90% Storm vs. 1-Year St	orm Comparison

Subcatchments	Р	Rv	A ¹	WQ _{v90}	WQ _v ²
	(in.)		(ac.)	(c.f.)	1-year (c.f.)
3.1S	1.4	0.52	4.2	11,099	22,695
4.1S	1.4	0.59	0.5	1,499	3,267
5.1S	1.4	0.68	4.4	15,205	28,793

¹ Information regarding contributing areas for the 1-year 24-hour storm event is shown in Appendix C. ² Refer to Appendix C for 1-year 24-hour water quality volume calculation.

As shown in Table 2.6.1 above, the volume produced by the 1-year, 24-hour design storm for subcatchments is larger than the volume produced by the 90% storm. Therefore, the 1-year, 24-hour design storm volumes shall be used for the WQv sizing for all of the proposed stormwater management practices.

The following table summarizes the amount of proposed impervious surfaces for each subcatchment and shows the proposed stormwater management practice that will treat each subwatershed:

Sub- Catchments	Total Area (acres)	Existing Impervious Surface Within	Proposed Impervious Surface Within	% Impervious Surface of Total	Proposed Management Treatme	Stormwater Practice (SMP) ent Train ¹
		Subcatchment (acres)	Subcatchment (acres)	Area	RR _v /SMP 1	SMP 2 (A second practice in series is only provided when % impervious is greater than 20% and infiltration is not provided)
3.1S	4.2	0.5	2.2	52.4%	I-2, Infiltration Basin	Not Required
4.1S	0.5	0.1	0.3	60.0%	O-2 Wet Swale	F-5 Bioretention Filter
5.1S	4.4	0.6	3.1	70.5%	I-2, Infiltration Basin	Not Required

¹ This table lists the standard SMP's used to treat the balance of the WQ_v/ RR $_v$ after the application of GIP's.

As shown in the above table, the project proposes an infiltration practice for Subcatchments 2.1S, 3.1S, 5.1S and 5.2S Subcatchments, therefore two practices in series are not required. Subcatchment 4.1S is greater than 20% imperviousness and a treatment train of two practices in series is provided. By proposing two stormwater management practices in series or an infiltration practice for all subcatchments, the NYSDEP requirement is met.

3.0 STORMWATER CONVEYANCE SYSTEM

The stormwater conveyance system for the project consists of grass swales, precast concrete drainage structures, and HDPE pipe. In the locations of new swales and stormwater piping, the system has been sized utilizing the Rational Method and is a standard method used by engineers to develop flow rates for sizing collection systems. The Rational Method calculates flows based on a one-hour design storm. Pipe sizing calculations can be found in Appendix G.

4.0 EROSION AND SEDIMENT CONTROL

Erosion and sediment control should be accomplished by four basic principles: diversion of clean water, containment of sediment, treatment of dirty water, and stabilization of disturbed areas. Diversion of clean water should be accomplished with swales. This diverted water should be safely conveyed around the construction area as necessary and discharged downstream of the disturbed areas. Sediment should be contained with the use of silt fence at the toe of disturbed slopes. Disturbed areas should be permanently stabilized within 7 days of final grading to limit the required length of time that the temporary facilities must be utilized. The owner will be responsible for the maintenance of the temporary erosion control facilities. Refer to the Project Drawings for further information implementation of the Erosion Control Plan.

4.1 Temporary Erosion and Sediment Control Facilities

Temporary erosion and sediment control facilities should be installed and maintained as required to reduce the impacts to off-site properties. The owner will be required to provide maintenance for the temporary erosion and sediment control facilities. In general, the following temporary methods and materials should be used to control erosion and sedimentation from the project site:

- Stabilized Construction Entrance
- Silt Fence Barriers
- Temporary Soil Stabilization

• Temporary Sediment Trap

All temporary erosion control measures shall be maintained in accordance with the Erosion & Sediment Control Maintenance Schedule contained on the Project Drawings, and as discussed below.

A stabilized construction entrance should be installed at the site entrance as shown on the project plans. The design drawings will include details to guide the contractor in the construction of this entrance. The intent of the stabilized construction entrance is to prevent the "tracking" of soil from the site. Dust control should be accomplished with water sprinkling trucks if required. During dry periods, sprinkler trucks should wet all exposed earth surfaces as required to prevent the transport of air-borne particles to adjoining areas.

Siltation barriers constructed of geosynthetic filter cloth should be installed at the toe of all disturbed slopes. The intent of these barriers is to contain silt and sediment at the source and inhibit its transport by stormwater runoff. The siltation barriers will also help reduce the rate of runoff by creating filters through which the stormwater must pass. During construction, the siltation barriers shall be inspected weekly and after a rainfall event and shall be cleaned/replaced when needed.

When land is exposed during development, the exposure shall be kept to the shortest practical period, but in no case more than 7 days. Temporary grass seed and mulch shall be applied to any construction area idle for two weeks. The temporary seeding and mulching shall be performed in accordance with the seeding notes illustrated on the project drawings. Disturbance shall be minimized in the areas required to perform construction. Upon completion of final grading topsoil, permanent seeding and mulch shall be applied in accordance with the project drawings.

The stormwater runoff will be managed by the temporary erosion and sediment control facilities during construction. As discussed in the construction sequences provided the project plans the stabilized construction entrance shall be installed at the site entrance and silt fence shall be installed along the downhill perimeter of where soil disturbing activities will occur containing sediment laden stormwater runoff on-site.

4.2 Permanent Erosion and Sediment Control Facilities

Permanent erosion and sediment control will be accomplished by diverting stormwater runoff from steep slopes, controlling/reducing stormwater runoff velocities and volumes, and vegetative and structural surface stabilization. All of the permanent facilities are relatively maintenance free and only require inspections monthly or after a significant rainfall event. The owner will provide maintenance for all the permanent erosion and sediment control facilities.

Rock outlet protection will be provided at the discharge end of all piped drainage systems and will be sized in accordance with the Blue Book. The purpose of the rock outlet protection is to reduce the depth, velocity, and energy of water, such that the flow will not erode the receiving downstream reach. The rock outlet protection shall be inspected for evidence of scour beneath the riprap and/or for any dislodged stones. Inspections of the rock outlet protection shall be performed during the inspections of the post-construction SMP's for the project.

Other than paved or gravel surfaces, disturbed surfaces will be stabilized with vegetation within 10 days of final grading. Permanent seed mix and mulch shall be applied to idle areas to minimize the amount of exposed soil. Permanent seed mixtures are proposed for the project and illustrated on project drawings. Application rates for the seed and mulch are provided on the project drawings. The vegetation will control stormwater runoff by preventing soil erosion, reducing runoff volume and velocities, and providing a filter medium. Permanent seeding should optimally be undertaken in the spring from March 21st through May 20th and in late summer from August 15th to October 15th.

5.0 IMPLEMENTATION AND MAINTENANCE

5.1 Construction Phase

Details associated with the implementation and maintenance of the proposed stormwater facilities and erosion control measures during construction are shown on the project drawings. Soil disturbance for the subject project shall not exceed five acres at any given time unless otherwise noted on the project plans. The erosion control plan will include associated details and notes to aid the contractor in implementing the plan. Construction is anticipated to begin in the spring of 2024 and anticipated to be completed by the summer of 2025.

During construction, a Site Log Book, Appendix D, is required to be kept per NYSDEC SPDES General Permit GP-0-20-001. Erosion and sediment control inspections are required to be conducted as necessary under coverage of the permit. The erosion and sediment control inspections must be performed daily by a trained contractor and the two (2) weekly inspection performed by a qualified inspector shall be performed on days separated by two (2) full calendar days. The owner or operator must begin implementing corrective actions within one business day and complete the corrective actions in a reasonable time frame. An updated logbook and a copy of the SWPPP is required to be kept on site for the duration of the construction activities. The Construction Site Log Book is an appendix taken from the *New York Standards and Specifications for Erosion and Sediment Control* (Blue Book).

In addition to the proposed erosion and sediment control facilities, the following good housekeeping best management practices shall be implemented to mitigate potential pollution during the construction phase of the project. The general contractor overseeing the day-to-day site operation shall be responsible for the good housekeeping best management practices included in the following general categories:

- Material Handling and Waste Management
- Establishment of Staging Areas
- Proper Equipment Fueling and Maintenance Practices
- Spill Prevention and Control Plan

All construction waste materials shall be collected and removed from the site regularly by the general contractor. The general contractor shall supply waste barrels for proper disposal of waste materials. All personnel working on the site shall be instructed of the proper procedures for construction waste disposal.

Although it is not anticipated any hazardous waste materials will be utilized during construction, any hazardous waste materials shall be disposed of in accordance with federal, state, and local regulations. No hazardous waste shall be disposed of on-site. Hazardous waste materials shall be stored in appropriate and clearly marked containers and segregated from the other non-waste materials. All hazardous waste shall be stored in a structurally sound and sealed shipping containers located in the staging areas. Material safety data sheets, material inventory, and emergency contact numbers will be maintained in the office trailer. All personnel working on the site shall be instructed of the proper procedures for hazardous waste disposal.

Temporary sanitary facilities (portable toilets) shall be provided on site during the entire length of construction. The sanitary facilities shall be located in the project staging area, or in an alternate area away from the construction activities on the site. The portable toilets shall be inspected weekly for evidence of leaking holding tanks.

All recyclables, including wood pallets, cardboard boxes, and all other recyclable construction scraps shall be disposed of in a designated recycling barrel provided by the contractor and removed from the site regularly. All personnel working on the site shall be instructed of the proper procedures for construction waste recycling.

All construction equipment and maintenance materials shall be stored in a construction staging area. Silt fence shall be installed down gradient of the construction staging area. Shipping containers shall be utilized to store hand tools, small parts, and other construction materials, not taken off site daily. Construction waste barrels,

recycling barrels and if necessary hazardous waste containers shall be located within the limits of the construction staging area.

Throughout the construction of the project, several types of vehicles and equipment will be used on-site. Fueling of the equipment shall occur within the limits of the construction staging area. Fuel will be delivered to the site as needed, by the general contractor, or a party chosen by the general contractor. Only minor vehicle equipment maintenance shall occur on-site, all major maintenance shall be performed off-site. All equipment fluids generated from minor maintenance activities shall be disposed of into designated drums and stored in accordance with the hazardous waste storage as previously discussed.

Vehicles and equipment shall be inspected on each day of use. Any leak discovered shall be repaired immediately. All leaking equipment unable to be repaired shall be removed from the site. Ample supplies of absorbent, spill-cleanup materials, and spill kits shall be located in the construction staging area. All spills shall be cleaned up immediately upon discovery. Spent absorbent materials and rags shall be hauled off-site immediately after the spill is cleaned for disposal at a local landfill. All personnel working on the site shall be instructed of the proper procedures for spill prevention and control. Any spill large enough to discharge to surface water will be immediately reported to the local fire / police departments, NYCDEP, the National Response Center 1-800-424-8802, and the NYS Spill Hotline 1-800-457-7362. See the NYSDEC spill reporting requirements for additional information and criteria on spill reporting. NYCDEP must be notified of any NYSDEC reportable spills that occur during construction.

Vegetation should be inspected every 30 days and after every major storm event until established, after which inspections should take place on a quarterly basis and after every large storm event. Damaged areas should be immediately re-seeded and re-mulched.

5.2 Soil Restoration

Soil Restoration is required to be applied across areas of the development site where soils have been disturbed and will be vegetated. The purpose is to recover the original properties and porosity of the soil compacted during construction activity. Soil Restoration is applied in the cleanup, restoration, and landscaping phase of construction followed by the permanent establishment of an appropriate, deeprooted groundcover to help maintain the restored soil structure. Soil restoration includes mechanical decompaction and compost amendment. The table below describes various soil disturbance activities related to land development, soil types and the requirements for soil restoration for each activity as identified in the Design Manual. Restoration is applied across areas of a development site where soils have been compacted and will be vegetated according to the criteria defined in the table below:

Soil Restoration Requirements ^{1, 2,4} (Onsite soils within the limit of disturbance belong to Hydrologic Soil Groups (HSG) A. B & D)						
Type of Soil Disturbance	Soil Restoration	on Requirement	Comments/Examples			
No soil disturbance	Restoration	not permitted	Preservation of Natural Features			
Minimal soil disturbance	Restoration	not required	Clearing and grubbing			
Areas where topsoil is	HSG A & B	HSG C&D	Protect area from any ongoing			
stripped only - no change in grade	Apply 6 inches of topsoil	Aerate ³ and apply 6 inches of topsoil	construction activities.			
	HSG A &B	HSG C&D				
Areas of cut or fill	Aerate ¹ and apply 6 inches of topsoil Apply full Soil Restoration ²					
Heavy traffic areas on site (especially in a zone 5-25 feet around buildings but not within a 5-foot perimeter around foundation walls)	Apply full Soil Restor and compost Enhancement ⁶)	ation (decompaction				
Areas where Runoff Reduction and/or Infiltration practices are applied	Restoration not requi applied to enhance th for appropriate practi	red, but may be ne reduction specified ces.	Keep construction equipment from crossing these areas. To protect newly installed practice from any ongoing construction activities construct a single phase operation fence area			
Redevelopment projects	Soil Restoration is re redevelopment project where existing imper- converted to pervious	quired on cts in areas vious area will be s area.				

1. Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which function like a mini-subsoiler.

2. Per "Deep Ripping and De-compaction, DEC 2008".

3. Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which functions like a mini-subsoiler.

4. During periods of relatively low to moderate subsoil moisture, the disturbed soils are returned to rough grade and the following Soil Restoration steps applied:

- 5.1. Apply 3 inches of compost over subsoil.
- 5.2. Till compost into subsoil to a depth of at least 12 inches using a cat-mounted ripper, tractor-mounted disc, or tiller, mixing, and circulating air and compost into subsoils.

5.3. Rock-pick until uplifted stone/rock materials of four inches and larger size area cleaned off the site.

- 5.4. Apply topsoil to a depth of 6 inches.
- 5.5. Vegetate as required by seeding notes located on the project drawings.
- 5.6. Tilling should not be performed within the drip line of any existing trees or over any utility installations that are within 24 inches of the surface.

6. Compost shall be aged, from plant derived materials, free of viable weed seeds, have no visible free water or dust produced when handling, pass through a half inch screen and have a pH suitable to grow desired plants.

After soil restoration is completed, an inspector should be able to push a 3/8" metal bar twelve inches into the soil with just body weight. Following decompaction/soil restoration activities, the following maintenance is anticipated during the first year:

- Initial inspections for the first six months (once after each storm greater than a half-inch).
- Reseeding to repair bare or eroding areas to assure grass stabilization.
- Water once every three days for first month, and then provide a half inch of water per week during first year. Irrigation plan may be adjusted according to the rain event.
- Fertilization may be needed in the fall after the first growing season to increase plant vigor.

In order to ensure the soil remains decompacted the following ongoing maintenance is recommended:

- Planting the appropriate ground cover with deep roots to maintain the soil structure.
- Keeping the site free of vehicular and foot traffic or other weight loads. Consider pedestrian footpaths (sometimes it may be necessary to de-thatch the turf every few years).

5.3 Long Term Maintenance Plan

The stormwater facilities for the subject project have been designed to minimize the required maintenance. This section discusses the minimum maintenance requirements to insure long-term performance of the stormwater facilities. Initially the stormwater facilities will require an increased maintenance and inspection schedule until all portions of the site are stable. Generally, the stormwater facilities consist of either collection and conveyance components or treatment components.

The stormwater collection and conveyance system is composed of precast concrete drainage structures and pipes. The owner will assume the maintenance responsibilities for the drainage system. Minimal maintenance is typically required for these facilities. All structures should be checked for debris and blockages and cleaned as required. During the cleaning process, the drainage structures should be inspected for structural integrity and overall condition; repairs and/or replacement should be made as required. Additionally, the infiltration basin shall be checked for deposited sediment as well. The Infiltration basin shall be cleaned as necessary to remove deposited sediment.

Additionally, the infiltration basin shall be checked for deposited sediment as well. Visual inspection of system through the inspection ports shall take place yearly, and the system shall be cleaned / jetted as necessary to remove deposited sediment.

APPENDIX A Runoff Reduction (RRv) Calculation Worksheets

RRv Calculation Worksheet - Design Point 3 (3.1S)

 Project:
 DPD

 Project #:
 22242.100

 Date:
 9/29/2023

 1. RRv Initial = Water



Date: 9/29/2023			
1. RRv Initial = Wate	r Quality Volume (WQv) ().573 ac-ft =	22,695 c.f.
(refer to HydroCAD S	ubcatchments 1.1S for Water Quality Volume)		
2. RRv Minimum =	[(P) (Rv) (S) (Aic)] /12 where		
	P = Rainfall (in.)	=	1.40 in.
	Rv = 0.05 + 0.009 (100%)	=	0.95
	S = Hydrologic Soil Group Specific Reduction Factor	or =	0.30
	[HSG A = 0.55] [HSG B = 0.40] [HSG C = 0.30] [H	HSG D = 0.20]	
	Aic = Total area of new impervious cover	=	1.7 Acres
	·		
	RRv Minimum	=	2,462 c.f.
3. RRv Required = R	Rv Initial - Green Infrastructure Practice (GIP) with A	rea Reduction	
GIP with a	Area Reduction Applied in Project		
5.3.1 Con		N/A	
5.3.2 She		N/A	
5.3.4 Tree		c.f.	
5.3.5 Disc		-	
5.3.6 Stre	am Daylighting		N/A
	-		
RRv Req	uired(=WQv-RRV by area)(Refer to HydroCAD output	t in this Appendix) =	22,695 c.f.

4. RRv Provided			
GIP with Volume Reduction Applied in Project	WQv Treated (c.f.)	% of WQv Applied to <i>RRv</i> <i>Provided</i>	RRv Provided (c.f.)
5.3.3 Vegetated Open Swales		20%	0
[HSG A / B = 20%] [HSG C / D = 10%] {Modified HSG C - D = 15% - 12%]		10%	0
5.3.7 Rain Garden		40%	0
[No underdrains / Good Soils = 100%] [With underdrains / Poor Soils = 40%]			
5.3.8 Green Roof		100%	0
[RRv provided equals volume provided in Green Roof]			
5.3.9 Stormwater Planters		45%	0
[Infiltration Planters = 100%] [Flow Through HSG C = 45%] [Flow Though HSG D = 30%]			
5.3.10 Rain Tank / Cisterns		100%	0
5.3.11 Porous Pavement		100%	0
Infiltration Practice (Standard SMP)	22695	100%	22,695
Bioretention Practice (Standard SMP)		40%	0
[Without Underdrains HSG A/B = 80%] [With Underdrain HSG C\D = 40%]			
Dry Swale (Open Channel Practice) (Standard SMP)		20%	0
[HSG A/B = 40%] [HSG C/D = 20%]			
RRv Provided =			22,695

5. Summary

RRv Initial	=	22,695 c.f.	
RRv Required	=	22,695 c.f.	
RRv Minimum	=	2,462 c.f.	
RRv Provided	=	22,695 c.f.	
WQv Required for Downstream SMP	=	0 c.f.	(= RRv Required - RRv Provided)
Is RRv Provided greater than or equal to RRv Minimum?		Yes	

RRv Calculation Worksheet - Design Point 4 (4.1S)

Project: DPD



Project #: Date:	22242.100 9/29/2023	AINEERING, SU DSCAPE ARCHITI	URVEYING & ECTURE, P.C.	
1. RRv Init	ial = Water Quality Volume (WQv)	0.075 ac-ft	=	3,267 c.f.
(refer to Hy	vdroCAD Subcatchments 1.1S for Water Quality	v Volume)		,
, ,		,,		
2. RRv Mir	mimum = [(P) (Rv) (S) (Aic)]/12 where			
	P = Rainfall (in.)		=	1.40 in.
	Rv = 0.05 + 0.009 (100%)		=	0.95
	S = Hydrologic Soil Group Specific	Reduction Factor	=	0.30
	[HSG A = 0.55] [HSG B = 0.4	0] [HSG C = 0.30] [HSG D = 0.20]		
	Aic = Total area of new impervious	cover	=	0.2 Acres
	RRv Minimum		=	290 c.f.
3. RRv Red	quired = RRv Initial - Green Infrastructure Prac	tice (GIP) with Area Reduction		
	GIP with Area Reduction Applied in Project			
	5.3.1 Conservation of Natural Area		N/A	
	5.3.2 Sheet Flow to Riparian Buffers or Filter S	N/A		
	5.3.4 Tree Planting / Tree Box		c.f.	
	5.3.5 Disconnection of Rooftop Runoff		-	
	5.3.6 Stream Daylighting		N/A	
	RRv Required(=WQv-RRV by area)(Refer to H	HydroCAD output in this Appendix)	=	3,267 c.f.

4. RRv Provided			
GIP with Volume Reduction Applied in Project	WQv Treated (c.f.)	% of WQv Applied to <i>RRv</i> <i>Provided</i>	RRv Provided (c.f.)
5.3.3 Vegetated Open Swales		20%	0
[HSG A / B = 20%] [HSG C / D = 10%] {Modified HSG C - D = 15% - 12%]		10%	0
5.3.7 Rain Garden		40%	0
[No underdrains / Good Soils = 100%] [With underdrains / Poor Soils = 40%]			
5.3.8 Green Roof		100%	0
[RRv provided equals volume provided in Green Roof]			
5.3.9 Stormwater Planters		45%	0
[Infiltration Planters = 100%] [Flow Through HSG C = 45%] [Flow Though HSG D = 30%]			
5.3.10 Rain Tank / Cisterns		100%	0
5.3.11 Porous Pavement		100%	0
Infiltration Practice (Standard SMP)		100%	0
Bioretention Practice (Standard SMP)	3,267	40%	1,307
[Without Underdrains HSG A/B = 80%] [With Underdrain HSG C\D = 40%]			
Dry Swale (Open Channel Practice) (Standard SMP)		20%	0
[HSG A/B = 40%] [HSG C/D = 20%]			
RRv Provided =			1,307

5. Summary

RRv Initial	=	3,267 c.f.	
RRv Required	=	3,267 c.f.	
RRv Minimum	=	290 c.f.	
RRv Provided	=	1,307 c.f.	
WQv Required for Downstream SMP	=	1,960 c.f.	(= RRv Required - RRv Provided)
Is RRv Provided greater than or equal to RRv Minimum?		Yes	

RRv Calculation Worksheet - Design Point 5 (5.1S) Project: DPD



Project #: 22242. Date: 9/29/20	ENGINEERING, S LANDSCAPE ARCHIT	CURVEYING & TECTURE, P.C.		
1. RRv Initial = Wa	ter Quality Volume (WQv)	1.021 ac-ft	=	28,793 c.f.
(refer to HydroCAE	Subcatchments 1.1S for Water Quality Volume)			
2. RRv Minimum =	[(P) (Rv) (S) (Aic)] /12 where			
	P = Rainfall (in.)		=	1.40 in.
	Rv = 0.05 + 0.009 (100%)		=	0.95
	S = Hydrologic Soil Group Specific Reduction Fact	or	=	0.30
	[HSG A = 0.55] [HSG B = 0.40] [HSG C = 0.30] [HSG D = 0.20]		
	Aic = Total area of new impervious cover		=	2.5 Acres
	RRv Minimum		=	3,621 c.f.
3. RRv Required =	RRv Initial - Green Infrastructure Practice (GIP) with A	Area Reduction		
<u>GIP wit</u>	n Area Reduction Applied in Project			
5.3.1 C	onservation of Natural Area		N//	Ą
5.3.2 S	N//	4		
5.3.4 Ti		c.f.		
5.3.5 D		-		
5.3.6 St	ream Daylighting		N//	Ą
RRv Re	equired(=WQv-RRV by area)(Refer to HydroCAD output	it in this Appendix	x) =	28,793 c.f.

4. RRv Provided			
GIP with Volume Reduction Applied in Project	WQv Treated (c.f.)	% of WQv Applied to <i>RRv</i> <i>Provided</i>	RRv Provided (c.f.)
5.3.3 Vegetated Open Swales		20%	0
[HSG A / B = 20%] [HSG C / D = 10%] {Modified HSG C - D = 15% - 12%]		10%	0
5.3.7 Rain Garden		40%	0
[No underdrains / Good Soils = 100%] [With underdrains / Poor Soils = 40%]			
5.3.8 Green Roof		100%	0
[RRv provided equals volume provided in Green Roof]			
5.3.9 Stormwater Planters		45%	0
[Infiltration Planters = 100%] [Flow Through HSG C = 45%] [Flow Though HSG D = 30%]			
5.3.10 Rain Tank / Cisterns		100%	0
5.3.11 Porous Pavement		100%	0
Infiltration Practice (Standard SMP)	28793	100%	28,793
Bioretention Practice (Standard SMP)		40%	0
[Without Underdrains HSG A/B = 80%] [With Underdrain HSG C\D = 40%]			
Dry Swale (Open Channel Practice) (Standard SMP)		20%	0
[HSG A/B = 40%] [HSG C/D = 20%]			
RRv Provided =			28,793

5. Summary

ls

RRv Initial	=	28,793 c.f.	
RRv Required	=	28,793 c.f.	
RRv Minimum	=	3,621 c.f.	
RRv Provided	=	28,793 c.f.	
WQv Required for Downstream SMP	=	0 c.f.	(= RRv Required - RRv Provided)
RRv Provided greater than or equal to RRv Minimum?		Yes	· · · ·

APPENDIX B

Pre Development Computer Data



NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C.Printed 5/11/2023HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLCPage 2

Summary for Subcatchment PRE 1:

Runoff = 3.5 cfs @ 12.22 hrs, Volume= 0.460 af, Depth= 0.52"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) (CN Des	cription			
0	.100	98 Pav	ed parking	, HSG C		
0	.500	96 Gra	vel surface	, HSG C		
0	.700	74 >75	% Grass c	over, Good	, HSG C	
1	.200	71 Mea	adow, non-g	grazed, HS	GC	
5	000	70 Wo	ods, Good,	HSG C		
0	.500	72 Wo	ods/grass o	comb., Goo	d, HSG C	
2	2.200	55 Wo	ods, Good,	HSG B		
0	.400	61 >75	% Grass c	over, Good	, HSG B	_
10	.600	69 Wei	ghted Aver	rage		
10	.500	99.0	06% Pervio	us Area		
0	.100	0.94	1% Impervi	ous Area		
-		01		A		
	Length	Slope	Velocity	Capacity	Description	
(min)	(teet)	(11/11)	(IT/SEC)	(CIS)		_
10.9	100	0.0150	0.15		Sheet Flow,	
	005	0 0500	0.05		Grass: Short $n = 0.150$ P2= 3.27"	
1.1	225	0.0500	3.35		Shallow Concentrated Flow,	
1.0	100	0 1 1 0 0	1.00		Grassed Waterway KV= 15.0 fps	
1.6	162	0.1100	1.00		Shallow Concentrated Flow,	
0 5	00	0 2000	0.74		Shallow Concentrated Flow	
0.5	90	0.3000	2.74		Woodland Ky 5.0 fpc	
22	840	0 0300	6 10	36.62		
2.0	040	0.0300	0.10	30.02	$\Delta r_{02} = 6.0 \text{ sf}$ Perim = 10.0' r = 0.60'	
					n=0.030 Earth grassed & winding	
16.4	1 / 17	Total			n= 0.000 Earth, grassed a winding	—
10.4	1,41/	rolai				

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 3

Subcatchment PRE 1:



NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C.Printed 5/11/2023HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLCPage 4

Summary for Subcatchment PRE 2:

Runoff = 1.6 cfs @ 12.11 hrs, Volume= 0.150 af, Depth= 0.64"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Des	cription					
0.	600	96 Grav	vel surface	, HSG C				
0.	100	74 >75	% Grass co	over, Good	, HSG C			
1.	300	70 Woo	ods, Good,	HSG C				
0.	700	55 Woo	ods, Good,	HSG B				
0.	100	61 >75	% Grass c	over, Good	, HSG B			
2.800 72 Weighted Average								
2.	2.800 100.00% Pervious Area							
Tc	Length	Slope	Velocity	Capacity	Description			
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
6.9	60	0.1200	0.15		Sheet Flow,			
					Woods: Light underbrush n= 0.400 P2= 3.27"			
0.4	40	0.0600	1.80		Sheet Flow,			
					Smooth surfaces n= 0.011 P2= 3.27"			
0.7	215	0.0600	4.97		Shallow Concentrated Flow,			
					Paved Kv= 20.3 fps			
1.5	180	0.1500	1.94		Shallow Concentrated Flow,			
					Woodland Kv= 5.0 fps			
0.6	280	0.0400	7.33	29.34	Channel Flow,			
					Area= 4.0 sf Perim= 10.0' r= 0.40'			
					n= 0.022 Earth, clean & straight			
10.1	775	Total						

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 5

Subcatchment PRE 2:



NY - DPD 24-hr S1 1-yr Rainfall=2.71" Printed 5/11/2023

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 6

Summary for Subcatchment PRE 3:

Runoff 5.5 cfs @ 12.24 hrs, Volume= 0.634 af, Depth= 0.93" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Desc	cription					
1.	600 9	8 Pave	ed parking	, HSG C				
0.	700 9	96 Grav	el surface	, HSG C				
1.	700 7	′4 >75°	% Grass co	over, Good	, HSG C			
3.	700 7	'0 Woo	ds, Good,	HSG C				
0.500 55 Woods, Good, HSG B								
8.200 78 Weighted Average								
6.	600	80.4	9% Pervio	us Area				
1.	600	19.5	1% Imperv	vious Area				
-				• •				
TC	Length	Slope	Velocity	Capacity	Description			
(min)	(feet)	(ft/ft)	(ft/sec)	(cts)				
12.8	100	0.0100	0.13		Sheet Flow,			
					Grass: Short n= 0.150 P2= 3.27"			
2.0	250	0.0200	2.12		Shallow Concentrated Flow,			
					Grassed Waterway Kv= 15.0 fps			
0.9	70	0.0700	1.32		Shallow Concentrated Flow,			
	100				Woodland Kv= 5.0 fps			
1.3	430	0.0750	5.56		Shallow Concentrated Flow,			
1.0	100	0.4400	4 00		Paved Kv= 20.3 fps			
1.3	130	0.1100	1.66		Shallow Concentrated Flow,			
0.5	000	0 0000	0.71		Woodland KV= 5.0 fps			
0.5	220	0.2000	0.71		Shallow Concentrated Flow,			
0.5	110	0.0500	0.05		Glassed Waterway KV= 15.0 lps			
0.5	110	0.0500	3.35		Crossed Waterway, Ky, 15.0 fps			
0.1	40	0.0100	7 20	20 00	Dina Chappal			
0.1	40	0.0100	1.20	20.00	$24.0^{\circ} \times 24.0^{\circ}$ Box Aroa- 4.0 of Borim- 8.0° r- 0.50°			
					24.0×24.0 DUX AIEd = 4.0 SI FEIIII = 0.0 I = 0.00			
0.3	1/0	0 2000	6 71		Shallow Concentrated Flow			
0.5	140	0.2000	0.71		Grassed Waterway, Ky= 15.0 fps			
					Grassed Walerway IV- 15.0 1ps			

19.7 1,490 Total

0-

Ó

5

10 15 20 25 30 35 40

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 7

Hydrograph 6 - Runoff 5.5 cfs NY - DPD 24-hr S1 1-yr 5-Rainfall=2.71" Runoff Area=8.200 ac 4 Runoff Volume=0.634 af Flow (cfs) Runoff Depth=0.93" 3 Flow Length=1,490' 2-Tc=19.7 min **CN=78** 1

70

75 80 85 90 95 100 105 110 115 120

45 50 55

60 65

Time (hours)

Subcatchment PRE 3:

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 8

Summary for Subcatchment PRE 4:

Runoff 7.2 cfs @ 12.12 hrs, Volume= 0.614 af, Depth= 1.42" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area (ac) C	N Dese	cription						
2.000 98 Paved parking, HSG C									
0.7	700 9	6 Grav	vel surface	, HSG C					
0.8	300 7	′4 >75°	% Grass co	over, Good	, HSG C				
0.1	8 00	30 >75°	% Grass co	over, Good	, HSG D				
0.4	100 7	'0 Woo	ods, Good,	HSG C					
1.200 72 Woods/grass comb., Good, HSG C									
5.200 86 Weighted Average									
3.200 61.54% Pervious Area									
2.0	2.000 38.46% Impervious Area								
_				-					
TC	Length	Slope	Velocity	Capacity	Description				
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
7.4	100	0.1000	0.22		Sheet Flow,				
					Grass: Dense n= 0.240 P2= 3.27"				
1.8	260	0.1200	2.42		Shallow Concentrated Flow,				
					Short Grass Pasture Kv= 7.0 fps				
0.5	190	0.1000	6.42		Shallow Concentrated Flow,				
					Paved Kv= 20.3 fps				
1.3	270	0.0500	3.35		Shallow Concentrated Flow,				
					Grassed Waterway Kv= 15.0 fps				
1.0	180	0.0200	2.87		Shallow Concentrated Flow,				
					Paved Kv= 20.3 tps				
12.0	1,000	Total							
NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 9

Hydrograph 8-- Runoff 7.2 cfs 7-NY - DPD 24-hr S1 1-yr Rainfall=2.71" 6-Runoff Area=5.200 ac 5 Runoff Volume=0.614 af Flow (cfs) **Runoff Depth=1.42**" 4 Flow Length=1,000' 3-Tc=12.0 min 2 **CN=86** 1 0-5 15 20 25 40 45 50 70 75 80 85 90 95 100 105 110 115 120 10 30 35 55 60 65 Ó Time (hours)

Subcatchment PRE 4:

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 10

Summary for Subcatchment PRE 5:

Runoff 17.7 cfs @ 12.70 hrs, Volume= 3.413 af, Depth= 0.88" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) (<u>CN De</u>	scription					
6.	000	98 Pa	ved parking	, HSG C				
0.	400	96 Gra	Gravel surface, HSG C					
1.	600	98 Wa	Vater Surface, HSG D					
9.	200	74 >7	5% Grass c	over, Good	, HSG C			
10.	000	71 Me	adow, non-	grazed, HS	GC			
9.	100	70 Wo	ods, Good,	HSG C				
1.	000	72 Wo	ods/grass o	comb., Goo	d, HSG C			
8.	800	77 Wo	ods, Good,	HSG D				
0.	700	80 >7	5% Grass c	over, Good	, HSG D			
46.	800	77 We	eighted Ave	rage				
39.	200	83.	76% Pervio	us Area				
7.	600	16.	24% Imperv	vious Area				
Tc	Length	Slope	e Velocity	Capacity	Description			
(min)	(feet)	(ft/ft	(ft/sec)	(cfs)				
18.6	100	0.0100	0.09		Sheet Flow,			
					Grass: Dense n= 0.240 P2= 3.27"			
4.3	770	0.0400) 3.00		Shallow Concentrated Flow,			
					Grassed Waterway Kv= 15.0 fps			
1.8	110	0.0400) 1.00		Shallow Concentrated Flow,			
					Woodland Kv= 5.0 fps			
23.1	980	0.0200) 0.71		Shallow Concentrated Flow,			
					Woodland Kv= 5.0 fps			
0.5	430		13.90		Lake or Reservoir,			
				~~~~	Mean Depth= 6.00			
2.4	/30	0.0200	4.98	29.90	Channel Flow,			
					Area= 6.0 st Perim= 10.0' r= 0.60'			
					n= 0.030 Earth, grassed & winding			

50.7 3,120 Total

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 11

Subcatchment PRE 5:



NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 12

# Summary for Subcatchment PRE 1:

Runoff 15.2 cfs @ 12.19 hrs, Volume= 1.640 af, Depth= 1.86" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area	(ac) (	CN Des	cription			
C	.100	98 Pav	ed parking	, HSG C		
C	.500	96 Gra	vel surface	, HSG C		
C	.700	74 >75	% Grass c	over, Good	, HSG C	
1	.200	71 Mea	adow, non-g	grazed, HS	GC	
5	000	70 Wo	ods, Good,	HSG C		
C	.500	72 Wo	ods/grass o	comb., Goo	d, HSG C	
2	2.200	55 Wo	ods, Good,	HSG B		
C	.400	61 >75	% Grass c	over, Good	, HSG B	
10	.600	69 Wei	ghted Aver	rage		
10	.500	99.0	)6% Pervio	us Area		
C	.100	0.94	1% Impervi	ous Area		
_				<b>a</b> 1.		
IC	Length	Slope	Velocity	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(CfS)		
10.9	100	0.0150	0.15		Sheet Flow,	
					Grass: Short n= 0.150 P2= 3.27"	
1.1	225	0.0500	3.35		Shallow Concentrated Flow,	
1.0	400	0 4 4 0 0	1 00		Grassed Waterway Kv= 15.0 fps	
1.6	162	0.1100	1.66		Shallow Concentrated Flow,	
0.5	00	0 0000	0.74		woodiand KV= 5.0 lps	
0.5	90	0.3000	2.74		Shallow Concentrated Flow,	
0.0	040	0 0200	6 10	26.62	Chapped Flow	
2.0	040	0.0300	0.10	30.02	Aron- 6.0 of Porim- 10.0' $r_{-}$ 0.60'	
					n = 0.030 Farth grassed & winding	
16.4	1 / 1 7	Total				
10.4	1,41/	Total				

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 13

Subcatchment PRE 1:



NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 14

# Summary for Subcatchment PRE 2:

Runoff 5.6 cfs @ 12.10 hrs, Volume= 0.488 af, Depth= 2.09" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (	ac) C	N Des	cription		
0.6	500 S	96 Grav	/el surface	, HSG C	
0.1	100 7	74 >75	% Grass co	over, Good	, HSG C
1.3	300 7	70 Woo	ods, Good,	HSG C	
0.7	700 5	55 Woo	ods, Good,	HSG B	
0.1	100 6	61 >75	% Grass co	over, Good	, HSG B
2.8	300 7	72 Wei	ghted Aver	age	
2.8	300	100.	00% Pervi	ous Area	
Тс	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
6.9	60	0.1200	0.15		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
0.4	40	0.0600	1.80		Sheet Flow,
					Smooth surfaces $n = 0.011$ P2= 3.27"
0.7	215	0.0600	4.97		Shallow Concentrated Flow,
					Paved Kv= 20.3 fps
1.5	180	0.1500	1.94		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.6	280	0.0400	7.33	29.34	Channel Flow,
					Area = 4.0 sf Perim = $10.0^{\circ}$ r = $0.40^{\circ}$
					n= 0.022 Earth, clean & straight
10.1	775	Total			

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 15



Subcatchment PRE 2:

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 16

# **Summary for Subcatchment PRE 3:**

Runoff 15.7 cfs @ 12.23 hrs, Volume= 1.772 af, Depth= 2.59" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area	(ac) C	N Desc	cription		
1.	600 9	8 Pave	ed parking	, HSG C	
0.	700 9	96 Grav	el surface	, HSG C	
1.	700 7	′4 >75°	% Grass co	over, Good	, HSG C
3.	700 7	'0 Woo	ds, Good,	HSG C	
0.	500 5	5 Woo	ds, Good,	HSG B	
8.	200 7	′8 Wei	ghted Aver	age	
6.	600	80.4	9% Pervio	us Area	
1.	600	19.5	1% Imperv	vious Area	
-				<b>o</b>	
IC	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(CfS)	
12.8	100	0.0100	0.13		Sheet Flow,
					Grass: Short n= 0.150 P2= 3.27"
2.0	250	0.0200	2.12		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 tps
0.9	70	0.0700	1.32		Shallow Concentrated Flow,
1.0	400	0 0750			Woodland Kv= 5.0 fps
1.3	430	0.0750	5.56		Shallow Concentrated Flow,
1.0	100	0 1 1 0 0	1.00		Paved KV= 20.3 fps
1.3	130	0.1100	1.66		Shallow Concentrated Flow,
0.5	000	0 0000	0.71		woodland KV= 5.0 lps
0.5	220	0.2000	0.71		Shallow Concentrated Flow,
0.5	110	0.0500	2.25		Chassed Waterway Kv= 15.0 lps
0.5	110	0.0500	3.35		Graceed Waterway, Ky 15.0 fpc
0.1	40	0.0100	7 20	28.80	Dina Channel
0.1	40	0.0100	1.20	20.00	$24.0^{\circ} \times 24.0^{\circ}$ Box Area $4.0$ of Perim 8.0' r 0.50'
					$p_{-} = 0.013$ Concrete pipe, hends & connections
03	140	0 2000	6 71		Shallow Concentrated Flow
0.0	1-10	0.2000	0.71		Grassed Waterway Ky- 15.0 fps
					Grassou waterway IV- 15.0 1ps

19.7 1,490 Total

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 17

Subcatchment PRE 3:



NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 18

# Summary for Subcatchment PRE 4:

Runoff 16.0 cfs @ 12.12 hrs, Volume= 1.446 af, Depth= 3.34" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (	ac) C	N Des	cription			
2.0	000 9	8 Pave	ed parking	, HSG C		
0.7	700 9	6 Grav	vel surface	, HSG C		
0.8	300 7	′4 >75°	% Grass co	over, Good	, HSG C	
0.1	8 00	30 >75°	% Grass co	over, Good	, HSG D	
0.4	100 7	'0 Woo	ods, Good,	HSG C		
1.2	200 7	'2 Woo	ods/grass o	omb., Goo	d, HSG C	
5.2	200 8	6 Weig	ghted Aver	age		
3.2	200	61.5	4% Pervio	us Area		
2.0	000	38.4	6% Imperv	vious Area		
Tc	Length	Slope	Velocity	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
7.4	100	0.1000	0.22		Sheet Flow,	
					Grass: Dense n= 0.240 P2= 3.27"	
1.8	260	0.1200	2.42		Shallow Concentrated Flow,	
					Short Grass Pasture Kv= 7.0 fps	
0.5	190	0.1000	6.42		Shallow Concentrated Flow,	
					Paved Kv= 20.3 fps	
1.3	270	0.0500	3.35		Shallow Concentrated Flow,	
					Grassed Waterway Kv= 15.0 fps	
1.0	180	0.0200	2.87		Shallow Concentrated Flow,	
					Paved Kv= 20.3 fps	
12.0	1,000	Total				

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 19

Subcatchment PRE 4:



NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 20

# Summary for Subcatchment PRE 5:

Runoff 53.6 cfs @ 12.67 hrs, Volume= 9.775 af, Depth= 2.51" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (	<u>ac) C</u>	N Des	cription						
6.0	000	8 Pave	ed parking	HSG C					
0.4	400 9	96 Grav	aravel surface, HSG C						
1.6	600 S	98 Wat	Vater Surface, HSG D						
9.2	200 7	74 >75°	-75% Grass cover, Good, HSG C						
10.0	000 7	71 Mea	dow, non-g	grazed, HS	GC				
9.1	100 7	70 Woo	ods, Good,	HSG C					
1.(	000 7	2 Woo	ods/grass o	comb., Goo	d, HSG C				
8.8	300 7	77 Woo	ods, Good,	HSG D					
0.7	700 8	<u>30 &gt;75</u>	% Grass co	over, Good	, HSG D				
46.8	300 7	77 Wei	ghted Aver	age					
39.2	200	83.7	6% Pervio	us Area					
7.6	600	16.2	4% Imperv	vious Area					
-				<b>o</b>					
	Length	Slope	Velocity	Capacity	Description				
(min)	(teet)	(11/11)	(II/Sec)	(CIS)					
18.6	100	0.0100	0.09		Sheet Flow,				
4.0	770	0.0400	0.00		Grass: Dense $n=0.240$ P2= $3.27^{\circ}$				
4.3	770	0.0400	3.00		Shallow Concentrated Flow,				
1.0	110	0.0400	1 00		Grassed waterway NV= 15.0 lps				
1.0	110	0.0400	1.00		Sitanow Concentrated Flow, Woodland Ky = 5.0 free				
22 I	080	0 0200	0.71		Shallow Concentrated Flow				
20.1	900	0.0200	0.71		Woodland Ky 50 frs				
05	430		13 90						
0.5	-00		10.00		Mean Denth- 6.00'				
24	730	0 0200	4 98	29.90	Channel Flow				
2.7	700	0.0200	4.00	20.00	Area= 6.0 sf Perim= 10.0' $r= 0.60'$				
					n = 0.030 Earth, grassed & winding				
	0.100	Tatal							

50.7 3,120 Total

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 21

Subcatchment PRE 5:



NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 22

# Summary for Subcatchment PRE 1:

Runoff 39.8 cfs @ 12.18 hrs, Volume= 4.319 af, Depth= 4.89" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

	Area	(ac) C	CN Des	scription			
	0.	100	98 Pav	ed parking	, HSG C		
	0.	500	96 Gra	vel surface	e, HSG C		
	0.	700	74 >75	5% Grass c	over, Good	, HSG C	
	1.	200	71 Me	adow, non-g	grazed, HS	GC	
	5.	000	70 Wo	ods, Good,	HSG C		
	0.	500	72 Wo	ods/grass o	comb., Goo	d, HSG C	
	2.200 55 Woods, Good, HSG B						
	0.	400	61 >75	5% Grass c	over, Good	, HSG B	
	10.	600	69 We	ighted Ave	rage		
	10.	500	99.	06% Pervio	ous Area		
	0.	100	0.9	4% Impervi	ous Area		
	-				<b>O</b> :-		
,		Length	Slope	Velocity	Capacity	Description	
_(	min)	(leet)	(11/11)	(IL/Sec)	(CIS)		
	10.9	100	0.0150	0.15		Sheet Flow,	
		005	0.0500	0.05		Grass: Short $n = 0.150$ P2= 3.2/"	
	1.1	225	0.0500	3.35		Shallow Concentrated Flow,	
	16	160	0 1 1 0 0	1.66		Grassed Waterway KV= 15.0 lps	
	1.0	102	0.1100	1.00		Shallow Concentrated Flow, $W_{00} = 5.0$ fps	
	05	90	0 3000	2 74		Shallow Concentrated Flow	
	0.5	50	0.0000	2.74		Woodland $K_{V-} = 5.0$ fps	
	23	840	0.0300	6 10	36.62	Channel Flow	
	2.0	010	0.0000	0.10	00.02	Area = 6.0 sf Perim = 10.0' $r = 0.60'$	
						n=0.030 Earth, grassed & winding	
	16.4	1 417	Total				
			10101				

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 23

Subcatchment PRE 1:



NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 24

# **Summary for Subcatchment PRE 2:**

Runoff 13.7 cfs @ 12.10 hrs, Volume= 1.225 af, Depth= 5.25" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area	(ac) C	N Des	cription		
0.	600	96 Gra	vel surface	, HSG C	
0.	100	74 >75	% Grass co	over, Good	, HSG C
1.	300	70 Wo	ods, Good,	HSG C	
0.	700	55 Woo	ods, Good,	HSG B	
0.	100	61 >75	% Grass co	over, Good	, HSG B
2.	800	72 Wei	ghted Aver	rage	
2.	800	100	.00% Pervi	ous Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
6.9	60	0.1200	0.15		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
0.4	40	0.0600	1.80		Sheet Flow,
					Smooth surfaces n= 0.011 P2= 3.27"
0.7	215	0.0600	4.97		Shallow Concentrated Flow,
					Paved Kv= 20.3 fps
1.5	180	0.1500	1.94		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.6	280	0.0400	7.33	29.34	Channel Flow,
					Area= 4.0 sf Perim= 10.0' r= 0.40'
					n= 0.022 Earth, clean & straight
10.1	775	Total			

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 25

Subcatchment PRE 2:



NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 26

# **Summary for Subcatchment PRE 3:**

Runoff 34.7 cfs @ 12.22 hrs, Volume= 4.084 af, Depth= 5.98" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area	(ac) C	N Desc	cription		
1.	600 9	8 Pave	ed parking	, HSG C	
0.	700 9	6 Grav	el surface	, HSG C	
1.	700 7	'4 >75°	% Grass co	over, Good,	, HSG C
3.	700 7	'0 Woo	ds, Good,	HSG C	
0.	500 5	5 Woo	ds, Good,	HSG B	
8.2	200 7	'8 Weig	ghted Aver	age	
6.	600	80.4	9% Pervio	us Area	
1.	600	19.5	1% Imperv	vious Area	
Та	Longth	Clana	Valasity	Conceitu	Description
IC (min)	Length			Capacity	Description
				(CIS)	Obact Flow
12.8	100	0.0100	0.13		Sneet Flow,
2.0	250	0 0 0 0 0 0	0 10		Glass. Short he u.150 PZ= 3.27
2.0	250	0.0200	2.12		Graceed Waterway, Ky 15.0 fpc
0.0	70	0 0700	1 22		Shallow Concentrated Flow
0.9	70	0.0700	1.52		Woodland $K_{V-} = 5.0$ fps
13	430	0 0750	5 56		Shallow Concentrated Flow
1.0	400	0.0700	0.00		Paved $K_v = 20.3 \text{ fps}$
13	130	0 1100	1 66		Shallow Concentrated Flow
		011100			Woodland $Kv = 5.0$ fps
0.5	220	0.2000	6.71		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
0.5	110	0.0500	3.35		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
0.1	40	0.0100	7.20	28.80	Pipe Channel,
					24.0" x 24.0" Box Area= 4.0 sf Perim= 8.0' r= 0.50'
					n= 0.013 Concrete pipe, bends & connections
0.3	140	0.2000	6.71		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps

19.7 1,490 Total

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 27

Subcatchment PRE 3:



NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 28

# Summary for Subcatchment PRE 4:

Runoff 30.6 cfs @ 12.12 hrs, Volume= 3.009 af, Depth= 6.94" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area (	ac) C	N Dese	cription			
2.0	000 9	8 Pave	ed parking	HSG C		
0.7	700 9	6 Grav	vel surface	, HSG C		
0.8	300 7	′4 >75°	% Grass co	over, Good	, HSG C	
0.1	8 00	30 >75°	% Grass co	over, Good	, HSG D	
0.4	100 7	'0 Woo	ods, Good,	HSG C		
1.2	200 7	'2 Woo	ods/grass o	omb., Goo	d, HSG C	
5.2	200 8	6 Weig	ghted Aver	age		
3.2	200	61.5	4% Pervio	us Area		
2.0	000	38.4	6% Imperv	vious Area		
_				-		
TC	Length	Slope	Velocity	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
7.4	100	0.1000	0.22		Sheet Flow,	
					Grass: Dense n= 0.240 P2= 3.27"	
1.8	260	0.1200	2.42		Shallow Concentrated Flow,	
					Short Grass Pasture Kv= 7.0 fps	
0.5	190	0.1000	6.42		Shallow Concentrated Flow,	
					Paved Kv= 20.3 fps	
1.3	270	0.0500	3.35		Shallow Concentrated Flow,	
					Grassed Waterway Kv= 15.0 tps	
1.0	180	0.0200	2.87		Shallow Concentrated Flow,	
					Paved Kv= 20.3 tps	
12.0	1,000	Total				

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 29

Subcatchment PRE 4:



NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 30

# Summary for Subcatchment PRE 5:

Runoff 123.3 cfs @ 12.65 hrs, Volume= 22.835 af, Depth= 5.86" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

	Area (a	ac) C	N Des	cription					
	6.0	000 9	8 Pav	ed parking	, HSG C				
	0.4	900	6 Grav	Gravel surface, HSG C					
	1.6	600 S	98 Wat	Vater Surface, HSG D					
	9.2	200 7	′4 >75°	% Grass co	over, Good	, HSG C			
	10.0	000 7	'1 Mea	dow, non-g	grazed, HS	GC			
	9.1	00 7	'0 Woo	ods, Good,	HSG C				
	1.0	000 7	'2 Woo	ods/grass o	comb., Goo	d, HSG C			
	8.8	300 7	77 Woo	ods, Good,	HSG D				
_	0.7	700 E	<u> </u>	% Grass co	over, Good	, HSG D			
	46.8	300 7	7 Wei	ghted Aver	age				
	39.2	200	83.7	6% Pervio	us Area				
	7.6	600	16.2	4% Imperv	vious Area				
	Tc	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	18.6	100	0.0100	0.09		Sheet Flow,			
						Grass: Dense n= 0.240 P2= 3.27"			
	4.3	770	0.0400	3.00		Shallow Concentrated Flow,			
						Grassed Waterway Kv= 15.0 fps			
	1.8	110	0.0400	1.00		Shallow Concentrated Flow,			
						Woodland Kv= 5.0 fps			
	23.1	980	0.0200	0.71		Shallow Concentrated Flow,			
						Woodland Kv= 5.0 fps			
	0.5	430		13.90		Lake or Reservoir,			
						Mean Depth= 6.00'			
	2.4	730	0.0200	4.98	29.90	Channel Flow,			
						Area= 6.0 st Perim= 10.0' r= 0.60'			
_						n= 0.030 Earth, grassed & winding			
		0 1 0 0	Tatal						

50.7 3,120 I otal

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 5/11/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 31



Subcatchment PRE 5:

## APPENDIX C Post Development Computer Data



NY - DPD 24-hr S1 1-yr Rainfall=2.71" Printed 9/29/2023

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 2

# Summary for Subcatchment 1.0S:

Runoff 2.8 cfs @ 12.23 hrs, Volume= 0.406 af, Depth= 0.45" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Des	cription		
1.	500 7	74 >75	% Grass co	over, Good	, HSG C
1.:	200 7	71 Mea	dow, non-g	grazed, HS	GC
5.	100 7	70 Woo	ods, Good,	HSG C	
0.	500 7	72 Woo	ods/grass o	comb., Goo	d, HSG C
2.	200 క	55 Woo	ods, Good,	HSG B	
0.4	400 6	61 >75°	% Grass co	over, Good	, HSG B
10.9	900 6	67 Weig	ghted Aver	age	
10.9	900	100.	00% Pervi	ous Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.9	100	0.0150	0.15		Sheet Flow,
					Grass: Short n= 0.150 P2= 3.27"
1.1	225	0.0500	3.35		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
1.6	162	0.1100	1.66		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.5	90	0.3000	2.74		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
2.3	840	0.0300	6.10	36.62	Channel Flow,
					Area= 6.0 sf Perim= 10.0' r= 0.60'
					n= 0.030 Earth, grassed & winding
16.4	1,417	Total			

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 3

Subcatchment 1.0S:



NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 4

# Summary for Subcatchment 2.0S:

Runoff 0.8 cfs @ 12.22 hrs, Volume= 0.116 af, Depth= 0.45" =

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Des	cription		
1.100 70 Woods, Good, HSG C				HSG C	
1.100 74 >75% Grass cover, Good, HSG C				, HSG C	
0.700 55 Woods, Good, HSG B				HSG B	
0.200 61 >75% Grass cover, Good, HSG B					, HSG B
3.	100	67 Wei	ghted Aver	rage	
3.	100	100	.00% Pervi	ous Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.7	100	0.1100	0.16		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
3.4	285	0.0800	1.41		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
1.0	150	0.2500	2.50		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.7	250	0.0250	5.80	23.19	Channel Flow,
					Area= 4.0 sf Perim= 10.0' r= 0.40'
					n= 0.022 Earth, clean & straight
15.8	785	Total			

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 5

Subcatchment 2.0S:



# Summary for Subcatchment 3.0S:

Runoff = 2.5 cfs @ 12.22 hrs, Volume= 0.292 af, Depth= 0.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

_	Area (	ac) C	N Des	scription		
	0.6	600 9	98 Pav	ved parking	, HSG C	
1.400 74 >75% Grass cover, Good, HSG C						, HSG C
2.400 70 Woods, Good, HSG C						
0.200 55 Woods, Good, HSG B						
0.100 61 >75% Grass cover, Good, HSG B						
_	0.1	100 8	30 >75	5% Grass c	over, Good	, HSG D
	4.8	300	74 We	ighted Ave	rage	
	4.2	200	87.	50% Pervio	us Area	
	0.6	600	12.	50% Imperv	vious Area	
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	14.7	100	0.0500	0.11		Sheet Flow,
	14.7	100	0.0500	0.11		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27"
	14.7 1.3	100 140	0.0500 0.1200	0.11 0.173		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow,
	14.7 1.3	100 140	0.0500	0.11	17.04	Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps
	14.7 1.3 0.2	100 140 40	0.0500 0.1200 0.0250	0.11 0.173 0.25	17.01	Sheet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow,
	14.7 1.3 0.2	100 140 40	0.0500 0.1200 0.0250	0.11 1.73 4.25	17.01	Sheet Flow, Woods: Light underbrush $n=0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' p=0.020 Forth grapped 8 winding
	14.7 1.3 0.2	100 140 40	0.0500 0.1200 0.0250	0 0.11 1.73 4.25	17.01	Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow
	14.7 1.3 0.2 1.1	100 140 40 360	0.0500 0.1200 0.0250 0.1400	0.11 1.73 4.25 5.61	17.01	Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway, Kv= 15.0 fpc
	14.7 1.3 0.2 1.1	100 140 40 360	0.0500 0.1200 0.0250 0.1400	0.11 1.73 4.25 5.61	17.01	Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow
	14.7 1.3 0.2 1.1 0.7	100 140 40 360 190	0.0500 0.1200 0.0250 0.1400 0.0250	<ul> <li>0.11</li> <li>1.73</li> <li>4.25</li> <li>5.61</li> <li>4.25</li> </ul>	17.01	Sheet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40'
	14.7 1.3 0.2 1.1 0.7	100 140 40 360 190	0.0500 0.1200 0.0250 0.1400 0.0250	<ul> <li>0.11</li> <li>1.73</li> <li>4.25</li> <li>5.61</li> <li>4.25</li> </ul>	17.01 17.01	Sheet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth grassed & winding
	14.7 1.3 0.2 1.1 0.7	100 140 40 360 190	0.0500 0.1200 0.0250 0.1400 0.0250	0.11 1.73 4.25 5.61 4.25	17.01	Sheet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 7

Subcatchment 3.0S:



## Summary for Subcatchment 3.1S:

Runoff = 5.9 cfs @ 12.13 hrs, Volume= 0.521 af, Depth= 1.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Des	cription			
2.	200 9	98 Pav	ed parking	, HSG C		
2.	000	74 >75	% Grass c	over, Good,	HSG C	
4.200 87 Weighted Average						
2.	000	47.6	2% Pervio	us Area		
2.	200	52.3	8% Imperv	vious Area		
Tc	Length	Slope	Velocity	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
10.4	100	0.1200	0.16		Sheet Flow,	
					Woods: Light underbrush n= 0.400 P2= 3.27"	
0.2	80	0.1500	5.81		Shallow Concentrated Flow,	
					Grassed Waterway Kv= 15.0 fps	
2.4	720	0.0100	4.91	3.86	Pipe Channel,	
					12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'	
					n= 0.012	
13.0	900	Total				

# Subcatchment 3.1S:



## Summary for Subcatchment 4.0S:

Runoff = 5.0 cfs @ 12.06 hrs, Volume= 0.352 af, Depth= 1.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

_	Area (	ac) (	CN	Desc	ription				
_	1.4	400	98	Pave	d parking,	HSG C			
	1.1	100	74	>75%	>75% Grass cover, Good, HSG C				
	0.0	300	80	>75%	>75% Grass cover, Good, HSG D				
	0.5	500	72	Wood	ds/grass c	omb., Goo	d, HSG C		
	3.0	300	84	Weig	hted Aver	age			
	1.9	900		57.58	3% Pervio	us Area			
	1.4	400		42.42	2% Imperv	vious Area			
	Тс	Length	S	lope	Velocity	Capacity	Description		
_	(min)	(feet)	(	ft/ft)	(ft/sec)	(cfs)			
	5.1	100	0.1	000	0.33		Sheet Flow,		
							Grass: Short n= 0.150 P2= 3.27"		
	2.5	700	0.1	000	4.74		Shallow Concentrated Flow,		
_							Grassed Waterway Kv= 15.0 fps		
	7.6	800	To	tal					

## Subcatchment 4.0S:



## Summary for Subcatchment 4.1S:

Runoff = 1.1 cfs @ 12.04 hrs, Volume= 0.075 af, Depth= 1.80"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"



## Summary for Subcatchment 5.0S:

Runoff = 17.2 cfs @ 12.69 hrs, Volume= 3.276 af, Depth= 0.93"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area (a	c)	CN	Desc	ription						
6.00	00	98	Pave	Paved parking, HSG C						
1.60	00	98	Wate	Water Surface, HSG D						
8.90	00	74	>75%	6 Grass co	over, Good	, HSG C				
7.30	00	71	Mead	dow, non-g	grazed, HS	GC				
8.70	00	70	Woo	ds, Good,	HSG C					
1.00	00	72	Woo	ds/grass c	comb., Goo	d, HSG C				
8.70	0	77	Woo	ds, Good,	HSG D					
0.20	0	80	>75%	6 Grass co	over, Good	, HSG D				
42.40	00	78	Weig	hted Aver	age					
34.80	4.800 82.08% Pervious Area									
7.60	00	0 17.92% Impervious Area								
Tc L	.ength	n i	Slope	Velocity	Capacity	Description				
(min)	(feet	)	(ft/ft) (ft/sec) (cfs)							
50.7						Direct Entry,				

## Subcatchment 5.0S:



## Summary for Subcatchment 5.1S:

Runoff = 8.4 cfs @ 12.09 hrs, Volume= 0.661 af, Depth= 1.80"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 1-yr Rainfall=2.71"

Area	(ac) C	N Des	cription						
3.100 98		98 Pav	Paved parking, HSG D						
1.300 74		74 >75	>75% Grass cover, Good, HSG C						
4.400 9		91 Wei	ghted Aver	rage					
1.	300	29.5	55% Pervious Area						
3.	100	70.4	5% Imperv	vious Area					
T.	المربع مرالم	Olaraa	Mala altri	0	Description				
IC (mine)	Length	Siope	Velocity	Capacity	Description				
(min)	(leel)	(11/11)	(IL/Sec)	(CIS)					
8.2	100	0.0300	0.20		Sheet Flow,				
					Grass: Short n= 0.150 P2= 3.27"				
0.1	40	0.2000	6.71		Shallow Concentrated Flow,				
					Grassed Waterway Kv= 15.0 fps				
0.3	120	0.1500	7.86		Shallow Concentrated Flow,				
					Paved Kv= 20.3 fps				
1.0	400	0.0100	6.44	11.38	Pipe Channel,				
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'				
					n= 0.012				



# Subcatchment 5.1S:

Hydrograph


## Summary for Reach DP 1: Design Point 1

Inflow /	Area	ι =	1	0.900 ac,	0.00% Impe	ervious,	Inflow D	)epth =	0.45	5" for 1	l-yr e∖	/ent
Inflow		=		2.8 cfs @	12.23 hrs,	Volume	∋=	0.406	af			
Outflov	V	=		2.8 cfs @	12.23 hrs,	Volume	9=	0.406	af,	Atten= 0	%, La	ag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## Reach DP 1: Design Point 1

## Summary for Reach DP 2: Design Point 2

Inflow A	Area	=	3.100 ac,	0.00% Impe	ervious,	Inflow Depth	= 0.4	5" for 1	-yr event
Inflow	=	=	0.8 cfs @	12.22 hrs,	Volume	e= 0.1	16 af		
Outflow	/ =	=	0.8 cfs @	12.22 hrs,	Volume	e= 0.1	16 af,	Atten= 0%	%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 2: Design Point 2**

# Summary for Reach DP 3: Design Point 3

Inflow Are	ea =	9.000 ac, 3	1.11% Impervious,	Inflow Depth = 0.3	39" for 1-yr event
Inflow	=	2.5 cfs @	12.22 hrs, Volum	e= 0.292 af	
Outflow	=	2.5 cfs @	12.22 hrs, Volum	e= 0.292 af,	Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 3: Design Point 3**

## Summary for Reach DP 4: Design Point 4

Inflow Are	ea =	3.800 ac, 4	4.74% Impervious,	Inflow Depth = 1.3	5" for 1-yr event
Inflow	=	5.1 cfs @	12.07 hrs, Volume	e= 0.429 af	
Outflow	=	5.1 cfs @	12.07 hrs, Volume	e= 0.429 af,	Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## Reach DP 4: Design Point 4

## Summary for Reach DP 5: Design Point 5

Inflow A	rea =	46.800 ac, 2	2.86% Imper	vious, In	flow Depth =	0.84	4" for 1-yr event
Inflow	=	17.2 cfs @	12.69 hrs, \	Volume=	3.276	af	
Outflow	=	17.2 cfs @	12.69 hrs, \	Volume=	3.276	af,	Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2

#### Hydrograph 19 - Inflow 18 17.2 cfs Outflow 17 Inflow Area=46.800 ac 16-15 14 13 12 11 (cfs) 10-Flow 9-8-7-6-5-4-3-2 1 0-5 15 20 25 30 35 40 45 50 65 70 75 80 85 90 95 100 105 110 115 120 Ó 10 55 60 Time (hours)

## **Reach DP 5: Design Point 5**

## Summary for Pond 1.4 FS: Flow Splitter

Inflow Area =	0.500 ac, 6	0.00% Impervious,	Inflow Depth = 1.8	0" for 1-yr event
Inflow =	0.8 cfs @	12.17 hrs, Volume	= 0.075 af	
Outflow =	0.8 cfs @	12.17 hrs, Volume	= 0.075 af,	Atten= 0%, Lag= 0.0 min
Primary =	0.8 cfs @	12.17 hrs, Volume	= 0.075 af	
Secondary =	0.2 cfs @	12.11 hrs, Volume	= 0.001 af	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.46' @ 12.17 hrs Flood Elev= 608.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	607.00'	<b>12.0" Vert. Orifice/Grate</b> C= 0.600
#2	Device 3	607.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00
			Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	604.50'	15.0" Round Culvert
			L= 20.0' CPP, square edge headwall, Ke= 0.500
			Inlet / Outlet Invert= 604.50' / 604.00' S= 0.0250 '/' Cc= 0.900 n= 0.120, Flow Area= 1.23 sf

Primary OutFlow Max=0.8 cfs @ 12.17 hrs HW=607.45' TW=606.61' (Dynamic Tailwater) **1=Orifice/Grate** (Orifice Controls 0.8 cfs @ 2.29 fps)

Secondary OutFlow Max=0.0 cfs @ 12.11 hrs HW=607.43' TW=0.00' (Dynamic Tailwater) 3=Culvert (Passes 0.0 cfs of 2.3 cfs potential flow) 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 19



Pond 1.4 FS: Flow Splitter

#### Summary for Pond 3.1AP: Pretreatment Basin

Inflow Area =	4.200 ac, 52.38% Impervious, Inflow De	pth = 1.49" for 1-yr event
Inflow =	5.9 cfs @ 12.13 hrs, Volume=	0.521 af
Outflow =	1.1 cfs @ 12.48 hrs, Volume=	0.521 af, Atten= 82%, Lag= 21.0 min
Primary =	1.1 cfs @ 12.48 hrs, Volume=	0.521 af
Secondary =	0.0 cfs @ 0.00 hrs, Volume=	0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.82' @ 12.75 hrs Surf.Area= 4,267 sf Storage= 6,529 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 155.5 min (1,005.9 - 850.4)

Volume	Invert	Avail.Stor	age Storage I	Description		
#1	606.00'	24,35	0 cf Custom	Stage Data (Pri	<b>ismatic)</b> Listed below (Reca	lc)
Elevatio (fee	on Su st)	rf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)		
606.0 608.0 610.0 611.0	00 00 00 00	2,900 4,400 6,100 7,000	0 7,300 10,500 6,550	0 7,300 17,800 24,350		
Device	Routing	Invert	Outlet Devices	3		
#1	Device 3	608.00'	<b>1.0' long x 0.5</b> Head (feet) 0. Coef. (English	<b>5' breadth Broa</b> 20 0.40 0.60 ) 2.80 2.92 3.0	<b>Id-Crested Rectangular We</b> 0.80 1.00 08 3.30 3.32	ir
#2	Primary	605.50'	6.0" Round C L= 40.0' CPP Inlet / Outlet In n= 0.012, Flow	<b>, square edge h</b> v, square edge h vert= 605.50' / w Area= 0.20 sf	neadwall, Ke= 0.500 605.00' S= 0.0125 '/' Cc=	0.900
#3	Secondary	605.50'	<b>24.0'' Round</b> L= 50.0' CPP Inlet / Outlet In n= 0.012, Flow	<b>Culvert</b> /, square edge h nvert= 605.50' / w Area= 3.14 sf	neadwall, Ke= 0.500 604.00' S= 0.0300 '/' Cc=	0.900
Primary	OutFlow Ma	ax=1.1 cfs @	12.48 hrs HW	=607.72' TW=6	605.72' (Dynamic Tailwater	)

**2=Culvert** (Outlet Controls 1.1 cfs @ 5.54 fps)

Secondary OutFlow Max=0.0 cfs @ 0.00 hrs HW=606.00' TW=0.00' (Dynamic Tailwater) 3=Culvert (Passes 0.0 cfs of 1.5 cfs potential flow) 1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C.Printed 9/29/2023HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLCPage 21

Hydrograph 5.9 cfs Inflow 6- Outflow – Primary Inflow Area=4.200 ac Secondary 5-Peak Elev=607.82' Storage=6,529 cf 4 Flow (cfs) 3-2 1.1 cfs 1 0.0 cfs 0-5 10 15 20 25 30 35 40 45 50 70 75 80 85 90 95 100 105 110 115 120 Ò 55 60 65 Time (hours)

Pond 3.1AP: Pretreatment Basin

## Summary for Pond 3.1P: Infiltration Basin

Inflow Area	. =	4.200 ac, 5	2.38% Impe	ervious, li	nflow Depth =	1.4	9" for	1-yr e	event	
Inflow	=	1.1 cfs @	12.48 hrs,	Volume=	= 0.521	af				
Outflow	=	0.3 cfs @	17.37 hrs,	Volume=	= 0.521	af,	Atten=	77%,	Lag= 2	93.0 min
Discarded	=	0.3 cfs @	17.37 hrs,	Volume=	= 0.521	af			-	
Primary	=	0.0 cfs @	0.00 hrs,	Volume=	= 0.000	) af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.01' @ 17.37 hrs Surf.Area= 5,464 sf Storage= 8,743 cf

Plug-Flow detention time= 400.1 min calculated for 0.521 af (100% of inflow) Center-of-Mass det. time= 400.1 min (1,406.0 - 1,005.9)

Volume	Invert	Avail.Sto	rage Storage	Description		
#1	605.00	34,80	00 cf Custom	Stage Data (Pr	ismatic) Listed be	elow (Recalc)
Elevatio	on S	urf.Area	Inc.Store	Cum.Store		
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)		
605.0	00	3,300	0	0		
606.0	00	4,300	3,800	3,800		
608.0	00	6,600	10,900	14,700		
610.0	00	9,000	15,600	30,300		
610.5	50	9,000	4,500	34,800		
Device	Routing	Invert	Outlet Device	S		
#1	Device 2	609.20'	2.5' long x 0.	.5' breadth Broa	ad-Crested Recta	ngular Weir X 2.00
			Head (feet) C	0.20 0.40 0.60	0.80 1.00	5
			Coef. (English	n) 2.80 2.92 3.	08 3.30 3.32	
#2	Primary	603.00'	15.0" Round	Culvert		
			L= 50.0' CPI	P, square edge l	headwall, Ke= 0.	500
			Inlet / Outlet I	nvert= 603.00' /	602.00' S= 0.02	200 '/' Cc= 0.900
			n= 0.012, Flo	ow Area= 1.23 st	İ	
#3	Discarded	605.00'	2.000 in/hr Ex	xfiltration over l	Horizontal area	Phase-In= 0.01'

**Discarded OutFlow** Max=0.3 cfs @ 17.37 hrs HW=607.01' (Free Discharge) **-3=Exfiltration** (Exfiltration Controls 0.3 cfs)

Primary OutFlow Max=0.0 cfs @ 0.00 hrs HW=605.00' TW=0.00' (Dynamic Tailwater) 2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) 1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023

Page 23



Pond 3.1P: Infiltration Basin

## Summary for Pond 4.1AP1: Wet Swale

Inflow Area	.= 0.50	0 ac, 60.	00% Impervious,	Inflow Depth =	1.80" for 1-y	r event
Inflow	= 1.1	cfs @ 1	2.04 hrs, Volum	e= 0.07	5 af	
Outflow	= 0.8	cfs @ 1	2.17 hrs, Volum	e= 0.07	5 af, Atten= 30%	6. Lag= 7.8 min
Primary	= 0.2	cfs @ 1	2.32 hrs. Volum	e= 0.05	5 af	, 0
Secondary	= 0.7	cfs @ 1	2.16 hrs. Volum	e= 0.020	) af	
<b>,</b>	-		,			
Routina by	Dvn-Stor-Ind	method.	Time Span= 0.00	-120.00 hrs. dt=	0.05 hrs / 2	
Starting Ele	ev= 607.00' \$	Surf.Area	= 950 sf Storage	e= 1.438 cf		
Peak Elev=	607.59' @ 1	2.12 hrs	Surf.Area= 1.120	6 sf Storage= 2	.045 cf (608 cf	above start)
	c c	-	,		,	
Plua-Flow of	detention time	e 312.1 n	nin calculated for	0.042 af (56% o	of inflow)	
Center-of-M	lass det. time	e= 50.0 mi	in ( 872.5 - 822.5	)	- /	
			(	1		
Volume	Invert	Avail Stor	rade Storade D	escription		
1 0101110	IIIVOIL	/ Wuii.0101	luge ololuge D	cooription		
#1	604.50'	2,53	B8 cf Custom S	Stage Data (Pris	matic) Listed bel	low (Recalc)
#1	604.50'	2,53	38 cf Custom S	Stage Data (Pris	natic) Listed bel	low (Recalc)
#1 Elevation	604.50' Surf.A	2,53 rea	38 cf Custom S	Cum.Store	natic) Listed bel	low (Recalc)
#1 Elevation (feet)	604.50' Surf.A	2,53 rea q-ft)	Bacf Custom S Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	natic) Listed bel	low (Recalc)
#1 Elevation (feet) 604.50	604.50' Surf.A (sc	2,53 rea <u>q-ft)</u> 200	B8 cf <b>Custom S</b> Inc.Store (cubic-feet) 0	Cum.Store (cubic-feet) 0	natic) Listed bel	ow (Recalc)
#1 Elevation (feet) 604.50 608.00	604.50' Surf.A (sc	2,53 rea <u>a-ft)</u> 200 250	B8 cf <b>Custom S</b> Inc.Store (cubic-feet) 0 2,538	Cum.Store (cubic-feet) 0 2,538	natic) Listed bel	ow (Recalc)
#1 Elevation (feet) 604.50 608.00	604.50' Surf.A (sc 1,2	2,53 rea <u>q-ft)</u> 200 250	Ba cf <b>Custom S</b> Inc.Store (cubic-feet) 0 2,538	Cum.Store (cubic-feet) 0 2,538	natic) Listed bel	ow (Recalc)
#1 Elevation (feet) 604.50 608.00 Device Re	604.50' Surf.A (sc 1,; outing	2,53 rea <u>q-ft)</u> 200 250 Invert	Ba cf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices	Cum.Store (cubic-feet) 0 2,538	natic) Listed bel	low (Recalc)
#1 Elevation (feet) 604.50 608.00 Device Re #1 Pi	604.50' Surf.A (sc 1,2 outing rimarv	2,53 rea <u>q-ft)</u> 200 250 <u>Invert</u> 607.00'	Ba cf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices 4.0" Vert. Orific	Cum.Store (cubic-feet) 0 2,538	natic) Listed be	low (Recalc)
#1 Elevation (feet) 604.50 608.00 Device Ro #1 Pr #2 Se	604.50' Surf.A (so 1,2 outing rimary econdary	2,53 rea a-ft) 200 250 Invert 607.00' 607.30'	Ba cf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices 4.0" Vert. Orific 4.0' long x 0.5'	Cum.Store (cubic-feet) 0 2,538 ce/Grate C= 0.	natic) Listed bel 600 Crested Rectar	low (Recalc)
#1 Elevation (feet) 604.50 608.00 Device Re #1 Pr #2 Se	604.50' Surf.A (sc 1,2 outing rimary econdary	2,53 200 250 <u>Invert</u> 607.00' 607.30'	Bacf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices 4.0'' Vert. Orific 4.0' long x 0.5' Head (feet) 0.2	Cum.Store (cubic-feet) 0 2,538 ce/Grate C= 0. breadth Broad	natic) Listed bel 600 Crested Rectar 30 1.00	low (Recalc) ngular Weir
#1 Elevation (feet) 604.50 608.00 Device Re #1 Pt #2 Se	604.50' Surf.A (sc 1,2 outing rimary econdary	2,53 rea <u>a-ft)</u> 200 250 <u>Invert</u> 607.00' 607.30'	Ba cf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices 4.0'' Vert. Orific 4.0' long x 0.5' Head (feet) 0.2 Coef. (English)	Cum.Store   (cubic-feet)   0   2,538   ce/Grate C= 0.   breadth Broad   20 0.40 0.60 0.   2,80 2.92 3.06	600 <b>Crested Rectar</b> 30 1.00	low (Recalc) ngular Weir
#1 Elevation (feet) 604.50 608.00 Device Ri #1 Pr #2 Se	604.50' Surf.A (so 1,i outing rimary econdary	2,53 rea <u>a-ft)</u> 200 250 <u>Invert</u> 607.00' 607.30'	Ba cf Custom S Inc.Store (cubic-feet) 0 2,538 Outlet Devices 4.0'' Vert. Orific 4.0' long x 0.5' Head (feet) 0.2 Coef. (English)	Cum.Store   (cubic-feet)   0   2,538   ce/Grate C= 0.   breadth Broad   20 0.40 0.60 0.   2.80 2.92 3.08	600 <b>Crested Rectar</b> 30 1.00 3.30 3.32	low (Recalc) ngular Weir

Primary OutFlow Max=0.1 cfs @ 12.32 hrs HW=607.40' TW=607.36' (Dynamic Tailwater) 1=Orifice/Grate (Orifice Controls 0.1 cfs @ 0.87 fps)

Secondary OutFlow Max=1.2 cfs @ 12.16 hrs HW=607.56' TW=607.45' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 1.2 cfs @ 1.16 fps)

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 25





#### Summary for Pond 4.1BP: Bioretention

Inflow Are	a =	0.500 ac, 60.00% l	mpervious, Inflow De	epth = 1.80" f	or 1-yr event
Inflow	=	0.8 cfs @ 12.17 l	nrs, Volume=	0.075 af	
Outflow	=	0.1 cfs @ 13.37 l	nrs, Volume=	0.075 af, Atter	n= 88%, Lag= 71.9 min
Primary	=	0.1 cfs @ 13.37 l	nrs, Volume=	0.075 af	-

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 606.75' @ 13.37 hrs Surf.Area= 4,204 sf Storage= 1,045 cf

Plug-Flow detention time= 86.0 min calculated for 0.075 af (100% of inflow) Center-of-Mass det. time= 86.0 min (958.5 - 872.5)

Volume	Invert	Avail.Stor	rage Storage D	escription					
#1	606.50'	4,40	00 cf Custom S	stage Data (Prisma	atic) Listec	below (Recalc)			
Elevation (feet)	Si	urf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)					
606.50 607.50		4,000 4,800	4,400	4,400					
Device F	Routing	Invert	Outlet Devices						
#1 [ #2 [ #3 F	Device 3 Device 3 Primary	606.50' 607.10' 603.00'	<b>1.000 in/hr Exfi</b> <b>12.0'' Vert. Orif</b> <b>8.0'' Round Cu</b> L= 10.0' CPP, Inlet / Outlet Inv n= 0.013 Corru	Itration over Surfa ice/Grate C= 0.6 Ilvert square edge head vert= 603.00' / 602. Igated PE, smooth	<b>ace area</b> 600 Iwall, Ke= .70' S= 0. interior, F	Phase-In= 0.01' 0.500 .0300 '/' Cc= 0.900 Flow Area= 0.35 sf			
Primary OutFlow Max=0.1 cfs @ 13.37 hrs HW=606.75' TW=0.00' (Dynamic Tailwater)									

-3=Culvert (Passes 0.1 cfs of 3.1 cfs potential flow)

-1=Exfiltration (Exfiltration Controls 0.1 cfs)

2=Orifice/Grate (Controls 0.0 cfs)

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 27



Time (hours)

#### Pond 4.1BP: Bioretention

#### Summary for Pond 5.1AP: Pretreatment Basin

Inflow Area	=	4.400 ac, 7	0.45% Impe	ervious, Inflow	Depth =	1.80"	for	1-yr e	vent		
Inflow =	=	8.4 cfs @	12.09 hrs,	Volume=	0.661	af					
Outflow =	=	1.4 cfs @	12.66 hrs,	Volume=	0.661	af, A	tten= 8	34%,	Lag= 3	34.1 mii	n
Primary =	=	1.4 cfs @	12.66 hrs,	Volume=	0.661	af			-		
Secondary =	=	0.0 cfs @	0.00 hrs,	Volume=	0.000	af					

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 658.21' @ 12.66 hrs Surf.Area= 5,381 sf Storage= 8,599 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 51.3 min (877.1 - 825.8)

Volume	Invert	Avail.Stor	rage Storage	Description							
#1	656.00'	40,30	0 cf Custom	Stage Data (Pri	ismatic) Listed below (Recalc)						
Elevatior	n Su	rf.Area	Inc.Store	Cum.Store							
(feet	)	(sq-ft)	(cubic-feet)	(cubic-feet)							
656.00	)	2,500	0	0							
658.00	)	5,000	7,500	7,500							
660.00	)	8,600	13,600	21,100							
662.00		10,600	19,200	40,300							
Device	Routing	Invert	Outlet Device	S							
#1 Device 3 659.30'		2.5' long x 0	.5' breadth Broa	d-Crested Rectangular Weir X 2.00							
			Head (feet) (	0.20 0.40 0.60	0.80 1.00						
			Coef. (English) 2.80 2.92 3.08 3.30 3.32								
#2	Primary	655.50'	6.0" Round Culvert								
			L= 30.0' CP	P, square edge h	neadwall, Ke= 0.500						
			Inlet / Outlet I	nvert= 655.50' /	655.00' S= 0.0167 '/' Cc= 0.900						
			n= 0.012, Flo	ow Area= 0.20 sf							
#3	Secondary	657.50'	30.0" Round	Culvert							
			L= 100.0' Cl	PP, square edge	headwall, Ke= 0.500						
			Inlet / Outlet Invert= 657.50' / 656.50' S= 0.0100 '/' Cc= 0.900								
			n= 0.012, Flo	ow Area= 4.91 sf							
Primary (		av_1 / cfe @	12.66 brs HM	/_658 21' TW_6	55 29' (Dynamic Tailwater)						
¹ −2=Cul	<b>Primary OutFlow</b> Max=1.4 cfs @ 12.66 hrs HW=658.21' TW=655.29' (Dynamic Tailwater) <b>2=Culvert</b> (Barrel Controls 1.4 cfs @ 7.04 fps)										

Secondary OutFlow Max=0.0 cfs @ 0.00 hrs HW=656.00' TW=0.00' (Dynamic Tailwater) -3=Culvert (Controls 0.0 cfs)

1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 29



Pond 5.1AP: Pretreatment Basin

## Summary for Pond 5.1P: Infiltration Basin

Inflow Area	ι =	4.400 ac, 70	0.45% Impe	rvious,	Inflow	Depth =	1.8	0" for	1-yr e	event		
Inflow	=	1.4 cfs @	12.66 hrs,	Volume	)=	0.661	af					
Outflow	=	0.5 cfs @	16.85 hrs,	Volume	)=	0.661	af,	Atten=	65%,	Lag= 2	251.4 m	nin
Discarded	=	0.5 cfs @	16.85 hrs,	Volume	)=	0.661	af			-		
Primary	=	0.0 cfs @	0.00 hrs,	Volume	)=	0.000	af					

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 656.04' @ 16.85 hrs Surf.Area= 10,573 sf Storage= 10,215 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 195.9 min (1,073.0 - 877.1)

Volume	Inver	t Avail.Sto	rage Storage	Description				
#1	655.00	' 64,95	50 cf Custom	Stage Data (Pr	ismatic) Listed below (Recalc)			
Elevation Surf		urf.Area	Inc.Store	Cum.Store				
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)				
655.00		9,000	0	0				
656.00		10,500	9,750	9,750				
660.0	00	17,100	55,200	64,950				
Device	Routing	Invert	Outlet Device	S				
#1	Device 2	659.00'	<b>4.0' long x 0.</b> Head (feet) C Coef. (English	<b>5' breadth Broa</b> 0.20 0.40 0.60 n) 2.80 2.92 3.	ad-Crested Rectangular Weir X 2.00 0.80 1.00 .08 3.30 3.32			
#2	#2 Primary 653.00		<b>15.0" Round Culvert</b> L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 653.00' / 652.50' S= 0.0500 '/' Cc= 0.900					
#3	Discarded	655.00'	2.000 in/hr Ex	cfiltration over	Horizontal area			

**Discarded OutFlow** Max=0.5 cfs @ 16.85 hrs HW=656.04' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 0.5 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=655.00' TW=0.00' (Dynamic Tailwater) -2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) -1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 1-yr Rainfall=2.71" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023

Page 31



Pond 5.1P: Infiltration Basin

## Summary for Subcatchment 1.0S:

Runoff = 14.1 cfs @ 12.19 hrs, Volume= 1.550 af, Depth= 1.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (	ac) C	N Desc	cription		
1.5	500 7	′4 >75°	% Grass co	over, Good	, HSG C
1.2	200 7	'1 Mea	dow, non-g	grazed, HS	GC
5.1	100 7	'0 Woo	ds, Good,	HSG C	
0.5	500 7	'2 Woo	ds/grass d	omb., Goo	d, HSG C
2.2	200 5	5 Woo	ds, Good,	HSG B	
0.4	400 6	51 >759	% Grass co	over, Good	, HSG B
10.9	900 6	7 Weig	ghted Aver	age	
10.9	900	100.	00% Pervi	ous Area	
Тс	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.9	100	0.0150	0.15		Sheet Flow,
					Grass: Short n= 0.150 P2= 3.27"
1.1	225	0.0500	3.35		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
1.6	162	0.1100	1.66		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.5	90	0.3000	2.74		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
2.3	840	0.0300	6.10	36.62	Channel Flow,
					Area= 6.0 sf Perim= 10.0' r= 0.60'
					n= 0.030 Earth, grassed & winding
16.4	1,417	Total			

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 33

Subcatchment 1.0S:



## Summary for Subcatchment 2.0S:

Runoff = 4.1 cfs @ 12.18 hrs, Volume= 0.441 af, Depth= 1.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (	(ac) C	N Des	cription		
1.	100	70 Wo	ods, Good,	HSG C	
1.	100	74 >75	% Grass c	over, Good,	, HSG C
0.	700	55 Wo	ods, Good,	HSG B	
0.3	200 (	61 >75	% Grass c	over, Good,	, HSG B
3.	100 (	67 We	ghted Aver	rage	
3.	100	100	.00% Pervi	ous Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.7	100	0.1100	0.16		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
3.4	285	0.0800	1.41		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
1.0	150	0.2500	2.50		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.7	250	0.0250	5.80	23.19	Channel Flow,
					Area= 4.0 sf Perim= 10.0' r= 0.40'
					n= 0.022 Earth, clean & straight
15.8	785	Total			

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 35

Subcatchment 2.0S:



## Summary for Subcatchment 3.0S:

Runoff = 8.2 cfs @ 12.21 hrs, Volume= 0.901 af, Depth= 2.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

71100	(ac) C	N Des	cription		
0.	600 9	98 Pav	ed parking	, HSG C	
1.	400	74 >75	% Grass c	over, Good,	HSG C
2.	400	70 Woo	ods, Good,	HSG C	
0.	200 క	55 Woo	ods, Good,	HSG B	
0.	100 6	51 >75	% Grass co	over, Good,	HSG B
0.	100 8	<u>30 &gt;75</u>	% Grass co	over, Good,	HSG D
4.	800	74 Wei	ghted Aver	age	
4.	200	87.5	0% Pervio	us Area	
0.	600	12.5	0% Imperv	vious Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
14 7	100		0 1 1		Chaot Flour
	100	0.0500	0.11		Sneet Flow,
,	100	0.0500	0.11		Woods: Light underbrush n= 0.400 P2= 3.27"
1.3	140	0.1200	1.73		Sneet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow,
1.3	140	0.1200	1.73		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps
1.3 0.2	140 40	0.0300 0.1200 0.0250	1.73 4.25	17.01	Woods: Light underbrush n= 0.400 P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow,
1.3 0.2	140 40	0.0300 0.1200 0.0250	1.73 4.25	17.01	Sneet Flow, Woods: Light underbrush $n= 0.400 P2= 3.27"$ Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40'
1.3 0.2	140 40	0.0300	1.73 4.25	17.01	Sneet Flow, Woods: Light underbrush $n= 0.400 P2= 3.27"$ Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding
1.3 0.2 1.1	140 40 360	0.0300 0.1200 0.0250 0.1400	1.73 4.25 5.61	17.01	Sneet Flow, Woods: Light underbrush $n= 0.400 P2= 3.27"$ Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Output Waterprovide 15.0 for
1.3 0.2 1.1	140 40 360	0.0300 0.1200 0.0250 0.1400	1.73 4.25 5.61	17.01	Sneet Flow,Woods: Light underbrush n= 0.400 P2= 3.27"Shallow Concentrated Flow,Woodland Kv= 5.0 fpsChannel Flow,Area= 4.0 sf Perim= 10.0' r= 0.40'n= 0.030 Earth, grassed & windingShallow Concentrated Flow,Grassed Waterway Kv= 15.0 fpsObserved Flow,
1.3 0.2 1.1 0.7	140 40 360 190	0.0300 0.1200 0.0250 0.1400 0.0250	1.73 4.25 5.61 4.25	17.01 17.01	Sneet Flow, Woods: Light underbrush $n= 0.400 P2= 3.27"$ Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area 4.0 sf Perim 10.0' r= 0.40'
1.3 0.2 1.1 0.7	140 40 360 190	0.1200 0.0250 0.1400 0.0250	1.73 4.25 5.61 4.25	17.01 17.01	Sneet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' p= 0.020 Earth grassed & winding
1.3 0.2 1.1 0.7	140 40 360 190	0.0300 0.1200 0.0250 0.1400 0.0250	1.73 4.25 5.61 4.25	17.01 17.01	Sneet Flow, Woods: Light underbrush $n= 0.400$ P2= 3.27" Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps Channel Flow, Area= 4.0 sf Perim= 10.0' r= 0.40' n= 0.030 Earth, grassed & winding

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 37

Subcatchment 3.0S:



#### Summary for Subcatchment 3.1S:

Runoff = 12.7 cfs @ 12.13 hrs, Volume= 1.202 af, Depth= 3.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area	(ac) C	N Des	cription		
2.2	200	98 Pav	ed parking	, HSG C	
2.	000	74 >75 [°]	% Grass c	over, Good,	HSG C
4.	200	87 Wei	ghted Avei	rage	
2.	000	47.6	2% Pervio	us Area	
2.	200	52.3	8% Imperv	vious Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.4	100	0.1200	0.16		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
0.2	80	0.1500	5.81		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
2.4	720	0.0100	4.91	3.86	Pipe Channel,
					12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'
					n= 0.012
13.0	900	Total			

#### Subcatchment 3.1S:



#### Summary for Subcatchment 4.0S:

Runoff = 11.4 cfs @ 12.06 hrs, Volume= 0.864 af, Depth= 3.14"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

	Area (	ac) (	CN	Desc	ription		
	1.4	100	98	Pave	d parking	, HSG C	
	1.1	00	74	>75%	6 Grass co	over, Good	, HSG C
	0.3	300	80	>75%	6 Grass co	over, Good	, HSG D
	0.5	500	72	Wood	ds/grass c	comb., Goo	d, HSG C
	3.3	300	84	Weig	hted Aver	age	
	1.9	900		57.58	3% Pervio	us Area	
	1.4	100		42.42	2% Imperv	vious Area	
	Тс	Length	S	lope	Velocity	Capacity	Description
_	(min)	(feet)	(	ft/ft)	(ft/sec)	(cfs)	
	5.1	100	0.1	000	0.33		Sheet Flow,
							Grass: Short n= 0.150 P2= 3.27"
	2.5	700	0.1	000	4.74		Shallow Concentrated Flow,
_							Grassed Waterway Kv= 15.0 fps
	7.6	800	То	tal			

#### Subcatchment 4.0S:



#### Summary for Subcatchment 4.1S:

Runoff = 2.2 cfs @ 12.04 hrs, Volume= 0.160 af, Depth= 3.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"



#### Summary for Subcatchment 5.0S:

Runoff = 50.3 cfs @ 12.67 hrs, Volume= 9.163 af, Depth= 2.59"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

Area (ac)	CN	Description							
6.000	98	Paved parking, HSG C							
1.600	98	Water Surface, HSG D							
8.900	74	>75% Grass cover, Good, HSG C							
7.300	71	Meadow, non-grazed, HSG C							
8.700	70	Woods, Good, HSG C							
1.000	72	2 Woods/grass comb., Good, HSG C							
8.700	0 77 Woods, Good, HSG D								
0.200	0.200 80 >75% Grass cover, Good, HSG D								
42.400	78	Weighted Average							
34.800		82.08% Pervious Area							
7.600		17.92% Impervious Area							
Tc Len	gth S	lope Velocity Capacity Description							
(min) (fe	et)	(ft/ft) (ft/sec) (cfs)							
50.7		Direct Entry,							

#### Subcatchment 5.0S:



#### Summary for Subcatchment 5.1S:

Runoff = 16.4 cfs @ 12.09 hrs, Volume= 1.410 af, Depth= 3.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 10-yr Rainfall=4.86"

	Area	(ac) C	N Des	cription		
	3.	100	98 Pav	ed parking	, HSG D	
_	1.	300	/4 >/5	% Grass co	over, Good	, HSG C
	4.	400 9	91 Wei	ghted Aver	rage	
	1.	300	29.5	5% Pervio	us Area	
	3.	100	70.4	5% Imperv	vious Area	
	•			e / ep e		
	Тс	Lenath	Slope	Velocitv	Capacity	Description
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	8.2	100	0.0300	0.20		Sheet Flow,
						Grass: Short n= 0.150 P2= 3.27"
	0.1	40	0.2000	6.71		Shallow Concentrated Flow,
						Grassed Waterway Kv= 15.0 fps
	0.3	120	0.1500	7.86		Shallow Concentrated Flow.
						Paved Kv= 20.3 fps
	1.0	400	0.0100	6.44	11.38	Pipe Channel.
						18.0" Bound Area= 1.8 sf Perim= 4.7' r= 0.38'
						n= 0.012
	9.6	660	Total			

660 Total

## Subcatchment 5.1S:

Hydrograph



## Summary for Reach DP 1: Design Point 1

Inflow A	Area	ι =	10.900 ac,	0.00% Imper	vious,	Inflow Depth =	1.7	1" for 10-y	vr event
Inflow		=	14.1 cfs @	12.19 hrs, \	Volume	= 1.550	) af		
Outflov	N	=	14.1 cfs @	12.19 hrs, \	Volume	= 1.550	) af,	Atten= 0%,	Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## Reach DP 1: Design Point 1

# Summary for Reach DP 2: Design Point 2

Inflow A	Area	=	3.100 ac,	0.00% Impe	rvious,	Inflow Dept	h = 1.7	71" for	10-yr event	
Inflow		=	4.1 cfs @	12.18 hrs,	Volume	e= 0	.441 af			
Outflow	/	=	4.1 cfs @	12.18 hrs,	Volume	e= 0	.441 af,	Atten=	0%, Lag= 0.0	0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 2: Design Point 2**

## Summary for Reach DP 3: Design Point 3

Inflow Are	a =	9.000 ac, 31	1.11% Imperviou	us, Inflow Depth =	1.67"	' for 10-y	r event
Inflow	=	11.8 cfs @	12.26 hrs, Volu	ume= 1.25	2 af		
Outflow	=	11.8 cfs @	12.26 hrs, Volu	ume= 1.25	2 af, A	Atten= 0%,	Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 3: Design Point 3**

## Summary for Reach DP 4: Design Point 4

Inflow A	rea =	3.800 ac, 4	4.74% Impervious, I	nflow Depth = 3.2	4" for 10-yr event
Inflow	=	11.9 cfs @	12.06 hrs, Volume=	= 1.026 af	
Outflow	=	11.9 cfs @	12.06 hrs, Volume=	= 1.026 af,	Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 4: Design Point 4**

## Summary for Reach DP 5: Design Point 5

Inflow Ar	ea =	46.800 ac, 2	2.86% Impervious,	Inflow Depth = 2.3	39" for 10-yr event
Inflow	=	52.8 cfs @	12.64 hrs, Volume	e= 9.327 af	
Outflow	=	52.8 cfs @	12.64 hrs, Volume	e= 9.327 af,	Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## **Reach DP 5: Design Point 5**

## Summary for Pond 1.4 FS: Flow Splitter

Inflow Area =	=	0.500 ac, 60	0.00% Impe	rvious,	Inflow Dep	oth =	3.85"	for 10-y	/r event
Inflow =	:	2.0 cfs @	12.10 hrs,	Volume	=	0.160	af		
Outflow =	:	2.0 cfs @	12.10 hrs,	Volume	=	0.160	af, At	tten= 0%,	Lag= 0.0 min
Primary =	:	1.4 cfs @	12.10 hrs,	Volume	=	0.153	af		
Secondary =	:	0.6 cfs @	12.10 hrs,	Volume	=	0.008	af		

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.64' @ 12.10 hrs Flood Elev= 608.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	607.00'	<b>12.0" Vert. Orifice/Grate</b> C= 0.600
#2	Device 3	607.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00
			Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	604.50'	15.0" Round Culvert
			L= 20.0' CPP, square edge headwall, Ke= 0.500
			Inlet / Outlet Invert= 604.50' / 604.00' S= 0.0250 '/' Cc= 0.900
			n= 0.120, Flow Area= 1.23 sf

Primary OutFlow Max=1.4 cfs @ 12.10 hrs HW=607.64' TW=606.76' (Dynamic Tailwater) **1=Orifice/Grate** (Orifice Controls 1.4 cfs @ 2.71 fps)

Secondary OutFlow Max=0.6 cfs @ 12.10 hrs HW=607.64' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 0.6 cfs of 2.4 cfs potential flow) -2=Broad-Crested Rectangular Weir (Weir Controls 0.6 cfs @ 1.03 fps)
NY - DPD 24-hr S1 10-yr Rainfall=4.86" Printed 9/29/2023

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 49



Pond 1.4 FS: Flow Splitter

#### Summary for Pond 3.1AP: Pretreatment Basin

Inflow Area =	4.200 ac, 52.38% Impervious, Inflow	Depth = 3.44" for 10-yr event
Inflow =	12.7 cfs @ 12.13 hrs, Volume=	1.202 af
Outflow =	6.0 cfs @ 12.38 hrs, Volume=	1.202 af, Atten= 53%, Lag= 14.7 min
Primary =	1.3 cfs @ 12.32 hrs, Volume=	0.851 af
Secondary =	4.6 cfs @ 12.38 hrs, Volume=	0.351 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 609.25' @ 12.38 hrs Surf.Area= 5,464 sf Storage= 13,473 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 186.1 min (1,006.6 - 820.5)

Volume	Invert	Avail.Stor	age Storage [	Description		
#1	606.00'	24,35	0 cf Custom	Stage Data (Pri	i <b>smatic)</b> Listed below (Recalc)	
Elevatior (feet)	n Su	rf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)		
606.00 608.00 610.00 611.00	) ) )	2,900 4,400 6,100 7,000	0 7,300 10,500 6,550	0 7,300 17,800 24,350		
Device	Routing	Invert	Outlet Devices	i		
#1	Device 3	608.00'	<b>1.0' long x 0.5</b> Head (feet) 0.1 Coef. (English)	<b>5' breadth Broa</b> 20 0.40 0.60 ( ) 2.80 2.92 3.0	d-Crested Rectangular Weir 0.80 1.00 08 3.30 3.32	
#2	Primary	605.50'	6.0" Round C L= 40.0' CPP Inlet / Outlet In n= 0.012, Flow	<b>ulvert</b> , square edge h vert= 605.50' / 6 v Area= 0.20 sf	neadwall, Ke= 0.500 605.00' S= 0.0125 '/' Cc= 0.900	
#3	Secondary	605.50'	<b>24.0'' Round (</b> L= 50.0' CPP Inlet / Outlet In n= 0.012, Flow	<b>Culvert</b> , square edge h vert= 605.50' / 6 v Area= 3.14 sf	neadwall, Ke= 0.500 604.00' S= 0.0300 '/' Cc= 0.900	
Primary (	DutFlow Ma	ax=1.3 cfs @	12.32 hrs HW=	=609.23' TW=6	606.30' (Dynamic Tailwater)	

**1−2=Culvert** (Outlet Controls 1.3 cfs @ 6.70 fps)

Secondary OutFlow Max=4.6 cfs @ 12.38 hrs HW=609.25' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 4.6 cfs of 25.1 cfs potential flow) **1=Broad-Crested Rectangular Weir** (Weir Controls 4.6 cfs @ 3.71 fps)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 51

Pond 3.1AP: Pretreatment Basin



# Summary for Pond 3.1P: Infiltration Basin

Inflow Area	=	4.200 ac, 5	2.38% Impe	rvious,	Inflow I	Depth =	2.43	3" for	10-yr	event	
Inflow	=	1.3 cfs @	12.32 hrs,	Volume	∋=	0.851	af				
Outflow	=	0.3 cfs @	21.57 hrs,	Volume	∋=	0.851	af,	Atten=	77%,	Lag= 5	55.0 mir
Discarded	=	0.3 cfs @	21.57 hrs,	Volume	∋=	0.851	af			-	
Primary	=	0.0 cfs @	0.00 hrs,	Volume	<del>)</del> =	0.000	af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.88' @ 21.57 hrs Surf.Area= 6,458 sf Storage= 13,894 cf

Plug-Flow detention time= 534.1 min calculated for 0.851 af (100% of inflow) Center-of-Mass det. time= 534.1 min (1,631.1 - 1,097.0)

Volume	Invert	Avail.Sto	rage Storage	Description		
#1	605.00	34,80	00 cf Custom	Stage Data (Pr	ismatic) Listed b	elow (Recalc)
Flovatio	n S	urf Area	Inc Store	Cum Store		
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)		
605.0	00	3,300	0	0		
606.0	00	4,300	3,800	3,800		
608.0	00	6,600	10,900	14,700		
610.0	00	9,000	15,600	30,300		
610.5	50	9,000	4,500	34,800		
Device	Routing	Invert	Outlet Device	S		
#1	Device 2	609.20'	2.5' long x 0.	.5' breadth Broa	ad-Crested Recta	angular Weir X 2.00
			Head (feet) 0	0.20 0.40 0.60	0.80 1.00	
			Coef. (English	n) 2.80 2.92 3.	.08 3.30 3.32	
#2	Primary	603.00'	15.0" Round	Culvert		
			L= 50.0' CPI	P, square edge l	headwall, Ke= 0.	500
			Inlet / Outlet I	nvert= 603.00' /	$602.00^{\circ}$ S= 0.02	200% Cc= 0.900
#0	Discorded	COE 00'	n = 0.012, FIO	W Area= 1.23 Si	l Harizantal area	Bhase In 0.01
#3	Discarded	605.00	2.000 In/nr E)	killtration over I	norizontal area	Phase-in= 0.01
<b>D</b> :					···· <b>D'</b> ···· · · · · · · · · · · · · · · · · ·	

**Discarded OutFlow** Max=0.3 cfs @ 21.57 hrs HW=607.88' (Free Discharge) **-3=Exfiltration** (Exfiltration Controls 0.3 cfs)

Primary OutFlow Max=0.0 cfs @ 0.00 hrs HW=605.00' TW=0.00' (Dynamic Tailwater) 2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) 1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 53

Pond 3.1P: Infiltration Basin



## Summary for Pond 4.1AP1: Wet Swale

Inflow Area	= 0.500 ac,	60.00% Imperviou	is, Inflow Depth = 3.85	5" for 10-yr event
Inflow =	= 2.2 cfs (	@ 12.04 hrs, Volu	ime= 0.160 af	-
Outflow =	= 2.0 cfs (	a 12.10 hrs, Volu	ime= 0.160 af,	Atten= 8%, Lag= 3.4 min
Primary =	= 0.2 cfs (	0 12.27 hrs. Volu	me= 0.100 af	, <b>G</b>
Secondary =	= 1.9 cfs (	@ 12.10 hrs Volu	ime= 0.061 af	
cocorridary				
Routing by [	Ovn-Stor-Ind meth	od Time Span- 0	00-120 00 brs dt= 0.05	hrs/2
Starting Elev	v = 607 00' Surf /	$\Delta r_{02} = 950 \text{ sf}$ Store	$a_{00} = 1.438 \text{ cf}$	
Poak Elov-	607 7 <i>1</i> ' @ 12 07	hre Surf Aroa $1.1$	72  sf Storage 2.224	of (786 of above start)
I Eak LIEV-	007.74 @ 12.07	IIIS JUII.AIGa- I,	172 SI Storage= 2,224	
Plug Flow d	otoption time_ 19	2.5 min coloulated	for 0 127 of (70% of infl	
Contor of M	elenilon line= 10	2.5 min calculated	101 0.127 al (79% 01 11110	Jvv)
Center-oi-w	ass det. time= 35	. 1 mm ( 831.3 - 796	0.2)	
	Louise Arros		Decemintics	
volume	Invert Avai	I.Storage Storage	Description	
#1	604.50'	2,538 cf <b>Custom</b>	n Stage Data (Prismatic	) Listed below (Recalc)
Elevation	Surf.Area	Inc.Store	Cum.Store	
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)	
604.50	200	0	0	
608.00	1.250	2.538	2.538	
	- ,	_,	_,	
Device Ro	outina In	vert Outlet Device	s	
#1 Pri	mary 607	00' 40" Vert Or	ifice/Grate C-0.600	
#2 So	nary 607	30' <b>10' long v 0</b>	5' breadth Broad-Cres	ted Bectangular Weir
#2 36		Upped (fact) (		
			J.20 $0.40$ $0.60$ $0.60$ $1$	
		Coer. (Englis	1) 2.80 2.92 3.08 3.30	J 3.32
<b>D</b> : 0				
Primary Ou	triow Max=0.0 c	ts@12.27 hrs HV	V=607.47 IW=607.51	(Dynamic Tailwater)

**1=Orifice/Grate** (Controls 0.0 cfs)

Secondary OutFlow Max=2.1 cfs @ 12.10 hrs HW=607.73' TW=607.63' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 2.1 cfs @ 1.21 fps)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Printed 9/29/2023

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 55



Pond 4.1AP1: Wet Swale

#### Summary for Pond 4.1BP: Bioretention

Inflow Area	. =	0.500 ac,	60.00% Impe	ervious,	Inflow	Depth =	3.68	8" for	10-yr	event	
Inflow	=	1.4 cfs @	2 12.10 hrs,	Volume	<del>)</del> =	0.153	af				
Outflow	=	0.1 cfs @	2 14.30 hrs,	Volume	<del>9</del> =	0.153	af,	Atten=	92%,	Lag= 13	2.2 min
Primary	=	0.1 cfs @	2 14.30 hrs,	Volume	9=	0.153	af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.13' @ 14.30 hrs Surf.Area= 4,508 sf Storage= 2,700 cf

Plug-Flow detention time= 242.8 min calculated for 0.153 af (100% of inflow) Center-of-Mass det. time= 242.8 min (1,078.8 - 836.0)

Volume	Inve	ert Avail.Sto	rage Storag	je Description	_
#1	606.5	0' 4,40	00 cf Custor	m Stage Data (Prismatic) Listed below (Recalc)	
Elevatio (fee 606.5	on et) 50	Surf.Area (sq-ft) 4,000 4 800	Inc.Store (cubic-feet) 0 4 400	Cum.Store (cubic-feet) 0 4 400	
Device	Routing	Invert	Outlet Devic	ces	
#1 #2 #3	Device 3 Device 3 Primary	606.50' 607.10' 603.00'	1.000 in/hr E 12.0" Vert. ( 8.0" Round L= 10.0' CF Inlet / Outlet n= 0.013 Co	Exfiltration over Surface area Phase-In= 0.01' Orifice/Grate C= 0.600 J Culvert PP, square edge headwall, Ke= 0.500 t Invert= 603.00' / 602.70' S= 0.0300 '/' Cc= 0.900 corrugated PE, smooth interior, Flow Area= 0.35 sf	

**Primary OutFlow** Max=0.1 cfs @ 14.30 hrs HW=607.13' TW=0.00' (Dynamic Tailwater) **3=Culvert** (Passes 0.1 cfs of 3.3 cfs potential flow) **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

**2=Orifice/Grate** (Orifice Controls 0.0 cfs @ 0.63 fps)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 57

Pond 4.1BP: Bioretention



#### Summary for Pond 5.1AP: Pretreatment Basin

Inflow Area =	4.400 ac, 70.45% Imperviou	s, Inflow Depth = 3.85"	for 10-yr event
Inflow =	16.4 cfs @ 12.09 hrs, Volu	me= 1.410 af	
Outflow =	5.3 cfs @ 12.41 hrs, Volu	me= 1.410 af, A	tten= 67%, Lag= 19.1 min
Primary =	1.7 cfs @ 12.39 hrs, Volu	me= 1.246 af	
Secondary =	3.6 cfs @ 12.41 hrs, Volu	me= 0.164 af	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 659.69' @ 12.41 hrs Surf.Area= 8,048 sf Storage= 18,547 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 112.9 min ( 912.4 - 799.5 )

Volume	Invert	Avail.Stor	age Storage	e Description		
#1	656.00'	40,30	0 cf Custom	n Stage Data (Pr	rismatic) Listed below (Recalc)	
Elevatio (fee	n Sı t)	urf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)		
656.0 658.0 660.0	0	2,500 5,000 8,600	0 7,500 13,600	0 7,500 21,100		
Device	Routing	Invert	Outlet Device	40,300 es		
#1	Device 3	659.30'	<b>2.5' long x 0</b> Head (feet) (	<b>.5' breadth Broa</b> 0.20 0.40 0.60 b) 2.80 2.92 3	ad-Crested Rectangular Weir X 2.0 0.80 1.00 08 3 30 3 32	0
#2	Primary	655.50'	6.0" Round L= 30.0' CP Inlet / Outlet	<b>Culvert</b> P, square edge I Invert= 655.50' /	headwall, Ke= 0.500 '655.00' S= 0.0167 '/' Cc= 0.900	
#3	Secondary	657.50'	n= 0.012, Flo 30.0" Round L= 100.0' C Inlet / Outlet n= 0.012, Flo	ow Area= 0.20 st <b>1 Culvert</b> PP, square edge Invert= 657.50' / ow Area= 4.91 st	f e headwall, Ke= 0.500 ' 656.50' S= 0.0100 '/' Cc= 0.900 f	
Drimory		lav_1 7 ofc @	10.20 bro UM	V_650 60' TW_4	655 48' (Dynamic Tailwator)	

Primary OutFlow Max=1.7 cfs @ 12.39 hrs HW=659.69' TW=655.48' (Dynamic Tailwater) -2=Culvert (Barrel Controls 1.7 cfs @ 8.76 fps)

Secondary OutFlow Max=3.6 cfs @ 12.41 hrs HW=659.69' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 3.6 cfs of 23.0 cfs potential flow) -1=Broad-Crested Rectangular Weir (Weir Controls 3.6 cfs @ 1.83 fps)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 59

Hydrograph 18 16.4 cfs Inflow 17 Outflow 16 – Primary Inflow Area=4.400 ac Secondary 15 14 Peak Elev=659.69' 13 Storage=18,547 cf 12 11 Flow (cfs) 10-9-8-7-5.3 cfs 6-5-3.6 cfs 4-3-1.7 cfs 2 1 0-10 15 20 25 30 35 40 45 50 55 60 65 70 75 80 85 90 95 100 105 110 115 120 5 Ó

Time (hours)

#### Pond 5.1AP: Pretreatment Basin

#### Summary for Pond 5.1P: Infiltration Basin

Inflow Area	ι =	4.400 ac, 70	0.45% Impe	ervious,	Inflow	Depth =	3.40	D" for	10-yr	event	
Inflow	=	1.7 cfs @	12.39 hrs,	Volume	)=	1.246	af				
Outflow	=	0.6 cfs @	20.05 hrs,	Volume	)=	1.246	af,	Atten=	67%,	Lag= 45	9.5 min
Discarded	=	0.6 cfs @	20.05 hrs,	Volume	}=	1.246	af				
Primary	=	0.0 cfs @	0.00 hrs,	Volume	)=	0.000	af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 657.00' @ 20.05 hrs Surf.Area= 12,143 sf Storage= 21,024 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 369.4 min (1,302.6 - 933.2)

Volume	Invert	t Avail.Sto	rage Storage	e Description						
#1	655.00	64,95	50 cf Custon	n Stage Data (Pr	ismatic) Listed below (Recalc)					
Elevatio	on S	urf.Area	Inc.Store	Cum.Store						
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)						
655.0	00	9,000	0	0						
656.0	00	10,500	9,750	9,750						
660.0	00	17,100	55,200	64,950						
Device	Routing	Invert	Outlet Device	es						
#1	Device 2	659.00'	<b>4.0' long x (</b> Head (feet) Coef. (Englis	<b>D.5' breadth Broa</b> 0.20 0.40 0.60 sh) 2.80 2.92 3.	ad-Crested Rectangular Weir X 2.00 0.80 1.00 08 3.30 3.32					
#2	Primary	653.00'	<b>15.0" Round</b> L= 10.0' CF Inlet / Outlet	Coef. (English) 2.80 2.92 3.08 3.30 3.32 <b>I5.0" Round Culvert</b> _= 10.0' CPP, square edge headwall, Ke= 0.500 nlet / Outlet Invert= 653.00' / 652.50' S= 0.0500 '/' Cc= 0.900						
#3	Discarded	655.00'	2.000 in/hr E	Exfiltration over	Horizontal area					

**Discarded OutFlow** Max=0.6 cfs @ 20.05 hrs HW=657.00' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 0.6 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=655.00' TW=0.00' (Dynamic Tailwater) -2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) -1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 10-yr Rainfall=4.86" Printed 9/29/2023 Page 61

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC



Pond 5.1P: Infiltration Basin

#### Summary for Subcatchment 1.0S:

Runoff = 38.9 cfs @ 12.19 hrs, Volume= 4.223 af, Depth= 4.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area (	<u>ac) C</u>	N Dese	cription			
1.5	500 7	′4 >75°	% Grass co	over, Good,	HSG C	
1.2	200 7	'1 Mea	dow, non-g	grazed, HS	GC	
5.1	100 7	'0 Woo	ods, Good,	HSG C		
0.5	500 7	'2 Woo	ods/grass o	omb., Goo	d, HSG C	
2.2	200 5	5 Woo	ods, Good,	HSG B		
0.4	400 6	51 >75 <u>9</u>	% Grass co	over, Good,	HSG B	
10.9	900 6	7 Weig	ghted Aver	age		
10.9	900	100.	00% Pervi	ous Area		
Tc	Length	Slope	Velocity	Capacity	Description	
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
10.9	100	0.0150	0.15		Sheet Flow,	
					Grass: Short n= 0.150 P2= 3.27"	
1.1	225	0.0500	3.35		Shallow Concentrated Flow,	
					Grassed Waterway Kv= 15.0 fps	
1.6	162	0.1100	1.66		Grassed Waterway Kv= 15.0 fps Shallow Concentrated Flow,	
1.6	162	0.1100	1.66		Grassed Waterway Kv= 15.0 fps Shallow Concentrated Flow, Woodland Kv= 5.0 fps	
1.6 0.5	162 90	0.1100 0.3000	1.66 2.74		Grassed Waterway Kv= 15.0 fps Shallow Concentrated Flow, Woodland Kv= 5.0 fps Shallow Concentrated Flow,	
1.6 0.5	162 90	0.1100 0.3000	1.66 2.74		Grassed Waterway Kv= 15.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps	
1.6 0.5 2.3	162 90 840	0.1100 0.3000 0.0300	1.66 2.74 6.10	36.62	Grassed Waterway Kv= 15.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps <b>Channel Flow,</b>	
1.6 0.5 2.3	162 90 840	0.1100 0.3000 0.0300	1.66 2.74 6.10	36.62	Grassed Waterway Kv= 15.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps <b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps <b>Channel Flow,</b> Area= 6.0 sf Perim= 10.0' r= 0.60'	
1.6 0.5 2.3	162 90 840	0.1100 0.3000 0.0300	1.66 2.74 6.10	36.62	Grassed Waterway Kv= 15.0 fps Shallow Concentrated Flow, Woodland Kv= 5.0 fps Shallow Concentrated Flow, Woodland Kv= 5.0 fps Channel Flow, Area= 6.0 sf Perim= 10.0' r= 0.60' n= 0.030 Earth, grassed & winding	

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 63

Subcatchment 1.0S:



#### Summary for Subcatchment 2.0S:

Runoff = 11.3 cfs @ 12.17 hrs, Volume= 1.201 af, Depth= 4.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area (	(ac) C	N Des	cription		
1.	100	70 Woo	ods, Good,	HSG C	
1.	100	74 >75	% Grass co	over, Good,	, HSG C
0.	700	55 Woo	ods, Good,	HSG B	
0.3	200	61 >75	% Grass co	over, Good,	, HSG B
3.	100	67 Wei	ghted Aver	age	
3.	100	100	.00% Pervi	ous Area	
Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
10.7	100	0.1100	0.16		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.27"
3.4	285	0.0800	1.41		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
1.0	150	0.2500	2.50		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
0.7	250	0.0250	5.80	23.19	Channel Flow,
					Area= 4.0 sf Perim= 10.0' r= 0.40'
					n= 0.022 Earth, clean & straight
15.8	785	Total			

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 65

Hydrograph 12-- Runoff 11.3 cfs 11 NY - DPD 24-hr S1 100-yr 10 Rainfall=8.63" 9 Runoff Area=3.100 ac 8-Runoff Volume=1.201 af Flow (cfs) 7-Runoff Depth=4.65" 6 Flow Length=785' 5-Tc=15.8 min 4-CN=67 3-2 1 0-5 15 20 25 30 35 40 45 50 55 60 65 70 75 80 85 90 95 100 105 110 115 120 10 Ó Time (hours)

#### Subcatchment 2.0S:

#### Summary for Subcatchment 3.0S:

Runoff = 19.5 cfs @ 12.20 hrs, Volume= 2.197 af, Depth= 5.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area	(ac) (	CN E	Desci	ription		
0.	600	98 F	ave	d parking,	HSG C	
1.	400	74 >	75%	Grass co	over, Good,	HSG C
2.	400	70 V	Vooc	ds, Good,	HSG C	
0.	200	55 V	Vooc	ds, Good,	HSG B	
0.	100	61 >	75%	Grass co	over, Good,	, HSG B
0.	100	80 >	75%	Grass co	over, Good,	HSG D
4.	800	74 V	Veig	hted Aver	age	
4.	200	8	7.50	% Pervio	us Area	
0.	600	1	2.50	)% Imperv	vious Area	
Tc	Length	Slo	ре	Velocity	Capacity	Description
(min)	(feet)	(ft/	/ft)	(ft/sec)	(cfs)	
14.7	100	0.05	00	0.11		Sheet Flow,
						Woods: Light underbrush n= 0.400 P2= 3.27"
1.3	140	0.12	00	1.73		Shallow Concentrated Flow,
						Woodland Kv= 5.0 fps
0.2	40	0.02	50	4.25	17.01	Channel Flow,
						Area= 4.0 sf Perim= 10.0' r= 0.40'
						n= 0.030 Earth, grassed & winding
1.1	360	0.14	00	5.61		Shallow Concentrated Flow,
07	100	0.00	50	4.05	17.01	Grassed Waterway Kv= 15.0 fps
0.7	190	0.02	50	4.25	17.01	Channel Flow,
						Area = 4.0 st Perim = $10.0^{\circ}$ r = $0.40^{\circ}$
						n= 0.030 Earth, grassed & Winding
18.0	830	Tota				

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 67

Subcatchment 3.0S:



#### Summary for Subcatchment 3.1S:

Runoff 24.0 cfs @ 12.13 hrs, Volume= 2.472 af, Depth= 7.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area	(ac) C	N Des	cription						
2.2	200 9	98 Pav	ed parking	, HSG C					
2.	000	74 >75	% Grass co	over, Good,	HSG C				
4.3	4.200 87 Weighted Average								
2.000 47.62% Pervious Area									
2.	200	52.3	8% Imperv	vious Area					
				_					
Tc	Length	Slope	Velocity	Capacity	Description				
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
10.4	100	0.1200	0.16		Sheet Flow,				
					Woods: Light underbrush n= 0.400 P2= 3.27"				
0.2	80	0.1500	5.81		Shallow Concentrated Flow,				
					Grassed Waterway Kv= 15.0 fps				
2.4	720	0.0100	4.91	3.86	Pipe Channel,				
					12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'				
					n= 0.012				
13.0	900	Total							

#### Subcatchment 3.1S:



#### Summary for Subcatchment 4.0S:

Runoff = 22.2 cfs @ 12.06 hrs, Volume= 1.843 af, Depth= 6.70"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

	Area (	(ac)	CN	Desc	ription		
_	1.4	400	98	Pave	d parking,	HSG C	
	1.	100	74	>75%	6 Grass co	over, Good	, HSG C
	0.3	300	80	>75%	6 Grass co	over, Good	, HSG D
_	0.	500	72	Woo	ds/grass c	omb., Goo	d, HSG C
	3.:	300	84	Weig	hted Aver	age	
	1.9	900		57.58	3% Pervio	us Area	
	1.4	400		42.42	2% Imperv	vious Area	
	Тс	Length	n S	Slope	Velocity	Capacity	Description
_	(min)	(feet)	)	(ft/ft)	(ft/sec)	(cfs)	
	5.1	100	0.	1000	0.33		Sheet Flow,
							Grass: Short n= 0.150 P2= 3.27"
	2.5	700	) 0.	1000	4.74		Shallow Concentrated Flow,
_							Grassed Waterway Kv= 15.0 fps
	7.6	800	) To	otal			

#### Subcatchment 4.0S:



#### Summary for Subcatchment 4.1S:

Runoff = 3.8 cfs @ 12.04 hrs, Volume= 0.314 af, Depth= 7.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"



#### Summary for Subcatchment 5.0S:

Runoff = 113.8 cfs @ 12.65 hrs, Volume= 21.116 af, Depth= 5.98"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area (a	IC)	CN	Desc	ription			
6.0	00	98	Pave	d parking	, HSG C		
1.6	00	98	Wate	er Surface	, HSG D		
8.9	00	74	>75%	6 Grass co	over, Good,	, HSG C	
7.3	00	71	Mead	dow, non-g	grazed, HS0	GC	
8.7	00	70	Woo	ds, Good,	HSG C		
1.0	00	72	Woo	ds/grass o	comb., Goo	d, HSG C	
8.7	00	77	Woo	ds, Good,	HSG D		
0.2	00	80	>75%	6 Grass co	over, Good,	, HSG D	
42.4	00	78	Weig	hted Aver	age		
34.8	00		82.08	3% Pervio	us Area		
7.6	00		17.92	2% Imperv	vious Area		
					<b>.</b> .		
TC I	_engtl	h :	Slope	Velocity	Capacity	Description	
(min)	(teet	.)	(†t/†t)	(ft/sec)	(cts)		
50.7						Direct Entry,	

#### Subcatchment 5.0S:



#### Summary for Subcatchment 5.1S:

Runoff = 29.2 cfs @ 12.09 hrs, Volume= 2.767 af, Depth= 7.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs NY - DPD 24-hr S1 100-yr Rainfall=8.63"

Area	(ac) C	N Des	cription		
3.	100	98 Pav	ed parking	, HSG D	
1.	300	74 >75	% Grass c	over, Good	, HSG C
4.	400	91 Wei	ghted Avei	age	
1.	300	29.5	5% Pervio	us Area	
3.	100	70.4	5% Imperv	vious Area	
т.	ما الديم مع ا	Olaraa	Valas!tr.	0	Description
IC (mine)	Length	Siope	Velocity	Capacity	Description
(min)	(leet)	(11/11)	(IL/Sec)	(CIS)	
8.2	100	0.0300	0.20		Sheet Flow,
					Grass: Short n= 0.150 P2= 3.27"
0.1	40	0.2000	6.71		Shallow Concentrated Flow,
					Grassed Waterway Kv= 15.0 fps
0.3	120	0.1500	7.86		Shallow Concentrated Flow,
					Paved Kv= 20.3 fps
1.0	400	0.0100	6.44	11.38	Pipe Channel,
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.012



#### Subcatchment 5.1S:

Hydrograph



## Summary for Reach DP 1: Design Point 1

Inflow /	Area	. =	10.900 ac,	0.00% Impervious,	Inflow Depth = 4	4.65" for	100-yr event
Inflow		=	38.9 cfs @	12.19 hrs, Volum	e= 4.223 a	af	
Outflov	N	=	38.9 cfs @	12.19 hrs, Volum	e= 4.223 a	af, Atten= (	0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2

#### Hydrograph 42 - Inflow 38.9 cfs 40 Outflow 38-Inflow Area=10.900 ac 36 34 32 30 28 26-(cts) 22-22-20-10 18-16-14 12 10-8-6-4-2 0-5 15 20 25 30 35 45 50 70 75 80 95 100 105 110 115 120 Ó 10 40 55 60 65 85 90 Time (hours)

## **Reach DP 1: Design Point 1**

## Summary for Reach DP 2: Design Point 2

Inflow A	Area	=	3.100 ac,	0.00% Impe	rvious,	Inflow Depth :	= 4.6	5" for 10	00-yr event	
Inflow	:	=	11.3 cfs @	12.17 hrs,	Volume	e= 1.20	01 af			
Outflow	/ :	=	11.3 cfs @	12.17 hrs,	Volume	e= 1.20	01 af,	Atten= 0%	%, Lag= 0.0 min	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



#### Reach DP 2: Design Point 2

### Summary for Reach DP 3: Design Point 3

Inflow Area	a =	9.000 ac, 3	1.11% Impe	rvious,	Inflow Depth	= 4.94	4" for 10	00-yr event
Inflow	=	33.4 cfs @	12.23 hrs,	Volume	e= 3.7	'04 af		
Outflow	=	33.4 cfs @	12.23 hrs,	Volume	e= 3.7	'04 af,	Atten= 0%	b, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2



## Reach DP 3: Design Point 3

### Summary for Reach DP 4: Design Point 4

Inflow Are	a =	3.800 ac, 44	4.74% Impe	rvious,	Inflow Depth	= 6.8	1" for 100	)-yr event
Inflow	=	23.9 cfs @	12.06 hrs,	Volume	= 2.	158 af		
Outflow	=	23.9 cfs @	12.06 hrs,	Volume	e= 2.1	158 af,	Atten= 0%,	Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2

15

0 5 10

20 25

30 35

45

50 55 60 65

40

#### Hydrograph 26 - Inflow 25 23.9 cfs Outflow 24 23-Inflow Area=3.800 ac 22 21 20 19 18 17 16 15-14-Flow (cfs) 13 12-11 10-9 8-7-6-5-4-3-2 1 0

Time (hours)

70 75

80 85 90

95 100 105 110 115 120

# Reach DP 4: Design Point 4

## Summary for Reach DP 5: Design Point 5

Inflow Are	a =	46.800 ac, 22	2.86% Impervious	Inflow Depth =	5.66" for	100-yr event
Inflow	=	120.4 cfs @	12.62 hrs, Volum	ie= 22.080 a	af	
Outflow	=	120.4 cfs @	12.62 hrs, Volum	ie= 22.080 a	af, Atten=	0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2

# Reach DP 5: Design Point 5



#### Summary for Pond 1.4 FS: Flow Splitter

Inflow Area =	=	0.500 ac, 60	).00% Impe	ervious, Inflow I	Depth = 7.5	5" for 100	-yr event
Inflow =	=	3.5 cfs @	12.08 hrs,	Volume=	0.314 af		
Outflow =	-	3.5 cfs @	12.08 hrs,	Volume=	0.314 af,	Atten= 0%,	Lag= 0.0 min
Primary =	-	1.9 cfs @	12.08 hrs,	Volume=	0.282 af		
Secondary =	:	1.6 cfs @	12.08 hrs,	Volume=	0.033 af		

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.77' @ 12.08 hrs Flood Elev= 608.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	607.00'	<b>12.0" Vert. Orifice/Grate</b> C= 0.600
#2	Device 3	607.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00
			Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	604.50'	15.0" Round Culvert
			L= 20.0' CPP, square edge headwall, Ke= 0.500
			Inlet / Outlet Invert= 604.50' / 604.00' S= 0.0250 '/' Cc= 0.900
			n= 0.120, Flow Area= 1.23 sf

Primary OutFlow Max=1.9 cfs @ 12.08 hrs HW=607.76' TW=607.13' (Dynamic Tailwater) **1=Orifice/Grate** (Orifice Controls 1.9 cfs @ 2.97 fps)

Secondary OutFlow Max=1.5 cfs @ 12.08 hrs HW=607.76' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 1.5 cfs of 2.4 cfs potential flow) -2=Broad-Crested Rectangular Weir (Weir Controls 1.5 cfs @ 1.46 fps)

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023

Page 79



Pond 1.4 FS: Flow Splitter

#### Summary for Pond 3.1AP: Pretreatment Basin

Inflow Area =	4.200 ac, 52.38% I	mpervious, Inflow	Depth = 7.06"	for 100-yr event
Inflow =	24.0 cfs @ 12.13	nrs, Volume=	2.472 af	
Outflow =	16.1 cfs @ 12.28	nrs, Volume=	2.472 af, Atte	en= 33%, Lag= 9.0 min
Primary =	1.4 cfs @ 12.26	nrs, Volume=	0.966 af	
Secondary =	14.6 cfs @ 12.28	nrs, Volume=	1.507 af	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 610.69' @ 12.28 hrs Surf.Area= 6,718 sf Storage= 22,201 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 115.7 min (912.0 - 796.3)

Volume	Invert	Avail.Stor	rage Storage	Description			
#1	606.00'	24,35	50 cf Custom	Stage Data (Pr	ismatic) Listed below (F	Recalc)	
Elevatio (fee	on Su t)	rf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)			
606.0 608.0 610.0 611.0	)0 )0 )0 )0	2,900 4,400 6,100 7,000	0 7,300 10,500 6,550	0 7,300 17,800 24,350			
Device	Routing	Invert	Outlet Device	S			
#1	Device 3	608.00'	<b>1.0' long x 0</b> Head (feet) 0 Coef. (English	<b>.5' breadth Broa</b> 0.20 0.40 0.60 n) 2.80 2.92 3.	id-Crested Rectangula 0.80 1.00 08 3.30 3.32	r Weir	
#2	Primary	605.50'	6.0" Round Culvert L= 40.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 605.50' / 605.00' S= 0.0125 '/' Cc= 0.900 n= 0.012 Flow Area= 0.20 st				
#3	Secondary	605.50'	<b>24.0'' Round</b> L= 50.0' CPI Inlet / Outlet I n= 0.012, Flo	<b>Culvert</b> P, square edge h nvert= 605.50' / pw Area= 3.14 sf	neadwall, Ke= 0.500 604.00' S= 0.0300 '/'	Cc= 0.900	
	• · • · · ·						

**Primary OutFlow** Max=1.4 cfs @ 12.26 hrs HW=610.68' TW=607.21' (Dynamic Tailwater) **2=Culvert** (Outlet Controls 1.4 cfs @ 7.29 fps)

Secondary OutFlow Max=14.6 cfs @ 12.28 hrs HW=610.68' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 14.6 cfs of 30.9 cfs potential flow)

**1=Broad-Crested Rectangular Weir** (Weir Controls 14.6 cfs @ 5.43 fps)

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 81

Pond 3.1AP: Pretreatment Basin



#### Summary for Pond 3.1P: Infiltration Basin

Inflow Area	. =	4.200 ac, 5	2.38% Impe	ervious, li	nflow Depth :	= 2.7	'6" for	100-y	/r event
Inflow	=	1.4 cfs @	12.26 hrs,	Volume=	= 0.9	66 af			
Outflow	=	0.3 cfs @	17.85 hrs,	Volume=	= 0.9	66 af,	Atten=	78%,	Lag= 335.5 min
Discarded	=	0.3 cfs @	17.85 hrs,	Volume=	= 0.9	66 af			•
Primary	=	0.0 cfs @	0.00 hrs,	Volume=	= 0.0	00 af			

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 608.15' @ 17.85 hrs Surf.Area= 6,775 sf Storage= 15,678 cf

Plug-Flow detention time= 576.3 min calculated for 0.966 af (100% of inflow) Center-of-Mass det. time= 576.3 min (1,598.8 - 1,022.4)

Volume	Invert	Avail.Sto	rage Storage	Description		
#1	605.00'	34,80	00 cf Custom	Stage Data (Pr	ismatic) Listed be	elow (Recalc)
Elevatio	on Si	urf.Area	Inc.Store	Cum.Store		
(tee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)		
605.0	00	3,300	0	0		
606.0	00	4,300	3,800	3,800		
608.0	00	6,600	10,900	14,700		
610.0	00	9,000	15,600	30,300		
610.5	50	9,000	4,500	34,800		
Device	Routing	Invert	Outlet Device	S		
#1	Device 2	609.20'	2.5' long x 0.	5' breadth Broa	d-Crested Recta	ngular Weir X 2.00
			Head (feet) 0	.20 0.40 0.60	0.80 1.00	0
			Coef. (English	) 2.80 2.92 3.	08 3.30 3.32	
#2	Primary	603.00'	0' 15.0" Round Culvert			
	-		L= 50.0' CPF	P, square edge h	neadwall, Ke= 0.8	500
			Inlet / Outlet I	nvert= 603.00' /	602.00' S= 0.02	00 '/' Cc= 0.900
			n= 0.012, Flo	w Area= 1.23 sf	•	
#3	Discarded	605.00'	2.000 in/hr Exfiltration over Horizontal area Phase-In= 0.01'			

**Discarded OutFlow** Max=0.3 cfs @ 17.85 hrs HW=608.15' (Free Discharge) **-3=Exfiltration** (Exfiltration Controls 0.3 cfs)

Primary OutFlow Max=0.0 cfs @ 0.00 hrs HW=605.00' TW=0.00' (Dynamic Tailwater) 2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) 1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Printed 9/29/2023 Page 83

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC



Pond 3.1P: Infiltration Basin

### Summary for Pond 4.1AP1: Wet Swale

Inflow Area = Inflow = Outflow = Primary = Secondary =	0.500 ac, 60.0 3.8 cfs @ 12 3.5 cfs @ 12 0.1 cfs @ 12 3.4 cfs @ 12	00% Impervious, 2.04 hrs, Volume 2.08 hrs, Volume 2.14 hrs, Volume 2.08 hrs, Volume	Inflow Depth = 0.314 a = 0.314 a = 0.314 a = 0.141 a = 0.174 a	7.55" for 100-yr event af af, Atten= 8%, Lag= 2.5 min af af				
Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Starting Elev= 607.00' Surf.Area= 950 sf Storage= 1,438 cf Peak Elev= 607.91' @ 12.07 hrs Surf.Area= 1,222 sf Storage= 2,423 cf (986 cf above start)								
Plug-Flow detention Center-of-Mass det	n time= 123.4 m t. time= 26.6 mi	nin calculated for n ( 801.9 - 775.2 )	0.281 af (89% of )	inflow)				
Volume Inver	rt Avail.Stor	age Storage De	escription					
#1 604.50' 2,538 cf Custom Stage Data (Prismatic) Listed below (Recalc)								
Elevation S	Surf.Area	Inc.Store	Cum.Store					
(feet)	(sa-ft)	(cubic-feet)	(cubic-feet)					
604.50	200	0	0					
608.00	1,250	2,538	2,538					
Device Routing	Invert	Outlet Devices						
#1 Primary 607.00' 4.0'' Vert. Orifice/Grate C= 0.600   #2 Secondary 607.30' 4.0'' long x 0.5' breadth Broad-Crested Rectangular Weir   Head (feet) 0.20 0.40 0.60 0.80 1.00   Coef. (English) 2.80 2.92 3.08 3.30 3.32								
Primary OutFlow Max=0.1 cfs @ 12.14 hrs HW=607.81' TW=607.73' (Dynamic Tailwater) 1=Orifice/Grate (Orifice Controls 0.1 cfs @ 1.40 fps)								

Secondary OutFlow Max=3.5 cfs @ 12.08 hrs HW=607.89' TW=607.76' (Dynamic Tailwater) 2=Broad-Crested Rectangular Weir (Weir Controls 3.5 cfs @ 1.49 fps)
#### **DPD - Post-Development**

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 85

Hydrograph 3.8 cfs Inflow 4 Outflow 3.5 cfs 3.4 cfs – Primary Inflow Area=0.500 ac Secondary Peak Elev=607.91' 3-Storage=2,423 cf Flow (cfs) 2 1 0. cfs 0 15 20 25 30 35 70 75 80 85 90 95 100 105 110 115 120 5 10 40 45 50 55 60 65 Ó Time (hours)

Pond 4.1AP1: Wet Swale

DPD - Post-DevelopmentNY - DPD 24-hr S1 100-yr Rainfall=8.63"Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C.Printed 9/29/2023HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLCPage 86

#### Summary for Pond 4.1BP: Bioretention

Inflow Area	ι= (	0.500 ac, 6	0.00% Impe	rvious, Inf	low Depth =	6.77" for	[.] 100-y	r event
Inflow	=	1.9 cfs @	12.08 hrs,	Volume=	0.282	af		
Outflow	=	0.6 cfs @	12.70 hrs,	Volume=	0.282	af, Atten=	70%,	Lag= 37.2 min
Primary	=	0.6 cfs @	12.70 hrs,	Volume=	0.282	af		
Primary	=	0.6 cfs @	12.70 hrs,	Volume=	0.282	af	, . ,	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 607.44' @ 12.70 hrs Surf.Area= 4,754 sf Storage= 4,124 cf

Plug-Flow detention time= 215.2 min calculated for 0.282 af (100% of inflow) Center-of-Mass det. time= 215.1 min (1,025.4 - 810.3)

Volume	Inve	ert Avail.Sto	rage Storag	Storage Description		
#1	606.5	60' 4,40	00 cf Custor	m Stage Data (Prismatic) Listed below (Recalc)		
Elevatio (fee 606.5	on et) 50	Surf.Area (sq-ft) 4,000 4 800	Inc.Store (cubic-feet) 0 4 400	Cum.Store (cubic-feet) 0 4 400		
Device #1	Routing Device 3	Invert 606.50'	Outlet Devic 1.000 in/hr I 12.0" Vort	ces Exfiltration over Surface area Phase-In= 0.01'	_	
#2 #3	Primary	603.00'	8.0" Round L= 10.0' Cf Inlet / Outlet n= 0.013 Co	<b>d Culvert</b> PP, square edge headwall, Ke= 0.500 t Invert= 603.00' / 602.70' S= 0.0300 '/' Cc= 0.900 corrugated PE, smooth interior, Flow Area= 0.35 sf		

**Primary OutFlow** Max=0.6 cfs @ 12.70 hrs HW=607.44' TW=0.00' (Dynamic Tailwater) **3=Culvert** (Passes 0.6 cfs of 3.4 cfs potential flow) **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

**2=Orifice/Grate** (Orifice Controls 0.5 cfs @ 1.99 fps)

#### **DPD - Post-Development**

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 87

Hydrograph 1.9 cfs Inflow 2 - Primary Inflow Area=0.500 ac Peak Elev=607.44' Storage=4,124 cf Flow (cfs) 1 0.6 cfs 0-5 10 15 20 25 30 35 70 75 80 85 90 95 100 105 110 115 120 40 45 50 55 60 65 Ó Time (hours)

#### Pond 4.1BP: Bioretention

**DPD - Post-Development** NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 88

#### Summary for Pond 5.1AP: Pretreatment Basin

Inflow Area =	4.400 ac, 70.45% Impervious, Inflow Depth = 7.55" for	100-yr event
Inflow =	29.2 cfs @ 12.09 hrs, Volume= 2.767 af	
Outflow =	22.7 cfs @ 12.17 hrs, Volume= 2.767 af, Atten=	22%, Lag= 5.2 min
Primary =	1.8 cfs @ 12.16 hrs, Volume= 1.803 af	-
Secondary =	20.9 cfs @ 12.17 hrs, Volume= 0.965 af	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 660.47' @ 12.17 hrs Surf.Area= 9,067 sf Storage= 25,227 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 116.6 min (895.2 - 778.6)

Volume	Invert	Avail.Stor	age Storage I	Description		
#1	656.00'	40,30	0 cf Custom	Stage Data (Pr	ismatic) Listed below (I	Recalc)
Elevatio (fee	n Su	urf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)		
656.0 658.0	0 0 0	2,500 5,000	0 7,500	0 7,500		
660.0 662.0	0	8,600 10,600	13,600 19,200	21,100 40,300		
Device	Routing	Invert	Outlet Devices	3		
#1	Device 3	659.30'	<b>2.5' long x 0.</b> Head (feet) 0. Coef, (English	<b>5' breadth Broa</b> 20 0.40 0.60 ) 2.80 2.92 3.	Id-Crested Rectangula 0.80 1.00 08 3.30 3.32	r Weir X 2.00
#2	Primary	655.50'	6.0" Round C L= 30.0' CPP Inlet / Outlet Ir n= 0.012 Flox	<b>culvert</b> , square edge h vert= 655.50' / w Area= 0.20 sf	neadwall, Ke= 0.500 655.00' S= 0.0167 '/'	Cc= 0.900
#3	Secondary	657.50'	<b>30.0'' Round</b> L= 100.0' CP Inlet / Outlet Ir n= 0.012, Flow	<b>Culvert</b> P, square edge overt= 657.50' / w Area= 4.91 sf	headwall, Ke= 0.500 656.50' S= 0.0100 '/'	Cc= 0.900

Primary OutFlow Max=1.8 cfs @ 12.16 hrs HW=660.45' TW=655.99' (Dynamic Tailwater) -2=Culvert (Outlet Controls 1.8 cfs @ 9.04 fps)

Secondary OutFlow Max=20.5 cfs @ 12.17 hrs HW=660.45' TW=0.00' (Dynamic Tailwater) -3=Culvert (Passes 20.5 cfs of 30.8 cfs potential flow)

**1=Broad-Crested Rectangular Weir** (Weir Controls 20.5 cfs @ 3.56 fps)

#### **DPD - Post-Development**

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Printed 9/29/2023 Page 89

Hydrograph 32 29.2 cfs Inflow 30 Outflow Primary 28 Inflow Area=4.400 ac Secondary 26 Peak Elev=660.47' 24 22.7 cfs 20.9 cfs 22-Storage=25,227 cf 20 Flow (cfs) 18 16 14 12-10 8-6 4 cfs 1.8 2-0-10 15 20 30 35 40 45 50 60 65 70 75 80 85 90 95 100 105 110 115 120 25 55 Ó 5

Time (hours)

Pond 5.1AP: Pretreatment Basin

**DPD - Post-Development** NY - DPD 24-hr S1 100-yr Rainfall=8.63" Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. Printed 9/29/2023 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC Page 90

#### Summary for Pond 5.1P: Infiltration Basin

Inflow Area	=	4.400 ac, 7	0.45% Impe	rvious, Inflov	v Depth =	4.92	2" for	100-y	/r event	
Inflow	=	1.8 cfs @	12.16 hrs,	Volume=	1.803	af				
Outflow	=	0.6 cfs @	24.11 hrs,	Volume=	1.803	af,	Atten=	65%,	Lag= 717	.1 min
Discarded	=	0.6 cfs @	24.11 hrs,	Volume=	1.803	af			-	
Primary	=	0.0 cfs @	0.00 hrs,	Volume=	0.000	af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs / 2 Peak Elev= 657.76' @ 24.11 hrs Surf.Area= 13,408 sf Storage= 30,818 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 498.1 min (1,470.6 - 972.5)

Volume	Invert	t Avail.Sto	rage Storag	e Description	
#1	655.00	64,95	50 cf Custo	m Stage Data (Pr	ismatic) Listed below (Recalc)
Elevatio	on S	urf.Area	Inc.Store	Cum.Store	
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)	
655.0	00	9,000	0	0	
656.0	00	10,500	9,750	9,750	
660.0	00	17,100	55,200	64,950	
Device	Routing	Invert	Outlet Devic	ces	
#1	Device 2	659.00'	<b>4.0' long x</b> Head (feet)	<b>0.5' breadth Broa</b> 0.20 0.40 0.60	ad-Crested Rectangular Weir X 2.00 0.80 1.00
#2	Primary	653.00'	<b>15.0'' Rour</b> L= 10.0' C Inlet / Outle	A Culvert PP, square edge 1 t Invert= 653.00' /	headwall, Ke= 0.500 652.50' S= 0.0500 '/' Cc= 0.900
#3	Discarded	655.00'	n= 0.012, F <b>2.000 in/hr</b>	Exfiltration over	Horizontal area

**Discarded OutFlow** Max=0.6 cfs @ 24.11 hrs HW=657.76' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 0.6 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=655.00' TW=0.00' (Dynamic Tailwater) -2=Culvert (Passes 0.0 cfs of 6.9 cfs potential flow) -1=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

#### **DPD - Post-Development**

NY - DPD 24-hr S1 100-yr Rainfall=8.63" Printed 9/29/2023 Page 91

Prepared by Insite Engineering, Surveying and Landscape Architecture, P.C. HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC



Pond 5.1P: Infiltration Basin

#### **APPENDIX D**

NYSDEC SPDES for Construction Activities Construction Site Log Book

#### APPENDIX F CONSTRUCTION SITE INSPECTION AND MAINTENANCE LOG BOOK

## STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM FOR CONSTRUCTION ACTIVITIES

### SAMPLE CONSTRUCTION SITE LOG BOOK

#### Table of Contents

- I. Pre-Construction Meeting Documents
  - a. Preamble to Site Assessment and Inspections
  - b. Pre-Construction Site Assessment Checklist

#### **II.** Construction Duration Inspections

- a. Directions
- b. Modification to the SWPPP

#### I. PRE-CONSTRUCTION MEETING DOCUMENTS

Project Name	
Permit No.	Date of Authorization
Name of Operator	
Prime Contractor	

#### a. Preamble to Site Assessment and Inspections

The Following Information To Be Read By All Person's Involved in The Construction of Stormwater Related Activities:

The Operator agrees to have a qualified inspector¹ conduct an assessment of the site prior to the commencement of construction² and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements. A preconstruction meeting should be held to review all of the SWPPP requirements with construction personnel.

When construction starts, site inspections shall be conducted by the qualified inspector at least every 7 calendar days. The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified inspector perform a final site inspection. The qualified inspector shall certify that the site has undergone final stabilization³ using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 Refer to "Qualified Inspector" inspection requirements in the current SPDES General Permit for Stormwater Discharges from Construction Activity for complete list of inspection requirements.

3 "Final stabilization" means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

^{2 &}quot;Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

#### b. Pre-construction Site Assessment Checklist (NOTE: Provide comments below as necessary)

1. Notice of Intent, SWPPP, and Contractors Certification:

#### Yes No NA

- [] [] Has a Notice of Intent been filed with the NYS Department of Conservation?
- [] [] [] Is the SWPPP on-site? Where?
- [] [] Is the Plan current? What is the latest revision date?_____
- [] [] Is a copy of the NOI (with brief description) onsite? Where?
- [] [] Have all contractors involved with stormwater related activities signed a contractor's certification?

#### 2. Resource Protection

#### Yes No NA

- [] [] Are construction limits clearly flagged or fenced?
- [] [] Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- [] [] Creek crossings installed prior to land-disturbing activity, including clearing and blasting.
- 3. Surface Water Protection

#### Yes No NA

- [] [] Clean stormwater runoff has been diverted from areas to be disturbed.
- [] [] Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- [] [] Appropriate practices to protect on-site or downstream surface water are installed.
- [] [] Are clearing and grading operations divided into areas <5 acres?

#### 4. Stabilized Construction Access

#### Yes No NA

- [] [] A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- [] [] Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- [] [] Sediment tracked onto public streets is removed or cleaned on a regular basis.
- 5. Sediment Controls

#### Yes No NA

- [] [] Silt fence material and installation comply with the standard drawing and specifications.
- [] [] Silt fences are installed at appropriate spacing intervals
- [] [] Sediment/detention basin was installed as first land disturbing activity.
- [] [] Sediment traps and barriers are installed.

#### 6. Pollution Prevention for Waste and Hazardous Materials

#### Yes No NA

- [] [] The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- [] [] The plan is contained in the SWPPP on page
- [] [] Appropriate materials to control spills are onsite. Where?

#### **II. CONSTRUCTION DURATION INSPECTIONS**

#### a. Directions:

#### Inspection Forms will be filled out during the entire construction phase of the project.

Required Elements:

- 1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;
- 2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;
- 3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;
- 4) Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);
- 5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and
- 6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

#### SITE PLAN/SKETCH

 Inspector (print name)
 Date of Inspection

 Qualified Inspector (print name)
 Qualified Inspector Signature

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

#### **CONSTRUCTION DURATION INSPECTIONS**

#### **Maintaining Water Quality**

#### Yes No NA

- [] [] Is there an increase in turbidity causing a substantial visible contrast to natural conditions at the outfalls?
- [] [] Is there residue from oil and floating substances, visible oil film, or globules or grease at the outfalls?
- [] [] All disturbance is within the limits of the approved plans.
- [] [] Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

#### Housekeeping

1. General Site Conditions

#### Yes No NA

- [] [] [] Is construction site litter, debris and spoils appropriately managed?
- [] [] Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- [] [] [] Is construction impacting the adjacent property?
- [] [] [] Is dust adequately controlled?

#### 2. Temporary Stream Crossing

#### Yes No NA

- [] [] Maximum diameter pipes necessary to span creek without dredging are installed.
- [] [] Installed non-woven geotextile fabric beneath approaches.
- [] [] Is fill composed of aggregate (no earth or soil)?
- [] [] [] Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.
- 3. Stabilized Construction Access

#### Yes No NA

- [] [] [] Stone is clean enough to effectively remove mud from vehicles.
- [] [] Installed per standards and specifications?
- [] [] Does all traffic use the stabilized entrance to enter and leave site?
- [] [] [] Is adequate drainage provided to prevent ponding at entrance?

#### **Runoff Control Practices**

1. Excavation Dewatering

#### Yes No NA

- [] [] Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- [] [] Clean water from upstream pool is being pumped to the downstream pool.
- [] [] Sediment laden water from work area is being discharged to a silt-trapping device.
- [] [] Constructed upstream berm with one-foot minimum freeboard.

#### **Runoff Control Practices (continued)**

2. Flow Spreader

#### Yes No NA

- [] [] [] Installed per plan.
- [] [] Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- [] [] Flow sheets out of level spreader without erosion on downstream edge.

#### 3. Interceptor Dikes and Swales

#### Yes No NA

- [] [] Installed per plan with minimum side slopes 2H:1V or flatter.
- [] [] Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- [] [] Sediment-laden runoff directed to sediment trapping structure

#### 4. Stone Check Dam

#### Yes No NA

- [] [] [] Is channel stable? (flow is not eroding soil underneath or around the structure).
- [] [] Check is in good condition (rocks in place and no permanent pools behind the structure).
- [] [] Has accumulated sediment been removed?.

#### 5. Rock Outlet Protection

#### Yes No NA

- [] [] [] Installed per plan.
- [] [] Installed concurrently with pipe installation.

#### Soil Stabilization

1. Topsoil and Spoil Stockpiles

#### Yes No NA

- [] [] [] Stockpiles are stabilized with vegetation and/or mulch.
- [] [] [] Sediment control is installed at the toe of the slope.
- 2. Revegetation

#### Yes No NA

- [] [] [] Temporary seedings and mulch have been applied to idle areas.
- [] [] 4 inches minimum of topsoil has been applied under permanent seedings

#### Sediment Control Practices

1. Silt Fence and Linear Barriers

#### Yes No NA

- [] [] Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- [] [] Joints constructed by wrapping the two ends together for continuous support.
- [] [] Fabric buried 6 inches minimum.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is ___% of design capacity.

#### CONSTRUCTION DURATION INSPECTIONS

Page 4 of _____

#### Sediment Control Practices (continued)

2. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated; Filter Sock or Manufactured practices)

#### Yes No NA

- [] [] Installed concrete blocks lengthwise so open ends face outward, not upward.
- [] [] Placed wire screen between No. 3 crushed stone and concrete blocks.
- [] [] Drainage area is 1acre or less.
- [] [] [] Excavated area is 900 cubic feet.
- [] [] Excavated side slopes should be 2:1.
- [] [] 2" x 4" frame is constructed and structurally sound.
- [] [] Posts 3-foot maximum spacing between posts.
- [] [] Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.
- [] [] [] Manufactured insert fabric is free of tears and punctures.
- [] [] Filter Sock is not torn or flattened and fill material is contained within the mesh sock.

Sediment accumulation ____% of design capacity.

3. Temporary Sediment Trap

#### Yes No NA

- [] [] Outlet structure is constructed per the approved plan or drawing.
- [] [] Geotextile fabric has been placed beneath rock fill.
- [] [] [] Sediment trap slopes and disturbed areas are stabilized.

Sediment accumulation is ___% of design capacity.

4. Temporary Sediment Basin

#### Yes No NA

- [] [] Basin and outlet structure constructed per the approved plan.
- [] [] Basin side slopes are stabilized with seed/mulch.
- [] [] Drainage structure flushed and basin surface restored upon removal of sediment basin facility.
- [] [] Sediment basin dewatering pool is dewatering at appropriate rate.

Sediment accumulation is ___% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design. All practices shall be maintained in accordance with their respective standards.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

#### **CONSTRUCTION DURATION INSPECTIONS**

#### b. Modifications to the SWPPP (To be completed as described below)

The Operator shall amend the SWPPP whenever:

- 1. There is a significant change in design, construction, operation, or maintenance which may have a significant effect on the potential for the discharge of pollutants to the waters of the United States and which has not otherwise been addressed in the SWPPP; or
- 2. The SWPPP proves to be ineffective in:
  - a. Eliminating or significantly minimizing pollutants from sources identified in the SWPPP and as required by this permit; or
  - b. Achieving the general objectives of controlling pollutants in stormwater discharges from permitted construction activity; and
- 3. Additionally, the SWPPP shall be amended to identify any new contractor or subcontractor that will implement any measure of the SWPPP.

#### **Modification & Reason:**

#### b. Operators Certification

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a class A misdemeanor pursuant to Section 210.45 of the Penal Law. "

Name (please print):			
Title		Date:	
Address:			
Phone:	Email:		
Signature:			

#### c. Qualified Professional's Credentials & Certification

" I hereby certify that I meet the criteria set forth in the General Permit to conduct site inspections for this project and that the appropriate erosion and sediment controls described in the SWPPP and as described in the following Pre-construction Site Assessment Checklist have been adequately installed or implemented, ensuring the overall preparedness of this site for the commencement of construction."

Name (please pri	int):		
Title		Date:	
Address:			
Phone:	Email:		
Signature:			

#### d. Contractors Certification Statement

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the owner or operator must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Signature of Contractor		Date	
Print Name	Title		
Signature of Trained Contractor		Date	
Print Name of Trained Contractor	Title		
Name of Contracting Firm			
Street Address			
City, State, Zip			
Telephone No.		Denne (car Dian (CW/DDD) for a s	

A copy of this statement shall be retained as part of the Stormwater Pollution Prevention Plan (SWPPP) for a period off at least five (5) years after the subject property is stabilized.

#### **APPENDIX E**

#### **Project and Owner Information**

Site Data:

4 Baldwin Place Road Town of Carmel, New York 10541 Area: 30.53 acres ±

Owner Information:

Bernad Creations LTD 124 Ridge Road Montgomery, NY 12549

Parties Responsible for Implementation of the Short and Long Term Maintenance Plan:

Bernad Creations LTD 124 Ridge Road Montgomery, NY 12549

and or the current owner(s) of the subject property.

Qualified Professional Responsible for Inspection of the Stormwater Pollution Prevention Plan:

Insite Engineering, Surveying & Landscape Architecture, P.C. 3 Garrett Place Carmel, New York 10512 845-225-96

#### **APPENDIX F**

**Bioretention Filter Sizing Calculation** 

SMP 4.1BP - NYSDEC Bioretention FiltProject:DPDProject #:22242.100Date:9/28/2023	er (Design F-4)	ENGIN LANDSC	<b>NSITE</b> EEERING, SURVEYING & CAPE ARCHITECTURE, P.C.
1a. WQv Required for Downstream SMP =	0.075 ac-ft	3,267 c.f.	
1b. Subcatchment % Imperviousness =	60.0% %		
2. Required Practice Volume			
2a. Total required volume = 75% of WQv (	in filter and pretreatment)	=	2,450 c.f.
2b. Total volume provided in filter =		=	2,544 c.f.

3. Pretreatment Requirements: Pretreatment will be provided by a gravel diaphraghm and grass filter strip.

4. Required Filter Area:		
4a. Required Filter Area =	WQv (	df)
	k (hf + df	) + tf
	df=	1.50 ft.
	hf=	0.25 ft.
	k=	0.50 ft./day
	tf=	2.00 days
Required F	Filter Area=	2800 s.f.
4b. Provided Filter Area =		4,000 s.f.
4c. Volume provided in filte	er=	2,544 c.f.

#### **APPENDIX G**

**Pipe Sizing Calculations** 



DRAINAGE SYSTEM CALCULATIONS Design Storm: 100-Year 
 PROJECT:
 DPD

 JOB NUMBER:
 22242.100

 BY:
 JWM
 DATE:
 9-29-23

 CHK:
 RDW
 DATE:
 9-29-23

FROM CB 17			1003	ANEA	FERV	1005	AREA	~ ~ ~	TIME O	F CONC	. (min.)		Q (CI	S)			E DESI	λN	
CB 17	то	A (ac.)	с	СА	A (ac.)	с	CA	CA	INLET	PIPE	TOTAL	I	DESIGN	CAP.	V(ft/s)	n	s (%)	L (ft)	DIA (in)
	CB 16	0.24	0.9	0.22	0.05	0.3	0.02	0.24	6	-	6	9.5	2.3	3.9	5.1	0.012	1.0	87	12
CB 16	CB 15	0.07	0.9	0.06	0.09	0.3	0.03	0.33	6	-	6	9.5	3.1	3.9	5.5	0.012	1.0	86	12
CB 15	CB 14	0.06	0.9	0.05	0.23	0.3	0.07	0.45	6	-	6	9.5	4.3	7.0	6.0	0.012	1.0	95	15
CB 14	CB 13	0.30	0.9	0.27	0.15	0.3	0.05	0.77	6	-	6	9.5	7.3	20.3	15.2	0.012	8.4	213	15
CB 13	CB 12	0.11	0.9	0.10	0.09	0.3	0.03	0.90	6	-	6	9.5	8.6	15.0	12.7	0.012	4.6	79	15
CB 12	CB 11	0.26	0.9	0.23	0.14	0.3	0.04	1.94	6	-	6	9.5	18.4	34.1	19.7	0.012	9.0	144	18
CB 11	CB 10	0.06	0.9	0.05	0.00	0.3	0.00	1.99	6	-	6	9.5	18.9	28.6	17.3	0.012	6.3	65	18
CB 10	CB 9	0.08	0.9	0.07	0.05	0.3	0.02	2.08	6	-	6	9.5	19.8	49.0	14.8	0.012	4.0	88	24
CB 9	ES 8	0.04	0.9	0.04	0.00	0.3	0.00	2.19	6	-	6	9.5	20.8	25.7	9.1	0.012	1.1	36	24
CB 12C	CB 12B	0.38	0.9	0.34	0.12	0.3	0.04	0.38	8	-	8	8.4	3.2	4.0	5.7	0.012	1.1	134	12
CB 12B	CB 12A	0.15	0.9	0.14	0.00	0.3	0.00	0.52	<8	-	8	8.4	4.4	1.1	6.5	0.012	1.2	126	15
CB 12A	CB 12	0.28	0.9	0.25	0.00	0.3	0.00	0.77	<8	-	8	8.4	6.5	15.3	12.0	0.012	4.8	188	15
CB 13A	CB 13	0.10	0.0	0.00	0.00	03	0.00	0.00	6	_	6	9.5	0.0	53	5.0	0.012	10	21	10
OB ISA	0013	0.10	0.9	0.03	0.00	0.5	0.00	0.03	0	-	0	9.5	0.9	5.5	5.0	0.012	1.9	21	12
CB 9B	CB 9A	0.02	0.9	0.02	0.00	0.3	0.00	0.02	6	-	6	9.5	0.2	7.7	4.2	0.012	4.0	72	12
CB 9A	CB 9	0.05	0.9	0.05	0.00	0.3	0.00	0.07	6	-	6	9.5	0.7	6.7	5.5	0.012	3.0	20	12
			•			•		•								••			•
OS 3.1AP	ES 7		r						PIPE	SIZED	IN HYDF	ROCA	D						
OS 3.1P	ES 6		<u> </u>						PIPE	SIZED	IN HYDF	ROCA	D						
		0.10	0.0	0.00	0.00	0.0	0.00	0.00	6		0	0.5	0.0	0.0	4.0	0.010	10	00	10
CB 5	6B 4	0.10	0.9	0.09	0.00	0.3	0.00	0.09	6	-	6	9.5	0.9	3.9	4.0	0.012	1.0	20	12
CD 4	E3 3	0.10	0.9	0.09	0.00	0.3	0.00	0.18	0	-	0	9.0	1.7	3.9	4.8	0.012	1.0	21	12
			I					!	DIDE	SIZED						ļ			
	EX DI								PIPE	SIZED									
	EXBI																		
OS 4.1BP	DMH 1								PIPE	SIZED	IN HYDF	ROCA	D						
OS 4.1BP	DMH 1								PIPE	SIZED	IN HYDF	ROCA	D						
OS 4.1BP CB 35	DMH 1 CB 34	0.13	0.9	0.12	0.07	0.3	0.02	0.14	PIPE 6	SIZED	IN HYDF 6	ROCA	D 15.9	52.6	14.7	0.012	4.6	80	24
OS 4.1BP CB 35 CB 34	DMH 1 CB 34 EX CB	0.13	0.9	0.12	0.07	0.3	0.02	0.14	PIPE 6 6	-	IN HYDF 6 6	9.5 9.5	D 15.9 16.7	52.6 77.5	14.7 19.7	0.012	4.6 10.0	80 11	24 24
OS 4.1BP CB 35 CB 34	DMH 1 CB 34 EX CB	0.13 0.05	0.9	0.12 0.05	0.07 0.10	0.3 0.3	0.02	0.14	PIPE 6 6	- -	IN HYDF 6 6	ROCA 9.5 9.5	<b>D</b> 15.9 16.7	52.6 77.5	14.7 19.7	0.012 0.012	4.6 10.0	80 11	24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP	DMH 1 CB 34 EX CB ES 19	0.13	0.9	0.12	0.07 0.10	0.3	0.02	0.14	PIPE 6 6 PIPE	- SIZED	IN HYDF 6 6 IN HYDF	9.5 9.5 9.5	D 15.9 16.7 D	52.6 77.5	14.7 19.7	0.012 0.012	4.6 10.0	80 11	24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP	DMH 1 CB 34 EX CB ES 19	0.13	0.9	0.12	0.07 0.10	0.3	0.02	0.14	PIPE 6 6 PIPE	SIZED	IN HYDF 6 6 IN HYDF	9.5 9.5 9.5	D 15.9 16.7 D	52.6 77.5	14.7 19.7	0.012 0.012	4.6 10.0	80 11	24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP	DMH 1 CB 34 EX CB ES 19 ES 18A	0.13 0.05	0.9	0.12	0.07 0.10	0.3	0.02	0.14	PIPE 6 6 PIPE PIPE	SIZED	IN HYDF 6 6 IN HYDF	9.5 9.5 9.5 ROCA	D 15.9 16.7 D	52.6 77.5	14.7 19.7	0.012 0.012	4.6 10.0	<u>80</u> 11	24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP	DMH 1 CB 34 EX CB ES 19 ES 18A	0.13	0.9	0.12	0.07 0.10	0.3	0.02	0.14	PIPE 6 6 PIPE PIPE	SIZED - SIZED SIZED	IN HYDF	9.5 9.5 80CA	D 15.9 16.7 D	52.6 77.5	14.7 19.7	0.012 0.012	4.6 10.0	<u>80</u> 11	24 24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18	0.13 0.05	0.9	0.12	0.07	0.3	0.02	0.14	PIPE 6 6 PIPE PIPE PIPE	SIZED - SIZED SIZED SIZED	IN HYDF 6 6 IN HYDF IN HYDF	9.5 9.5 80CA	D 15.9 16.7 D	52.6 77.5	14.7 19.7	0.012	4.6 10.0	<u>80</u> 11	24 24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18 CB 21A	0.13 0.05	0.9	0.12 0.05	0.07 0.10	0.3	0.02	0.14 0.22	PIPE 6 6 PIPE PIPE PIPE 6	SIZED - SIZED SIZED SIZED	IN HYDF	ROCA 9.5 9.5 ROCA ROCA ROCA	D 15.9 16.7 D D D 0.9	52.6 77.5	<u>14.7</u> <u>19.7</u>	0.012	<u>4.6</u> 10.0	80 11 20	24 24 24
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21	0.13 0.05	0.9	0.12 0.05	0.07 0.10	0.3 0.3 0.3	0.02 0.03	0.14 0.22 0.09 0.24	PIPE 6 6 PIPE PIPE PIPE 6 8	SIZED - SIZED SIZED SIZED - -	IN HYDF 6 6 IN HYDF IN HYDF 6 8	ROCA 9.5 9.5 ROCA ROCA ROCA ROCA ROCA	D 15.9 16.7 D D D 0.9 2.0	52.6 77.5 5.5 5.9	14.7 19.7 5.1 4.3	0.012 0.012 0.012	4.6 10.0 2.0 0.7	80 11 20 361	24 24 12 15
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21	0.13 0.05	0.9 0.9 0.9	0.12 0.05 0.07 0.09	0.07 0.10 0.05 0.20	0.3 0.3 0.3	0.02 0.03 0.02 0.02 0.06	0.14 0.22 0.09 0.24	PIPE 6 6 PIPE PIPE 6 8	SIZED - SIZED SIZED SIZED - -	IN HYDF 6 6 10 HYDF 10 HYDF 6 8	9.5 9.5 80CA 80CA 80CA 80CA 9.5 8.4	D 15.9 16.7 D D D 0.9 2.0	52.6 77.5 5.5 5.9	14.7 19.7 5.1 4.3	0.012 0.012 0.012	4.6 10.0 2.0 0.7	80 11 20 361	24 24 24 12 15
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21 CB 29	0.13 0.05 0.08 0.10 0.07	0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06	0.07 0.10 0.05 0.20 0.00	0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.02 0.06	0.14 0.22 0.09 0.24 0.06	PIPE 6 6 PIPE PIPE 6 8 6	SIZED - SIZED SIZED SIZED - - -	IN HYDF 6 6 IN HYDF IN HYDF 6 8 6	9.5 9.5 80CA 80CA 80CA 80CA 9.5 8.4	D 15.9 16.7 D D D 0.9 2.0 0.6	52.6 77.5 5.5 5.9 3.9	14.7 19.7 5.1 4.3 3.5	0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0	80 11 20 361 104	24 24 12 15 12
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21 CB 29 CB 28	0.13 0.05 0.05 0.08 0.10 0.07 0.42	0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38	0.07 0.10 0.05 0.20 0.00 0.00	0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.02 0.06 0.06 0.00	0.14 0.22 0.09 0.24 0.06 0.44	PIPE 6 6 PIPE PIPE 6 6 8 6 6	SIZED - SIZED SIZED SIZED - - - -	IN HYDF 6 6 IN HYDF IN HYDF 6 8 6 6 6	9.5 9.5 9.5 80CA 80CA 80CA 80CA 9.5 8.4 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2	52.6 77.5 5.5 5.9 3.9 7.0	14.7 19.7 5.1 4.3 3.5 6.0	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0	80 11 20 361 104 104	24 24 12 15 12 15
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18	0.07 0.10 0.05 0.20 0.00 0.00 0.00	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.02 0.06 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6	SIZED - SIZED SIZED SIZED - - - - - -	IN HYDF 6 6 IN HYDF IN HYDF 6 8 6 6 6 6 6	9.5 9.5 9.5 80CA 80CA 80CA 9.5 8.4 9.5 9.5 9.5	D 15.9 16.7 D D D 0.9 2.0 0.6 4.2 5.9	52.6 77.5 5.5 5.9 3.9 7.0 7.3	14.7 19.7 5.1 4.3 3.5 6.0 6.7	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1	80 11 20 361 104 104 37	24 24 24 12 15 12 15 15
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28 DMH 27	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20 0.00	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.02 0.06 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62	PIPE 6 6 PIPE PIPE 9 PIPE 6 8 6 6 6 6 6	SIZED - SIZED SIZED SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 IN HYDF IN HYDF 6 8 6 6 6 6 6 6 6	9.5 9.5 9.5 80CA 80CA 80CA 9.5 8.4 9.5 9.5 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0	80 11 20 361 104 104 37 139	24 24 24 12 15 15 15 15 15
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26	DMH 1 CB 34 EX CB ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20 0.00 0.08	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62 0.77	PIPE 6 6 PIPE PIPE 6 6 8 6 6 6 6 6 6	SIZED - SIZED SIZED SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 1N HYDF IN HYDF 6 8 6 6 6 6 6 6 6 6	80CA 9.5 9.5 80CA 80CA 80CA 9.5 8.4 9.5 9.5 9.5 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9	80 11 20 361 104 104 37 139 76	24 24 24 12 15 15 15 15 15 18
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25	DMH 1 CB 34 EX CB ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20 0.00 0.08 0.10	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62 0.77 0.86	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6	SIZED - SIZED SIZED SIZED - SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 1N HYDF IN HYDF 6 8 6 6 6 6 6 6 6 6 6 6 6	ROCAI 9.5 9.5 8.5 8.6 8.6 8.7 8.7 8.7 8.7 8.7 8.7 8.7 8.7 9.5 9.5 9.5 9.5 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7	80 11 20 361 104 104 37 139 76 104	24 24 24 12 15 15 15 15 15 18 18
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 25 CB 24	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 23 CB 23	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20 0.00 0.08 0.10 0.08 0.10 0.08	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.07 0.09 0.37	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62 0.77 0.86 1.23	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 1N HYDF IN HYDF 6 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	80CA 9.5 9.5 80CA 80CA 80CA 9.5 8.4 9.5 9.5 9.5 9.5 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2 11.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7 10.7	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5 13.5	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4	80 11 20 361 104 104 37 139 76 104 104	24 24 24 12 15 15 15 15 15 18 18 18 18 25
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21A CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 25	DMH 1 CB 34 EX CB ES 19 ES 18A ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 CB 22 CB 22	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.02 0.00 0.00 0.08 0.10 0.08 0.10 0.041 0.041 0.041	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62 0.77 0.86 1.23 1.30	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 1N HYDF IN HYDF 6 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	80CA 9.5 9.5 9.5 80CA 80CA 80CA 9.5 9.5 9.5 9.5 9.5 9.5 9.5 9.5 9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2 11.7 12.4 22.2	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 8.6 7.8 26 2	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 0.9	80 11 20 361 104 104 37 139 76 104 104 104	24 24 24 15 15 15 15 15 18 18 18 18 18 24 24 25
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 27	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 CB 20 CB 22 CB 23 CB 22 CB 22 CB 22	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.02 0.00 0.00 0.00 0.08 0.10 0.041 0.08 0.41 0.08 0.41	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07 0.37 0.07 0.37	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.77 0.86 1.23 1.30 2.34	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 1N HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	ROCAI           9.5           9.5           9.5           ROCAI           ROCAI           ROCAI           ROCAI           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2 11.7 12.4 22.2 24.5	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 24.5 118.5 20.7	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 29.0 9.7	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 2.0	80 11 20 361 104 104 37 139 76 104 104 104 104	24 24 24 12 15 15 15 15 15 18 18 18 18 18 24 24 24 22
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 ES 20	0.13 0.05 0.05 0.08 0.10 0.07 0.42 0.20 0.00 0.08 0.10 0.08 0.10 0.08 0.10 0.041 0.08 0.41 0.00	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07 0.37 0.00	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.62 0.77 0.86 1.23 1.30 2.34 2.58	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 8 IN HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	80CA           9.5           9.5           9.5           80CA           80CA           80CA           80CA           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2 11.7 12.4 22.2 24.5	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 39.7	14.7           19.7           5.1           4.3           3.5           6.0           6.7           13.4           6.6           6.1           8.6           7.8           29.0           8.5	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 0.8	80 11 20 361 104 104 37 139 76 104 104 104 104 106 76	24 24 24 12 15 15 15 15 15 18 18 18 18 18 24 24 24 30
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 20 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 CB 33	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 ES 20 CB 32	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.02 0.00 0.00 0.00 0.00 0.0	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07 0.37 0.07 0.37 0.00	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.77 0.86 1.23 1.30 2.34 2.58	PIPE 6 6 PIPE PIPE 6 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 8 IN HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	80CA           9.5           9.5           9.5           80CA           80CA           80CA           80CA           80CA           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 5.9 7.3 8.2 11.7 12.4 22.2 24.5 4.8	52.6 77.5 5.5 5.9 3.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 39.7 3.9 7.0	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 29.0 8.5 7.7	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 0.8 1.9	80 11 20 361 104 104 37 139 76 104 104 104 104 106 76	24 24 24 12 15 15 15 15 15 18 18 18 18 18 18 24 24 24 30 
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 CB 33 CB 32	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 ES 20 CB 32 CB 32 CB 31	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.00 0.00 0.00 0.00 0.00	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07 0.37 0.07 0.37 0.00	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.77 0.86 1.23 1.30 2.34 2.58 0.51 0.55	PIPE 6 6 PIPE PIPE 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - SIZED - - - - - - - - - - - - - - - - - - -	IN HYDF 6 6 8 IN HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	ROCAI           9.5           9.5           9.5           ROCAI           ROCAI           ROCAI           ROCAI           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 7.3 8.2 11.7 12.4 22.2 24.5 4.8 5.5	52.6 77.5 77.5 5.5 5.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 39.7 5.3 9.4	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 29.0 8.5 7.7 8.0	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 0.8 1.9 1.8	80 11 20 361 104 104 37 139 76 104 104 104 104 104 106 76 76 175 28	24 24 24 12 15 15 15 15 15 15 18 18 18 18 18 24 24 24 30 
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 30 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 CB 33 CB 32 CB 31	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 ES 20 CB 32 CB 31 CB 32 CB 31 CB 22	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.42 0.20 0.00 0.08 0.10 0.08 0.10 0.041 0.08 0.41 0.08 0.41 0.00 0.57 0.07 0.10	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.05 0.07 0.09 0.06 0.38 0.18 0.00 0.07 0.09 0.37 0.07 0.37 0.07 0.37 0.00 0.51 0.06 0.09	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.77 0.86 1.23 1.30 2.34 2.58 0.51 0.55 0.67	PIPE 6 6 PIPE PIPE 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - - - - - - - - - - - - -	IN HYDF 6 6 8 IN HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	ROCAI           9.5           9.5           9.5           ROCAI           ROCAI           ROCAI           ROCAI           ROCAI           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 7.3 8.2 11.7 12.4 22.2 24.5 4.8 5.5 6.4	52.6 77.5 77.5 5.5 5.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 39.7 5.3 9.4 15.7	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 29.0 8.5 7.7 8.0 8.4	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 0.8 1.9 1.8 1.9	80 11 20 361 104 104 104 104 104 104 104 104 106 76 76 175 28 104	24 24 24 12 15 15 15 15 15 15 18 18 18 18 24 24 24 30 12 15 18
OS 4.1BP CB 35 CB 34 OS 5.1AP OS 5.1AP OS 5.1AP OS 5.1P CB 21B CB 21B CB 21A CB 30 CB 29 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 CB 33 CB 32 CB 31	DMH 1 CB 34 EX CB ES 19 ES 19 ES 18A CB 21A DMH 21 CB 29 CB 28 DMH 27 CB 26 CB 25 CB 24 CB 23 CB 22 DMH 21 ES 20 CB 32 CB 31 CB 32 CB 31 CB 22	0.13 0.05 0.05 0.08 0.10 0.07 0.07 0.07 0.00 0.00 0.00 0.00	0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9 0.9	0.12 0.05 0.05 0.09 0.06 0.38 0.09 0.07 0.09 0.37 0.07 0.07 0.37 0.07 0.37 0.00 0.51 0.06 0.09	0.07 0.10 0.05 0.20 0.00 0.00 0.00 0.00 0.00 0.0	0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3	0.02 0.03 0.03 0.02 0.06 0.00 0.00 0.00 0.00 0.00 0.00	0.14 0.22 0.09 0.24 0.06 0.44 0.62 0.77 0.86 1.23 1.30 2.34 2.58 0.51 0.58 0.67	PIPE 6 6 PIPE PIPE 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	SIZED - - SIZED SIZED - - - - - - - - - - - - -	IN HYDF 6 6 8 IN HYDF IN HYDF 6 8 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	ROCAI           9.5           9.5           9.5           ROCAI           ROCAI           ROCAI           ROCAI           9.5           8.4           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5           9.5	D 15.9 16.7 D D 0.9 2.0 0.6 4.2 5.9 7.3 8.2 11.7 12.4 22.2 24.5 4.8 5.5 6.4	52.6 77.5 77.5 5.5 5.9 7.0 7.3 18.5 10.8 9.5 13.5 24.5 118.5 39.7 5.3 9.4 15.7	14.7 19.7 5.1 4.3 3.5 6.0 6.7 13.4 6.6 6.1 8.6 7.8 29.0 8.5 7.7 8.0 8.4	0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012	4.6 10.0 2.0 0.7 1.0 1.0 1.1 7.0 0.9 0.7 1.4 1.0 23.4 0.8 1.9 1.8 1.9	80 11 20 361 104 104 104 104 104 104 104 104 104 10	24 24 24 12 15 15 15 15 15 15 18 18 18 18 24 24 24 30 12 15 18

#### **FIGURES**













# SELF STORAGE

#### **PROJECT: Carmel, NY**

Self Storage 4 Baldwin Place Rd. Carmel, NY 10512

#### REFERENCE NUMBER

#### HUD 1482-Self Storage-Carmel NY





10500 Windfern Road Suite 100 Houston, TX 77064 832.960.7277

All design, manufacturing, reproduction, use, and sale of this document is strictly prohibited without the written consent of HudSign, Inc. This document is submitted under a confidential understanding that the recipient of this document assumes custody and agrees that the document and any part of it's content not to be copied. reproduced in whole or part, or any of it's contents be revealed in whole or part to other parties except for which it is agreed upon by HudSign, Inc. and recipient, nor shall any design features unique to this document be incorporated in any other project.

REFERENCE NUMBER

#### HUD1482

Client:	Self Storage
Location:	Carmel, NY
Site No.:	
Acct. Rep:	-
Proj. Mgr.:	-
Drawn By	: DOL
Date:	09/28/23
File Name	: HUD 1482-Self Storage-Carmel NY
Rev.	
Rev.	
Notes:	
	PAGE
	1 of 5

#### **SIGN CODE & AERIAL VIEW**

#### This drawing is the property of

#### SIGN CODE:

Jurisdiction: City of Carmel Zone: Commerce Business Park Code: wall signs - 2 sq. ft. per linear ft of building frontage. Max 40 sq. ft., Box Cabinet/Entire letter set; including Backer Panel, 1 allowed per wall facing street; freestanding signs - Count each face when computing area. Requires min. bldg setback of 20 ft from property lines. 32 sq. ft. (16 sq. ft. per side); 12' max allowed OAH/ 8' min clearance, 1 allowed, setback out of ROW







10500 Windfern Road Suite 100 Houston, TX 77064 832.960.7277

All design, manufacturing, reproduction, use, and sale of this document is strictly prohibited without the written consent of HudSign, Inc. This document is submitted under a confidential understanding that the recipient of this document assumes custody and agrees that the document and any part of it's content not to be copied, reproduced in whole or part, or any of it's contents be revealed in whole or part to other parties except for which it is agreed upon by HudSign, Inc. and recipient, nor shall any design features unique to this document be incorporated in any other project.

REFERENCE NUMBER

#### HUD1482

Client:	Self Storage
Location:	Carmel, NY
Site No.:	
Acct. Rep:	-
Proj. Mgr.:	-
Drawn By	DOL
Date:	09/28/23
File Name	: HUD 1482-Self Storage-Carmel NY
Rev.	
Rev.	
Notes:	
	PAGE
	2 of 5

#### SPECIFICATIONS

#### SIGN 1

SCOPE OF WORK:

INSTALL NEW MONUMENT SIGN SETBACK OUT OF ROW







SCOPE OF WORK:



4 of 5
#### **RACEWAY MOUNTED CHANNEL LETTERS**



8	LOW VOLTAGE ELECTRONIC POWER SUPPLY MOUNTED IN A 7 ½" x 7 ½" EXTRUDED .050
	ALUM. RACEWAY SUPPORT/WIRING BOX
	F.I.M. DOILDING FASCIA

6

10

9 VISIBLE CUT-OFF SWITCH WITH FLIP-UP COVER

10 ¼" WEEP HOLES (2) TWO PER LETTER

GROUNDED WALL PASS-THRU SEALED WATER TIGHT. WHIP ON LEFT SIDE. 120V CIRCUITS ARE REQUIRED FOR ALL SIGNS

PAGE 5 of 5

<u>Rev.</u> Notes



KATHY HOCHUL Governor ERIK KULLESEID Commissioner

September 19, 2023

Adam Thyberg Project Landscape Architect Insite Engineering, Surveying & Landscape Architecture, PC Insite Engineering 3 Garrett PI Carmel, NY 10512

Re: SEQRA

Diamond Point Development Self Storage Facility 6 Baldwin Place Rd, Mahopac, NY 10541 21PR05193

Dear Adam Thyberg:

Thank you for requesting the comments of the Office of Parks, Recreation and Historic Preservation (OPRHP). We have reviewed the project in accordance with the New York State Historic Preservation Act of 1980 (Section 14.09 of the New York Parks, Recreation and Historic Preservation Law). These comments are those of the OPRHP and relate only to Historic/Cultural resources. They do not include potential environmental impacts to New York State Parkland that may be involved in or near your project. Such impacts must be considered as part of the environmental review of the project pursuant to the State Environmental Quality Review Act (New York Environmental Conservation Law Article 8) and its implementing regulations (6 NYCRR Part 617).

Based upon this review, it is the opinion of OPRHP that no properties, including archaeological and/or historic resources, listed in or eligible for the New York State and National Registers of Historic Places will be impacted by this project.

If further correspondence is required regarding this project, please be sure to refer to the OPRHP Project Review (PR) number noted above.

Sincerely,

June Med

R. Daniel Mackay

Deputy Commissioner for Historic Preservation Division for Historic Preservation

rev: T. O'Connell













































FACULTATIVE (FACW) WETLAND MEADOW MX.

TTP) 6





30" X 48" DRAIN INLET DETAIL

(N.T.S.)































3 in. CLEAN STONE

START AT EXIST. PAVEMENT



(M.T.S.)















CONSTRUCTION SEQUENCE:

process the same pairs are set on same two strengths are paired as a subscription of the same of the

An operations and maintenance plan that includes superclim and maintenance schedules and actions to ensure continuous and effective operation of each the entity that all be responsible for the long term operation and maintenance of each provided on these plans ensures to solity this requirement.

- Sol testing results and locations. This SMPPP requirement is provided in the report tilled Stormeater Pollution Prevention Plan for DPD Self Storage. Infitration testing results. This SMPPP requirement is provided in the report tilled Starmwater Pollution Prevention Plan for DPD – Self Storage.
- avoum meterios serve to asocray this SIRPP regularement. A Stommeter Modelling and Angular Manch Industry gran-d-missionnest conditions, post-industriants conditions, that neutral of the atometer mediality, a summor label demonstrative fuel text conditions that have nedlespice a conformance with the above, and Mentilication of any Justice Industry and Angular Single Sing
- A site map/construction drawing(s) showing the specific location and size of eac post-construction stormwater management practice. This plan, and details/notes shown hereon serve to solisify this SBMPP requirement.
- Identification of all post-construction starmwater management practices to be constructed as part of the project; This plan, and details/notes shown hereon serve to satisfy this SatePP requirement.
- Aroust to the NTSEC SPEES General Permit for Stomwolar Distances from Construction Arthly (GP--D-20-00), of construction projects meeting building projects and the second provides provides and the second construction with the most constructive second se

#### REQUIRED POST-CONSTRUCTION STORMWATER MANAGEMENT PRACTICE COMPONENTS:

- And the force process and the restriction of the second se
- bes of relatively low to moderate subset immediate a subset immediate a subset immediate and and the following. So Restoration steps applied: 3 there are an applied and the following so the subset of the subset of the subset of the subset of a checken subset of a model in a subset of a depth of all heast 12 inches using a model where, tractor-mounted disc, or ther, mixing, and circulating ar and a subset of the subs
- Aerotion includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the sol, a roler with many spikes making indentations in the sol, or pronge which functions like a miti-subsolite. During periods of relatively low to madered subsoli moliture, the delaturbed as
- Per Deep Ripping
- Aeration includes the use of machines such as tractor-drawn implements with coullers making a narrow silt in the solt, a roller with many spikes making indentations in the solt, or prongs which function like a mini-subsoliw.



ONSTE SOLS WITHIN THE LIMIT OF DISTURBANCE BELONG TO THE HIGHOLOGIC SOL

TYPE OF SOIL DISTURBANCE SOIL RESTORATION REQUIREMENT COMMENTS/EXAMPLES

THE CONTRACTOR SHALL BE REGISTED TO PERFORM THE FOLLOWING SOL RESTORATION TECHNOLES FROM TO DESTINATION TOPICS, 2010 AND MALON, THIS STREAM IN THE FOLLOWING TAKES TO ADD THIS TO BE PERFORMED









arour (Hsa) D)

Preservation of Natural Feature



and Sedimer requirement.

d. Construction phasing bin / sequence due town to Sequence and phasing bind / sequence describes. The Construction Sequence and phasing bind on these pinar provide the regular phasing / Schedule has been provided. The Schemittelia and Eracia Institution of the contained herein outline a general sequence of operations for the property provide herein outline a general sequence of approximation and the original herein outline a general sequence of approximation and of adhubance shall be limited to the shortest period of the approximation protocolaw.

Description of erosion and sediment control practices: This plan, and details / notes shown hereon serve to satisfy this SWPPP requirement.

Temporary and permanent soil stabilization plan: The Sedimentation and Erosian Control Notes and Details provided heron identify temporary and permanent stabilization measures to be employed with respect to specifi elements of the project, and at the various stages of development.

Site map / construction drawing: This plan serves to satisfy this SWPPF requirement.

lapacitions as olived in the Salementation and Danish Calmark Meters. A description of publication prevention measures that will be used to control the second sec

Identification of any elements of the design that are not in confo with the technical standard, "New York Standards and Specification Torsian and Sediment Control." All proposed elements of this SM been designed in accordance with the "New York Standards and Specifications for Exosian and Sediment Control."

openniciations in SUSIC "SPES General Primit In Stammeter Darkarges from Construction Mitting" (SP-C) - 2001, all construction projects meeting construction Mitting" (SP-C) - 2001, all constructions projects meeting constructions profiles analysis of constructions with the most converse technical standard. New York State Stammeter Management Delay Manual (Delay Manuar), Wee provide construction analysis of the State Stammeter Amount of the State Stammeter Management Delay Manual (Delay Manuar), Berg Landow (SP-S), and State Stammeter Management Delay Manual (Delay Amount), Berg Landow (SP-S), and State Statemeter Management Delay Manual Amount (SP-S), and Statement Management Delay Manual (Delay Manuar), Berg Landow (SP-S), and Manual Manual Manual Amount (SP-S), and Statement Management Delay Manual (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and Amount (SP-S), and Amount (SP-S), and Amount Amount (SP-S), and 
a Identification of all post-construction stormwater management practices to be constructed as part of the project; This plan, and details/notes shown hereon serve to satisfy this SMPPP requirement.

A site map/construction drawing(s) showing the specific location and size of each post-construction stormeater management practice. This plan, and detals/notes shown hereon serve to satisfy this SMPPP requirement.

alizari nareto tareto i se ossi ji ili alerri reglatamini. A Siemeste davide god Adala Regol hickalar pre-development condition tale demostrating biot esch procities has leen designer in conformace sall he Bidty officies, ilicentification of adjustitication for orga development tale david procession and adjustitication for orga development regolard analysis is provided in the report lifed Amended Stemester Polyton Prevention Pien for DPD Sol Strange.

Sol testing results and locations. This SWPPP requirement is provided in the report USed Amended Stormwater Pollution Prevention Plan for DPD Self Storag

e. Infiltration testing results. This SWPPP requirement is provided in the report tilled Amended Stammanter Pollution Prevention Plan for DPD Self Stargue.

An operations and maintenance plan that includes impaction and maintenance consults and actions to ensure continuous and effective operation of each entity that set be responsible for the long term operation and maintenance of each practice. The Fernance Starweater Facilities Meintenance Schedule provided on these plans epirose to solity that requirement.

 $\mu$ -cover in more pure series 10 statuy to its replanet. Thereof Requires constrained in the series of the seri

iption and location of any stormwater discharges associated with a activity other than construction at the site: There are no know a stormwater discharges present or proposed at the site.

mensions, material specifications, instaliation details, and operation antenance requirements for all erosion and sealment control les: The details, Erosion and Sealment Control Notes, and Erosio diment Control Maintenance Schedule serve to satisfy this SWPP

- strategin rooms, a. The opplicant proposes to construct 9 self-storage buildings and a 1,110 std office building which would be constructed on the tax map bot number Access to the self will be provided with the statisting curb curis on the US constructed. A proposed drilled well and applic system will service the project. A Stramester Pollution Prevention Pion has been pussed.
- Background Information: The subject project consists of the co self-storage facility.

REQUIRED SWPPP CONTENTS PER GP-0-20-001: Amurani Ia the NYSICE "DESIG Sameral Partial for Stammatic Datasympt turn Construction Archity (Gar-Ca-Do-Ol), Stammatic Pathology Ban (DWPP) and Include ension and sediment control practices designed in conforman with the most current version of the technical landors," Twe Trick Standard Specifications for Drawin and Sediment Control." Mene evolution and sediment contro Specifications for Drawin and Sediment Control." Mene evolution and sediment contro-genetic must demonstrate survivance to the technical tandard. These development of the Standard State (State) and State (State) and of regulard SWPP components is previded in accordance with Part 8.2.1a-1 of General Partial Co-O-20-001.

All construction activities involving the removal or disposition of soil are to be provid appropriate protective measures to minimize erosion and contain sediment disposition Minimum all excession and sediment control measures shall be implemented or a shown plans and shall be installed in accordance with New York Standards and Specificable Dealers and Sediment Control, Ideals addition.

Wherever feasible, natural vegetation should be related and protected. Disturbance shall be minimized in the areas required to perform construction. No more than 5 acres of unprotects soil shall be exposed at any one time.

We also be updated on up one units Mean land lengesed during development, the exposure shall be kept to the shortest practical period of time. In the areas where soil distutionics activity has temporarily or permanently coased, the application of soil attabilization measure must be hildback by the end of the next business day and completed within seven (7) days from the date the current soil disturbaces colifying coased. Disturbance shall be inhibited to the areas registed to perform construction.

Sill fence shall be installed as shown on the plans prior to beginning any clearing, grubbing or enrithmask

(create by) min de deel or importery seeming in nor on an internet despositions, and have all additional terms distributions or construction traffic, permonent or temportery, and have all additionation measures infolled for permonent seeming and the second reserve a minimum of logical (from second s

See mining to be particle research that and the set of the period of the set of

Grass seed mix may be applied by either mechanical or hydroseeding methods. Seeding shall be performed in accordance slit the current edition of the "NISDOT Standard Specification, Construction and Materials, Section 610–3.02, Method No. 1". Hydroseeding shall be performed using materials and methods are approved by the slite anahees.

Cut or fill slopes steeper than 3:1 shall be stabilized immediately after grasling with Curlex I Single Net Erosion Control Blanket, or approved equal.

All storm drahage outlets shall be stabilized, as required, before the discharge points become operational.

14. Doain or a adment control measures shall be inspected and maintained or a daily basis by the G.F.R. to insure that channels, temporary and permanent dictates and piece are clear of debries, find emokements and pieces hereached and that of a stras basis and fercise are black. Any fabre of erabins and sediment control measures shall be inmediately regulated by the contractor and inspected for approval by the U.R. and/or able espisee.

15. Dust shall be controlled by sprinkling or other approved methods as necessary, or as directed by the O.F.R.

16. Cut and fills shall not endanger adjoining property, nor divert water onto the property of others

17. All file shall be placed and compacted in 6° lifts to provide stability of material and to prevent artifement. The C.F.R. shall inspect downstream conditions for evidence of sedimentation on a weekly basis and after rainstorms.

19. As warranted by field conditions, special additional erosion and sediment control measures, as specified by the site angineer and/or the Town Engineer shall be installed by the contractor.

EROSION AND SEDIMENT CONTROL MAINTENANCE SCHEDULE

MAINTENANCE REQUIREMENTS

AFTER CONSTRUCTION

Remove

Remove

N/A

Resed to 80% Coverage

Remove

Remove

Mow Permor

Grass/Repiace/ Repair Rip Rap

Clean/Replace Stones/Repair

Clean Sumps/ Remove Debris/ Repair/Replace

Clean /Repair

Clean

Stormwater Facilities Maintenance Schedule on Drawing SP-3.1

REVISED PER PLANNING BOARD COMMENTS

REVISED PER PLANNING BOARD COMMENTS

REASED PER TOWN COMMENTS

REVISED PER PB COMMENT.

REVISIO

ITECTURE

DETAILS

TSM

BY MEU BY

3 Garrett Place Carmel, NY 10512 (845) 225-9690 (845) 225-9717 fax

Rale A

15 D-2

ORAMING NO. 947

R.D.W.

D.S.W.

A.D.T.

DURING CONSTRUCTION

Clean/Replace Stone and Fabric

Mulching/ Spraying Water

Water/Reseal/ Remulch

Clean/Repair/ Replace

Mulching/ Silt Fence Repair

Clean/Mulch/ Repair

Clean/Replace Stones/Repair

Clean Sumps/ Remove Debris/ Repair/Replace

Clean/Repair

Clean

Ciean/Mulch/ Repair/Resead

20. Erosion and sediment control measures shall remain in place until all disturbed areas are suitably stabilized.

inspect

Inspect

Inspect

Inspect

WEEKLY RAINFALL

hspect Inspect Clean/Replac

hspect Inspect

hspect

napect

hspect Inspect

Inspect Inspect

Inspect Inspect

Inspect Inspect

Inspect Inspect

Inspect Inspect

offer constructor ... Bernad Crashins Ltd 124 Ridge Road Montgomery, NY 12549 and/or the current owner(s) of the subject property.

SCAFE

Permanent registrion is considered stabilized when SOR of the plant density is established presion control measures shall remain in place with all deturbed oreas are permanently a presion control measures shall remain in place with all deturbed oreas are permanently a control stabilized or an anti-stabilized or an employment schedule during and the stabilized or an anti-stabilized or an employment schedule during and the stabilized or an anti-stabilized or an anti-stabilized or an are permanently a schedule during and schedule during and the stabilized or an anti-stabilized or an are permanently a schedule during and schedule during and the schedule during and the schedule during and schedule during and the schedule during an anti-schedule during and the schedule during and schedule during and the schedule during an anti-schedule during and the schedule during and schedule during an anti-schedule during and the schedule during an anti-schedule during an anti-schedule during and the schedule during an anti-schedule durin

MONITORING REQUIREMENTS

PRACTICE DAILY

SILT FENCE BARRER

STABILIZED CONSTRUCTION ENTRANCE

UST CONTROL

*VEGETATIVE ESTABLISHMENT

INLET ROTECTION

SOIL TOCKPILES

SWALES

CHECK DAMS

CONCRETE DRAWAGE STRUCTURES

DRAINAGE

ROAD & PAVEMENT

*STORMINA TER TRAP/BASIN

The party responsible after construction is:

11. The site shall at all times be graded and maintained such that all stormwater runoff is diverted to soil erasion and sediment control facilities.

13. Stormeater from disturbed areas must be passed through erosion control barriers before discharge beyond disturbed areas or discharged into other drainage systems.

10. Paved roadways shall be kept clean at all times

All topsoil to be stripped from the area being developed shall be stockp seeded for temporary stabilization. Ryegrass (annual or perennial) at a acre shall be used for temporary seeding in spring, summer or sarly fail (cereal rys) shall be used for temporary seeding in late fail and initize.

EROSION & SEDIMENT CONTROL NOTES:

The cener's field representative (0.F.R.) will be responsible for the implementation and maintenance of erosion and sediment control measures on this site prior to and during





September 27, 2023

Town of Carmel Planning Board 60 McAlpin Avenue Mahopac, New York 10541

RE: Evan's Septic Town of Carmel TM# 55.11-1-18

Dear Chairman Paeprer and Members of the Board:

Please find enclosed the following plans and documents in support of an application for site plan approval for the above referenced project:

- Site Plan Application, dated September 27, 2023. (11 copies)
- Site Plan Completeness Certification Form, dated September 14, 2023. (11 copies).
- Disclosure Addendum Statement, dated September 11, 2023. (2 copies)
- Site Plan set, dated September 27, 2023. (5 copies)
- Schematic Building Plans and Brochure from Capital Steel (5 Copies)
- SEQR Short EAF, dated September 27, 2023. (11 copies)
- Property Deed & Filed Map #1264. (2 copies)
- List of Property Owners within 500' of the Site Boundary. (2 copies)
- Check number 11173, in the amount of \$3,300, for the application fee.

The applicant seeks site plan approval for the construction of a 6,300 square foot steel building. The building would house the applicant's septic service business. Also proposed are the appurtenant parking, driveways, drainage system and water and wastewater services.

Please place the project on the October 12, 2023 Planning Board agenda for a discussion of the project with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:

Jeffrey J. Contelmo, PE Senior Associate Engineer

JJC/adt

Enclosures

cc: (All via email only) Charlie Evans, Frank Smith, Esq

3 Garrett Place, Carmel, New York 10512 (845) 225-9690 Fax (845) 225-9717 www.insite-eng.com



## TOWN OF CARMEL SITE PLAN APPLICATION INSTRUCTIONS



The Town of Carmel Planning Board meetings are held twice a month, on the second **Thursday** and fourth **Wednesday**, at 7:00 PM at Carmel Town Hall, 60 McAlpin Avenue, Carmel

The submission deadline is 10 days prior to the Planning Board meeting. New site plan applications that have been deemed complete will be placed on the agenda in the order they are received.

#### No application will be placed on the agenda that is incomplete

#### Pre-Submission:

Prior to the formal submission of the site plan, a pre-submission conference may be requested by the applicant to be conducted with representatives from the Town, which may include the Town Planner, Town Engineer, Director of Code Enforcement and/or the Planning Board Attorney. This conference will serve to educate the applicant on the process he/she must follow, clarify the information required to submit a complete site plan application, and to highlight any specific areas of concern. You may arrange a pre-submission conference through the Planning Board Secretary at (845) 628-1500 extension 190.

#### Submission Requirements:

At least 10 days prior to the Planning Board meeting, the site plan application shall be submitted to the Planning Board Secretary as follows:

- All site plans shall be signed, sealed and folded with the title box legible. The application package shall include:
- 5 copies of the Site Plan Application Form, signed and notarized.
- 5 copies of the SEQR Environmental Assessment Form (use of short form or long form shall be determined at pre-submission conference).
- 5 full size sets of the Site Plan (including floor plans and elevations)
- 1 CD (in pdf. format) containing an electronic version of the Site Plan
- 2 copies of the Disclosure Statement
  - 5 copies of the Site Plan Completeness Certification Form
  - All supplemental studies, reports, plans and renderings.
- 2 copies of the current deed.
  - 2 copies of all easements, covenants and restrictions.
- The appropriate fee, determined from the attached fee schedule. Make checks payable to the *Town of Carmel*.

Planning Board Secretary:

own Engineer: Date

1 of 3



## TOWN OF CARMEL



#### Per Town of Carmel Code - Section 156 - Zoning

SITE IDENTIFICATION INFORMATION				
Application Name:		Application #	Date Submitted:	
Site Address:		23-0007	4127123	
No. 53 Street: Old Route 6 H	amlet: Carn	nel	1	
Property Location: (Identify landmarks, distance from	n intersectio	ons, etc.)		
600'± south of Putnam County Board of Elections				
Town of Carmel Tax Map Designation:           Section 55.11         Block         1         Lot(s)         18	Zoning D C	esignation of Site	:	
Property Deed Recorded in County Clerk's Office           Date         Liber 1621         Page 62	Liens, Mo Yes	ortgages or other I No	Encumbrances	
Existing Easements Relating to the Site           No         Yes           Describe and attach copies:	Are Ease	ments Proposed? Describe and	l attach copies:	
Have Property Owners within a 500' Radius of the s	Site Been In lication For	dentified?		
APPLICANT/C	WNER INF	ORMATION		
Property Owner: Liberty Bell Trucking Co., Inc., Lee Schultz	Phone #: Fax#:	845-878-9294	Email:	
Owners Address:				
No. 200 Street: South White Rock Road To	wn: Holmes	3	State:NY Zip:12531	
Evans Septic Tank Service	Phone #: Fax#:	845-628-0166	Email:	
Applicant Address (If different than owner): No. 162 Street: Barrett Hill Road Tot	wn:Mahopa	с	State NY Zin 10541	
Individual/ Firm Responsible for Preparing Site	Phone #:845-225-9690 Fax#: 845-225-9717		Email:	
Plan: Jeffrey J. Contelmo, P.E. Insite Engineering, Surveying & Landscape Architecture, P.C.			jcontelmo@insite-eng.com	
Address: No.3 Street: Garrett Place Tow	vn. Carmel		State NY 7in 10512	
Other Representatives:	Phone #: Fax#:		Email:	
Owners Address:				
No. Street: Tow	vn:		State: Zip:	
PROJECT D	ESCRIPTIC	<b>N</b>		
Describe the project, proposed use and operation t	hereof:			
practice, landscaping and parking.				

G:\Engineering\Planning Board\01 - Application info\Final Site and Subdivision\06-10-15 Site Plan Application Form v3 docx

## TOWN OF CARMEL SITE PLAN APPLICATION

PROJE	CT INFORMATION					
Lot size:	Square footage of all existing structures (by floor):					
Acres: 1.02 Square Feet:	0					
# of existing parking spaces: 0	# of proposed parking spaces: 13					
# of existing dwelling units: 0	# of proposed dwelling units 0					
Is the site served by the following public util	ity infrastructure:					
Is project in sewer district or will priv	ate septic system(s) be installed? CSD #2					
<ul> <li>If yes to Sanitary Sewer answer the feet</li> </ul>	ollowing:					
<ul> <li>Does approval exist to</li> <li>Is this an in-district co</li> <li>What is the total sewe</li> <li>What is your anticipate</li> <li>For Town of Carmel Town Engineer</li> <li>What is the sewer cape</li> </ul>	<ul> <li>Does approval exist to connect to sewer main? Yes: □ No: □</li> <li>Is this an in-district connection? YesOut-of district connection?</li> <li>What is the total sewer capacity at time of application? TBD</li> <li>What is your anticipated average and maximum daily flow 200 gpd max</li> </ul> For Town of Carmel Town Engineer What is the sewer capacity					
<ul> <li>Water Supply</li> </ul>	Yes: 🖸 No: 🗆 CWD #2					
If Yes: <ul> <li>Does approval exist to</li> <li>What is the total water</li> <li>What is your anticipate</li> </ul>	connect to water main? Yes: No: ' capacity at time of application? TBD d average and maximum daily demand 200 gpd max					
- Storm Sewer	Yes: ☑ No: □					
Electric Service	Yes: 🖸 No: 🗆					
<ul> <li>Gas Service</li> </ul>	Yes: 🖸 No: 🗆					
<ul> <li>Telephone/Cable Lines</li> </ul>	Yes: 🗹 No: 🗆					
For Town of Carmel Town Engineer						
Water Flows Sewer Flows ROP 1/6/13 Town Engineer: Date						
What is the predominant soil type(s) on the	What is the approximate depth to water table?					
site?						
Estimated quantity of exervation:	<u>25-35% 3 % &gt;35% 15 %</u>					
Le Blasting Proposed Very D						
Is the site located in a decignated Critical From						
Does a curb cut eviet on the Are new such	auto proposed 2   With the first in the interview of the second 2   With the first interview of the second 2   With the second 2   Wit					
site? Yes: Vo: Vo: Vo: Vo: Vo: Vo: Vo: Vo: Vo: Vo	cuts proposed? What is the sight distance?					
Is the site located within 500' of						
<ul> <li>The boundary of an adjoining city, town or</li> </ul>	rvillage Yes: □ No: ☑					
• The boundary of a state or county park, re	creation area or road right-of-way 🛛 Yes: 🗹 No: 🗖					
<ul> <li>A county drainage channel line.</li> </ul>	Yes: 🗆 No: 🗹					
The boundary of state or county owned law	nd on which a building is located Yes: ☑ No: □					

## TOWN OF CARMEL SITE PLAN APPLICATION

Is the site listed on the State or Endoral Register of Ulateria Dial					
Yes: No. Register of Historic Place (or substantially contiguous)					
Is the site located in a designated floor	dalain?				
Yes: P No: D	upiant:				
Will the project require coverage under	ar the Current NVSD	EC Stormuster Dear	ulation of		
and project require coverage and		EC Stornwater Regt	liations		
	Erosion Contr	ol Only	Vac II No. II		
			Tes: I NO: L		
Will the project require coverage under	er the Current NYCD	EP Stormwater Regu	lations		
		= otoninitator rtegt	nations		
			Yes: No. 1		
Does the site disturb more than 5,000	sq ft	Yes: 🗹 No: 🗆			
-					
Does the site disturb more than 1 acre		Yes: 🗆 No: 🗹			
Deep the site of the set of the set of the					
Does the site contain treshwater wetla	inds?				
Invisition:					
If present the wotlands must be delined	nel: Ll				
the Site Plan	led in the held by a v	vetiand Professional,	and survey located on		
Are encroachments in regulated wetla	nds or wetland huffe	vrs proposed 2 V			
Does this application require a	referral to the	Environmental Vac			
Conservation Board?	terentar to the l	Livironmental Yes			
Does the site contain waterbodies, stro	eams or watercourse	s? Yes I N	o. [2]		
			о, с <u>а</u>		
Are any encroachments, crossings or	alterations proposed	d? Yes:□ No	o: 🗖 N/A		
Is the site located adjacent to New Yor	k City watershed lan	ds? Yes: 🖸 No	<u>у П</u>		
Is the project funded, partially or in tot	al, by grants or loan	s from a public sour	ce?		
Yes: 🗆 No: 🗹					
Will municipal or private solid waste di	sposal be utilized?				
Public: D Private: D					
Has this application been referred to the	e Fire Department?	Yes: 🖸 N	o: 🗆		
<u>д</u>					
What is the estimated time of construc	tion for the project?				
		1 year			
		,			
ZONING	COMPLIANCE INFO	RMATION			
Zoning Provision	Required	Existing	Proposed		
Lot Area	40,000	43,647 sf	43,647 sf		
Lot Coverage	30%(40% for offices)	N/A	N/A		
Lot Width	200	125'*	125'*		
Lot Depth	200	255'	255'		
Front Yard	40	N/A	02.01		
Side Yard	25		03.0		
Lines Manual	25	N/A	27'		
Rear Yard	30	N/A N/A	27' 78.3'		
Minimum Required Floor Area	30 5,000	N/A N/A N/A	27' 78.3' 6,300 sf		
Minimum Required Floor Area Floor Area Ratio	30 5,000	N/A N/A N/A N/A	27' 78.3' 6,300 sf N/A		
Minimum Required Floor Area Floor Area Ratio Height	30 5,000  35(60 for office)	N/A N/A N/A N/A N/A	27' 78.3' 6,300 sf N/A <35'		
Minimum Required Floor Area Floor Area Ratio Height Off-Street Parking	25 30 5,000  35(60 for office) 13	N/A N/A N/A N/A N/A N/A	27' 78.3' 6,300 sf N/A <35' 13		

* Pre-existing nonconforming condition.

## TOWN OF CARMEL SITE PLAN APPLICATION

Will variances be required? Yes: □ No: ⊡	If yes, identify variances:
PROPO	SED BUILDING MATERIALS
Foundation	Reinforced Concrete
Structural System	Steel
Roof	Steel
Exterior Walls	Steel
APPEIG	A PROVIDENCE AND A PROVID
Applicants Name 11th Sworn before me this	Applicants Signature day of September 20.23
Notary Public	

FRANK J. SMITH III NOTARY PUBLIC-STATE OF NEW YORK No. 02SM6399348 Qualified in Putnam County My Commission Expires 10-21-2023



## TOWN OF CARMEL SITE PLAN COMPLETENSS CERTIFICATION FORM



All Site Plans submitted to the Planning Board for review shall include the following information and details, as set forth in Section 156-61 B of the Town of Carmel Zoning Ordinance.

	Requirement Data	To Be Completed by the Applicant	Waived by the Town
1	Name and title of person preparing the site plan		
2	Name of the applicant and owner (if different from applicant)		
3	Original drawing date, revision dates, scale and north arrow		
4	Tax map, block and lot number(s), zoning district	<b></b>	
5	All existing property lines, name of owner of each property within a 500' radius of the site		
6	Contour lines at two-foot intervals, grades of all roads, driveways, sanitary and storm sewers		
7	The location of all water bodies, streams, watercourses, wetland areas, wooded areas, rights-of-way, streets, roads, highways, railroads, buildings, structures	V	
8	The location of all existing and proposed easements		
9	The location of all existing and proposed structures, their use, setback dimensions, floor plans, front, side and rear elevations, buildable area.		
10	On site circulation systems, access, egress ways and service roads, emergency service access and traffic mitigation measures		
11	Sidewalks, paths and other means of pedestrian circulation	Ľ	
12	On-site parking and loading spaces and travel aisles with dimensions	Ľ	
13	The location, height and type of exterior lighting fixtures	2	
14	Proposed signage	<b></b>	
15	For non-residential uses, an estimate of the number of employees who will be using the site, description of the operation, types of products sold, types of machinery and equipment used	Ē	

## This form shall be included with the site plan submission



## TOWN OF CARMEL SITE PLAN COMPLETENSS CERTIFICATION FORM



		in the first and the factor of	and see paid of the
16	The location of clubhouses, swimming pools, open spaces, parks or other recreational areas, and identification of who is responsible for maintenance	N/A	
	and water management. A comprehensive landscaping plan in accordance with the Tree	×1	
18	The location of public and private utilities, maintenance responsibilities, trash and garbage areas		
19	A list, certified by the Town Assessor, of all property owners within 500 feet of the site boundary		
20	Any other information required by the Planning Board which is reasonably necessary to ascertain compliance with this chapter	X	

Applicants Certification (to be completed by the licensed professional preparing the

Jeffrey J. Contelmo, P.E.

hereby certify that the site plan to which I have attached my seal and signature, meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:

Signatu Si ature Owner

9/11/2] Date 9/14/00)



**Professionals Seal** 

2 of 3



## TOWN OF CARMEL SITE PLAN COMPLETENSS **CERTIFICATION FORM**



Town Certification (to be completed by the Town)

hereby confirm that the site plan meets all of the requirements of §156-61B of the Town of Carmel Zoning Ordinance:

- Planning Board Secretary Signature

Signature - Toy Engineer

<u>9/28/23</u> Date

#### Short Environmental Assessment Form Part 1 - Project Information

#### Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 Project and Spansor Information				
rart 1 – Project and Sponsor Information				
Name of Action or Project:				
Evans Septic Tank Service				
Project Location (describe, and attach a location map):				
53 Old Route 6, Carmel, NY 10512				
Brief Description of Proposed Action:				
The applicant seeks to construct 6,300 sf office and storage space with associated stormwat	er management practice, land	Iscaping and parking		
Name of Applicant or Sponsor:	Telephone: 845-225-969	0		
Jeffrey J. Contelmo, P.E.	E-Mail: jcontelmo@insite	eng.com		
Address:	· · · · · · · · · · · · · · · · · · ·			
3 Garrett Place				
City/PO:	State:	Zip Code:		
Carmel	NY	10512		
1. Does the proposed action only involve the legislative adoption of a plan, loca administrative rule, or regulation?	al law, ordinance,	NO YES		
If Yes, attach a narrative description of the intent of the proposed action and the	environmental resources th	iat 🔽 🗖		
may be affected in the municipality and proceed to Part 2. If no, continue to que	stion 2.			
2. Does the proposed action require a permit, approval or funding from any oth	er government Agency?	NO YES		
11 Yes, list agency(s) name and permit or approval: NYSDEC GP-0-20-001 - ESC On Town of Carmel - Building Permit	ly			
3. a. Total acreage of the site of the proposed action?	1.0 acres			
b. Total acreage to be physically disturbed?	0.8± acres			
or controlled by the applicant or project sponsor?	1.0 acres			
4. Check all land uses that occur on, are adjoining or near the proposed action:				
5. 📋 Urban 📋 Rural (non-agriculture) 🗹 Industrial 🗹 Commercial 🗌 Residential (suburban)				
Forest Agriculture Aquatic Other(Specify):				
🗹 Parkland				

5.	Is	the proposed action,	NO	YES	N/A
	a.	A permitted use under the zoning regulations?		~	
	b.	Consistent with the adopted comprehensive plan?		~	
6.	Is	the proposed action consistent with the predominant character of the existing built or natural landscape?		NO	YES
7.	Is	the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?		NO	YES
If Y	es,	identify:			
8.	a.	Will the proposed action result in a substantial increase in traffic above present levels?	c.	NO	YES
	b.	Are public transportation services available at or near the site of the proposed action?			
	c.	Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?			
9.	Do	the proposed action meet or exceed the state energy code requirements?		NO	YES
Ifth	ie p	roposed action will exceed requirements, describe design features and technologies:			
				$\square$	
10.	Wi	ill the proposed action connect to an existing public/private water supply?	-	NO	YES
		If No, describe method for providing potable water:			
11.	Wi	If the proposed action connect to existing wastewater utilities?		210	1/20
				NO	YES
		If No, describe method for providing wastewater treatment:			
				المسيل	
12.	a. I	Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district	L I	NO	YES
Con	ch i nmi	s listed on the National or State Register of Historic Places, or that has been determined by the ssioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the		~	
Stat	e R	egister of Historic Places?			
	1				
arch	D.	Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for logical sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?			
13.	a. we	Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain tlands or other waterbodies regulated by a federal, state or local agency?		NO	YES
	b. 1	Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?			
IfY	es.	identify the wetland or waterbody and extent of alterations in square feet or acrest			
	-, .				
				12	
-				135	

14 Identify the typical babitat types that occur on or are likely to be found on the project site. Check all that applied		
The interview of the state of t		
ShorelineForestAgricultural/grasslandsEarly mid-successional		
Wetland 🗹 Urban 🗹 Suburban		
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Endered government as threatened or endergoesed?	NO	YES
Northern Long-eared Bat		~
16. Is the project site located in the 100-year flood plan?	NO	YES
		~
17. Will the proposed action create storm water discharge, either from point or non-point sources?	NO	YES
If Yes,		~
a. Will storm water discharges flow to adjacent properties?		~
b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? If Yes, briefly describe:		
	200-6	
Cach basins and piping will convey stormwater to an existing drainage ditch and the property frontage.	33	
18. Does the proposed action include construction or other activities that would result in the impoundment of water	NO	YES
or other liquids (e.g., retention pond, waste lagoon, dam)? If Yes, explain the purpose and size of the impoundment:		
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility?	NO	YES
	Ľ	
20.Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste?	NO	YES
If Yes, describe:		
Putnam County Landfill		
I CERTIFY THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BE MY KNOWLEDGE	ST OF	
Applicant/sponsor/name: Jeffrey J. Contelmo, P.E. Date: 9/27/23		
Signature:		

### EAF Mapper Summary Report

Part 1 / Question 15 [Threatened or Endangered Animal]

Part 1 / Question 15 [Threatened or Endangered Animal - Name]

Part 1 / Question 16 [100 Year Flood Plain]

Part 1 / Question 20 [Remediation Site]

Davi Ra	Disclaimer: The EAF Mapper is a screening tool intended to assist project sponsors and reviewing agencies in preparing an environmental assessment form (EAF). Not all questions asked in the EAF are answered by the EAF Mapper. Additional information on any EAF question can be obtained by consulting the EAF Workbooks. Although the EAF Mapper provides the most up-to-date digital data available to DEC, you may also need to contact local or other data sources in order to obtain data not provided by the Mapper. Digital data is not a substitute for agency determinations.
Samin, USGS, Internap, INCREMENTP, NRCan, Esri Japa Korea, Esri (Thailand), NGCC, (c) OpenStreetMap contril	n, METI, Esri China (Hong Kong, Esri putors, and the GIS User Community
Part 1 / Question 7 [Critical Environmental Area]	Νο
Part 1 / Question 12a [National or State Register of Historic Places or State Eligible Sites]	No
Part 1 / Question 12b [Archeological Sites]	Yes
Part 1 / Question 13a [Wetlands or Other Regulated Waterbodies]	Yes - Digital mapping information on local and federal wetlands and waterbodies is known to be incomplete. Refer to EAE Workbook

Yes

Yes

Yes

Northern Long-eared Bat



## **BASE BUILDING PACKAGE**











Your local Capital Steel dealer will deliver the highest quality building system in accordance with our strict CSI brand quality guidelines. THE STRONGEST AND HIGHEST QUALITY BUILDING AVAILABLE

### WHAT'S INCLUDED:



Primary and Secondary Framing

1:12 Roof Pitch

26 Gauge Roof and Wall Sheeting • Baked on Kynar Finish

Fasteners

Sealants and Flashing

Deluxe Trim Package

Ridge Cap

Engineered Stamped Drawings

Your Choice of Wall and Trim Colors

Galvalume Roof Included

 Adding Color to the Roof May Carry an Additional Charge

50 Year Structural Warranty

40 Year Paint Warranty

25 Year Galvalume Roof Warranty

20 Year Standing Seam Roof Warranty

Engineered for Your Location

## **POPULAR COLORS**



# **BASE BUILDING**



#### **BUSINESSES, CHURCHES AND ORGANIZATIONS:**

In addition to churches and organizations of all sizes, America's largest companies like General Motors, Boeing and Dow Chemical start their business expansions with our base building package. Capital Steel building packages are economical, efficient, durable and completely customizable. Each building our local dealers deliver is designed individually according to intended use and to expand easily in the future; making our building system the right choice for growing operations and entrepreneurs alike

#### PRIVATE INDIVIDUALS:

Capital Steel buildings are engineered for reliability and guaranteed by the most extensive warranties in the industry. Simply put, our buildings are designed to last for generations, to withstand historic blizzards, seismic activity and to endure the strongest hurricanes on record. Whether you are building a modest workshop, aircraft hangar or garage for a car collection you expect to be in your family for decades, you can rest assured that our team delivered a building you can count on.



## ALL I-BEAM CONSTRUCTION, 26 GAUGE SHEETING

• Building bolts together, no welding necessary

- Framed openings are cut at the factory, holes in primary and secondary framing are pre punched
- Your local CSI dealer can erect most buildings in weeks or less saving you time and money

# + CUSTOMIZATIONS



Insulation



Colored or Standing Seam Roof



Man Doors



Roll Up and Sectional Doors



Windows



Roof Pitch



Gutters and Downspouts

## ENGINEERED FOR YOUR LOCAL CODES & LOADS

- Wind speeds
- Snow loads
- Seismic activity

## **POPULAR COMPONENTS**

CUSTOMIZE THE LOOK AND FUNCTIONALITY



You can personalize and easily transform your base building package into a fully customized metal building system with our extensive collection of high quality building components. Your local Capital Steel dealer will keep you on budget while guiding you through the selection of carefully thought out access points and bring attention to details like natural light, drainage, insulation and ventilation.

> 100% AMERICAN MADE


There are no regions in North America free from natural disasters, significant storms or acts of God. The Southeastern United States is home to more billion dollar weather disasters than any other region and the remainder of the USA finds itself commonly dealing with high winds, snow or seismic activity.

We understand that your Capital Steel building is a meaningful investment and for many, the largest purchase in a lifetime. We will never cut corners, compromise our brand image or most importantly deliver a building that we cannot stand behind and endorse. Our warranties didn't set the bar, they are the bar.



































18" X 18" DRAIN INLET DETAIL (N.T.S.)



RIP RAP SWALE DETAIL

(N.T.S.)

COMPACTED SUBGRAD

X" D₅₀ STONE SIZE

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTIC OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.



SIDE DRAIN INLET DETAIL













SECTION

CONSTRUCTION NOTES FOR FABRICATED SILT FENCE

SILT FENCE DETAIL (N.T.S.)

EMBED FILTER CLOTH -MIN. 8" INTO GROUND

1. FILTER CLOTH TO BE FASTENED SECURELY TO POSTS AT TOP AND MID SECTION.

WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED.

SIX INCHES AND FOLDED. 3. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.































POSTS: STEEL EITHER T OR U TYPE OR 2" HARDWOOD

OK 2 HANDWOOD FILTER CLOTH: FILTER MUNIKA THAON, OR APPROVED EQUAL PREFABRICATED UNIT: GEOFAB, ENWROFENCE, OR APPROVED EQUAL





PLAN 1. STONE SIZE - USE 3" STONE

5. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE, FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY RESUBACE LOT.

SURFACE WATER – ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL. A MOUNTABLE BERM WITH 5: SLOPES WILL BE PERMITTED.

MANTERANCE - THE DIRANCE SHALL BE MANTANED IN A CONDITION WHICH HIS MAY PECUNIE PERFORT TO PRESSION WHIT CONTONAL STORE AS CONDITIONS DEMMA AND REPRORT TO PRESSION WHIT CONTONAL STORE AS CONDITIONS DEMMA AND REPRORT AND/OR CLARMOUT OF ANY WEXTRES USED TRAP SEDMENT, ALL SEDMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PROJEC MONTO F WAY MASS DE REMOVED AMERICATELY.

8. WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY, WHEN WASHING IS REQUIRED, IT SHALL BE DOME ON AN AREA STABILIZED WITH STOKE AND WHICH DRAINS INTO AN APPROVED SEDMENT TRAPPING DEVICE.

9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER

STABILIZED CONSTRUCTION ENTRANCE DETAIL

(N.T.S.)



EROSION & SEDIMENT CONTROL NOTES:

3. Wherever feasible, natural vegetation should be retained and protected. Disturbance shall be minimized in the areas required to perform construction. No more than 5 acres of unprotected soil shall be exposed at any one time.

Bothe of unprovide and and the second wing account shall be kept to the shortest practical period of time. In the oreas where sol disturbance activity has temporarily by the exist of the next busitess and your discripted within sever (7) days from the date the current sol disturbance activity cases. Disturbance shall be minimized to the areas regulated to perform construction.

Silt fence shall be installed as shown on the plans prior to beginning any clearing, grubbing or earthwork.

All topol to be stripped from the area being developed shall be stockpiled and immediately seeded for temporary stabilization. Pyegrass (annual or perennel) at a rate of 30 bis. per core shall be used for temporary seedely is parties, summer or early fail. Viristock Whiter Rie (cereal rye) shall be used for temporary seedely is parties.

Any disturbed even not subject to further disturbance or construction ratio, any disturbed even not subject to further disturbance or construction ratio, respection cover in combination with a suitable much within 1 business day of final grading. All events and any subject to minimum 4⁻¹ evened topoli for addopt pacing and the subject of the suitable subject and the subject of the pacing subject of the subject of the subject of the subject of the pacing subject of the subject of the subject of the subject of the pacing subject of the subject of the subject of the subject of the pacing subject of the pacing subject of the subje

Cut or fill slopes 3:1 and steeper shall be stabilized immediately after grading with Curlex I Single Net Erosion Control Blanket, or approved equal.

The site shall at all times be graded and maintained such that all stormwater runoff is diverted to soil erosion and sediment control facilities.

All storm drainage outlets shall be stabilized, as required, before the discharge points become operational.

12. Starmwater from disturbed areas must be passed through erosion control barriers before discharge beyond disturbed areas or discharged into other drainage systems.

13. Erasion and sedimant control measures shall be inspected and maintained on a daily basis by the DFR, to human that channess, temporary and permanent ditches and that all strates bases and all forecas are heats. Any failure of arosision and sediment control measures shall be immediciely repaired by the contractor and inspected for approval by the DFR, and/or site engineer.

Cut and fills shall not endanger adjoining property, nor divert water onto the propert of others.

16. All fills shall be placed and compacted in 6^{*} lifts to provide stability of material and to prevent settlement.

Erosion and sediment control measures shall remain in place until all disturbed areas are suitabily stabilized.

Dust shall be controlled by sprinkling or other approved methods as nece as directed by the O.F.R.

The contractor shall inspect downstream conditions for evidence of sed a weekly basis and after rolnstorms.

18. As warranted by field conditions, special additional erosion and sedime measures, as specified by the site engineer and/or the Town Engineer installed by the contractor.

9. Paved roadways shall be kept clean at all times.



12' MIN MIDT













- d. Description of erosion and sediment control practices: This plan, and details / notes shown hereon serve to satisfy this SWPPP requirement.
- Temporary and permanent soil stabilization plan: The Sedimentation and Erosion Control Notes and Datalia provided heron identify temporary and permanent stabilization measures to be employed with respect to specific elements of the project, and at the various stages of development.
- g. The dimensions, material specifications, installation details, and operation and maintenance requirements for all erosion and sediment control practices: The details, Erosion and Sediment Control Notes, and Erosion and Sediment Control Maintenance Schedule serve to satisfy this SWPPP requirement.
- An inspection schedule: Inspections are not required per the General Permit GP-0-020-001.
- Hemmit Giv-G-G20-407.
  A description of pollution prevention measures that will be used to control filter, construction detentions and construction detrics. In general, all the general construction detentions will be used to control filter, constructions data subject there easits barries of datapate programments disposed. Any construction detentions utilized during constructions that which be removed from list doty by the construction expression which be prevent from list doty by the constructions excellent and be disposed of nonlise, and shall utilized by the construction excellent and be disposed of consistent and shall utilized by the construction excellent and be disposed of consistent and the different by the disposed of in accordance with detrod, state and chair disposed of non-cordance with the hole, temporer parameters believed by the shall be maintained by the general contraction for all construction, and heney tabled on the final, temporers parameters final the disposed be disposed of the parameters of the parameters of the disposed beat of the disposed of the parameters.
- A description and location of any stormwater discharges associated with industrial activity other than construction at the site: There are no know industrial stormwater discharges present or proposed at the site.
- Identification of any elements of the design that are not in conformance with the technical standard, "New York Standards and Specifications for Ersakan and Sadiment Control," All proposed elements of this SMPP has been designed in accordance with the "New York Standards and Specifications for Ersakin and Sediment Control." have





 The contractor will be responsible for the implementation and maintenance of erosion and sediment control measures on this site prior to and during construction. 2. All construction activities involving the removal or dispetition of aid are to be provided with appropriate protective measures to minimize erasion and contain eachiment disposition within, Minimum sub erasion and eachiment control measure results of the second second second second second second second Year York Standards and Specifications For Erasion and Sediment Control," late edition.

REQUIRED SWPPP 'CONTENTS PER CP-0-20-001: 1. Arcunit to the W128C 'W28C' General Ammilt to Starmartic Delargosa from (CMPP) table to the W128C 'W28C' and the Starmartic Delargosa from (CMPP) table to the sector of the scholard and table to the Starbart and protection and adapted to continuence with the fended scholard, the sec-prection and adapted to continuence with the fended scholard, the sec-prection and adapted to continuence with the fended scholard, the sec-or directly Starbart components is the fended scholard, the sec-der explored scholard and the societaries with Pert ILE. In-1 of General Parties' components is produce in societaries with Pert ILE. In-1 of General Parties' components is produce in Starbart (BLS) and the Star

- b. Description of the soils present at the site: Onsite soils located within the proposed limits of disturbance consist of Chatfield-Charton complex (CaD) and Udorthents (Uc) as identified on the Soil Conservation Service Web Soil Survey. These soil types being to Hydrologic Soil Groups "B" & "D".
- Construction sequence of operations: The Construction Sequence and phosing found on these plans provide the required phosing. A Construct Sequence and Exation and Sadimut Control Molitoniane Schedul has to control to general sequence of operations for the proposed project. In general all evolution and sediment Cortol facilities and be installed prof-commensement with land disturbing activities, and areas of disturbance shall be limited to the short section of the proceedings.

- Site map / construction drawing: This plan serves to satisfy this SWPPP requirement.



October 2, 2023

Craing Paeprer Chariman & Members of The Carmel Planning Board Town of Carmel 60 McAlpin Ave. Mahopac, NY 10541

RE: John Chang 716 Route 6 Mahopac, NY 10541 TaxMap #76.30-1-26

Dear Mr. Paeprer and Members Of the Planning Board

At the Zoning Board Meeting of September 28th 2023, the variances required where approved. I would appreciate being placed on the agenda for your next meeting on Thursday October 12,2023 so that you can schedule a public hearing for Wednesday October 25, 2023.

Thanking you in advance for your cooperation in this matter.

Very Truly You Joel Greer





## ALFRED A. CAPPELLI, JR. ARCHITECT 23 DIDDELL ROAD WAPPINGERS FALLS, NY 12590

## Telephone: 845-632-6500 Fax: 845-632-6499 Email: acappe2102@aol.com

Sept. 26, 2023

Town of Carmel Planning Board 60 McAlpin Ave. Mahopac NY

Attn: Chairman Paeprer & Planning Board Members

Re: Zakon Project Completion Rt. 6 & Nicole Way Full Bond Return

Dear Chairman Paeprer & Planning Board Members,

The applicant, Joe Zakon, would like to discuss at your next available planning board agenda the arrangement of a final site inspection to have the balance of the bond reduced to zero as the work is now 100% complete.

If you need additional information, please do not hesitate to reach out to our office. Thank you in advance for your time and consideration.

Very truly yours,

Alfred A. Cappelli, Jr. Architect

AAC/dc

## ZAKON, NICOLE WAY PERFORMANCE BOND FULL BOND RETURN

ITEM	TOTAL ORIGNAL AMOUNT	PERCENTAGE COMPLETED	VALUE COMPLETED	BALANCE TO COMPLETE	
EROSION CONTROLS					
Silt fence	\$ 660.00	100%	\$ 660.00	0	
Orange const. fence	\$ 1,167.00	100%	\$ 1,167.00	0	
Erosion blankets	\$ 7,150.00	100%	\$ 7,150.00	0	
Soil stockpile					
stabilization	\$ 1,500.00	100%	\$ 1,500.00	0	
Stabilized const.					
entrance	\$ 1,500.00	100%	\$ 1,500.00	0	
EARTHWORK					
Clear & grub	\$ 4,800.00	100%	\$ 4,800.00	0	
Retaining walls					
(exposed face)	\$41,250.00	100%	\$41,250.00	0	
Cut/export	\$69,875.00	100%	\$69,875.00	0	
DRAINAGE					
8" perforated PVC	\$ 2,720.00	100%	\$ 2,720.00	0	
15"HDPE	\$ 2,090.00	100%	\$ 2,090.00	0	
Catch basins	\$ 2,500.00	100%	\$ 2,500.00	0	
CURBING					
Curbing	\$ 9,900.00	100%	\$ 9,900.00	0	
TRAFFIC AREA					
15" item #4 base	\$15,155.00	100%	\$15,155.00	0	
2 ½" asphalt					
binder course	\$16,060.00	100%	\$16,060.00	0	
2" asphalt top					
course	\$12,430.00	100%	\$12,430.00	0	
Gravel storage area	\$ 2,478.00	100%	\$ 2,478.00	0	
Porous pavement					
gravel base	\$ 9,345.00	100%	\$ 9,345.00	0	
Porous pavement	\$ 7,144.00	100%	\$ 7,144.00	0	
Pole lighting	\$12,500.00	100%	\$12,250.00	0	
PAVEMENT MARKINGS					
4" epoxy striping	\$ 1,740.00	100%	\$ 1,740.00	0	
FENCING					
Privacy fence	\$ 2,250.00	100%	\$ 2,250.00	0	

ITEM	TOTAL ORIGINAL AMOUNT	PERCENTAGE COMPLETED	VALUE	BALANCE		
SIGNAGE Traffic control signs	\$ 225.00	100%	\$ 225.00	0		
LANDSCAPING Trees	\$ 2,208.00	100%	\$ 2,208.00	0		
Shrubs Seed & mulch	\$ 500.00 \$ 3,125.00	100% 100%	\$    500.00 \$  3,125.00	0 0		
SUB-TOTAL	\$230,022.00	100%	\$230,022.00	0		
CONTINGENCIES (5%)	\$11,501.10					
TOTAL	\$241,523.10 (TO	TAL COMPLETED TO DATE)				
PREVIOUS BOND REDUCTION BALANCE FROM FEBRUARY 2023 \$97,667.10						

KEMPEY, ENGMEERING

## **Convultants in Environmental Engineering**

1569 East Beecher Hill Road, Owego, NY 13827 (607) 223-4653 Facsimile (607) 223-1591

September 21, 2023

Mr. Craig Paeper Chairman Planning Board Town of Carmel Carmel Town Hall 60 McAlpin Avenue Mahopac, New York 10541

> Re: 70 Old Route 6, LLC Town of Carmel Planning Board Site Plan Approval Tompkins Recycling Center 70 Old Route 6 Town of Carmel Tax Map #55.11-1-15 Request for Site Plan Re-Approval (Regrant)

Dear Chairman Paeper and Members of the Board:

The Planning Board granted a one-year extension of the Site Plan Approval for the Tompkins Recycling Center Project to 70 Old Route 6, LLC on October 13, 2022. We request that the Board consider a Re-Approval (Regrant) of the expiring Site Plan Approval at this time. In addition, we would like advise the Board that Kempey Engineering has completed the revised construction documents for the project, which are currently being reviewed and anticipates filing the building permit application within the next 15 to 30-days. Also, we would like the advise the Board that our anticipated filing date for the building permit application delineated in our September 14, 2022 letter to the Board was delayed due to substantial subsurface soil issues consisting of the potential for significant adverse building settlement resulting from the consolidation of the underlying peat and clay layers of the site which required almost a year of additional geotechnical investigations of the site to develop a construction method to sufficiently reduce or eliminate the adverse building settlement in order to allow the final building foundation design to be completed.

The project has the following permits:

1.	Town of Carmel - Site Plan Approval	Expires 10/21/2023
2.	Town of Carmel Wetland Permit Number 933	Expires 12/30/2023
3.	NYSDEC Solid Waste Management Facility Permit Number 3-3720-00371/00001	Expires 02/07/2024 (See Below)

Mr. Craig Paeper Chairman

Expires 01/29/2027

4.	NYSDEC Freshwater Wetland Permit Number	Expires 12/31/2027
	3-3720-00371/00004	

5. NYSDEP SWPPP Approval

of construction.

6. NYSDEC SPDES Multi-Sector General Permit for Stormwater Discharges Associated with Construction Activities GP-10-001 - Permit NYR 10Q049. This permit is valid (open) until a Notice of Termination is filed to close out the project after the completion

In addition, Kempey Engineering submitted the Application to Renew New York State Department of Environmental Conservation Permit to Construct and Operate a Solid Waste Management Facility Number 3-3720-00371/00001 on August 10, 2023. Therefore, since we have submitted the abovementioned permit renewal application for the Department's review within the 180-day submission deadline cited in 6 NYCRR Part 360.16(g), 70 Old Route 6, LLC is authorized by the State Administrative Procedure Act (SAPA) and the provisions of 6 NYCRR Part 360.16(g) to continue the construction and operations of the Construction and Demolition Debris Handling and Recovery Facility (Tompkins Recycling Facility) under the current permit should it expire prior to the New York State Department of Environmental Conservation completing its review and issuing the permit renewal.

Also, FEMA has issued a conditional letter of map revision (July 24, 2014) based on the fill which will remove the property from the flood plain once the "as-built" topographic survey is submitted verifying compliance with the design drawings.

Further, transmitted herewith is Project Environmental Services, Inc.'s Check Number 1885 dated September 21, 2023 in the amount of Two Thousand Five Hundred Dollars and Zero Cent (\$ 2,500.00) for the Site Plan Re-Approval (Regrant) Application Fee required to Re-Approve (Regrant) the expiring Town of Carmel Planning Board Site Plan Approval for construction of 70 Old Route 6, LLC's proposed 70 Old Route 6, Carmel, New York Construction and Demolition Debris Handling and Recovery Facility (Tompkins Recycling Center).

If you have any questions or require any additional information, please advise.

Very truly yours,



XC: Gandolfo Schiavone, 70 Old Route 6, LLC

2